FUEL CUT-OFF FOR MISSILES.... page 126

Simple Computers ... 128

Electronigraphs for '55 .... 7 to 26

electronics

JANUARY · 1956



ULTRASONIC SLICING OF QUARTZ CRYSTALS

A McGRAW-HILL PUBLICATION • PRICE 75 CENTS

NEW HERMETIC POWER COMPONENTS

HIGHEST RELIABILITY FOR MILITARY AND INDUSTRIAL USE



Listed below are just a few of the 50 new **stock items** in the United hermetic power series. These MIL-T-27 power components add to the 200 other hermetic stock items of filter, audio, and magnetic amplifier types. Through the use of proven new materials and design concepts, an unparalleled degree of life and reliability has been attained, considerably exceeding MIL-T-27 requirements. Test proved ratings are provided, not only for military applications but for **industrial, broadcast, and test equipment service (55°C. ambient).**

For complete listing of these new items, write for Catalogue #56.

MIL-T-27 RATINGS IN REGULAR TYPE — INDUSTRIAL RATINGS IN BOLD TYPE

TYPICAL POWER TRANSFORMERS, PRI: 115V., 50-60 cycles.

Type No.	HV Sec. C.T.		Approx* DC volts	DC MA	Fil. Wdg.		Approx* DC volts	MA DC	Fil. Wdg.	MIL Case
H-81	500	L	180	65		L	170	75		
		C	265	55	6.3VCT-3A	C	240	65	6.3VCT-3A	HA
	550	L	200	60	5V-2A	L	190	70	5V-2A	
		C	300	50		C	280	60		
H-84	700	L	255	170		L	240	210		
		C	400	110	6.3V-5A	C	360	150	6.3V-6A	KA
	750	L	275	160	6.3V-1A	L	260	200	6.3V-1.5A	
		C	420	105	5V-3A	C	380	140	5V-4A	
H-87	730	L	245	320		L	210	420		
		C	390	210	6.3V-6A	C	350	310	6.3V-6A	NB
	800	L	275	300	6.3V-2A	L	245	400	6.3V-2A	
		C	440	200	5V-4A	C	400	300	5V-4A	
H-93	1000	L	370	280	6.3V-8A	L	340	340	6.3V-10A	0A
	1200	L	465	250	6.3V-4A 5V-6A	L	455	300	6.3V-5A 5V-6A	

*After appropriate H series choke. L ratings are choke input filter, C ratings are condenser input.

United "H" series power transformers are available in types suited to every electronic application. Proven ratings are listed for both high voltage outputs . . . condenser and choke input filter circuits . . . military and **industrial** applications.

United "H" series filter reactors are extremely flexible in design and rating. Listings show actual inductance at four different values of DC. Bold type listings are **industrial** application maximums.

A FEW TYPICAL LISTINGS OF FILTER REACTORS.

Type No.	Ind. @ Hys.	MA DC	Ind. @ Hys.	MA DC	Ind. @ Hys.	MA DC	Ind. @ Hys.	MA DC	Res. Ohms	Max. DCV* Ch. Input	Test V. RMS	MIL Case
H-71	20	40	18.5	50	15.5	60	10	70	350	500	2500	FB
H-73	11	100	9.5	125	7.5	150	5.5	175	150	700	2500	HB
H-75	11	200	10	230	8.5	250	6.5	300	90	700	2500	KB
H-77	10	300	9	350	8	390	6.5	435	60	2000	5500	MB
H-79	7	800	6.5	900	6	1000	5.5	1250	20	3000	9000	9x7x8

*Based on maximum ripple voltage across choke in **choke input** filter circuit, in terms of DC output voltage.

TYPICAL FILAMENT TRANSFORMERS, PRI: 105/115/210/220V., 50-60 cycles.

Type No.	Sec. Volts	Amps. (MIL)	Amps. (Ind)	Test Volts RMS	MIL Case
H-121	2.5	10	12	10000	JB
H-124	5	3	3	2000	FB
H-127	5	20	30	21000	NA
H-131	6.3CT	2	2.5	2500	FB
H-132	6.3CT 6.3CT	6 6	7 7	2500	JA
H-136	14, 12, 11CT	10	14	2500	LA

United "H" series filament transformers have multi-tapped primaries, good regulation, and are rated for **industrial** as well as military service.

United "H" series plate transformers incorporate dual high voltage ratings and tapped primaries to provide versatile units for a wide range of military and **industrial** electronic applications. Large units have terminals opposite mounting for typical transmitter use.

TYPICAL PLATE TRANSFORMERS, PRI: 105/115/210/220V., 50-60 cycles.

No. Type	Sec. V. C.T.	Approx.* DC volts	MA DC	Choke No.	MA DC	Choke No.	Case
H-110	1050 1200	380 465	275 250	H-75 H-75	385 350	H-77 H-77	MB
H-113	2500 3000	1050 1275	280 250	H-77 H-76	340 300	H-77 H-76	5¼ x 6 x 7
H-115	3500 4400	1500 1900	265 225	H-77 H-77	350 300	H-77 H-77	8⅜ x 6½ x 8
H-117	5000 6000	2125 2550	900 800	H-79 H-79	1100 1050	H-79 H-79	13½ x 11 x 14½

*After filter choke. All ratings are for choke input filter.

UNITED TRANSFORMER CO.

150 Varick Street, New York 13, N. Y. • EXPORT DIVISION: 13 E. 40th St., New York 16, N. Y.

CABLES: "ARLAB"

electronics

A McGRAW-HILL PUBLICATION

JANUARY • 1956

ULTRASONIC SLICING OF QUARTZ CRYSTALS—Multiple-blade cutting tool mounted on cone of Raytheon 25,000-cps impact grinder slices quartz block into 20 thin wafers for frequency control crystals. Stream of abrasive fluid is directed at setup (see p 132) ..... COVER

SHOPTALK 2

FIGURES OF THE MONTH 6

INDUSTRY REPORT 7

Electronigraphs 7-26
Scatter Circuits Link Continents 7
Auto Firms Eye Radar Brake Unit 7
Electronics Output Hits New High 8
Desk-top Analog Computer Appears 8
Slow-Scan TV Speeds Data 10
Mergers Keep Pace In Electronics 10
Casey Jones Goes Electronic 12
Parts Houses Gain Business 14
Electronics In Chemical Labs 14
Airplane Firms Spread Interests 16
U. S. Counts Engineers 16
Army Buys $4-Million Computer 20
Russians Look At Electronics 22
TV Flexes Its Muscles 22
Particle Accelerators Gain 24
Firms Invest In Australia 26
Financial Roundup 28
TV Eyes Teeth 28
Future Meetings 28
Industry Shorts 28

CROSSTALK 121

H. W. MATEER, *Publisher*

W. W. MacDONALD, *Editor*
VIN ZELUFF, *Managing Editor*
JOHN MARKUS, *Associate Editor*
ALEXANDER A. McKENZIE, *Associate Editor*
JOHN M. CARROLL, *Associate Editor*
WILLIAM P. O'BRIEN, *Assistant Editor*
WILLIAM G. ARNOLD, *Assistant Editor*
DAVID A. FINDLAY, *Assistant Editor*
HAIG A. MANOOGIAN, *Assistant Editor*
GLORIA J. FILIPPONE, *Editorial Assistant*
ARLENE SCHILP, *Editorial Assistant*
FRANCES SULLIVAN, *Editorial Assistant*
CAROLE A. MORRIS, *Editorial Assistant*
GLADYS T. MONTGOMERY, *Washington Editor*
HARRY PHILLIPS, *Art Director*

WALLACE B. BLOOD, *Manager*
R. S. QUINT, *Buyers' Guide Manager*
FRANK H. WARD, *Business Manager*
GEORGE E. POMEROY, *Classified Manager*
DONALD H. MILLER, *New York*
JAMES GIRDWOOD, *New York*
WM. S. HODGKINSON, *New England*
JAMES T. HAUPTLI, *Philadelphia*
CHARLES WARDNER, *Chicago*
BRUCE WINNER, *Chicago*
HENRY M. SHAW, *Cleveland*
T. H. CARMODY, *San Francisco*
R. C. ALCORN, *San Francisco*
CARL W. DYSINGER, *Los Angeles*
WM. D. LANIER, *Atlanta*
JAMES H. CASH, *Dallas*

KEITH HENNEY, *Consultant*

FEATURES

Transistors Up Reliability of Broadcast Remotes 122
By Paul G. Wulfsberg

Fuel Cut-Off Control for Guided Missiles 126
By Gerald L. Zomber and Donald MacMillan

Simplified Analog Computer 128
By Victor B. Corey

Ultrasonic Machining of Brittle Materials 132
By Maurice S. Hartley

Servo Amplifier Uses Silicon Power Transistors 136
By J. W. Lacy and P. D. Davis, Jr.

Measuring Phase at R-F and Video Frequencies 138
By Y. P. Yu

Biasing Large Amplifiers 141
By W. G. Wadey

Scale Weighs Moving Trucks 142
By Arthur L. Thurston

CONTINUED ON NEXT PAGE

contents

continued

Gas Tubes Protect High-Power Transmitters 144
By W. N. Parker and M. V. Hoover

Digital Presentation Vacuum-Tube Voltmeter 148
By August Nuut and Clarence Munsey

Magnetic-Switch Transient Analyzer 150
By W. A. Geyger

Analog-to-Digital Data Converter 152
By Sherman Rigby

Phase Shifter Circuits Test Power Meters 156
By P. Venkata Rao

Electrically Variable Gas-Dielectric Capacitor 158
By James F. Gordon

Transistor Characteristics for Circuit Designers 161
By Seymour Schwartz

ELECTRONS AT WORK 176

Wrist Receiver Circuit.....176
Breakdown In Gas Tubes.....176
Computer Stores Program.....178
Transistor Telephone Repeaters...178
Transistor Broadcast Receiver.....180
Frequency Diversity 180
Scatter Symposium 180
Interaction Between Antennas....182
Paging Receiver Uses Two Tubes..184
Single-Sideband Mobile Radio....185
Citizen Radio Evaluation.....185
Radar Data Via Wire.....185
Photocontrol for Tunnels.....186
Hawaii Cable Authorized.....188
FCC Mobile Monitor.....188
South Africa Time Signals.....190
Microwave Facsimile 190
Gamma Rays Preserve Meat.....192
Tiny Loudspeaker 192
Electrostethograph Measures Heart.194
Multimegawatt Fluorescent 194
Delay-Line Pulse Generator.....196
Pertinent Patents 198

PRODUCTION TECHNIQUES 214

Captive Alignment Screwdrives....214
Wood Pallet for Wiring Boards....214
Machines Speed Cutting.....216
Blower-Cleaned Trays for Grids...219
Fluorescent Lamps Aid Inspection..219
Conveyorized Oven Bakes Resist..220
Fiber Tote Tray Is Chassis.....220
Producing Inkless Drawings.....228
Under-Bench Wire Bins.....234
Pre-Tinning Etched Wiring 234
Split Coil for Induction Heater..240
Twisting Insulated Wire.....242
Insulating Aluminum for Coils....244
Basing Pencil Triodes with Resin..246
Aluminum Hole-Filler 252

NEW PRODUCTS 254

LITERATURE 303

PLANTS AND PEOPLE 322

NEW BOOKS 350

THUMBNAIL REVIEWS 355

BACKTALK 356

INDEX TO ADVERTISERS 411

SHOP

► **IN THIS ISSUE . . .** Because of the rapidly increasing use of transistors, ELECTRONICS felt that engineer-readers would find a complete new compilation of transistor properties and design data useful in their work.

About a year ago, associate editor Carroll sent out an inquiry to manufacturers of transistors requesting information on their products.

Soon we learned via the grapevine that Seymour Schwartz, an engineer at MIT's Lincoln Lab, was also asking manufacturers for the same data. We contacted him and learned that not only was the information necessary in his work on Project Lincoln but that he also had an article for ELECTRONICS up his sleeve.

We thereupon presented him with all the material we had collected to date and told him his proposed article would be welcome as the flowers in May. It begins on p 161 and covers a dozen other pages.

Incidentally, the author did not merely follow product bulletins in obtaining his data. He tells us that he has personally checked the characteristics and circuit behavior of many of the units in the course of his work.

► **STANDARD PRACTICE . . .** Like many engineers, we have small offices or modules. These provide considerable desk area as well as storage space in drawers for old editorial projects, love letters and the like. Usually loaded, a shelf facing a seated editor is convenient for holding back copies of ELECTRONICS.

On a recent trip in the field, one editor reports he felt completely at home. While visiting a chief engineer and two staff engineers of a company not usually considered as being in

electronics

JANUARY, 1956 Vol. 29, No. 1

Member ABC and ABP

TALK

People We Edit For . . .

the electronics industry, he found himself sitting in each of their offices, facing a shelf holding three years of ELECTRONICS.

▶ **NEXT MONTH** . . . Growing interest in automatic production, or automatization, has caused a number of machine tool manufacturers to add electronic controls to their equipment.

February ELECTRONICS will contain an article, "Electronic Controls for Machine Tools", that will tell engineer readers about the techniques and circuitry employed. One new bandsaw, for example, provides a new look for the machine shop. It steers just like an airplane.

Prepared by assistant editor Findlay, the article involves a survey of more than five hundred machine-tool makers. Dave traveled nearly 4,000 miles while gathering the material.

Some of the original diagrams set new records. One covered two six-foot desks and left an overhang all around.

Only about 12 square feet of the original 60-odd-foot circuit drawing will appear in the article, however. (In reduced size, of course.)

He tells us that he will never again be able to read the old-style parallel-line capacitor symbol. He has seen so many of that one in industrial circuits that it now means only a contactor to him.

Bandsaw pilot and control panel of DoAll machine for cutting extrusion dies

Published monthly with an additional issue in June by McGraw-Hill Publishing Company, Inc., James H. McGraw (1860-1948), Founder. **Executive, Editorial and Advertising Offices: McGraw-Hill Building, 330 W. 42 St., New York 36, N. Y.** Longacre 4-3000. Publication Office, 99-129 North Broadway, Albany 1, N. Y. Donald C. McGraw, President; Paul Montgomery, Executive Vice-President; Joseph A. Gerardi, Vice-President and Treasurer; John J. Cooke, Secretary; Nelson Bond, Executive Vice-President, Publications Division; Ralph B. Smith, Vice-President and Editorial Director; Joseph H. Allen, Vice-President and Director of Advertising; J. E. Blackburn, Jr., Vice-President and Circulation Director.

Subscriptions: Address correspondence to Electronics—Subscription Service, 330 W. 42nd St., New York 36, N. Y. Allow one month for change of address. Subscriptions are solicited only from persons engaged in theory, research, design, production, maintenance and use of electronic and industrial control components, parts and end products. Position and company connection must be indicated on subscription orders.

Single copies 75¢ for United States and possessions, and Canada; $1.25 for Latin America; $2.00 for all other foreign countries. Buyers' Guide $3.00. Subscription rates—United States and possessions, $6.00 a year; $9.00 for two years. Canada, $10.00 a year; $16.00 for two years. Other western hemisphere countries and the Philippines, $15.00 a year; $25 for two years. All other countries $20.00 a year; $30.00 for two years. Three-year rates, accepted on renewals only, are double the one-year rate. Entered as second-class matter August 29, 1936, at the Post Office at Albany, N. Y., under act of Mar. 3, 1879. Printed in U.S.A. Copyright 1955 by McGraw-Hill Publishing Co., Inc.—All Rights Reserved.

BRANCH OFFICES: 520 North Michigan Avenue, Chicago 11, Ill.; 68 Post Street, San Francisco 4; McGraw-Hill House, London, E. C. 4; Washington, D. C. 4; Philadelphia 3; Cleveland 15; Detroit 26; St. Louis 8; Boston 16; 1321 Rhodes-Haverty Bldg.; Atlanta 3, Ga.; 1111 Wilshire Blvd., Los Angeles 17; 919 Oliver Building, Pittsburgh 23. ELECTRONICS is indexed regularly in The Engineering Index.

SEND FOR *New*

SORENSEN CATALOG

SPECIFICATIONS — PERFORMANCE DATA —

condensed information on regulated power equipment for every application

The new 1956 Sorensen condensed catalog gives you specifications on more than 65 different types of regulated power supplies — a cross section of Sorensen equipment engineered to create new standards of accuracy, dependability, ruggedness and appearance.

Included are new precision tubeless and transistorized AC and DC sources . . . a tubeless wide-range regulated DC supply . . . a 750 volt AC voltage reference source . . . heavy duty tubeless regulated DC sources for critical industrial applications . . . plus advanced versions of Sorensen's complete line of regulators and Nobatrons.

The new 1956 Sorensen catalog is a quick, one-stop guide to equipment for your needs — engineered, tested and backed by the reputation of Sorensen . . . "the *world's authority on regulated power.*"

CONTROLLED POWER FOR Sorensen *RESEARCH AND INDUSTRY*

SORENSEN & COMPANY, INC. • 375 FAIRFIELD AVENUE • STAMFORD, CONNECTICUT

Want more information? Use post card on last page.

An unbeatable Combination

high capacity and small size with MUIRHEAD model D-698A Weston standard cell

This new standard cell is hermetically sealed and mounted in a bakelite case, and its miniaturization permits mounting in even the most compact test assemblies. It is of the Cadmium type with a constant absolute voltage of 1.01859 volts (+ 110 microvolts, —90 microvolts) at 20° C. Internal resistance is approximately 600 ohms and the temperature coefficient is —0.00004 per degree C. Currents of up to 20 microamps may be drawn for short periods.

With a weight of only 4 ounces and dimensions of $1\frac{5}{16}$" x 1" x $3\frac{3}{8}$", this cell may be used with a potentiometer for measuring current or voltage, and also in circuits of the NULL balance type.

Write today for Bulletin 5716 and technical data on the complete line of MUIRHEAD Weston Standard Cells, available from New York stock.

MUIRHEAD

MUIRHEAD INSTRUMENTS, Inc. 677 Fifth Ave., New York 22, N.Y.

United States Sales and Service for **MUIRHEAD & CO., LTD.** • Beckenham • Kent • England



FIGURES OF THE MONTH

RECEIVER PRODUCTION

(Source: RETMA)	Latest Month	Previous Month	Year Ago
	Oct. '55	Sept. '55	Oct. '54
Television sets, total	759,735	939,515	921,476
With UHF	109,574	140,022	161,431
Color sets	nr	nr	nr
Radio sets, total	1,500,206	1,302,350	997,788
With F-M	38,920	27,313	12,151
Home sets	398,087	417,802	343,269
Clock radios	282,393	234,106	220,505
Portable sets	168,709	139,164	97,331
Auto sets	651,017	511,278	336,683

RECEIVER SALES

(Source: RETMA)	Oct. '55	Sept. '55	Oct. '54
Television sets, units	746,274	978,833	799,164
Radio sets (except auto)	724,305	753,068	570,285

RECEIVING TUBE SALES

(Source: RETMA)	Oct. '55	Sept. '55	Oct. '54
Receiv. tubes, total units	48,119,000	47,588,000	42,347,794
Receiv. tubes, value	$35,000,000	$34,596,000	$29,228,992
Picture tubes, total units	1,224,990	1,202,430	1,269,674
Picture tubes, value	$23,800,000	$22,867,851	$26,597,702

SEMICONDUCTOR SALES

	Sept. '55	Aug. '55	Sept. '54
Germanium diodes, units / Silicon diodes, units	1,850,000	1,700,000	1,433,021

INDUSTRIAL TUBE SALES

(Source: NEMA)	Latest Quarter	Previous Quarter	Year Ago
	3rd '55	2nd '55	3rd '54
	Quarterly Figures		
Vacuum (non-receiving)	$9,027,845	$8,933,453	$8,803,740
Gas or vapor	$3,438,835	$3,365,008	$3,570,586
Phototubes	nr	nr	nr
Magnetrons and velocity modulation tubes	$10,998,967	$13,193,395	$13,112,244
Gaps and T/R boxes	$1,421,138	$1,677,574	$1,476,407

TV SETS INSTALLED*

(Source: NBC Research Dept.)	Latest Month	Previous Month	Year Ago
	July '55	June '55	July '54
Total sets	36,477,000	36,100,000	30,717,000

BROADCAST STATIONS

(Source: FCC)	Nov. '55	Oct. '55	Nov. '54
TV stations on air	477	473	434
TV stations CPs—not on air	109	110	141
TV stations—new requests	28	35	18
A-M stations on air	2,808	2,788	2,650
A-M stations CPs—not on air	115	110	112
A-M stations—new requests	217	235	174
F-M stations on air	536	539	554
F-M stations CPs—not on air	20	14	11
F-M stations—new requests	4	9	3

COMMUNICATION AUTHORIZATIONS

(Source: FCC)	Oct. '55	Sept. '55	Oct. '54
Aeronautical	43,648	44,183	39,873
Marine	53,426	52,908	48,116
Police, fire, etc.	19,377	19,153	16,546
Industrial	27,091	26,357	22,579
Land transportation	8,216	8,078	7,071
Amateur	140,799	139,628	124,563
Citizens radio	13,862	13,530	8,945
Disaster	319	319	306
Experimental	662	661	627
Common carrier	2,040	2,001	1,737

EMPLOYMENT AND PAYROLLS

(Source: Bur. Labor Statistics)	Sept. '55	Aug. '55	Sept. '54
Prod. workers, comm. equip.	389,700-p	371,300-r	359,900
Av. wkly. earnings, comm.	$74.34 -p	$72.32 -r	$69.55
Av. wkly. earnings, radio	$70.30 -p	$69.43 -r	$68.34
Av. wkly. hours, comm.	41.3 -p	40.4 -r	40.2
Av. wkly. hours, radio	40.4 -p	39.9 -r	40.2

STOCK PRICE AVERAGES

(Source: Standard and Poor's)	Nov. '55	Oct. '55	Nov. '54
Radio-tv & electronics	438.4	428.9	454.6
Radio broadcasters	502.7	486.9	408.1

p—provisional; r—revised
nr—not reported
*being revised in light of Census data

FIGURES OF THE YEAR

	TOTALS FOR FIRST TEN MONTHS 1955	1954	Percent Change	1954 Total
Television set production	6,520,241	5,654,791	+15.3	7,346,715
Radio set production	11,527,568	8,040,230	+43.4	10,400,530
Television set sales	5,896,251	5,444,227	+ 8.3	7,317,034
Radio set sales (except auto)	4,666,981	4,602,989	+ 1.4	6,430,743
Receiving tube sales	395,787,000	308,398,701	+28.3	385,089,458
Cathode-ray tube sales	8,905,771	7,746,240	+15.0	9,913,504

Scatter Circuits To Link Three Continents

Paris-Naples-Ismir, Turkey system planned by NATO will extend US-UK links now in use

COMMUNICATIONS system to connect radar stations from Norway to Turkey has been approved by NATO Ministerial Council. The system will use both tropospheric and ionospheric forward-scatter circuits.

▶**Pilot**—U. S. will finance and supply a pilot tropospheric system for Norway and an ionospheric circuit linking Paris, Naples and Ismir, Turkey. Cost will be about $45 million.

U. S. will shoulder one-fourth or more of the cost of the entire system. The countries in which the equipment will be installed will let final contracts on competitive bids subject to NATO approval. Work will take about three years.

Forward-scatter circuits linking U. S. and Canada with United Kingdom

▶**Tie In**—The completed NATO system will tie into existing forward scatter circuits connecting points in the U. S., Canada and the United Kingdom as shown on the map.

▶**Radar**—Coincident with establishing the new communications network, existing national radar systems of NATO members will be integrated into an overall European radar fence. This move will not necessarily involve installing new equipment.

Auto Firms Eye Radar Brake Unit

PACKARD Motor Car is considering radar controlled automobile brakes for use in its 1957 models.

Ford and General Motors have seen demonstrations of the $300 system, which is being promoted by a Detroit new-car dealer.

▶**System Details**—An antenna about 5 inches high and 30 inches

ELECTRONIGRAPHS—*A Year-End Glance at Electronics Industry Figures*



wide is mounted between the front bumper and grille of the demonstration car. Circuitry fits into the glove compartment.

The car's brakes are applied with a force proportional to the distance away that an object appears on the road ahead. The driver may brake manually while the radar control is in operation and may, at will, disconnect the radar control.

Electronics Output Hits New High

DOUBLING of the electronics industry since 1950 is indicated by the ELECTRONICS Output Index which this year is expected to hit a yearly average of nearly 250 points.

▶ **Comparison**—However, the gross national product has increased by only 35 percent according to RCA. By the end of 1965, the firm expects the value of electronics to more than triple its 1950 value. The gross national product is not expected to have quite doubled.

Now there are 1.6 million workers directly employed and 3 million indirectly employed in companies that serve the electronics industry, according to RCA. In ten years, the firm believes that the industry will employ more than 6 million workers directly and indirectly.



ENGINEER gets assist in solving differential equation as . . .

Desk-Top Analog Computer Appears

Digital computers also figure in the news. Russian computer ordered by India

BURGEONING computer business passed more mileposts during the recent month.

An electronic differential analyzer about the size of a portable typewriter has been announced by California's Litton Industries. Selling in the $10,000 range, the computer contains 20 integrators with accuracies of one part in 250,000. Control is provided by a five-button panel. Answers appear in a miniature crt. The firm indicates the computer will be available in quantity about the first of the year.

▶ **Digital Bookkeeper**—A new digital computer, the Modac 404 will handle accounting for a book club. Produced by Mountain Systems of Thornwood, N. Y., the computer uses magnetic-drum storage with capacity for 20,000 six-digit num-

(Continued on page 10)

ELECTRONIGRAPHS *Continued*





Duplexer built by Airtron Inc. for RCA aircraft weather radar

New "BANTAM" TR tube saves space and weight in airborne weather radar

If your Microwave design includes a branched duplexer, here's a new concept in TR tubes which can produce savings in equipment weight and space and offers simplified mounting with easier maintenance.

These were the primary considerations when Sylvania, in close co-operation with Airtron Inc., developed a special TR tube for use in RCA aircraft weather radar.

The "Bantam" TR type 6624 is the product of this development. Its smaller, more compact design with contact mounting moves the TR a full step toward miniaturization.

The 6624 is a broad-band, fixed tuned TR tube. Operational center is at 5400 mc. Contact mounting is at the input end. The Sylvania ATR type 6591 serves as the companion to the TR 6624.

Write for complete data on the Type 6624 and Sylvania "Bantam" TR tubes for other frequency bands.

"Another reason why it pays to specify Sylvania"

SYLVANIA®

SYLVANIA ELECTRIC PRODUCTS INC.
1740 Broadway, New York 19, N. Y.
In Canada: Sylvania Electronic (Canada) Ltd.
University Tower Bldg., Montreal

LIGHTING · RADIO · ELECTRONICS · TELEVISION · ATOMIC ENERGY

bers on the drum.

Read-in and read-out are done by perforated paper tape. Addition and substraction are accomplished at 15 operations per second. Output to paper tape is 20 characters per second.

▶**Soviet Brain**—The Indian Statistical Institute in Calcutta has ordered a Soviet-made electronic computer to cost $500,000. The computer will supplement a British-made machine currently being installed.

▶**More Memory**—High-speed storage capacity of the IBM 704 scientific computer will be increased by 32,768 words by a new magnetic-core storage unit. Magnetic cores will add 20,000 memory positions to the IBM 705 business computer. The magnetic-core memories supplement existing magnetic tape and drum memories.

▶**Electronic Scales**—An electronic scanning and counting unit announced by Toledo Scale may tie into automatic industrial control applications. Lines on a graduated scale that moves to register weight are scanned and counted electronically. Digital read-out is available at a remote point.

Slow-Scan TV Speeds Business Data

Transmission via telephone lines cuts closed-circuit tv costs

ELIMINATING the need for microwave and coaxial links in closed-circuit tv systems, a low-speed scanning system transmits business data over 25 miles on conventional telephone circuits.

▶**Showing**—The Pennsylvania Bell Telephone Co. recently demonstrated the closed-circuit equipment developed by Dage Television Division of Thompson Products. Present plans are for Bell to offer the service in metropolitan areas with distance between transmitter and receiver limited to 25 miles.

▶**Operation**—Using a scanning system that completes the picture on the screen in two to four seconds, the transmission requires a band of 8,000 cps—about 1/500 of that required for conventional television. A long-persistence picture tube retains the image over the relatively long scanning cycle.

▶**Applications**—Uses for the new system include transmission of signatures for verification at branch banks, printed materials, meter and gage faces, and other types of slow or nonmoving pictures.

Mergers Keep Pace In Electronics

New companies move into the field, old ones enlarge their holdings

IN 1955 more than 200 companies were involved in mergers in the electronics field. In the first six months, nearly 50 mergers were consummated or planned (ELECTRONICS, p 15, July '55). Almost as many took place in the second half. Nearly twice as many took place in 1955 as in 1954.

▶**Why**—According to the Federal Trade Commission, the most frequent advantage to be gained by an acquisition is additional capacity to supply a market already supplied by the acquirer. This was observed in two acquisitions out of every five studied by the FTC in making its merger report of May, 1955.

▶**Size**—High in the merger rate in the electronics industry in number of firms acquired is Litton Industries. The company has integrated 10 firms into its operations in the past 24 months.

Two of the largest mergers in the past year were the Sperry, Remington Rand and the Strom-

(Continued on page 12)

ELECTRONIGRAPHS *Continued*



More Charts Following

new!

a solid-dielectric molded paper tubular capacitor

with flat capacitance-temperature characteristics



HCX*—impregnated Black Beauty® capacitors

offer improved circuit performance

Sprague, on request, will provide you with complete application engineering service for optimum results in the use of molded paper tubular capacitors.

SPRAGUE'S NEW TYPE 109P CAPACITORS use a unique new impregnant identified by the trademark HCX. Developed in the Sprague research laboratories in the search for a better material than the polyesters customarily used for impregnating solid dielectric paper tubulars, HCX is a hydrocarbon which polymerizes after the rolled section has been vacuum impregnated. Its salient electrical characteristic of insulation resistance, power factor, and capacitance change with temperature are superior to those of the ordinary polyester units on the market today.

Type 109P Black Beauty Telecaps are molded in non-flammable phenolic and are mechanically rugged. They make an ideal capacitor for all TV and auto radio operations and are well suited for automation assembly by machine since the lead concentricity is closely fixed and there is no outer wax dip to jam inserting heads or magazines.

Complete performance data covering the wide range of sizes and ratings are in Engineering Bulletin 223, available on letterhead request to the Technical Literature Section, Sprague Electric Company, 35 Marshall Street, North Adams, Massachusetts.

★ Trademark

SPRAGUE® *world's largest capacitor manufacturer*

Export for the Americas: Sprague Electric International Ltd., North Adams, Massachusetts. CABLE: SPREXINT.

berg Carlson, General Dynamics. The Sperry Rand action formed a new firm with assets of approximately $484 million. The Stromberg, General Dynamics merger joined the 55,000 employees of General with the 5,200 of Stromberg for a total work force of over 60,000.

▶ **Character**—Following is a list of mergers in the electronics field in the last half of 1955. Most companies are parts manufacturers and instrument firms.

Mergers In Electronics
(Last Six Months 1955)
Air Associates, Great American Industries
American Cyanamid, The Formica Co.
American Electronics, R-C Scientific
Atomic Instrument, Kaye Development
Beckman Inst., Liston-Becker
Beckman Inst., Place Ceramics
Borg-Warner, Byron Jackson
Cinch Mfg., Graphik Circuits
Frank Cook, Hart Machine
Eastern Industries, Neptune Meter
Electromation, Kinevox
General Cable, General Insulated Wire
General Instrument, Automatic Mfg.
Titus Haffa, Webster Chicago
Hall-Scott, Dynamic Analysis
Hermetic Seal, Glass Solder
Hoffman, National Fabricated
Hoover, Phebco
Hupp Corp., Pioneer Electric
IDEA, Radio Apparatus Corp.
IRC, EMEC
IT&T, Kuthe Labs
Jerrold Electronics, Cable Vision
Litton, Automatic Seriographic
National Aircraft, Florida Aviation, Hydro-Aire Division, Mag-Electric
N. Y. Transformer, Tartack Electronics
Norden-Ketay, Frohman Mfg.
Ohmite, American Relay
Penn-Texas, Hallicrafters
H. K. Porter, Electric Service Eng.
J. B. Rea, Robey Rotor Co.
RCA Estate, Seeger, Whirlpool, Sears Roebuck
Siegler, Hallamore Mfg.
Sperry Products, Western Inspection
Stewart-Warner, J. W. Hobbs
Stromberg-Carlson, Electronic Control Systems
Superior Tube, Johnson & Hoffman Mfg.
Thomas Industries, White Corp.
United Carr, Plastic Process
Van Norman, Insuline and Transitron, Inc.



WAYSIDE station controls, left, and safety equipment in car run train as . . .

Casey Jones Goes Electronic

Remote control, cab signal gear and two-way communications are used in test run

A LOCOMOTIVE on the New Haven Railroad in the New Rochelle to Rye, N. Y. area moved east or west, coasted or stopped, without an engineer at the controls. Its movements were controlled by remote control equipment at a wayside station.

Automatic train control equipment on the train continuously monitored conditions ahead to make sure all was safe. Two-way inductive voice communication equipment was available to keep passengers informed of control changes to be made. The control, safety and communication equipment was provided by Union Switch & Signal Division of Westinghouse.

▶ **Remote**—The way side equipment has a locomotive control panel with two control levers. One controls direction and the other selects between "neutral," "run," and "stop." When the lever is on neutral, the train brakes are released and power is cut off. To stop, a service application of the train brakes follows, bringing the train to a halt.

The electronic portion of the wayside equipment consists of a power supply, an audio oscillator and a carrier modulator. A carrier frequency is modulated with certain audio frequencies, depending on the control desired. Amplified to the desired level of signal cur-

(Continued on page 14)

ELECTRONIGRAPHS Continued


RECEIVER SALES
MILLIONS OF SETS
2.0
1.5
1.0
0.5
0
RADIO (EXCEPT AUTO)
TELEVISION
D J F M A M J J A S O N D J F M A M J J A S O N D J F M A M J J A S O N D
1953
1954
1955

More Charts Following



Magnets for rotors or stators ...any design or size you may require

"MAGNETIC MATERIALS CATALOG"

Write for your copy

Contains handy data on various types of Alnico Magnets, partial lists of stock items, and information on other permanent magnet materials. Also includes valuable technical data on Arnold tape-wound cores, powder cores, and types "C" and "E" split cores in various tape gauges and core sizes.

ADDRESS DEPT. E-61

The use of Alnico permanent magnets in rotor and stator assemblies of motors, generators, magnetoes and tachometers has revolutionized the designs of these devices. Whatever your need may be —from a tiny rotor for a timing device to a large slab for power generators—Arnold can take care of your requirements, either for experimental samples or production quantities.

• *Let us work with you.* You will have the advantage of working with a leading producer of rotor magnets, whose manufacturing and testing facilities—the most modern in the business—give you the best assurance of high quality standards and uniform performance.

WAD5184

THE ARNOLD ENGINEERING COMPANY

SUBSIDIARY OF ALLEGHENY LUDLUM STEEL CORPORATION

General Office & Plant: Marengo, Illinois

DISTRICT SALES OFFICES . . . New York: 350 Fifth Ave.

Los Angeles: 3450 Wilshire Blvd. Boston: 200 Berkeley St.

rent, the carrier output is fed to existing line wires which parallel the track.

The train receives its commands through inductive coupling between the modulated carrier current flowing in the line wires and a receiving coil mounted on the locomotive.

When the remote control lever is in the run position, two audio frequencies are introduced into the modulator—when the lever is in the neutral position only one audio frequency is used—and when the lever is in the stop position no audio is present. A visual indicator on the train displays the control commands transmitted from the remote station.

▶ **Transistors**—For safety, the locomotive used was equipped with additional automatic train control. It is continuously responsive to rail-carried currents which reflect track conditions in advance of a train. If all is not safe, the brakes are automatically applied and the train is brought to a stop regardless of control signals from the wayside station. Junction-type silicon transistors were used in place of vacuum tubes.

Parts Houses Gain Business

INCREASING volume of electronic parts and products rolling off the production lines of the industry has swelled the importance of the distribution side of the business.

▶ **Number**—According to Market Planning Service, a division of the National Credit Office, there are some 1,143 electronics parts distributors in the U.S. today with 300 branches. In 1954 there were 1,100 with 250 branch locations.

In addition, there are some 230 distributors who handle electronics parts but whose main business volume lies in other fields.

▶ **Volume**—In 1954 all these companies did over $1.3 billion, a seven-percent increase over 1953.

Sales were 12 percent ahead of '54 in the first quarter, 9 percent ahead in the second and 15 percent ahead in the third quarter. If the increase is maintained in the fourth quarter, total sales for the year should exceed $1.5 billion.

Parts inventories have been some 17 percent ahead of 1954. Purchases equaled 77 percent of sales in the first three quarters of 1955, indicating fast turnover.

▶ **Future**—Sylvania's president, Don G. Mitchell, predicts that by 1965 the distribution and service businesses will reach a combined volume of $5.1 billion. For 1956 he foresees a volume of $2.3 billion and $3.3 billion by 1960.

Electronics Invades Chemical Labs

MORE than 1,000 chemical laboratories are maintained by major colleges, metal producers, chemical plants and drug houses. At a typical laboratory, that of Lehigh University in Bethlehem, Pa., the chemistry department uses 142 electronic instruments having a value of roughly $250,000.

Instrument	Number of Tubes	Number of Instruments
Conductivity bridge	3–5	4
Recording potentiometer	5–8	15
Colorimeter	4–5	2
Radiation counter	6–20	4
Dielectric-constant meter	6	1
Electrometer	20–24	2
Electron microscope	60	1
Frequency meter	6–12	3
Strain-gage amplifier	6	2
Oxygen analyzer	4	1
pH meter	2–5	20
Impedance bridge	4	1
Ionization gage	5–6	6
R-F combustion furnace	8	1
Mass spectrometer	40–60	2
Gauss meter	6	1
Audio oscillator	2–8	3
R-F oscillator	4–5	3
Ultrasonic oscillator	4–14	2
Oscilloscope	10	4
Electronic relay	1–2	20
Servomechanisms	5	4
Photoelectric x-ray spectrometer	40	1
Infrared spectrophotometer	25	1
Ultraviolet spectrophotometer	2–18	3
Stroboscope	4	1
Electronic timer	3	2
X-ray thickness gage	20	2
Thyratron relay	4	4
Titrimeter	4	10
Voltage regulator	8	2
Tube tester	4	3
Nephlometer	3	1
Viscometer	5	1
Vacuum-tube voltmeter	4	8
X-ray diffraction equipment	45	1

(Continued on page 16)

ELECTRONIGRAPHS Continued



KĀHLE

automatic machines

WILL PRODUCE YOUR

PRECISION GRIDS

TUBE COMPONENTS, GLASS DIODES, TRANSISTORS AND SUBMINIATURE TUBES *faster,* MORE ECONOMICALLY



AUTOMATIC GRID WINDING MACHINE #2686

Send for KAHLE'S valuable file on automatic equipment —today!

Kähle ENGINEERING COMPANY
1310 SEVENTH STREET • NORTH BERGEN, N. J.

DESIGNERS AND BUILDERS OF AUTOMATIC AND SEMI-AUTOMATIC EQUIPMENT FOR ALL INDUSTRIAL OPERATIONS

PLANT facilities such as these will be used by Hughes Aircraft for commercial production as . . .

Airplane Firms Spread Interests

Manufacturers apply military electronics know-how to civilian products

IN little more than a year's time, three large aircraft manufacturers have moved into the non-aviation side of the electronics business.

Curtiss-Wright now makes and sells industrial tv equipment. General Dynamics, through the acquisition of Stromberg-Carlson, is now heavily engaged in all phases of commercial electronics. Latest aircraft manufacturer to make the move from primarily military electronics to civilian products is Hughes Aircraft Co.

▶ **Products**—The firm has set up the Hughes Products Division which will be responsible for making the products created by its research activities available to industry. The new division, initially, will concentrate on the field of semi-conductors, producing germanium diodes, silicon diodes and transistors; electronic storage tubes, display tubes and related products. All of these are outgrowths of developments made in the areas of electronic systems, computers and guided missiles.

Up to now the developments of the company's research have been used in the Falcon guided missile and electronic systems for interceptor airplanes.

▶ **Size**—Magnitude of Hughes Aircraft operations is indicated by the fact that it employs some 19,000 persons. Total plant area of the company is 3.1 million sq ft. Its total annual payroll is $81.4 million and sales in 1954 exceeded $200 million. Its current backlog of orders exceeds $316 million.

The company has produced more than 8,000 electronic control systems for interceptor planes. Each system is the equivalent, in number of parts, of 200 tv sets. Today it has approximately 5,000 scientists, engineers and technicians employed in electronics research and development work.

U. S. Counts Engineers In Industry Fields

Report consolidates latest valid figures on scientific personnel resources

SUMMARY of significant data on the supply, utilization and training of scientific and technical personnel in the U. S. has been made

(Continued on page 20)

ELECTRONIGRAPHS *Continued*



Type 970 Potentiometer

... An Achievement in Simplicity

Linearity Better than ±0.2% *for Larger Units graded to ±2% for smaller sizes*

Seventeen Stock Resistances *from 2 to 500,000 ohms*

Ratings From 2 to 20 Watts *at 40° Ambient*

1¼" Diameter to 4¼"

Prices From $3.10 to $10.00



All Phenolic Case chosen for minimum capacitance to ground — geometry of these moldings prevents unequal curing or aging stresses, providing a uniformly concentric surface on which to mount the wound-wire card — cleanliness resulting from total enclosure helps keep noise low.

External Phasing— only two screws in rotating hub secure the shaft; this permits convenient brush orientation and substitution of shafts of other materials or lengths without exposing interior to dust.

Glass-Reinforced Polyester Shaft for superior electrical performance, strength and insurance against warpage.



Good Linearity, Low Electrical Noise — brush rides on edge of tightly-wound resistance card where wire is firmly seated and holds its spacing — card is cemented to cylindrical surface of base, and complete assembly is baked to cure cement and stress-relieve the card — linearity of high order is obtained and this important characteristic is not affected by age, temperature or moisture — each pot is individually tested for conformity with linearity specifications and acceptable noise.

Precious Metal-Alloy Brush is specially selected for compatibility with metal of winding — brush is spot welded to spring arm and has small diameter giving best possible resolution — alloy used is noncorrosive to keep electrical noise low, is heat hardened to give long life.

Uniform Contact Pressure — phosphor bronze brush-arm acts as extra long spring assuring uniform pressure at all settings — bearing in same plane as contact brush minimizes effects of side-thrust on shaft.

Single Cover Retaining Screw also acts as brush stop — easy inspection even when pot is mounted — restraining force of stop does not act on active portion of brush spring, preventing bending or straining of operating elements.

Electrical Continuity — terminals are solder-secured directly to winding ends for positive connection — no permanent electrical connections depend on pressure.

Mounting Rigidity — potentiometers may be mounted on any thickness of panel or shelf by screws through base; units are then keyed against rotation.

The G-R Type 970 Potentiometer is not just another potentiometer, but a precision unit which is sturdy and versatile, has resistance-performance characteristics approaching the best available, a-c performance substantially better than that found in higher precision types, *but which is available at reasonable cost.*

This potentiometer is different by its simplicity . . . a simplicity of design which makes possible manufacturing economies with no sacrifice in quality. This design makes available a potentiometer of superior performance at very low price.

The new 970 Series Potentiometers have accurate resistance values and low capacitance; feature good linearity and long contact life; have low noise and are totally enclosed; there are no fixed-pressure connections, and settings are stable and repeatable. Ganged units are available with no loss of the low capacitance characteristic which makes the individual units so valuable in instrument service.

This simple, well thought-out design provides performance which you don't expect at low cost. The outstanding mechanical and electrical performance built into these units has been obtained only by utilizing to the utmost today's materials and manufacturing techniques.

Versatility — In addition to potentiometers normally stocked, units will be provided on special order with: 360° mechanical rotation—taps as close as ¼" apart along entire winding — special all-metal or metal-filled shafts — resistance values other than standard — resistance functions other than linear — resistance and linearity tolerances better than standard.

Attractive prices can be offered when quantities are sufficient to warrant special production.

Write for the G-R POTENTIOMETER BULLETIN which gives complete specifications for all resistance sizes and power ratings.

General Radio Company

275 Massachusetts Avenue, Cambridge 39, Massachusetts

90 West Street **NEW YORK 6**
8055 13th St., Silver Spring, Md. **WASHINGTON, D. C.**
1150 York Road, Abington, Pa. **PHILADELPHIA**
920 S. Michigan Ave. **CHICAGO 5**
1000 N. Seward St. **LOS ANGELES 38**

WE SELL DIRECT. Prices are net, F.O.B. Cambridge or West Concord, Mass.



Why Raytheon Voltage Stabilizers mean satisfied customers for you

When you incorporate a Raytheon Voltage Stabilizer in your equipment, you help assure complete customer satisfaction—for these important reasons:

1. Your equipment will operate as it was designed to, regardless of voltage variations of your customers' electrical source.

2. Since most components have maximum life when operating at their designed voltage, a Raytheon Voltage Stabilizer prolongs the life of components—and your equipment. A plus feature is provided by the short-circuit protection inherent in Raytheon Voltage Stabilizers.

3. Because Raytheon Voltage Stabilizers are superior to any other static type stabilizer under virtually all operating conditions, your equipment will work better and longer—characteristics your customers really appreciate.

Check these important points of Raytheon Voltage Stabilizer superiority

Raytheon Model VR-6113 (120 watts) chosen at random and compared with a similarly rated competitive model.

- Guaranteed to deliver accurate AC voltage within ±½% (competitive model 1%)
- 14% lighter, 22% smaller
- Three times more accurate no-load to full-load regulation
- 17% less change in voltage output as frequency varies
- 28% closer regulation as temperature changes

For full information see your electronic supply house or write Dept. 6120

RAYTHEON MANUFACTURING COMPANY

Equipment Marketing Division, **Waltham 54, Mass.**

RAYTHEON

Excellence in Electronics

Want more information? Use post card on last page.

X-RAY

a new and important contribution to

QUALITY CONTROL

of RAYTHEON RELIABLE Miniature and Subminiature Tubes

You're looking at the last word in quality control technique — an X-ray sampling check on all Raytheon Reliable Tubes.

X-ray analyses are instantly transmitted to Raytheon's engineering and production personnel for guidance in continuous maintenance and improvement of tube quality.



Subminiature Tube X-ray shown 3 times actual size

Here in a lead-lined room specially designed by Raytheon engineers is the 300,000 volt X-ray unit equipped with fractional focus tube to provide high resolution of even the smallest parts. The room with its specially developed equipment has no counterpart in the tube industry.

Raytheon's X-ray equipment looks right through the tube to make sure that there are no cold, burned, brittle welds or weld blowholes. The X-ray proves that grid siderods are straight, grid wires properly spaced, glass perfectly sealed, getters intact, and heater coating free of chips. X-ray examination checks internal defects of leads, proper lead spacing, parts alignment, tube completeness, and tube cleanliness.

The X-ray photographs of tube structures are examined by trained experts. Potential defects are instantly detected. Thus Raytheon adds one more safeguard to the control of tube quality and reliability.

RAYTHEON

Excellence in Electronics

SPECIAL TUBE DIVISION

RAYTHEON MANUFACTURING CO.

Home Office: 55 Chapel St., Newton 58, Mass., Bigelow 4-7500
For application information write or call the Home Office or:
9501 Grand Ave., Franklin Park (Chicago), Ill., TUxedo 9-5400
589 Fifth Avenue, New York 17, New York, PLaza 9-3900
622 South La Brea Ave., Los Angeles 36, Calif.,
WEbster 8-2851

by various groups. National Science Foundation estimates that there were approximately 200,000 scientists and 650,000 engineers in the U. S. in 1954.

▶ **Electronics**—The Bureau of Census reported approximately 105,000 electrical engineers in the country in 1950. Some 90 percent were employed by private industry with 21.1 percent employed in electrical machinery and electronics, 8 percent by government agencies and 2 percent by educational and nonprofit institutions in this country.

▶ **Degrees**—According to the U. S. Office of Education, 4,485 bachelor's degrees in electrical engineering were conferred in 1954, a decline of some 8,000 since 1950.

Master's degrees in the field also decreased, from 1,114 in 1951 to 978 in 1954. Doctor's degrees conferred in 1954 numbered 111 compared to 113 in 1951.

▶ **Education**—Nearly 11 percent of those classified as electrical engineers in the 1950 census had less than four years of high school. Sixteen percent had completed high school but did not go on farther. Another 16 percent completed 1 to 3 years of college.

Largest percentage, 39 percent, completed 4 years of college and 13 percent completed 5 years of college or more.



LATEST giant brain is unveiled as . . .

Army Buys $4-Million Computer

Large-scale digital unit will inventory replacement parts for tanks and autos

FIVE years abuilding, RCA's entry in the digital computer field, Bizmac, has been purchased by the Army Ordnance Tank-Automotive Command in Detroit.

The $4-million computer will maintain stock control on 200,000 kinds of tank and auto replacement parts.

▶ **Performance** — The computer stores 2.5 million characters on a 10½-in. reel of magnetic tape. It reads 10,000 characters a second at a tape speed of 80 in. a second.

Operations include addition, subtraction, multiplication and division. Internal program storage provides for 4,000 three-address instructions.

▶ **Design**—There are 200 units of 13 equipment types that make up the computer. Magnetic-core rapid-access storage is used.

An electronic sorter assists in file maintenance. An interrogation unit can query the magnetic-tape files. Central control of all units minimizes idle time throughout

(Continued on page 22)

ELECTRONIGRAPHS *Continued*



Here's Why Clifford Specifies ALL-ANGL Barry Mounts to Protect Reliability thru Every Flight Attitude of the F-100

Clifford miniaturized heat-control unit — only 3-1/8 inches high.

It's an important story of engineering for shock and vibration control

North American Aviation, builders of the F-100 Super Sabre, specify that the control box must be able to mount at any angle. MIL-E-5272A requires the mount to operate under vibration as high as 0.080" double amplitude. Temperature requirements preclude the use of rubber mountings. And experience demands that the mounting system handle the load bias added by large connectors and cables — often a serious problem with miniaturized equipment.

Because they are specifically designed for jet and missile service, ALL-ANGL Barry Mounts meet all these requirements. So Clifford's choice of this mount assures the protection of their new miniaturized heat control under every operational condition.

The ALL-ANGL Barrymount® isolators used in the Clifford base are standard miniature size. These advanced-design mountings are also available in MIL-size 1 and (Feb. 1) MIL-size 2. Write for data sheets.

When your problem is protection through all flight attitudes, your answer is ALL-ANGL Barry Mounts. For recommendations, call your Barry Sales Representative.

BARRY B MOUNT

BARRY CONTROLS
INCORPORATED
SALES REPRESENTATIVES IN ALL PRINCIPAL CITIES

New engineering opportunities are open in Barry's expansion program, at all levels in all departments. Send resumé.

707 PLEASANT STREET, WATERTOWN 72, MASS.

the installation. The computer accommodates variable word and message lengths.

▶ **Input/Output**—The input equipment produces a verified punched paper tape and a typed copy. A punched tape to magnetic tape converter transcribes characters electronically at 12,000 characters a minute. A card-to-tape converter handles 400 cards a minute.

Output is a 600 line-a-minute printer and a magnetic tape to punched tape converter.

Russians Look At U. S. Electronics

Two engineers express disappointment after tour of electronics plants

GEORGI P. Kazanski of the Collegium Radio-Technical Ministry in Moscow, who specializes in electronics, and Vladimire P. Loukine of the Machine Construction Ministry in Moscow, who specializes in instruments for automation, both expressed disappointment in American industry with regard to electronics and automatic production.

After a two-week tour of U. S. plants they said they did not see what they had expected to see and expressed the doubt that the impressions gained from the tour represented the true state of affairs.

▶ **Visits**—Among the places visited by the two engineers while in the U. S. were the International Automation Exposition in Chicago, Panellit Co. in Skokie, Ill., Ford engine plant in Cleveland, AT&T's relay station in Washington, D. C., and RCA in New York City.

Their official host on the trip was the ASME which provided an escort for the engineers at the request of the State Department.

▶ **Transistors**—When asked about the use of transistors in Russia, Kazanski said that they are replacing vacuum tubes to about the same extent as in the U. S. He said that transistors are used largely in measuring instruments and computers.

▶ **Computers**—The Soviet engineers said that Russia is using computers particularly for statistical work. They indicated that production of electronic apparatus in the Soviet Union has increased five-fold since 1950 but gave no specific estimates as to the size of the increases.

They expressed particular interest in flow meters and estimated that 20 percent of the flow meters used in Russia are electronic.

▶ **Return**—Three U. S. engineers are making a reciprocal two-week trip in Russia. They are N. L. Bean of Ford's automatic transmission division, W. H. Brandt, engineering manager of Westinghouse and A. C. Hall, general manager of research for Bendix.

TV Flexes Its Muscles And Takes First Place

Final FCC report shows how tv topped radio revenue record for the first time

THE radio and tv broadcasting industry passed the $1-billion mark in total revenue in 1954 for the first time, according to FCC. Television accounted for $593 million and radio for $449 million. Thus, 1954 was the first year in which tv revenues exceeded that of radio.

The tv total of $593 million surpassed the all-time high for radio of $475 million, reached in 1953. Radio revenues in 1954 dropped 5 percent compared to 1953 totals, the first time in the last 16 years that the radio industry failed to establish a new high for total revenues.

(Continued on page 24)

ELECTRONIGRAPHS Continued



G.E. again helps TV manufacturers cut costs...introduces new 2B3 high-voltage rectifier, with 1.75-v filament!

IN LINE with General Electric policy to help manufacturers cut costs of volume-production TV sets, the new 2B3 rectifier tube saves by eliminating a resistor, associated wiring, plus their share of circuit-assembly expense.

No need for filament-voltage stepdown . . . instead, the new 2B3, supplying power to the picture-tube anode, operates directly from the flyback transformer!

Designed to replace the 1B3-GT for increased circuit economy, G.E.'s 2B3 also outperforms its prototype. A new filament construction gives longer tube life, increases dependability.

Step by step, General Electric tube engineers have cooperated with designers and builders in reducing TV-set costs. In 1954 came the 6CD6-GA and 6AU4-GTA—new G-E sweep tubes with high ratings, usable both for monochrome and color, lower in cost than any color sweep tubes then available.

Also in 1954, the famous "600-series" family of 50 G-E tubes, all with controlled heater warm-up time . . . making possible mass production of reliable, economical series-string TV receivers. Last year, General Electric introduced the 6CN7 duo-diode triode—saving some $.23 over the 6AQ7-GT whose circuit functions it assumed.

Profit from G.E.'s consistent drive to cut TV manufacturing expense with new tubes that save components, circuitry, and labor! Get ratings, characteristics, and prices of the cost-saving 2B3! Address *Tube Department, General Electric Company, Schenectady 5, New York.*

Progress Is Our Most Important Product

GENERAL ELECTRIC

162-1A1

▶ **Profits**—Radio and tv stations made profits before taxes of $132 million in 1954, some 7 percent above 1953. Television broadcast profits of $90 million were 32.8 percent higher, while radio profits of $42 million were 24 percent lower than in 1953.

▶ **Contrast**—Changing make-up of revenues in the broadcasting business since tv is shown in the report. Of the $593 million total tv revenue, $452 million or 76 percent was from the sale of time and $141 million or 24 percent from sales of talent, program material and production. Radio's total revenue of $449 million consisted of $404 million or 90 percent in time sales and $45 million or 10 percent from talent and program sales.

▶ **Nets**—TV networks, including the 16 owned and operated stations, accounted for $306.7 million or 52 percent of tv total revenues. The other 394 stations reported $286 million or 48 percent of total revenues. Profits of the four nationwide and three regional radio networks including 21 owned stations were reported at $8.2 million or 22 percent below 1953. A total of 2,577 other radio stations had combined profits of $34 million, or an amount that represents the value of 24.5 percent below station profits for 1953.



BABY-SIZED accelerator developed by High Voltage Engineering because . . .

Particle Accelerators Gain Sales

Use of the instruments in industry and in institutions is steadily increasing

ALTHOUGH only a handful of companies are in the particle accelerator manufacturing business and total dollar volume is small, the field is gaining in importance.

There are probably not more than 300 particle accelerators in use in the world today and many of these are homemade.

Prices of the units vary considerably depending on size and installation costs. Most units are in the one-million electron volt plus range. However, there are commercial accelerators available rated to 50-million electron volts.

A new machine being constructed at the Brookhaven National Laboratory is expected to accelerate protons to an energy of 25 billion electron volts.

(Continued on page 26)

ELECTRONIGRAPHS *Continued*



for VARIABLE CAPACITORS...



"BFC" butterfly-type capacitor with isolated rotor, very low minimum capacity and low inductance. For VHF applications as series capacitor with no rotor connection.

"MAC" Low minimum capacity and very low inductance. Ideal for VHF-UHF applications. Designed for use in miniaturization. Also available as butterfly type "MACBF".

"APC" A compact, high quality air dielectric trimmer. Extremely high resistance to temperature changes, moisture and vibration.

"MAPC" A scaled down version of the "APC". Designed to fill the needs of miniaturization. Suitable for VHF use.

"HF" A high frequency design featuring extra long sleeve bearing and positive contact nickel-plated phosphor bronze wiper. Also available as a dual unit.

naturally,

"HFA" Similar to "HF" model, but with larger air gaps for higher breakdown ratings. Used for high-frequency, low-power transmitting. Also available as dual unit.

"MC" Designed for maximum versatility in mountings, connections and capacity characteristics. Rotor stop permits 180° clockwise rotation with increasing capacity. Also available as dual unit.

"RMC" Similar to "MC-S" but featuring extra rigid design. Heavy frame of aluminum tie rods and end plates.

"NZ" Compact transmitting neutralizing capacitor designed for easy and accurate adjustment. Long leakage paths to ground from both rotor and stator.

"VU" Permits use of "lumped constant" circuits up to 500 MC. Two sections in series eliminate rotor wiper. Pyrex glass ball bearings eliminate noise from usual metal-to-metal bearings.

it's HAMMARLUND

For commercial, military and industrial applications, you just can't beat Hammarlund Variable Capacitors for uniformly high quality design, materials and workmanship. The capacitors illustrated here are just a small representative portion of the complete Hammarlund line. In addition to stock designs, Hammarlund offers you unparalleled variable capacitor know-how in development, design and production. Whatever your needs, when it comes to special or standard variable capacitors, naturally, come to Hammarlund.

● *Send for your copy of Bulletin 55E*

HAMMARLUND MANUFACTURING COMPANY, INC.
460 West 34th Street, New York 1, N. Y.

▶ **Growth**—Steady growth of the field is indicated by the rising sales of companies producing the instruments. High Voltage Engineering Corp., sole manufacturer of the Van de Graaff accelerator, has had sales increases of approximately $200,000 nearly every year since its formation in 1947 and expects sales to hit the $1.8 million mark in 1955. Other manufacturers in the field are American Instrument, GE, Marblette Corp. and Stanford Laboratories.

▶ **Firm**—New manufacturer to enter the accelerator field is Varian Associates. The company is planing construction of its own linear electron accelerator, under license from Stanford University, and is developing special accelerator parts for others. According to Varian, it is the second firm to contract with Stanford for manufacture of the high-energy machines. General Electric signed a similar contract in 1954.

▶ **Markets**—Principal markets for accelerators lie in the fields of scientific research, medical therapy, industrial radiography and radiation processing. The market for instruments in industry and institutions engaged in general nuclear research and development is growing.

Projections by the Atomic Industrial Forum indicate that $13.5 million will be spent by private industry between 1954 and 1958 on research and development in the use of particle accelerators and that institutions will spend about $1.5 million. In 1953 industry spent $698,000 on particle accelerator research and institutions spent $234,000.

Industry Invests In Australia

Country lists 37 U.S. electronics firms with manufacturing interests there

AN estimated $240 million in private U. S. investment has been made in Australian manufacturing and a substantial portion is accounted for by U. S. electronics firms.

Some 37 U. S. electronics manufacturers have direct financial interests in Australia. An increase in such investments is expected in the future as tv takes hold down under.

▶ **Reasons**—To encourage investment from overseas, Australia has negotiated a double taxation convention with the U. S. It prevents double taxation on income flowing between the two countries.

Also, Australia allows all net income after taxes, earned by U. S. firms in Australia, to be remitted without restriction.

▶ **Set-up**—Nine of the U. S. electronics firms with investments in Australia have a subsidiary or affiliate in the country. The remaining 28 companies have other arrangements with companies in Australia such as license or royalty agreements.

▶ **Companies**—Following is the list of U. S. electronics firms with investments in Australian electronics in 1955:

Admiral
Aerovox
Alertronic Corp.
Alliance Mfg.
Am. Phenolic
Armour Research
Astatic Corp.
Automatic Electric
Bendix Aviation
Bussman Mfg.
A. B. Du Mont
Federal Telephone & Radio
Foxboro Co.
General Ceramics
General Magnetic
General Radio
Hazeltine Electronics
IBM
Int'l GE
Int'l Resistance
IT&T
Jensen Mfg.
Walter Kidde
Magnecord
P. R. Mallory
Motorola
New England Mica
Philco
RCA
Shure Bros.
Sola Electric
Stromberg-Carlson
Western Electric
Westinghouse
Westrex Corp.
X-ray Mfg. of Am.
Zenith

(Continued on page 28)

ELECTRONIGRAPHS



2 TO 36 VOLTS @ 15 AMPS DC POWER SUPPLY

The NEW PERKIN MODEL MR532-15A with ±½% REGULATION

IMMEDIATE DELIVERY !



Now...for Your Laboratory...the most versatile TUBELESS, Regulated and Filtered Power Supply

For **PROMPT REPLY**, wire the factory collect or phone our nearest sales office.

New York City:	HUnter 2-7784
Philadelphia:	NOrristown 5-2600
Chicago:	DIversey 8-6885
Los Angeles:	SYcamore 8-5790
St. Louis:	DElmar 7701
Kansas City, Mo.:	Jefferson 7221
Dallas:	FOrrest 8-8306
Denver:	MAin 3-0343
San Francisco:	ULmar 1-7129
Syracuse:	2-1167
Pittsburgh:	WAlnut 1-2959
Minneapolis:	MIdway 2-7884
Seattle:	MOhawk 4895
Albuquerque:	5-9632
Boston:	MIssion 8-0756
Atlanta:	Elgin 3020
Winston Salem, N.C.:	4-0750
Ontario, Canada	AXminister 3-5771

- **REMOTE SENSING** • **VERNIER VOLTAGE CONTROL**
- **NO TUBES, MOVING PARTS OR VIBRATING CONTACTS**

Specifications . . . .

REGULATION: 5-32V Range: ± ½% for combined line changes of 105-125VAC and load of 0-15A. DC.
2-5V Range: ± 2% for combined line changes of 105-125VAC and load changes of 0-15A. DC.
32-36V Range: ± 2% for combined line changes of 110-125VAC and load changes of 0-15A. DC.

RIPPLE: 1% rms max. @ 36 volts and full load. Increases to 2% @ 2 volts and full load.

AC INPUT: 105 to 125 volts, 1 phase, 60 cps. (8 amps, Input)

RESPONSE TIME: 0.1 to 0.2 seconds maximum.

DIMENSIONS: 19½" wide x 15½" deep x 13¼" high with cabinet. (19" wide x 14¾" deep x 12¼" high rack panel construction)

FINISH: Gray Hammertone **WEIGHT:** *Approx. 135 lbs.*

Write for Bulletin MR 532-15A

PERKIN D C power supplies

PERKIN ENGINEERING CORP.

345 KANSAS ST. • EL SEGUNDO, CALIF. • ORegon 8-7215 or EAstgate 2-1375

Want more information? Use post card on last page.

Financial Roundup

Firms report varied profit positions for 1955's first 9 months

ELEVEN companies in the electronics field made financial reports in the past month. Two firms announced security transactions.

► **Score**—Following are the net profit reports of the electronics firms for the fiscal periods indicated:

Company	Net Profit 1955	1954
Admiral Corp. 9 m.	$3,385,676	$4,382,175
Am. Cable & Radio 9m	716,490	1,286,494
Beckman Instruments 3m	369,712	290,786
CBS 9m	8,718,713	7,299,130
A. B. Du Mont 9m	2,019,000*	612,000
Electronics Corp. of Am. 9m	295,000	135,700
Gabriel Co. 9m	69,905	89,302
Gen. Dynamics 9m	13,754,390	14,161,038
Litton Industries 3m	212,000	
Nuclear Inst. & Chem. 9m	108,820	19,772
Sperry Rand 6m	18,541,828	

* loss

► **Securities** — Applied Science Corp of Princeton offered 16,100 shares of common stock, par $2, at $12 per share to common stockholders on the basis of 14 new shares for each 100 shares held. Proceeds will be used for plant and equipment expansion, working capital and other corporate use.

Tracerlab registered with SEC covering $1.5 million of 5-percent convertible debentures, due Nov. 1, 1970. Price to be announced.

TV Eyes Teeth

Industrial tv as a classroom aid to teaching dental techniques to large groups was demonstrated recently by Temple University and RCA

FUTURE MEETINGS

JAN. 9-10, 1956: Second National Symposium on Reliability and Quality Control in Electronics, ASQC and RETMA, Hotel Statler, Washington, D. C.

JAN. 18-20: 12th Annual Technical Conference, Society of Plastics Engineers, Hotel Statler, Cleveland, Ohio.

JAN. 19-21: IRE National Simulation Conference, AIEE, ACM, Baker Hotel, Dallas.

JAN. 25-26: Third Annual Industrial Show, Penn Sherwood Hotel, Philadelphia, Pa.

JAN. 30-FEB. 3: Winter General Meeting, AIEE, Hotel Statler, New York, N. Y.

FEB. 2-3, 1956: IRE National Symposium on Microwave Techniques, University of Pennsylvania, Philadelphia.

FEB. 9-11: IRE Southwestern Regional Conference and Show University of Pa. Philadelphia, Pa.

FEB. 15-17: 1956 Conference On High-Speed Computers, Louisiana State University, Baton Rouge, La.

FEB. 16-17: IRE, AIEE, Univ. of Pa. Conference on Transistor Circuits, University of Pennsylvania, Philadelphia, Pa.

FEB. 27-29: Second Annual Electronic Conference & Exhibit, AMA, Hotel Commodore, New York, N. Y.

FEB. 28-29: Scintillation Counter Symposium, IRE, AIEE, Shoreham Hotel, Washington, D. C.

MARCH 6-7: Conference on Radio Interference Reduction, Armour Research Foundation, Chicago, Ill.

MAR. 15-16: AIEE Fifth Annual Spring Conf., Cleveland, Ohio.

MAR. 19-22: IRE National Convention, Waldorf-Astoria Hotel, Kingsbridge Armory, New York, N. Y.

Industry Shorts

► **Critical** shortage of nickel threatens to curtail tube production, according to RETMA. An estimated 262,000 pounds a month will be required by tube makers in 1956. The Association has appealed to the government for help from the nickel stockpile.

► **Realignment** of GE organization assigns six operations in the field of producers and military electronics to the electronics division along with an industrial electronics lab, a computer section and an electronics business study. The home radio and tv sections of the division were shifted to a consumer's products group. No change in manufacturing facilities will be made.

► **Beam** power tube that can deliver a synchronizing-level power output of 25 to 30 kw when used as a grid-driven power amplifier in tv service, has been developed by RCA.

► **Radio**-controlled traffic signals system, designed and built by GE, went into operation at 13 street intersections in Chicago.

► **FCC** nullified its action that would have permitted use of maximum power with antenna heights up to 1,250 feet for vhf tv stations in zone 1. As the rules now stand, maximum power of tv stations is 100 kw on vhf channels 2-6, 316 kw on 7-13 and 1,000 kw on uhf channels 14-83.

► **Line** of five color tv sets, all with 26-tube circuits and 21-inch picture tubes, has been introduced by RCA at retail prices ranging from $695 to $995.

► **Four** million tubes will be procured by the Army Signal Corps for the Army and Air Force during fiscal 1956. Four tube types will be ordered in quantities of over 100,000. They are 6SJ7Y, 140,000; 6V6Y, 160,000; 5749/6BA6W, 250,000; 5692, 300,000.

► **Total** of 25 electronic-electrical firms have set up in Puerto Rico.

KAY

Multiple Variable Time Delay Units

KAY *Auto-Vox*

Variable time delay designed to introduce controlled amounts of delay into an audio system. Auto-Vox provides one output as a reference and a second output with variable delay in 2 ranges. The unit permits 2 signals to be delayed in 2 independent channels with separate or mixed output.

USES: To simulate controlled delay in servo-mechanisms • To simulate delay of desired magnitude in computer output • Use as negative delay in tracking time • Use in Auto correlation and analog computer work • Use to measure displacement of spectrum to right or left from object in motion • Use as artificial echo chamber for time delay before and after pure sound • Use as a precision variable time delay or as component in analog electronic correlator • An auxiliary to a sampling analog correlator to speed up computation of correlation function • Haas effect in speech delay and other psycho-acoustical studies • To preserve realism in speech reinforcement studies • Used in speech intelligence scrambling and decoding.

Price: $1795.00 F.O.B. Factory

SPECIFICATIONS

Frequency Response: 40—12,000 cps ±1.5 db—Short Delay Range
±2.0 db—Long Delay Range

Time Delay: 2 Ranges, Negative to Positive, passing thru Zero.

Negative Delays as follows:

A. Three Outputs available on short delay range
1. Reference
2. —100 ms thru "0" to +220 ms
3. —80 ms thru "0" to +240 ms

Continuously variable to the following:
1. Reference
2. "0" ms to +320 ms
3. +20 ms to +340 ms

B. Three outputs available on long delay range
1. Reference
2. —300 ms thru "0" to +660 ms
3. —240 ms thru "0" to +720 ms

Also continuously variable to the following:
1. Reference
2. "0" ms to +960 ms
3. +60 ms to +1020ms

C. Panel controls provide a convenient method of obtaining all positive delays in the following ranges:

Three outputs available on short delay range:
1. +20 ms to +120 ms
2. +20 ms to +340 ms
3. +40 ms to +360 ms

Three outputs available on long delay range:
1. +60 ms to +360 ms
2. +60 ms to +1020 ms
3. +120 ms to +1080 ms

Flutter: Less than ±0.14% at short delay range
±0.17% at long delay range
Signal-To-Noise-Ratio: 45 db
Input Signal Required: Average operation .5 V rms
Input Impedance: 600 ohms
Output to Input Ratio: 1-1 (Unity Gain)
2 Output Impedances: Low 600 ohms, High 100 K ohms
Power Requirements: 115 Volts, 60 cps (50 cps on spec. order)
Dimensions: 18" x 18" x 20"
Weight: 90 pounds
Catalog No. 740-A



KAY *Echo-Vox, Sr.*

MULTIPLE TIME DELAY

Precision multiple acoustical time delay providing three separate periods of delay within either of two ranges and, in addition, a single, high-quality direct channel. Employs precision metallic tape recording over the full audible range from 40-12,000 cps. Delay variable from 20-540 and 60-1600 milliseconds.

Echo-Vox, Sr. may be used as a transient wave analyzer. By repeating stored data, a Fourier analysis may be obtained. It may also be used for Haas psycho-acoustical effect study, for multiple speaker phasing, for "Echo" effects, for improved fidelity effects (short delays provide fuller, more pleasing sound), as an acoustical repeater for material up to 2 seconds in length, as a narrow band low frequency filter, and for measurement of Doppler Sonar.

Price: $1295.00 F.O.B. Plant

SPECIFICATIONS

Linearity:
a. 20-540 millisecond range: ± 1.5 db
b. 60-1600 millisecond range: ± 2.0 db

Flutter:
a. 20-540 millisecond range: ± 0.14%
b. 60-1600 millisecond range: ± 0.17%

Signal to noise ratio: 45 db
Recommended input signal: 500 mv
Input Impedance: 600 ohms
Output: 1:1 ratio (Unity gain)
Output Impedance: 600 ohms
Power Requirements: 175 watts, 117 v (±10%), 60 cps, A/C

For Complete Information and Detailed Specifications, Write:

KAY ELECTRIC COMPANY

Dept. E-1 **PINE BROOK, N. J.**

Another Advancement by General Ceramics

Presenting— SUPER FERRAMICS

Superior in Quality – Lower in Cost

- Higher Initial Permeability
- Higher Effective Permeability at Higher Saturation Levels
- Lower Core Loss Resulting in Less Temperature Rise
- Greater Uniformity Through Improved Production Techniques

New Super-Grade Ferrites from the Laboratories of General Ceramics –

New Super-Ferramics are magnetic ferrites with properties once considered beyond the realm of achievement. The first of this series Ferramic O, (see property chart) has been released and is now available in production quantities. Engineers and product designers are invited to request complete information on Ferramic O. Call or write for data today!

MAGNETIC PROPERTIES OF FERRAMIC O-1

PROPERTIES	UNIT	FERRAMIC O-1
μ_{40} at 50 kcs.	—	1200
μ_{max}	—	6000
Saturation Flux Density B_s	Gauss	4100
Residual Magnetism B_r	Gauss	2500
Coercive Force H_c	Oersteds	0.20
Curie Temperature	+ °C.	165
Volume Resistivity	—	Low
Loss Factor at 50 kcs.	$\frac{1}{\mu_0 Q}$	0.000010
Temp. Coeff. of Initial Perm. (50 Kcs)	%/°C.	+0.75

GENERAL CERAMICS CORPORATION

TELEPHONE: VALLEY 6-5100

GENERAL OFFICES and PLANT: KEASBEY, NEW JERSEY

MAKERS OF STEATITE, ALUMINA, ZIRCON, PORCELAIN, SOLDERSEAL TERMINALS, "ADVAC" HIGH TEMPERATURE SEALS, CHEMICAL STONEWARE, IMPERVIOUS GRAPHITE, FERRAMIC MAGNETIC CORES

Want more information? Use post card on last page.

filtered by FILTRON

Guided Missile

Jet Aircraft

T-38 Sky Sweeper
Self-Aiming
Anti-Aircraft Gun

Atomic Submarine
U.S.S. NAUTILUS

FROM GUIDED MISSILES TO ATOMIC SUBMARINES...

FILTRON PROVIDES EXACTLY THE FILTER THEY NEED

1 Electrical Test
2 Shielded Laboratory Measurements
3 Screen Room Interference Testing
4 Environmental Testing
5 Attenuation Test Consoles (per MIL-STD-220)

From the best equipped Radio Interference Laboratories in the world—staffed with the most experienced Radio Interference Engineers, tomorrow's electric and electronic components and systems are made "Radio Interference Free" today.

FILTRON's exceptional facilities are available for the Radio Interference testing AND filtering of your equipment to meet Military Radio Interference Specifications.

Combining engineering facilities, application experience, and manufacturing ability, Filtron competently handles RF interference problems from start to finish.

FILTRON's four plants, with complete production facilities—capacitor manufacturing, coil winding, metal fabricating and stamping, tool and die department, assembly division—are producing more RF interference filters than ever before.

FILTRON—the most dependable name in RF Interference Filters—is the choice of engineers, manufacturers, and military and commercial laboratories the world over.

Send for our free 20-page RADIO INTERFERENCE FILTER CATALOG.

Main Plant, Flushing, N. Y.

FILTRON CO., INC., FLUSHING, LONG ISLAND, NEW YORK

PLANTS IN FLUSHING, NEW YORK, AND LOS ANGELES, CALIFORNIA

goes a sleeving!

All around some conductor rods
Heat was put to some sleevings.
The oven thought 'twas all in fun—
Pop—goes a sleeving!

. . . the sleeving that doesn't go "pop" is BH "1151" . . . it never does! A patented combination of braided Fiberglas and silicone rubber, BH "1151" has what it takes to stand up under all kinds of punishment.

Look at this test: Samples of comparable sleevings were slipped over conductor rods bent to a "U" with an approximate ½" diameter. Then they were oven heated at 250°C., for eight hours. The BH "1151" samples showed no ill effects from the test, while the coatings of other samples broke open at points of maximum stress around the bend of the "U".

Heat-bend resistance is just one feature of BH "1151". It is "safe" for continuous operation from –90°F. to 400°F. Meets all industry specifications for Class H insulation, as well as MIL-I-18057. It also offers permanent flexibility, excellent oil, chemical and fungus resistance. It is self extinguishing within 15 seconds. And, BH "1151" can be twisted and bent without cracking or crazing.

Available in all standard colors, BH "1151" is packaged in spools or coil put-up, with 36" lengths or short pieces on special order. Try it now—send for data sheets and free Production Testing Samples.

BENTLEY, HARRIS MANUFACTURING CO.
1301 Barclay St.
CONSHOHOCKEN, PA. Telephone: Conshohocken 6-0634

BENTLEY, HARRIS *Fiberglas** **SLEEVINGS**

*BH Non-Fraying Fiberglas Sleevings are made by an exclusive Bentley, Harris process (U.S. Pat. Nos. 2595530; 2647296 and 2647288). "Fiberglas" is Reg. TM of Owens-Corning Fiberglas Corp.

THERMALLY BALANCED..

to Prevent Crazing



OHMITE®

"Brown Devil"® RESISTORS

Ohmite "Brown Devil" Resistors have been carefully designed to provide *balanced thermal expansion.* All parts—core, resistance wire, vitreous enamel coating, and terminal band—have a thermal expansion that has been carefully matched. Consequently, Ohmite "Brown Devil" Resistors expand and contract as a unit. This eliminates cracking of the enamel, keeps terminals firmly anchored, and prevents the entrance of moisture.

THE RESULT: You are assured high-quality resistors that provide the utmost in dependability under the toughest service. Specify Ohmite "Brown Devils" on your next job.

They Last Longer!

1 PATENTED WELDED TERMINALS

Ohmite welded terminals provide a perfect and permanently stable electrical connection that is unaffected by vibration or high temperature.

2 HIGH TEMPERATURE STEATITE CORE

This strong, rugged, steatite core has excellent electrical characteristics, and a coefficient of thermal expansion that matches the other resistor materials.

3 EXCLUSIVE HIGH TEMPERATURE VITREOUS ENAMEL

This special-formula enamel was developed by Ohmite after extensive research. Its thermal expansion is properly related to that of the steatite core, terminal, and resistance wire.

Be Right with OHMITE®

OHMITE MANUFACTURING COMPANY, 3610 Howard Street, Skokie, Illinois (Suburb of Chicago)

RHEOSTATS • RESISTORS • RELAYS • TAP SWITCHES

WON'T CHAR OR BURN!

OHMITE® HIGH CURRENT ROTARY TAP SWITCHES

ALL-CERAMIC AND METAL

Ohmite rotary tap switches are preferred by industry everywhere because they are compact, dependable, all-ceramic and metal units ideally suited to a-c operation. They are available in the single-pole, non-shorting type with up to 12 taps. The self-cleaning, silver-to-silver contacts require no maintenance. The rugged, one-piece ceramic body is unaffected by heat or arcing. Two or three of these switches can be grouped in tandem to form multi-pole assemblies. Open-type models are also available for shorting and non-shorting applications.

Write on company letterhead for Catalog and Engineering Manual No. 40.

OHMITE MANUFACTURING CO.
3610 Howard St., Skokie, Ill.
(Suburb of Chicago)

Be Right with **OHMITE®**

RHEOSTATS • RESISTORS • RELAYS • TAP SWITCHES

5 SIZES

AC RATINGS

AMP	VOLTS	NO. TAPS
10	150	2 to 11
15	150	2 to 12
25	300*	2 to 12
50	300*	2 to 12
100	300	2 to 8

*150 Volts between taps.

AIRPAX PRODUCTS



MANUFACTURED WITH LABORATORY PRECISION IN PRODUCTION QUANTITIES

Airpax Products Company specializes in making electromagnetic components in production quantities to laboratory precision. Where your equipment requires a quality product that you can rely upon, ask Airpax to make it for you.

Standard Airpax components include a wide variety of signal choppers both in octal-based and 7-pin miniature sizes. They are designed for operation at 60 or 400 cps (other ratings available on special order).

For your power needs seriously consider the advantages of an Airpax supply. You can minimize the weight of your airborne equipment by using a Airpax 400-cps power vibrator, or, for the fullest saving in space and weight, ask Airpax to manufacture the complete power supply: transformers, chokes, wired, potted and tested to your specifications.

Several standard supplies, converters, and inverters are available based on our 400-cps vibrators and quality transformers—ratings up to 30 watts, higher for intermittent operation.

Equipment manufacturers who pride themselves on producing the most reliable devices use Airpax custom designed and built transformers and reactors. These include audio units for communication equipment, pulse and high-voltage units for navigation equipment, and power units for control equipment—all to the same high precision.

For protection against adverse environments, as in military equipment, these units are hermetically sealed and conform in all respects to MIL-T-27A. Where light weight is important, they can be protected by encapsulation.

You can rely upon Airpax to maintain high quality in making any quantity of these products that you may need. We do not attempt to produce both a quality grade and a commercial grade; Airpax personnel are trained to maintain quality first. Your engineering design will show to best advantage when built with Airpax components.

Write today for technical data; place your present design and production problems in competent hands at

AIRPAX
DESIGNERS ENGINEERS

MIDDLE RIVER BALTIMORE 20, MD.

Want more information? Use post card on last page.



Radar

Navigation

Timing



Nucleonics

Geophysics

Ordnance

PRECISION DIGITAL DELAY GENERATOR

FOR GENERAL-PURPOSE LABORATORY USE

Generates pulses accurately spaced in time with respect to an internally generated reference pulse—range 0 to 100,000 microseconds

Complete generality permits numerous and varied uses such as radar range calibration, target simulation, generation of secondary frequency standards, elapsed time measurements, phase measurements, etc. Fields of application include Radar, Navigation, Telemetry, Nuclear Studies, Computor Research, Geophysics, Ordnance, and any other fields in which timing is significant.

The ability to generate a specific delay at accurate variable repetition rates sets this instrument apart from any other pulse or delay generator in the field today. Write for full details.

Pulses can be supplied under either one-shot conditions or at variable repetition rates. Both pulse delay and repetition period can be established in increments as small as 1 microsecond.

The repetition period can also be externally triggered, in which case two independently variable delayed pulses are available. Accuracy of both repetition period and pulse delay are held to one part in 10^6 by the thermostatically controlled crystal oscillator. The digital circuitry and the built-in self-checking features make continuous calibration unnecessary.



MODEL 743

Observed pulse as viewed on a suitable synchroscope

KAISER METAL PRODUCTS, INC.
BRISTOL, PA.

Want more information? Use post card on last page.

Raytheon — World's Largest Manufacturer of Magnetrons and Klystrons

Excellence in Electronics

RAYTHEON

RAYTHEON MANUFACTURING COMPANY

Microwave and Power Tube Operations, Section PT-44

Waltham 54, Massachusetts

Raytheon makes: Magnetrons and Klystrons, Backward Wave Oscillators, Traveling Wave Tubes, Storage Tubes, Power Tubes, Receiving Tubes, Transistors

AXEL ELECTRONICS
EXPANSION



and what it means to YOU...

Expanded Building...

With greatly enlarged space in a new convenient location geared to provide top quality products with speedy, efficient service.

Expanded Staff...

Headed by five new top sales and design engineers – each of them a specialist, expertly skilled in progressive design.

Expanded Equipment..

Modern production, laboratory and test equipment – designed to meet the high standards of quality and reliability made famous by Axel Bros.

PRECISION MANUFACTURERS OF

- **Paper & film dielectric capacitors**
- **Precision wire wound resistors**
- **Radio noise filters**
- **Pulse networks**
- **Delay lines**

WRITE US

We will be pleased to send you our regular Engineering Bulletins. Address: "Dept. E"

Quality and Precision Since 1916

Axel BROS., INC. Electronics Division

134-20 JAMAICA AVENUE, RICHMOND HILL 18, NEW YORK • REPUBLIC 9-1700

Want more information? Use post card on last page.

DRIVER-HARRIS

salutes a great engineering achievement

CUTLER-HAMMER

Eutectic Overload Protection

Cutler-Hammer engineers made history with their eutectic alloy type overload relay for electric motor protection. Virtually all leading manufacturers of motor control today offer this type of overload protection. And more than 25 million electric motors in daily use bear witness to the acceptability and dependability of this proven protection.

Driver-Harris salutes this Cutler-Hammer achievement. The Cutler-Hammer Eutectic Overload Relay shows the dependability of certain alloys in practical use. In the Cutler-Hammer Relay, both the eutectic element which must function so precisely and the heater element which causes it to function are alloys. We are proud that Driver-Harris Nichrome is the resistance alloy used in the heater element of millions and millions of these successful overload relays.

It is not surprising that Driver-Harris alloys are selected by so many leaders of American industry. Driver-Harris alloys are the product of manufacturing methods employing the most precise metallurgical checks and quality controls. Nichrome*V and Nichrome* have long been accepted as the standard by which all electrical resistance alloys are measured. And these are only two of the 112 special purpose alloys developed by Driver-Harris since 1899 for electrical heating, resistance, and electronic applications. Do you need a special alloy? Send us your specifications.

*T.M. Reg. U. S. Pat. Off.

Why Eutectic Alloy Overload Relays Stay Accurate

Basic in any overload relay is the need of having a disconnect mechanism respond to dangerous heating of the motor windings. All such relays use heater coils in series with the windings to provide the danger signal within the control unit. In the millions of overload relays using eutectic alloy elements to respond to the increased heating, disconnect occurs when the alloy melts. As this alloy has one definite melting point, the overload relay must always be accurate, regardless of how often or how infrequently it operates.

Sole producers of Nichrome V and Nichrome

Driver-Harris COMPANY HARRISON, NEW JERSEY

BRANCHES: Chicago, Detroit, Cleveland, Louisville, Los Angeles, San Francisco • In Canada: The B. GREENING WIRE COMPANY, Ltd., Hamilton, Ontario

MAKERS OF THE MOST COMPLETE LINE OF ELECTRIC HEATING, RESISTANCE, AND ELECTRONIC ALLOYS IN THE WORLD

WHY engineers vote Lambda Power Supplies FIRST

This year again, in an impartial preference survey, LAMBDA has been the overwhelming first choice of engineers concerned with power supplies. The superior design and construction of LAMBDA equipment have been, of course, important elements in achieving this leadership.

Four new heavy-duty models, 60, 60M, 61 and 61M reflect these desirable qualities. These models, for fixed voltage use but adjustable over ranges indicated, have been engineered primarily for industrial applications. They will stand up under continuous-duty operations at maximum ratings.

LAMBDA'S "600 MA" series now includes twelve models, six voltage ranges to 405V. They are exceptionally suited for television studio and transmitter equipment, tube ageing apparatus, computer installations and multi-channel equipment, among other applications.

Send for complete LAMBDA power supply catalog.



SCHEDULE OF PRICES

Model 60	$259.50	Model 63	$239.50
Model 60M	289.50	Model 63M	269.50
Model 61	249.50	Model 64	244.50
Model 61M	279.50	Model 64M	274.50
Model 62	239.50	Model 65	249.50
Model 62M	269.50	Model 65M	279.50

Available for immediate delivery. Prices F.O.B. factory, College Point 56, N.Y.


Heavy-duty barrier-type terminal board located for convenient rack cabling
Durable baked enamel finishes applied over primer bases
Tubes secured in place by tube clamps
All tubes and controls clearly identified and marked on chassis
Voltage controls easily accessible
Thermal time-delay element used in conjunction with contactor
All tubes readily accessible for replacement
AC input terminals for permanent rack installations
Line cord easily removed. Disassembly of chassis unnecessary
Heavy-duty extra-length industrial cord
Internal failure protection
Lambda vacuum varnish impregnated transformers and chokes are engineered for continuous heavy duty service. They are designed especially for Lambda Power Supplies and manufactured in our own plant.
All capacitors are hermetically sealed and oil-filled

Interior photos of new 405V models show construction for continuous heavy-duty service


"600 MA" series
Stable, low-noise wire-wound voltage reference networks and controls
Every connection and solder joint individually inspected and checked
Vitreous enameled wire-wound power resistors
All components securely mounted
Heavy-duty contactor
All capacitors are hermetically sealed and oil-filled
All parts easily accessible for inspection and servicing
Durable baked enamel finishes applied over primer bases
Heavy gauge chassis and panel construction
Sturdy cable clamp anchors
Nylon jacketed vinyl wire
Harness wiring
Schematic diagram permanently mounted in every unit
External overload protection
Accurate, dependable meters

SPECIFICATIONS FOR "600 MA SERIES"

AC Input:
105-125VAC, 50-60C, 840W (Model 60); 810W (Model 61); 775W (Model 62); 715W (Model 63); 675W (Model 64); 585W (Model 65)

DC Output (regulated)
Voltage and currents:

Models	Voltage range*	Current range**
60 & 60M	345-405VDC	0-600MA
61 & 61M	295-355VDC	0-600MA
62 & 62M	245-305VDC	0-600MA
63 & 63M	195-255VDC	0-600MA
64 & 64M	100-200VDC	0-600MA
65 & 65M	0-100VDC	50-600MA

**Voltage range for any given model is completely covered in four continuously variable bands.*
***Current rating applies over entire voltage range.*

Regulation (line) ..... Better than 0.15% or 0.3V
Regulation (load) ..... Better than 0.25% or 0.3V
Impedance ..... Less than 2 ohms
Ripple and Noise ..... Less than 5 millivolts rms
Polarity ..... Either positive or negative may be grounded

AC Output (unregulated):
6.5VAC at 20A (at 115VAC input). Allows for voltage drop in connecting leads. Isolated and ungrounded.

Ambient Temperature and Duty Cycle:
Continuous duty at full load up to 50°C (122°F) ambient.

Controls, Terminals and Overload Protection:

DC output controls:	Band-switches and screw-driver adjusting vernier-control, rear of chassis
AC and DC switches:	Front panel
External overload protection:	AC and DC fuses, front panel
Internal failure protection:	Fuses, rear of chassis
Input and output terminals:	Barrier terminal block, rear of chassis

Meters:
3½" rectangular voltmeter and milliameter (Models 60M, 61M, 62M, 63M, 64M and 65M only).

Voltage Reference Tube:
A stable 5651 voltage reference tube is used to obtain superior long-time voltage stability.

Time-Delay Relay Circuit:
A 30-second time-delay relay circuit is provided to allow tube heaters to come to proper operating temperatures before high-voltage can be applied.

Physical Data:

Size:	Standard 19" relay-rack mounting 12¼" H x 19" W x 9" D
Weight:	70 lb. net; 110 lb., shipping
Panel Finish:	Black dipple enamel (standard)

LAMBDA Electronics Corp.
THE FIRST NAME IN POWER SUPPLIES
11-11 131 STREET • COLLEGE POINT 56, NEW YORK • INdependence 1-8500

Radio Receptor's NEW money saving rectifier mounting!



"QUI-KLIP" *snap-in type* SELENIUM RECTIFIERS

QUICK MOUNTING! QUICK REMOVAL!

Spring steel clips with safe edges snap into two round, large tolerance holes in chassis (approx 7/16" dia., 3/4" c. to c.). Solderless connectors as shown, when used, simplify servicing

Radio Receptor's unique QUI-KLIP rectifiers will soon make their debut in TV sets produced by one of the country's leading manufacturers, saving them countless dollars in production costs.

QUI-KLIP requires no tools or sockets for mounting. There are no studs to break or threads to strip and the locating tab is now unnecessary. QUI-KLIP provides a positive seat for the rectifier – no rocking. Yet any serviceman can remove the stack quickly by squeezing the QUI-KLIP prongs with his fingers and removing the solderless connectors.

Let us show you how to put the cost saving QUI-KLIP selenium rectifiers to work in *your* production . . . Available in most popular sizes with cells from 1" square to 2" square, for radio, TV and other electronic circuits. For detailed information, write Dept. E-14.



- Speeds assembly time.
- Slashes production costs.
- Simplifies assembly.
- Eliminates stud rejects (No studs or nuts needed.)
- Permits easier replacement in the field.

Really R|R Reliable

Semiconductor Division

RADIO RECEPTOR COMPANY, INC.

In Radio and Electronics Since 1922

SALES OFFICES: 251 WEST 19TH ST., NEW YORK 11, N. Y., WAtkins 4-3633 • Factories in Brooklyn, N. Y.

SELENIUM RECTIFIERS, THERMATRON DIELECTRIC HEATING GENERATORS AND PRESSES, COMMUNICATION, RADAR AND NAVIGATION EQUIPMENT

5 Waldes Truarc rings eliminate parts, speed assembly, in light, compact dictating machine

Edison's "V. P." Voicewriter



Edison engineers built this new dictating instrument for small size, light weight, and rugged performance. Waldes Truarc rings replace old fashioned fasteners, cut production costs; keep unit light, compact, and achieve faster more economical assembly.

Disc Lever Cover Assembly



Two Waldes Truarc E-Rings (Series 5133) replace nut, bolt, washer assembly, eliminate one component and assure precise alignment of parts. Truarc rings facilitate pivoting without binding. Production assembly time is decreased.

Lift Bracket and Fork Assembly



A single, easily assembled Waldes Truarc E-Ring (Series 5133) replaces nut-bolt-washer fastening. Free pivoting is assured, one component eliminated, labor and material costs reduced.

Clutch Plate Assembly

Two Truarc E-Rings eliminate staking operation, prevent damage to spring coil. Simple assembly operation speeds production, eliminates rejects, reduces labor and material costs.

Whatever you make, there's a Waldes Truarc Retaining Ring designed to improve your product... to save you material, machining and labor costs. They're quick and easy to assemble, and they do a better job of holding parts together. Truarc rings are precision engineered and precision made, quality controlled from raw material to finished ring.

36 functionally different types... as many as 97 different sizes within a type... 5 metal specifications and 14 different finishes. Truarc rings are available from 90 stocking points throughout the U. S. A. and Canada.

More than 30 engineering-minded factory representatives and 700 field men are available to you on call. Send us your blueprints today. Let our Truarc engineers help you solve design, assembly and production problems, without obligation.

For precision internal grooving and undercutting... Waldes Truarc Grooving Tool!

WALDES
TRUARC®
RETAINING RINGS

Send for new catalog supplement

Waldes Kohinoor, Inc., 47-16 Austel Place, L. I. C. 1, N. Y.
Please send the new supplement No. 1 which brings Truarc Catalog RR 9-52 up to date.
(Please print)

Name.....
Title.....
Company.....
Business Address.....
City.....*Zone*.....*State*.....

E-018

WALDES TRUARC Retaining Rings, Grooving Tools, Pliers, Applicators and Dispensers are protected by one or more of the following U. S. Patents: 2,382,948; 2,411,426; 2,411,761; 2,416,852; 2,420,921; 2,428,341; 2,439,785; 2,441,846; 2,455,165; 2,483,379; 2,483,380; 2,483,383; 2,487,802; 2,487,803; 2,491,306; 2,491,310; 2,509,081; 2,544,631; 2,546,616; 2,547,263; 2,558,704; 2,574,034; 2,577,319; 2,595,787, and other U. S. Patents pending. Equal patent protection established in foreign countries.



Always tense but never tired

Again CTC comes up with an advancement for more secure, more effective electronic assemblies. It's the new Perma-Torq* constant tensioning device for tuning cores of standard CTC ceramic coil forms.

CTC's Perma-Torq, a compression spring of heat treated beryllium copper, has very high resistance to fatigue and keeps coils tuned as set, under extreme shock and vibration. It allows for immediate readjustment without removal or loosening of any mounting nut or locking spring. But most important of all — Perma-Torq like all CTC components is *quality controlled*.

CTC's *quality-control* means you get consistent top quality components. Each step of production is checked, each component part — even though already certified — is checked again. And finally CTC's finished product is checked. That's why CTC can offer you a guaranteed electronic component — standard or custom — whose performance you can depend upon.

CTC researchers and practical experts are always available to help solve your components problems. For samples, specifications and prices write to Sales Engineering Dept., Cambridge Thermionic Corporation, 437 Concord Ave., Cambridge 38, Mass. On the West Coast contact E. V. Roberts, 5068 West Washington Blvd., Los Angeles 16 or 988 Market St., San Francisco, Cal.



NEW PERMA-TORQ UNITS come completely factory assembled to mounting studs, eliminating the bother of assembling and adjusting separate locking springs. CTC coil forms with Perma-Torq Tensioning Device are designated PLST, PLS5, PLS6 and PLS7, are completely interchangeable with the LST, LS5, LS6 and LS7 series, and are available at no increase in price.

*Patent pending

CTC

CAMBRIDGE THERMIONIC CORPORATION

makers of guaranteed electronic components
custom or standard

Want more information? Use post card on last page.



Highest Frequency Transistor...

Commercially Available Today!

PHILCO S-B-T (Surface Barrier Transistor)

Available now! . . . in quantity . . . Philco Surface Barrier Transistors are opening entirely new fields for design engineers . . . are being incorporated in high frequency units *now in production!* Commercial, industrial and military thinking is swinging over fast . . . to complete transistorization.

Philco has gained a wealth of experience in the practical application of Surface Barrier Transistors. Make the Philco S-B-T a part of your forward looking plans—now.

FEATURES

- **Lowest Power Consumption**
- **Hermetically Sealed Resistance-Welded Metal Case with Leads Sealed in Glass**
- **Long Life and Reliability of Operation**
- **Uniform Characteristics Insured by Controlled Processing and Complete Testing**
- **Extremely Low Collector Cut Off Current for Stable Operation**
- **Extremely Low Output Capacitance for Ease of Neutralization**

For complete technical information on the PHILCO SB Transistor write Dept. E

PHILCO CORPORATION

GOVERNMENT AND INDUSTRIAL DIVISION • PHILADELPHIA 44, PENNSYLVANIA

In Canada: Philco Corporation of Canada Limited, Don Mills, Ontario



UNRETOUCHED OSCILLOGRAMS OF OUTPUT VOLTAGE: 1000va Sola Harmonic-Neutralized Constant Voltage Transformer operating from 110v input and correcting output to 115v with less than 3% harmonic distortion. "Commercial sine wave" is maintained regardless of load capacity served.

±1% static magnetic voltage regulation with less than 3% harmonic distortion

Static magnetic voltage regulation with all its advantages —automatic, continuous operation; instantaneous response; no maintenance; self-protection against short circuits; and input-output circuit isolation — has harmonics in its output voltage. In the case of the Sola Standard CV Regulator, harmonic distortion is held within an average of only 14% at full load. However, even 14% is excessive on some applications.

Sola Harmonic-Neutralized Constant Voltage Transformers have the characteristics of the Standard Sola CV Stabilizer *plus* the added advantage of less than 3% harmonic distortion in the output voltage wave.

Sola sinusoidal output stabilizers are ideal for the most exacting applications. They are widely used to provide stabilized undistorted voltage for instruments, production control components, and communication gear. They are especially suitable for input to a rectifier when close regulation of the dc output is required.

Six standard ratings from 60 to 2,000va are immediately available from your electronic distributor's stock. Custom-built designs with ratings from 30 to 15,000va can be ordered in production quantities. A Sola sales engineer will be happy to discuss your specific requirements.

***TYPICAL HARMONIC ANALYSES, TYPE CVH CONSTANT VOLTAGE TRANSFORMER**

	Input Volts	Output Volts	3rd	5th	7th
Full Load	115	115.0	0.77%	1.20%	0.34%
50% Load	115	116.1	1.00	0.70	0.55
No Load	115	116.2	0.65	0.36	0.60

**On production units, the lowest residual harmonic content may occur anywhere between full load and no load.*



TYPICAL MECHANICAL STRUCTURES: The two stabilizers on the left are stock units, the transformer on the right is a "special" in the 7,500va size range.

SOLA *Constant Voltage* **TRANSFORMERS**

WRITE FOR BULLETIN 7A-CV-200 FOR COMPLETE DATA

CONSTANT VOLTAGE TRANSFORMERS for Regulation of Electronic and Electrical Equipment • **LIGHTING TRANSFORMERS** for All Types of Fluorescent and Mercury Vapor Lamps. • **SOLA ELECTRIC CO., 4633 West 16th Street, Chicago 50, Illinois, Bishop 2-1414** • *BOSTON:* 272 Centre Street, Newton 58, Massachusetts • *NEW YORK 35:* 103 East 125th Street • *LOS ANGELES 26:* 2025 Sunset Boulevard • *PHILADELPHIA:* Commercial Trust Building • *CLEVELAND 15:* 1836 Euclid Avenue • *KANSAS CITY 2, MISSOURI:* 406 West 34th Street • *Representatives in Other Principal Cities*

TUNG-SOL MINIATURE GERMANIUM TRANSISTORS NOW IN PRODUCTION

These new Tung-Sol Transistors, now available in production, meet a wide range of applications where miniaturization of equipment is essential.

The Tung-Sol semiconductor design and development program is characterized by laboratory-control processing and 100% testing—including rigid life, mechanical and electrical tests. It is your assurance of uniformity, long life and reliability *in excess of design specifications.*

High production standards for Tung-Sol Transistors are consistent with the manufacturing policy which safeguards Tung-Sol's *second-to-none* reputation for quality in all its products.

For engineering assistance in adapting Tung-Sol Transistors to your product, write to Commercial Engineering Department.

TUNG-SOL ELECTRIC INC. Newark 4, New Jersey

Sales Offices: Atlanta, Chicago, Columbus, Culver City, Dallas, Denver, Detroit, Newark, Seattle.

CHARACTERISTICS OF TUNG-SOL TRANSISTORS

RATINGS (Abs. Max.)	TS-162	TS-163	TS-164	TS-165	TS-166
Collector Volts	−10	−25	−25	−25	−10
Collector MA	10	10	10	10	10
Dissipation at 25°C (MW)	50	50	50	50	50
Junction Temp. (°C)	85	85	85	85	85
AVERAGE CHARACTERISTICS (Common Base, I_e = 1.0MA, E_c = −6v)					
Cutoff μA (Max.)	15@−10v	25@−25v	25@−25v	25@−25v	15@−10v
Current Gain	.93	.96	.98	.99	.97
Noise Figure	20	20	20	20	15
Frequency Cutoff (MC)	0.5	0.7	0.9	1.1	—
Power Gain (DB)	37	39	41	42	36

The Tung-Sol semiconductor development program also includes a line of high frequency and high power transistors.

Want more information? Use post card on last page.



FIXED COMPOSITION RESISTORS IN FOUR SIZES

All rated at 70C — not 40C

There is an EXTRA MARGIN OF SAFETY in Allen-Bradley molded fixed resistors, because they are rated at 70C ambient temperature . . . not at 40C. These resistors can withstand extremes of temperature, pressure, and humidity without deterioration. They require no impregnation to pass salt-water immersion tests.

Allen-Bradley fixed resistors are available in 4 sizes... Type HB—2 watt; Type GB—1 watt; Type EB—1/2 watt; and Type TR—1/10th watt, in standard RETMA values from 10 ohms to 22 megohms. Their close dimension tolerances are an outstanding advantage when used in automatic assembly lines. The color coding does not chip.

For applications where resistors must not fail, use Allen-Bradley. Of course, they are also "the best" for all uses . . . and they cost no more than ordinary resistors. Send for Allen-Bradley resistor data.

Allen-Bradley Resistors Are Packaged in Cartons and on Reels

Allen-Bradley resistor patented cartons have corrugated strips which hold the resistors in an upright position which prevents bending or tangling of leads.

Allen-Bradley fixed resistors are furnished, as standard, in patented cartons. They can also be supplied in reels for automatic assembling equipment.

The resistors are aligned on a narrow, pressure-sensitive tape and wound on a fiberboard reel with a 9/16-inch mandrel. A lateral pull on the resistor leads detaches the units from the tape.

Reels contain from 1,000 to 2,500 units per reel, depending upon the size of the resistor. If automatic assembling is one of your problems, it may pay you to investigate the reel-packaging of A-B QUALITY resistors.

Allen-Bradley Co., 110 West Greenfield Avenue

In Canada—Allen-Bradley Canada Ltd. Galt, Ont.

Allen-Bradley resistors on fiberboard reel for automatic assembling lines. Reels contain from 1,000 to 2,500 units.

ALLEN-BRADLEY

RADIO, ELECTRONIC AND TELEVISION COMPONENTS

THE SPERRY RAND CORPORATION ANNOUNCES

THE FORMATION OF

Remington Rand Univac

as a new division of the Corporation encompassing all phases of computer research, design and development, engineering, production and sales.

Offices and laboratories are located at . . . . .

● PHILADELPHIA, PA.
Remington Rand Univac
2300 West Allegheny Ave.
(Formerly: Eckert-Mauchly Div.)

● ST. PAUL, MINNESOTA
Remington Rand Univac
1902 West Minnehaha Ave.
(Formerly: Engineering Research Assoc. Div.)

● SO. NORWALK, CONN.
Remington Rand Univac
Wilson Avenue
(Formerly: Laboratory for Advanced Research)

Univac® The FIRST Name in Electronic Computing Systems

We are growing at....





Univac® the FIRST name in complete Electronic Computer Systems, now offers positions presenting personal challenge and outstanding opportunities for professional development to the following:

- Electrical Engineers
- Mechanical Engineers
- Physicists
- Logical Designers
- Mathematicians
- Programmers
- Field Location Engineers
- Production Engineers
- Specification Engineers
- Contract Administration Engineers
- Technical Liaison Engineers
- Product Planning Engineers
- Metallurgists
- Computer Sales Engineers
- Proposal and Quotation Experts and Instrumentation and Component Sales Engineers.

Our Engineers grow with UNIVAC through our policy of regular merit reviews and promotion from within the organization. Excellent salaries, good company benefits, tuition allowances for advanced studies and household moving expenses are yours with UNIVAC.

Send complete resumé to . . . . . .

univac

Where the advancements of tomorrow are being made possible today!



SCIENTIFIC SYSTEMS

UNIVAC SCIENTIFIC 1103 A



Laboratory under Construction at St. Paul, Minn.

Offices of Philadelphia, Pa. Plant

Laboratory for Advanced Research at South Norwalk, Conn.

RESEARCH facilities are constantly being improved and expanded. The finest, most modern equipment is available at all locations of UNIVAC. Achievements in these laboratories have given us world-wide leadership in the computer field.

DEVELOPMENT laboratories are geared to today's rapid advancements in electronics and advanced techniques employing new concepts and new components: magnetic cores, semiconductors, and ferro-electric materials.

Remington Rand Univac

DIVISION OF SPERRY RAND CORPORATION

1902 WEST MINNEHAHA AVENUE, SAINT PAUL W4, MINNESOTA

MR. D. A. BOWDOIN, Dept. JP-2
2300 W. Allegheny Ave.
Philadelphia, Pa.

MR. JAMES WOODBURY, Dept. JS-2
1902 W. Minnehaha Ave.
St. Paul W4, Minn.

MR. FRANK KING, Dept. JN-2
Wilson Avenue
South Norwalk, Conn.

versatile

Multi-channel -- telegraph A1 or telephone A3.

FROM GROUND TO AIR OR POINT TO POINT

STABLE

High stability (.003%) under normal operating conditions.

RUGGED

Components conservatively rated. Completely tropicalized.



Model 446 transmitter operates on 4 crystal-controlled frequencies (plus 2 closely spaced frequencies) in the band 2.5-24.0 Mcs (1.6-2.5 Mcs available). Operates on one frequency at a time; channeling time 2 seconds. Carrier power 350 watts, A1 or A3. Stability .003%. Operates in ambient –35° to 45°C. Nominal 220 volt, 50/60 cycle supply. Conservatively rated, sturdily constructed. Complete technical data on request.

Here's the ideal general-purpose high-frequency transmitter! Model 446... 4-channel, 6-frequency, medium power, high stability. Suitable for point-to-point or ground-to-air communication. Can be remotely located from operating position. Co-axial fitting to accept frequency shift signals.

Now! Complete-package, lightweight airborne communications equipment by Aer-O-Com! Write us today for details!

AER -O- COM

3090 DOUGLAS ROAD MIAMI 33, FLA.

ANOTHER FIRST BY

FOR

APPROVED AND IN USE BY MAJOR ELECTRONIC MANUFACTURERS

A RESULT OF OVER 5 YEARS OF RESEARCH AT

ALPHA

PRINTED CIRCUIT or GENERAL DIP SOLDERING OPERATION

CLEANS and WETS ALL SURFACES INSTANTLY

RETAINS ACTIVITY THROUGH FULL SOLDER DIP TEMPERATURE CYCLE

EXCELLENT CAPILLARY ACTION FOR 2 SIDED BOARDS

NON BRIDGING, NON TEARING

TAKES TO ALL DIFFICULT-TO-SOLDER METALS WHERE ROSIN FLUXES ARE USED

CAN BE SPRAYED, DIPPED OR BRUSH APPLIED

ALPHA
ANOTHER
ALPHA
PRODUCT
SOLDERING
FLUX
LABORATORY
SPECIALISTS IN SOLDER FOR OVER FIFTY YEARS
CONTROLLED
346
LIQUID ROSIN FLUX
Solids Content 50%
Density .928 g/ml
A modified rosin base flux for use on copper, brass, bronze, zinc, cadmium plate, tin plate, silver plate, nickel plate, and zinc plate. Residue non-corrosive and non-conductive when completely heated. KEEP CLOSED when not in use.
Can be diluted as desired with Alpha 446 THINNER for spray application.
PASSED J W
LOT NUMBER 76312
MFD. BY ALPHA METALS, INC., JERSEY CITY 4, N. J.

ORDER A SAMPLE GALLON TODAY

AT SPECIAL AD PRICE

$6.50 A GALLON

(prices on larger quantities available on request)

PACKED 4 GALLONS PER CASE

AVAILABLE IN 5 GALLON CANS 55 GALLON DRUMS

ALPHA METALS, INC.

59 Water Street
Jersey City, N. J.

POLARAD
PROVEN RELIABILITY



DIRECT READING SPECTRUM ANALYZER

UNI-DIAL CONTROL

Years of day-in, day-out field operation by most exacting users, have proven the Polarad Model TSA Spectrum Analyzer to be a versatile test instrument of highest reliability and accuracy for both laboratory and production applications.

It is a broadband instrument with greatest pulse sensitivity over the band—10 to 44,000 mc. And each of its five interchangeable RF tuning heads operate with utmost simplicity and frequency stability. All tuning is by Uni-Dial control. Frequencies are read with 1% accuracy right on the linear dial as the set is tuned. No mode charts or interpolations necessary.

The Polarad Model TSA has been designed to save engineering manhours. Its 5 inch CRT display of the RF spectrum is bright and easily defined. And its 1 cycle sweep speed makes for fine resolution. For detailed specifications, contact your nearest Polarad Representative, or write directly to the factory.

APPLICATIONS

- Transmitter characteristics tests
- Broadband receiver for AM, FM, CW, MCW, and pulse modulated signals
- Component tests
- Frequency measurements
- Leakage, interference and radiation measurements
- Bandwidth measurements
- Modulation tests
- Adjacent signal channel tests
- Attenuation measurements
- Filter measurements
- Standing wave measurements

MULTI-PULSE SPECTRUM SELECTOR



MODEL SD-1

Increases the versatility of Polarad Spectrum Analyzers. It displays and allows selection for analysis of a specific train of microwave pulses, as well as any one pulse in the train; selects and gates a group of pulses up to 180 μsec. in length; and is designed to work with fast, narrow pulses; can be adjusted to gate any pulse including the first at zero time. Special circuitry discriminates automatically once pulses have been selected. Operates at any of the frequencies accepted by Polarad Spectrum Analyzers.

FEATURES:

Continuously variable sweep width; 15 to 180 μsec. • Continuously variable gate widths for pulse selection; 0.4 to 10 μsec. • Continuously variable gate delays for pulse selection; .3 to 180 μsec. • Automatic gating of spectrum analyzer during time of pulse consideration. • Intensified gate (brightening) to facilitate manual pulse selection. • Triggered sweep on first pulse in any train. • No sweep in absence of signal.

SPECIFICATIONS:

Maximum Pulse Train Time 180 μsec. • Pulse Rise Time .05 μsec. Minimum • Minimum Pulse Separation .2 μsec. • Repetition Rate 10–10,000 pps. • Minimum Pulse Width .1 μsec. • Input Power 95 to 130 volts, 50/60 cps., 325 watts. • Input Impedance 50 ohms. • Output Impedance 50 ohms (to match TSA Spectrum Analyzer).

BROADBAND SPECTRUM ANALYZER

FEATURES

- Greatest signal sensitivity over entire frequency band.
- Single frequency control with direct-reading dial accurate to ±1%.
- Complete frequency coverage from 10 mc to 44,000 mc.
- Internal RF attenuator (RF Tuning Unit Models STU-1, STU-2A, STU-3A).
- Adjustable frequency display from 400 kc to 25 mc.
- Frequency differences as small as 40 kc measurable by means of adjustable frequency marker with variable amplitude.
- 25-kc resolution for all bands.
- Stable klystron oscillators using non-contacting plungers to insure longer life.
- No klystron modes to set.
- 5-inch CRT display.
- Portable and completely self-contained.



SPECIFICATIONS

Model No.	Equipment
Model Du.....	Spectrum Display and Power Unit
Model STU-1...	RF Tunning Unit 10-1,000 mc.
Model STU-2A.	RF Tuning Unit 910-4, 560 mc.
Model STU-3A.	RF Tuning Unit 4,370-22,000 mc.
Model STU-4	RF Tuning Unit 21,000-33,000 mc.
Model STU-5...	RF Tuning Unit 33,000-44,000 mc.

SPECIFICATIONS:

Frequency Range: 10 mc to 44,000 mc.

Frequency Accuracy: ±1%

Resolution: 25 kc.

Frequency Dispersion: Electronically controlled, continually adjustable from 400 kc to 25 mc per one screen diameter (horizontal expansion to 20 kc per inch)

Input Impedance: 50 ohms—nominal

Sensitivity:*

STU-1 10-400 mcs—89 dbm
400-1000 mcs—84dbm

STU-2A 910-2,200 mcs—87 dbm
1,980-4,560 mcs—77 dbm

STU-3A 4,370-10,920 mcs—75 dbm
8,900-22,000 mcs—80 dbm

STU-4 21,000-33,000 mcs—55 dbm

STU-5 33,000-44,000 mcs—45 dbm

Overall Gain: 120 db

Attenuation:
**RF internal 100 db continuously variable, IF 60 db continuously variable

Input Power: 400 Watts

*Minimum Discernible Signal

**STU-1, STU-2A, STU-3A

AVAILABLE ON EQUIPMENT LEASE PLAN

FIELD MAINTENANCE SERVICE AVAILABLE THROUGHOUT THE COUNTRY

Consult us on your Spectrum Analysis Problems

Write for your copy of the Polarad "Handbook of Spectrum Analyzer Techniques". 50c per copy. Includes discussion of Spectrum Analyzer operation, applications and formulae for analysis techniques.

POLARAD PROVEN RELIABILITY **ELECTRONICS CORPORATION** 43-20 34th STREET, LONG ISLAND CITY 1, N. Y.

REPRESENTATIVES • Albuquerque • Atlanta • Baltimore • Boston • Buffalo • Chicago • Dayton • Englewood • Fort Worth • Los Angeles • New York Philadelphia • San Francisco • Syracuse • Washington, D. C. • Westbury • Winston-Salem • Canada, Arnprior, Toronto—Export: Rocke International Corporation

THE MOST COMPLETE LINE OF FREQUENCY METERS!

Shown here are 12 of the 31 Precision Direct Reading Frequency Meters made by PRD.

Also Available . . .

- ✔ Calibrated Precision Frequency Meters
- ✔ Drum Dial Direct Reading Frequency Meters
- ✔ Frequency Standard Multiplier
- ✔ Custom Designs

PRD offers 44 different models. Coverage from 400 to 40,000 mc/s. Request 1955 catalog.

Polytechnic RESEARCH & DEVELOPMENT CO., INC.

202 TILLARY STREET
BROOKLYN 1, N. Y.
Telephone:
ULster 2-6800

Midwest Sales Office:
1 SOUTH NORTHWEST HIGHWAY, PARK RIDGE, ILLINOIS — TAlcot 3-3174
Western Sales Office:
7411½ NORTH SEWARD STREET, HOLLYWOOD 38, CAL. — HOllywood 5-5287



here's what's behind the crystal that's so far ahead

The Midland Factory shown above is the world's largest plant devoted exclusively to producing crystals for frequency control. It is equipped with the finest and most complete production and testing machinery ever developed for this purpose. Here Midland pioneered development of crystals for color television, and is now ready for full-scale production.

All this is important to you for just one good reason: Every Midland crystal you use has been produced by such advanced techniques and under such rigid quality controls that you can be sure it will prove its completely reliable quality under every operating stress.

Midland Critical Quality Control extends through every step of crystal production, and includes precise angular control by X-ray. Uniform accuracy is maintained to the millionth part of an inch.

Whatever your Crystal need, conventional or highly specialized,
When it has to be exactly right, contact

Midland MANUFACTURING COMPANY, INC.
3155 Fiberglas Road Kansas City, Kansas

WORLD'S LARGEST PRODUCER OF QUARTZ CRYSTALS

MALLORY



These contacts look alike, but one of them . . . made from a more readily fabricated alloy recommended by Mallory . . . costs 32% less!

Mallory Engineered Materials Selection Can Cut Your Contact Costs

Mallory Contact Engineering Offers Five Ways To Improve Economy

1. **The most effective contact material** from the extensive line developed by Mallory. More economical alloys often can satisfy *actual* service conditions.
2. **The most economical contact design** . . . for your purchasing, production and product needs.
3. **The most economical backing material** . . . from a group of Mallory alloys developed for this use.
4. **The most economical backing member design** . . . in relation to contact and product design requirements.
5. **The most economical method of assembly** of contact and backing member.

By coordinating *all* these important elements of contact design, Mallory can help you put into effect a long-range plan for cutting contact cost and assuring peak performance.

CHOOSING the contact material that exactly matches your product requirements can often reduce over-all contact costs. For example, designers of a circuit breaker selected one of the Mallory Elkonite® materials for the contacts. This is a superior material for heavy-duty service, with high resistance to sticking and arc erosion.

Mallory engineers examined the product requirements . . . and recommended a change in materials. They found another ELKONITE, a higher silver content material, would give excellent performance on this medium-duty application. And because this material involved fewer manufacturing operations, the contacts could be made at lower cost. The customer's savings amounted to $10.16 per thousand . . . a total of over $8,000!

Mallory engineers are especially well qualified to help you get the best economy and performance in your contacts. They have a uniquely broad range of Mallory contact alloys from which to choose. And their extensive application experience is valuable in coordinating *all* phases of contact, backing member and assembly design to assure you of top value for your contact dollar. Write or call Mallory for a consultation on your particular application.

Expect more . . . get more from

P. R. MALLORY & CO. Inc.
MALLORY
P. R. MALLORY & CO., Inc., INDIANAPOLIS 6, INDIANA

Serving Industry with These Products:

Electromechanical—Resistors • Switches • Television Tuners • Vibrators
Electrochemical — Capacitors • Rectifiers • Mercury Batteries
Metallurgical—Contacts • Special Metals and Ceramics • Welding Materials

REVERSIBLE SILICON MIXER DIODES

by Bomac



1N415 - 1N416 SERIES

Here's another step forward by Bomac — a *reversible* silicon mixer diode. The 1N415 and 1N416 series are the first silicon diodes to have selective polarity.

Polarity is indicated by the letters REV located at one end of the diode. To change the polarity, just switch the position of the end cap.

With the end cap attached to the contact pin at the unmarked end of the cartridge, the diode will be of normal polarity. With the end cap attached to the end marked REV, the diode will be of reverse polarity. The complete assembly, with either polarity, is electrically the same as its equivalent type of regular silicon diodes.

The Bomac 1N415 and 1N416 series will meet all conditions of JAN 1A specifications.

UNIQUE PACKAGE PROTECTION

For complete protection during shipment and storage Bomac has designed a reusable RF Protective Package* which conforms with MIL-E1B specification. Diodes stored in this package are completely protected no matter how many times they are handled after the original seal is broken.

*PAT. APPLIED FOR

Band	Type	Equivalent Type	Frequency (Mc)	Max. Conversion Loss (db)	Noise Ratio (Times)	Max. (VSWR)	IF Imped. (OHMS)	Burnout (erg)
X	1N415B	1N23B	9375	6.5	2.7	—	—	1.0
		1N23BR	9375	6.5	2.7	—	—	1.0
X	1N415C	1N23C	9375	6.0	2.0	1.50	325-475	1.0
		1N23CR	9375	6.0	2.0	1.50	325-475	1.0
X	1N415D	1N23D	9375	5.0	1.7	1.30	350-450	1.0
		1N23DR	9375	5.0	1.7	1.30	350-450	1.0
S	1N416B	1N21B	3060	6.5	2.0	—	—	2.0
		1N21BR	3060	6.5	2.0	—	—	2.0
S	1N416C	1N21C	3060	5.5	1.5	—	—	2.0
		1N21CR	3060	5.5	1.5	—	—	2.0

We invite your inquiries regarding
- ENGINEERING
- DEVELOPMENT
- PRODUCTION

Bomac Laboratories, Inc.
BEVERLY, MASSACHUSETTS

GAS SWITCHING TUBES, TR, ATR and Pre-TR · DUAL TR and ATR TUBES · SILICON DIODES · WAVEGUIDE SWITCHES
REFERENCE CAVITIES · MAGNETRONS · PRESSURIZING WINDOWS · SHUTTER TUBES · HYDROGEN THYRATRONS
REFLEX KLYSTRONS · TRAVELING WAVE AMPLIFIER TUBES · SYSTEMS

Catalog on request. Write (on your company letterhead) Dept. E-1 BOMAC Laboratories, Inc. Beverly, Mass., or phone Beverly 6000.

for
HEARING
AIDS

or
RECORDING
HEADS

or *ANY* MAGNETIC MATERIALS JOB . . .

Write for your Copy
"MAGNETIC MATERIALS"

This 32-page book contains valuable data on all Allegheny Ludlum magnetic materials, silicon steels and special electrical alloys. Illustrated in full color, includes essential information on properties, characteristics, applications, etc. Your copy gladly sent free.

ADDRESS DEPT. E-73

You can *rely* on core materials like the Allegheny 4750 components illustrated above, in your receivers, recording heads or microphone assemblies.

In fact, whether your equipment is small or large, the extra-broad line of A-L magnetic materials will solve your magnetic core problems. It includes all grades of silicon steel sheets or coil strip, as well as Allegheny Silectron (grain-oriented silicon steel), and a wide selection of high-permeability alloys such as 4750, Mumetal, Permendur, etc.

Our service on these materials also includes complete facilities for the fabrication and heat treatment of laminations. (For users of electrical sheets and strip, our lamination know-how is a real bonus value!) Either way, we'll welcome the chance to serve you. *Allegheny Ludlum Steel Corporation, Oliver Building, Pittsburgh 22, Pa.*

STEELMAKERS to the Electrical Industry

Allegheny Ludlum

WAD 5335

AL
STEELS FOR THE ELECTRONIC AGE

Want more information? Use post card on last page.

UNITED ELECTRONICS

PRESENTS

Three NEW Miniaturized

HIGH VOLTAGE, HIGH VACUUM

External Anode Thermionic Rectifiers

TYPES: 552, 554, 589



actual size

These new United tubes will provide immediate answers to many complex design problems of modern electronic instrumentation.

Among the advanced design features, the flanged construction of the external Kovar anode provides for a rugged glass-metal seal which minimizes high thermic rise and electron deterioration of the glass seal region.

The use of specialized techniques in cathode processing in types 554 and 589, and the exclusive UNITED *bonded thoria tungsten core filament* in type 552, contribute to high emitter efficiency.

Far-sighted practical UNITED designing establishes new milestones by building into these tubes qualities which meet supremely well not one but all *five* vital requirements: good service life expectancy, ruggedness, small size, light weight, ease of installation. Also—moderate cost. Orders filled rapidly.

For Oil or Air Cooled Operation

TUBE TYPE	CATHODE			MAX. TOTAL LENGTH WITH LEADS	MAXIMUM DIMENSIONS			IMPACT RATING G	ANODE RATINGS							
	DESCRIPTION	SUPPLY			LENGTH EXCLUDING LEADS	DIAMETER AT ANODE SEAL	ANODE CONTACT DIAMETER		AS RECTIFIER			AS CLIPPER DIODE			ENVIRONMENT
		VOLTS	AMPS						eps ea hv	Ib av Δ	Ib av mAdc	eps ea hv	Ib av Δ	Ib av mAdc	
552	FILAMENTARY	2.5	1.67	3.04	1.375	.875	.553	200	20	040	10				AIR
									20	040	10				OIL
554	UNIPOTENTIAL OXIDE-COATED	6.3	3.5	3.91	2.25	1.200	0.88	200	17	225	70	16	12	20	AIR
									17	470	150	16	12	60	OIL
589	UNIPOTENTIAL OXIDE-COATED	6.3	1.55	3.50	1.94	.875	.590	200	10	180	45				AIR
									16	125	30	10	6	10	AIR
									10	400	100	10	6	20	OIL
									16	250	65				OIL

UNITED ELECTRONICS, 42 Spring Street, Newark 4, N. J.

Want more information? Use post card on last page.



Hughes-equipped T-29 "flying laboratory" for systems evaluation.

Flight evaluation of advanced interceptor electronic system uses unique approach.

T-29 "INTERCEPTOR"

THE DEVELOPMENT OF AIRBORNE ELECTRONIC SYSTEMS REQUIRES THOROUGH FLIGHT EVALUATION OF BREADBOARD AND PROTOTYPE EQUIPMENT PRIOR TO FINAL DESIGN. AT HUGHES, SYSTEMS FOR INTERCEPTORS ARE FIRST TESTED IN "FLYING LABORATORIES" IN WHICH THE EQUIPMENT IS READILY ACCESSIBLE TO SYSTEMS TEST ENGINEERS.

One interesting problem recently confronting Hughes engineers was that of evaluating the requirements imposed upon the pilot of a high-speed one-man interceptor. This arose in the development of a new integrated electronic system to control several phases of an all-weather interceptor's flight. Because of the great importance of providing the pilot with the optimum design and arrangement of displays and controls, it became necessary to determine accurately the pilot's work load during flight, and the human factors that affect his ability to carry out his task.

The solution was to install a complete mock-up of the actual interceptor cockpit in a large T-29 aircraft in which a breadboard model of the system was being tested. From this cockpit a test pilot can simultaneously operate the electronic system and fly the T-29, performing all the functions of an interceptor pilot. Systems test engineers and psychologists analyze his problems and his performance, and adapt the cockpit design to the natural abilities of the human pilot. The result will be a much better "fit" of pilot and electronic system prior to final flight testing in the tactical interceptor.



Convair F-102 all-weather interceptor, Hughes-equipped.

SYSTEMS ENGINEERS

Required are engineers with a basic interest in the system concept, who have the ability to develop new evaluation techniques and conduct highly controlled tests. They should be able to resolve complex circuitry problems, and have sufficient resourcefulness and follow-through to carry a difficult program to its ultimate goal.

Scientific Staff Relations

HUGHES

RESEARCH AND DEVELOPMENT LABORATORIES

Culver City, Los Angeles County, California

HUGHES

SILICON JUNCTION

DIODES



Dimensions are maximum for standard Hughes Silicon Junction Diodes.



*High Temperature Operation**

Extremely High Back Resistance

Exceptionally Stable Characteristics

FEATURES—High temperature operation...*extremely* high back resistance . . . very sharp back voltage breakdown . . . one-piece, fusion-sealed glass body . . . axial leads for easy mounting . . . subminiature size . . . exceptionally stable characteristics.

TESTED—All Hughes Silicon Junction Diodes are subjected to rigorous testing procedures. Specific electrical characteristics are measured and, when specified, special tests are also performed.

CONSTRUCTION—Hughes Silicon Junction Diodes are packaged in the famous fusion-sealed glass body, developed at Hughes. This construction is impervious to moisture penetration—*ensures* electrical and mechanical stability, and freedom from contamination.

When high temperatures or high back resistance requirements call for silicon, be sure to specify *Hughes* Silicon Junction Diodes. They are first of all—for RELIABILITY!

Diode glass body is coated with opaque black enamel, color-coded on cathode end. Available now in nine types: HD6001, HD6002, HD6003, HD6005, HD6006, HD6007, HD6008, HD6009, HD6011. Ask for descriptive Bulletin SP-4.

**Characteristics rated at 25°C and at 150°C. Ambient operating range, −80°C to +200°C.*



Actual Size

HUGHES PRODUCTS DIVISION

Aircraft Company, Los Angeles 45, Calif.

New York Chicago Los Angeles

Are *You* Looking Ahead?



Wouldn't you rather have an oscilloscope that isn't limited to your present requirements? One that can be quickly converted to the many applications you'll face in the future? The Tektronix Type 531 is that kind of instrument... versatility and top performance with a single plug-in unit— five other plug-in units available in reserve for future requirements. Ask your Tektronix Field Engineer or Representative for complete specifications, or write for descriptive booklet.

VERTICAL-AMPLIFIER CHARACTERISTICS. With the Type 53B Plug-in Preamplifier the Type 531 offers accurately calibrated sensitivity to 0.05 v/cm from dc to 10 mc, 0.035-μsec risetime... to 0.005 v/cm from 5 cycles to 9 mc, 0.04-μsec risetime. Full 6 cm linear vertical deflection.

SWEEP CHARACTERISTICS. Miller-runup circuitry generates linear sweeps in the extremely wide range of 0.02 μsec/cm to 12 sec/cm (600,000,000-to-1 ratio), with 24 accurately calibrated sweeps from 0.1 μsec/cm to 5 sec/cm. 5x magnifier is accurate on all ranges.

TRIGGERING FACILITIES. The Type 531 offers amplitude-level selection, automatic triggering, high-frequency sync in addition to all standard triggering modes.

WRITING CHARACTERISTICS. New Tektronix precision metallized crt with 10-kv accelerating potential provides high brightness, improved focus, and excellent linearity. (Recorded writing rate exceeds 175 cm/μsec).

VERSATILITY. Quick change plug-in preamplifiers and inherent oscilloscope capabilities combine to convert the Type 531 to applications normally requiring separate highly-specialized instruments. Available plug-in units provide for dual-trace... low level differential... wide-band differential... and micro-sensitive applications in addition to wide-band high-gain applications. Current development work promises greatly-extended capabilities through new designs in plug-in units.

Type 531 Oscilloscope—**$995**

Type 53B Plug-in Unit—**$125**

Prices f.o.b. Portland (Beaverton), Oregon



Tektronix, Inc.

P. O. BOX 831, PORTLAND 7, OREGON

CYpress 2-2611 • Cable: TEKTRONIX

DU PONT

Better Things for Better Living ... through Chemistry

ELECTRONIC DESIGN NEWS

PROPERTY AND APPLICATION DATA ON THESE VERSATILE ENGINEERING MATERIALS: "ZYTEL," "ALATHON," "TEFLON," "LUCITE."

Fastenings of ZYTEL® won't shake loose



Fastenings made of "Zytel" nylon resin are available in many types and sizes. An example is the "Nylo-Fast" fastenings shown above. These precision-machined bolts are lightweight and durable. The resiliency of "Zytel" permits interference fit which prevents loosening under vibrational conditions. The electrical insulating properties of "Zytel" are good. Temperatures as high as 250°F. will not affect the "Nylo-Fast" parts of "Zytel." Where color coding is desirable, various colors are available. (Manufactured and stocked by Anti-Corrosive Metal Products Company, Inc., Castleton-on-Hudson, New York, from rod stock supplied by The Polymer Corporation of Reading, Pa.)

Laminations of TEFLON® for printed circuit bases

Typical uses for laminations of glass cloth and Du Pont "Teflon" tetrafluoroethylene resin include: conductor and ground insulation, hookup wire, power cable, printed circuit bases and structural parts. The laminations combine the dielectric properties, chemical inertness and heat resistance of "Teflon" with the tensile strength, resistance to cut-through, and resistance to creep, of woven glass fiber.

An informative free bulletin describing the preparation and uses of laminations and impregnations of glass cloth employing "Teflon" tetrafluoroethylene resin is now available. Specify Bulletin X-64.



Coil forms of "Zytel" for the General Electric AK-4 and AK-5 hook-on volt-ammeters are shown above. The high dielectric strength and easy moldability of this material make it suited for such applications. Photo below shows relative size of easily held volt-ammeter.

Light, molded coil forms of ZYTEL® simplify ammeter design problem

Compact designs, such as the coil form for this G.E. hook-on volt-ammeter, are possible when using "Zytel" nylon resin. This is because "Zytel" can be molded into complex shapes . . . retains its strength even in thin sections. Another important advantage of Du Pont "Zytel" is that it can be injection-molded at low cost per part.

In electronic applications of all kinds, "Zytel" offers many design advantages. Whether it is used for molded components or jacketing for wire and cable, its mechanical strength and heat resistance, coupled with its superior insulating characteristics, give outstanding results. A thin jacketing of "Zytel" nylon resin on electrical wire provides good insulation and abrasion resistance.

You can get all the details on "Zytel" by mailing the coupon below.

NEED MORE INFORMATION?

CLIP THE COUPON for additional data on the properties and applications of these Du Pont engineering materials.

**"Teflon," "Alathon," "Zytel" and "Lucite" are registered trade-marks of E. I. du Pont de Nemours & Co. (Inc.).*

E. I. du Pont de Nemours & Co. (Inc.), Polychemicals Department
Room 221, Du Pont Building, Wilmington 98, Delaware
In Canada: Du Pont Company of Canada Limited,
P. O. Box 660, Montreal, Quebec

Please send me more information on the Du Pont engineering materials checked: ☐ "Teflon"* tetrafluoroethylene resin; ☐ "Alathon"* polyethylene resin; ☐ "Zytel"* nylon resin; ☐ "Lucite"* acrylic resin
I am interested in evaluating these materials for_____

NAME_____

COMPANY_____ POSITION_____

STREET_____

CITY_____ STATE_____

TYPE OF BUSINESS_____

built to do just one servo control job . . .

perfectly



An incremental synchro positioner before wiring to header and hermetic sealing. The synchro rotor is stepped in one or fifteen degree increments clockwise or counterclockwise depending upon which of four coils is momentarily energized by a d-c pulse. The synchro can be rotated any number of degrees or revolutions. The cylindrical member resets the synchro to electrical zero if a pulse is applied to the "reset" circuit.

Like all Transicoil servo assemblies, this incremental positioner "does the job right" because it was designed for a single application . . . by a company whose major function is to provide complete servo assemblies precisely engineered and manufactured to solve individual servo control problems.

Of course, if you merely want servo *components*, you'll find Transicoil's control motors, motor-gear train combinations, motor-gear train-generator combinations, and servo amplifiers built to the highest order of precision and accuracy. But it is in the "package" engineering of unique assemblies that Transicoil's experience and creative imagination offer the greatest value. And in most cases, these assemblies cost no more than the individual components would purchased separately.

That's why it pays to check your servo problems out with Transicoil first. Write outlining your problem, and ask for Transicoil's new gear-motor bulletin. You'll find it a mighty handy availability guide in designing for tight production schedules.

Transicoil

CORPORATION

Worcester • Montgomery County • Pennsylvania

Want more information? Use post card on last page.

ALSIMAG®
HIGH TEMPERATURE HERMETIC TERMINALS
INDIVIDUALLY LEAK TESTED



AlSiMag
No. Y-35255

AlSiMag
Y-35254

AlSiMag
Y-35253

AlSiMag
Y-35252

AlSiMag
Y-35251

AlSiMag
Y-33755

AlSiMag
Y-31490

STRONGER!
Alumina ceramics with higher tensile and impact strengths. Permanent bonding. New glaze with superior surface resistivity. Rugged. Greater resistance to wear, chipping and breakage. Exceed MIL-T-27A torque requirements.

HIGHER TEMPERATURES!
New, superior metalizing techniques. Pace-setting AlSiMag Alumina ceramics. Greatly extended operating temperature range. Readily attached with hard solder. Permit designing to higher temperatures.

GREATER THERMAL SHOCK RESISTANCE:
Retain their excellent electrical and mechanical characteristics and deliver outstanding performance throughout their wider operating temperature range.



CUSTOM ITEMS
in High Temperature Alumina Ceramics with High Temperature Metalizing also available, produced by the same highly skilled techniques. For special applications, a wide choice is offered in metals and ceramics in appropriate design configurations. Metalized parts for low temperature applications can also be supplied. Send blueprint or sketch for complete details.

WRITE FOR FREE BULLETIN FULLY DESCRIBING STANDARD PARTS SHOWN ABOVE

AMERICAN LAVA CORPORATION

54TH YEAR OF CERAMIC LEADERSHIP

CHATTANOOGA 5, TENNESSEE
A Subsidiary of
Minnesota Mining and Manufacturing Company

Branch offices in these cities (see your local telephone directory): Cambridge, Mass. • Chicago, Ill. • Cleveland, Ohio • Dallas-Houston, Texas • Indianapolis, Ind. • Los Angeles, Calif. • Newark, N. J. • Philadelphia, Pa. • St. Louis, Mo. • South San Francisco, Calif. • Syracuse, N. Y. • Tulsa, Okla. **Canada:** Irvington Varnish & Insulator Div., Minnesota Mining & Mfg. of Canada, Ltd., P. O. Box 757, London, Ontario. **All other export:** Minnesota Mining & Mfg. Co., International Division, 99 Park Ave., New York, N. Y.



What carries the current in the wireless chandelier of New York City's Barbizon-Plaza Hotel? The fixture is constructed of gleaming Inco Nickel tubing in an intricate pattern — and the tubing carries the current! Nickel tubing is light and rigid, too — so the chandelier can be slowly rotated from above. The chandelier was designed by Richard Kelly and fabricated by Edison Price – both of New York City.

A chandelier without wires!

. . . *and three other unique designs in* Inco Nickel Alloy *tubing*

There's a similarity in all four tubing applications here.

In each, a needed *combination* of useful properties is provided by Inco Nickel or an Inco Nickel Alloy. For example, in the chandelier above: electrical conductivity *plus* rigidity and light weight. Or in the radar antenna lens at the right: electrical properties *plus* strength and corrosion resistance *plus* brazing facility.

Perhaps *your* design requires a hard-to-find combination of electrical properties with others such as thermal conductivity, non-magnetic properties, resistance to corrosion, or to vibration, shock, and fatigue. With these alloys you also get the advantages of fabricability, high strength-to-weight ratio, hardness, rigidity, or other properties.

So for help in selecting the alloy that fits your needs, call on Inco's Technical Service Section.

And, remember, you can get Inco Nickel Alloy tubing in all useful sizes from your distributor — or from redrawers who supply it as fine as 0.012″ O.D.

The International Nickel Company, Inc.
67 Wall Street New York 5, N. Y.

INCO TRADE MARK **Nickel Alloys**



Radar antenna lens uses square seamless tubing of Monel* nickel-copper alloy. Superior Tube Company, Norristown, Pa., recommended Monel to I-T-E Circuit Breaker Company, of Philadelphia, for strength, corrosion resistance, electrical properties, and brazing facility. *Registered Trademark

Aircraft fire detector's 0.065-in. diameter Inconel tube encloses two Inconel wires. A special ceramic between them becomes conductive when heated — closes the circuit. The box flashes a warning. Walter Kidde & Company, Inc., Belleville, N. J., uses Inconel nickel-chromium alloy because it withstands temperatures up to 2000°F., resists vibration and shock.



Nuclear reactors' temperatures measured—Inconel* nickel-chromium alloy tube, almost as thin as a hypodermic needle, is both thermocouple unit and thermocouple protection tube. The Inconel tube resists oxidation, which might set up a heat barrier and interfere with accuracy of the reading. Photo courtesy of Argonne National Laboratory, Lemont, Ill.



Servo trouble shooting

with the Solartron Transfer Function Analyser

- Tests AC, DC or carrier servos
- Plots high accuracy Nyquist diagrams
- Covers 0.1 c/s to 1,000 c/s
- Independent of harmonics, noise & spurious frequencies
- Answers G.M., fire-control, simulator, computor, vibration, magamp and all servo problems

Instability, backlash, underdamped response—all these problems can be identified, measured and rectified with the aid of the Solartron T.F.A. Now adopted as the standard British test equipment for all Guided Missile development and testing. It has recently been hailed in the U.S.A. as the world's foremost servo test equipment.

Other Servo Testing Equipment available

T.F.R. CONSOLE	CARRIER CONVERTOR JX 541
SERVO TEST SET JX 563	MECHANICAL REFERENCE GENERATOR

THE SOLARTRON ELECTRONIC GROUP LTD.

Cables: Solartron, Thames Ditton. THAMES DITTON, SURREY, ENGLAND. Telephone: EMBerbrook 5522.

Want more information? Use post card on last page.

Still "On Tap" after 1,000,000 OPERATING CYCLES!

That's why the SYSTEM ANALYZER CORP. Chose Tech Laboratories Tap Switches for $200,000 Electronic "Brain"

With more than 2100 tap switches incorporated in the design for their huge analog computer, engineers at the System Analyzer Corp., Nokomis, Illinois, made exhaustive tests to check the efficiency and operating life of many types. Of all those tested, Tech Laboratories Type 2C and 2A Tap Switches were the **only** ones that met every requirement. After 1,000,000 complete cycles of operation, they showed approximately the same contact resistance as at the beginning.

Designed primarily for analyzing electrical power networks — as large as the power system of an entire city — the electronic "brain" handles mathematical problems with as many at 220 unknowns, 400 times faster than the work can be done manually. It is easy to understand why dependability is a major factor in the selection of its components.

WRITE FOR FULL INFORMATION

TYPE 2C TAP SWITCH SPECIFICATIONS

Contact resistance: 3-4 milliohms
Contact material: Silver plated brass
Contact design: Laminated wiper arm, self-cleaning, shorting or non-shorting
No. of contacts: 2 to 24 single pole, 2 to 11 double pole, 2 to 7 triple pole, 2 to 5 four pole; shorting or non-shorting
Spacing: 15° or 20° shorting or non-shorting
No. of poles per deck: 1 to 4
No. of decks: According to requirements
Current carrying cap.: 3 amp.
Max. operating voltage: 120 V., a.c.
Mounting: Single hole, ⅜"-32 bushing
Size: 1¾" dia.
Detent: Ball and spring
Weight: Approx. 1 oz. per deck

TECH LABORATORIES, INC.

Manufacturers of
Precision Electrical Resistance Instruments
PALISADES PARK, NEW JERSEY



FRENCHTOWN ENGINEERED CERAMICS OFFER

big advantages!

Whether you plan the development of a new product, or are seeking ways to further improve existing ones, you'll want to look into the many new possibilities which are open to the design engineer who includes *engineered* ceramics in his planning. Our ceramic engineers have developed many formulae which, together with modern fabricating methods,* have greatly enlarged the usefulness of these amazing materials. Always outstanding as electrical insulators, Frenchtown ceramics, particularly the high alumina bodies, are being specified more and more for critical mechanical applications.

Check these BIG advantages:

- MECHANICAL STRENGTH
  Compressive strength up to 187,000 psi.
- ABRASION RESISTANCE
  Demonstrated by use for sand blast nozzles.
- HEAT RESISTANCE
  Softening temperatures up to 1971° C.
- THERMAL CONDUCTIVITY
  Coefficient (c.g.s. units) up to 0.0180.
- THERMAL EXPANSION
  as low as 2% cumulative at 700° C.

**Grinding and extrusion facilities* • NICOTE® *Metallized Ceramics*

Send for this helpful bulletin giving complete data on mechanical and electrical properties of all Frenchtown Engineered Ceramics.

frenchtown PORCELAIN COMPANY

86 MUIRHEAD AVENUE | TRENTON 9, NEW JERSEY



smaller lighter more versatile actuators

Oster®

A wide variety of smaller, lighter, more versatile linear and rotary actuators. One can be adapted to your specifications.

- 25% smaller, lighter because gear train and motor blended into single, unique homogeneous unit.
- 180,000 #/in.^{2} yield strength steel used in all gears.
- New high stability limit switch can be adjusted internally or externally.
- Unique design positive mechanical stops.
- Exclusive overload clutch dissipates extremely high forces in "impact" stopping.

LINEAR ACTUATORS

- 0.0018" end play in screw and nut. Specially designed acme screw made to AGMA pitch diameter standards but held to much closer tolerances than specified by any known standard today.
- Exceptionally long life due to new different continuous self-lubrication on acme screw.
- Rate adjustable from 1.6" to 30" per minute.

ROTARY ACTUATORS

- 3:1 to 523:1 gear ratio range available.
- 60° to 360° travel.
- 2° maximum backlash on output shaft.

TYPE	LINEAR	LINEAR	LINEAR	LINEAR	ROTARY	ROTARY
PART NO	ACT-3090	ACT-2425	ACT-3047	ACT-2439	ACT-2274	ACT-2408
WEIGHT	1.3# WITH 1.5" STROKE	3.1#	3.25#	3#	5#	2.2#
NORMAL OPERATING RATE & LOAD	1500# IN./MIN.	10.5 IN. PER MIN. 200# LOAD	2.9 IN. PER MIN. 10# LOAD	0.5 IN. PER SEC. 240# LOAD	5 RPM AT 250# IN.	200 RPM AT 3# IN.
TEMP. RANGE	—65° F TO 300° F	—65° F TO 260° F	—60° F TO 250° F	—65° F TO 250° F	—60° F TO 160° F	—65° F TO 260° F
VOLTAGE	28 V.D.C.	26 V.D.C.	26 V.D.C.	28 V.D.C.	27 V.D.C.	27 V.D.C.

Write for further details, stating your requirements.

Other products include Servos, AC Drive Motors, DC Motors, Motor-Gear-Trains, Fast Response Resolvers, Servo Torque Units, Synchros, Reference Generators, Tachometer Generators, and Motor Driven Blower and Fan Assemblies.

John Oster MANUFACTURING CO.
your rotating equipment specialist

Avionic Division
RACINE, WISCONSIN

The Capacity for Achievement



Since 1937 Librascope has earned and achieved—on an ever expanding scale—a position of leadership in the design, development and manufacture of computers, automatic controls and data handling systems for military and industrial applications.

Librascope, through a unique combination of electronic, magnetic, mechanical and optical techniques, consistently demonstrates an outstanding facility for the production of precision instrumentation and devices.

The creative ability of an exceptional engineering staff and the production capacity of a superbly equipped 200,000 sq. ft. plant facility can be focused on *your* computer-control problem. Consult Librascope today.

ENGINEERS . . . *learn about Librascope's new creative "Project Development Teams"* . . . *write Mac McKeague, Personnel Director*

A SUBSIDIARY OF GENERAL PRECISION EQUIPMENT CORPORATION

LIBRASCOPE

LIBRASCOPE, INC. · 808 WESTERN AVE. · GLENDALE · CALIFORNIA

announcing a new era in microwave measuring!

2 KMC TO 12.4 KMC

Broad band amplification

Amplitude, pulse modulation

Frequency, phase modulation

Constant gain, output

NOW 4 *-hp-* TRAVELING-WAVE TUBE AMPLIFIERS!



With the introduction of two brand-new traveling-wave tube amplifiers, Models 492A and 494A, *-hp-* now offers you a totally new standard of electronic measurement — one that brings the ease, accuracy and versatility of low frequency measurements *to the microwave range 2 to 12.4 KMC!*

Think what this means! With these *-hp-* instruments you can eliminate klystron starting delay and jitter, make wide dynamic-range antenna tests and SWR measurements, generate a stable power level, calibrate CW Doppler radar systems, calibrate attenuators over a wide range, FM a high stability SHF source, amplify wide band width signals containing complicated modulation. These are but a few of the ways *-hp-* traveling-wave tube amplifiers provide straightforward solutions to complex measuring problems—or do routine laboratory measurements better and faster.

New *-hp-* 492A (4 to 8 KMC), 494A (7 to 12.4 KMC) and the established *-hp-* 490A (2 to 4

KMC) are low level, high gain instruments, providing unique versatility of amplitude, pulse, phase and frequency modulation.

-hp- 491A is a power amplifier providing 1 watt output and 30 db gain for the frequency range 2 to 4 KMC. This instrument, together with a 1 mw signal generator such as *-hp-* 616A, provides a highly useful 1 watt source for "S" band testing.

All *-hp-* traveling-wave tube amplifiers use the exclusive *-hp-* coupling system with two separate helices for full transfer of energy over a broad frequency band. All have front panel controls for varying grid or anode and helix voltage, and a meter and selector for measuring basic currents in performance evaluation or continuous monitoring. Modulation connections are also brought to the front panel for greater convenience. During normal operation of the amplifiers, no adjustments are necessary. To do away with critical pre-operation adjustments of traveling-wave tubes, and assure that tubes and helices are properly matched, *-hp-* original equipment and replacement tubes are encapsulated in a single unit. This unit is factory tested, ready to install and use.

WRITE NOW FOR APPLICATION NOTES!

Explains how to use *-hp-* TWT Amplifiers as sensitive linear detectors, buffer-isolators, narrow band low noise level amplifiers and many other new applications. Sent immediately — no charge or obligation. Write today!

SPECIFICATIONS	-hp- 490A	-hp- 491A	-hp- 492A	-hp- 494A
Frequency Range:	2 KMC to 4 KMC	2 KMC to 4 KMC	4 KMC to 8 KMC	7 KMC to 12.4 KMC
Gain:	35 db minimum	30 db minimum	30 db minimum	25 db minimum
Output Power:	10 milliwatts minimum into 50-ohm load.	1 watt minimum into 50-ohm load.	10 milliwatts minimum into 50-ohm load.	5 milliwatts minimum into 50-ohm load.
Noise Figure:	Less than 25 db.	Less than 30 db.	Less than 25 db.	Less than 25 db.
Pulse Rise & Decay Time:	Approx. 0.015 μsec.	Mod. not provided.	Approx. 0.015 μsec.	Approx. 0.015 μsec.
Modulated Pulse Delay:	Approx. 0.035 μsec.	Mod. not provided.	Approx. 0.020 μsec.	Aprox. 0.015 μsec.
Amplitude Modulating Voltage:	Approx. 50 volt peak positive pulse will produce a 40 db change in rf power output. Sensitivity, approximately 1 db/volt.	Mod. not provided.	Approx. 50 volt peak positive pulse will produce a 40 db change in rf power level. Sensitivity, approximately 1 db/volt.	Approx. 50 volt peak positive pulse will produce a 40 db change in rf power level. Sensitivity, approximately 1 db/volt.
Helix Modulating Voltage:	Approx. 30 volts peak to peak provides 360° phase shift. Input impedance 1 megohm.	Mod. not provided.	Approx. 30 volts peak to peak. Provides 360° phase shift. Input impedance 1 megohm.	Approx. 30 volts peak to peak. Provides 360° phase shift. Input impedance 50 ohms.
Hum & Spurious Modulation:	At least 30 db below signal level.	At least 30 db below signal level.	At least 30 db below signal level.	At least 30 db below signal level.
Input Impedance:	50 ohms, SWR less than 2.	50 ohms, SWR less than 2.	50 ohms, SWR less than 2.	50 ohms, SWR less than 2.
Output Internal Impedance:	50 ohms, SWR less than 3.	50 ohms, SWR less than 3.	50 ohms, SWR less than 3.	50 ohms, SWR less than 3.
Size:	7" wide, 10¾" high, 18" deep. 55 lbs.	7" wide, 10¾" high, 18" deep. 65 lbs.	7" wide, 10¾" high, 18" deep. 55 lbs.	7" wide, 10¾" high, 18" deep. 55 lbs.
Power Supply:	115 volts ±10%, 50-60 cps, approx. 125 w.	115 volts ±10%, 50-60 cps, approx. 250 w.	115 volts ±10%, 50-60 cps, approx. 175 watts.	115 volts ±10%, 50-60 cps, approx. 175 watts.
Traveling-Wave Tube:	Huggins Laboratories HA-1.	Huggins Laboratories HA-2.	Huggins Laboratories HA-3B	Huggins Laboratories HA-4
Price (including tube):	$1,100.00	$1,100.00	$1,500.00	$1,500.00

Data subject to change without notice. Prices f.o.b. Palo Alto, Calif.

HEWLETT-PACKARD COMPANY

3576A PAGE MILL ROAD • PALO ALTO, CALIFORNIA, U.S.A.
CABLE "HEWPACK" • DAVENPORT 5-4451
SALES ENGINEERS IN ALL PRINCIPAL AREAS

PUBLICATION DATE
JANUARY, 1956



FOR EVERYONE

with a problem

in

RUBBER APPLICATION

KEL-F® Elastomer is a fluorocarbon rubber developed by The M. W. Kellogg Company. Possessing an unusual combination of elastomeric properties, chemical resistance, and thermal stability, KEL-F Elastomer can help solve difficult problems of rubber application under severe operating conditions. Return the coupon below to obtain a copy of this new booklet.

THE M. W. KELLOGG CO.

Chemical Manufacturing Division P. O. Box 469, Jersey City, N. J.

SUBSIDIARY OF PULLMAN COMPANY

Send me copy of newly published booklet "KEL-F Elastomer."

Name_____

Title_____

Company Name_____

Address_____

THE M. W. KELLOGG CO.

Chemical Manufacturing Division
P. O. Box 469, Jersey City, N. J.

SUBSIDIARY OF PULLMAN COMPANY

®Registered trademark of The M. W. Kellogg Company for its fluorocarbon polymers.

EIMAC klystrons bring high power to another frequency range...

225-400mc

20kw CW Power Output

TYPICAL CW OPERATION

Eimac X590D Amplifier Klystron
225-400mc

D-C Beam Voltage	20kv
D-C Beam Current	2.32 amps
Power Input	46.4kw
Power Output	20kw
Driving Power	11w
Efficiency	43%
Power Gain	32.6db

Another frequency range, 225-400mc, has been spanned with a commercially available Eimac high power amplifier klystron. The Eimac X590D, the first klystron developed for operation at the VHF-UHF junction, delivers 20kw/CW power output with only 11 watts drive. Its high power gain of 1800 times and efficiency of 43% typifies the incomparable performance of Eimac klystrons.

Incorporation of Eimac's unique modulating anode gives X590D outstanding versatility. It can be 100% modulated to peaks of 40kw in AM operation or easily pulse modulated with low pulsing power.

A new, indirectly heated oxide cathode greatly simplifies cathode power and cooling requirements.

With the X590D, Eimac now covers the 225-1000mc range at high power with only four klystron types. Wide range tuning and an easy, economical approach to high power UHF transmitters is made possible by the Eimac feature of completing RF circuitry outside the vacuum system with permanent circuit components.

Microwave high power is easily obtained by driving an Eimac klystron amplifier with existing low power equipment.

Transmitters employing Eimac klystrons give incomparable performance and reliability plus unmatched economy, since costly RF circuitry is not repurchased with each tube replacement.

Eimac X590D amplifier klystron with circuit components permit ease of transmitter design by equipment manufacturers

● *Eimac offers the most extensive selection of high power amplifier klystrons for pulse, CW and AM applications. For information contact our Technical Services Dept.*

Eimac

EITEL-McCULLOUGH, INC.
SAN BRUNO, CALIFORNIA
The World's Largest Manufacturer of Transmitting Tubes

TRADE

Buss Fuses

ELECTRICITY'S SAFETY VALVE

MARK

. . a source you can trust for fuses of unquestioned high quality!





The BUSS trademark has appeared on millions upon millions of fuses used in homes, farms, and in industries, as well as electronic equipment over the past 41 years. It is a trademark known and recognized by manufacturers, service organizations and customers as standing for the highest quality in fuses.

To make sure the BUSS reputation for dependable electrical protection is maintained — every BUSS fuse, normally used by the Electronic Industries, is tested in a sensitive electronic device. Any fuse not correctly calibrated, properly constructed and right in all physical dimensions is automatically rejected.

This careful testing results in fuses that will open and prevent damage to equipment when there is trouble on the circuit . . . . and just as important, BUSS fuses won't blow when trouble doesn't exist. Users are not annoyed with useless shutdowns caused by needless blows.

So rely on BUSS for all your fuse needs. You will be protecting both the product and your good name against troubles and complaints often caused by use of poor quality fuses.

For more information on BUSS and FUSETRON small dimension fuses and fuseholders . . .Write for bulletin SFB.

Makers of a complete line of fuses for home, farm, commercial, electronic and industrial use.

BUSSMANN MFG. CO. (Div. of McGraw Electric Co.)

University at Jefferson, St. Louis 7, Mo.

FUSETRON

TRUSTWORTHY NAMES IN ELECTRICAL PROTECTION

BUSS

ELRC 156



The ancient mariner's "marks of mobility" were few. Today's aircraft navigate the celestial sphere with confidence — thanks to Kollsman's scientific instruments and controls.

the marks of mobility

In an aircraft, instruments and controls are the very marks of its mobility . . . for accurate measurement and observation are the only guides to safe, predictable flight. There are no "marks of mobility" more accurate and dependable than Kollsman in the seven fields of . . .

AIRCRAFT INSTRUMENTS
PRECISION CONTROLS
PRECISION COMPUTERS AND COMPONENTS
OPTICAL COMPONENTS AND SYSTEMS
RADIO COMMUNICATIONS AND NAVIGATION EQUIPMENT
MOTORS AND SYNCHROS
INSTRUMENTS FOR SIMULATED FLIGHT TRAINERS

Our manufacturing and research facilities . . . our skills and talents, are available to those seeking solutions to instrumentation and control problems.

kollsman INSTRUMENT CORPORATION

80-08 45th AVE., ELMHURST, N. Y. • GLENDALE, CALIF. • SUBSIDIARY OF *Standard* COIL PRODUCTS CO. INC.

Want more information? Use post card on last page.

Where voices are powered by the sun



Lineman mounting solar battery on pole near Americus, Ga. The battery supplies power directly to the line by day and also charges a storage battery for night-time use. The solar battery contains 432 specially prepared silicon cells, cushioned in oil and covered by glass.

A new kind of telephone system developed by Bell Telephone Laboratories for rural areas is being operated experimentally by electric current derived from sunlight. Electric current is generated as sunlight falls on the Bell Solar Battery, which a lineman is seen adjusting in position.

The exciting achievement is made possible by two Laboratories inventions—the solar battery and the transistor. The new system uses transistors to the complete exclusion of electron tubes. Transistors require little power and this power can be easily supplied by the solar battery.

Compact and economical, the transistorized system can carry several voices simultaneously without interference. It has proved its ruggedness by standing up to heat, cold, rain and lightning. It promises more and improved telephone service for rural areas and it typifies the Laboratories' continuing efforts to make American telephony still better each year.

In sending and receiving terminals, transistors are used as oscillators, amplifiers and regulators, and for signaling.

One of the transistors (actual size) used in the new system. New ideas, new tools, new equipment and new methods had to be developed for this project.

BELL TELEPHONE LABORATORIES

IMPROVING AMERICA'S TELEPHONE SERVICE PROVIDES CAREERS FOR CREATIVE MEN IN SCIENTIFIC AND TECHNICAL FIELDS

Want more information? Use post card on last page.

Representing the nation's leading manufacturers of electronic equipment in an area covering over 500,000 square miles requires specialized service facilities in key locations... experienced engineering liaison... and the ability to apply the latest electronic instrumentation to the complex needs of today's industry.

All of these essential services—and more—are important components in a new concept of representation pioneered by Neely Enterprises — with over half a hundred qualified personnel to serve the Western Electronic Market.

For up-to-the minute information on electronic instrumentation, call any of the six conveniently located Neely Enterprises offices which serve the four state area of California, Arizona, Nevada and New Mexico.

SERVICE

MAKES A WORLD OF DIFFERENCE

NEELY ENTERPRISES

ELECTRONIC MANUFACTURERS' REPRESENTATIVES

LOS ANGELES OFFICE
3839 Lankershim Blvd.
Phone: STanley 7-0721

SAN FRANCISCO OFFICE
2830 Geary Boulevard
Phone: VIA 1-2361

SACRAMENTO OFFICE
1317 Fifteenth Street
Phone: GI 2-0981

SAN DIEGO OFFICE
1029 Rosecrans Street
Phone: AC 3-8105

ALBUQUERQUE OFFICE
107 Washington Street, S.E.
Phone: 5-5586

PHOENIX OFFICE
641 E. Missouri Avenue
Phone: CR 4-5431

It's a dozen test instruments in one!

—the Adjustable Span *ElectroniK* Recorder



Here's a recording potentiometer that is a real jack-of-all-trades (and master of each one) in any development or test laboratory. Just turn the dials, and in seconds, you can set it up for the exact range and sensitivity you want. You don't have to do any rewiring or changing of calibrating circuits.

50-to-1 span adjustment. Millivolt span of the recorder is continuously variable over as much as a 50:1 range. Span adjustment is independent of zero setting.

Variable zero suppression. Coarse and fine adjustment dials let you move the electrical zero point up and down scale, to concentrate recording on only the part of the span in which you're interested. Zero adjustment does *not* affect span setting.

Sensitivity adjustment makes it easy to get the recording characteristics you want to match the span being used.

Many optional features: you can choose from recording speeds of ½, 1, 2, 4½, 12 or 24 seconds full scale . . . fully automatic, push-button, or solenoid-actuated remote or locally controlled standardization.

Find out how this versatile instrument can save time in your test work, by calling your local Honeywell sales engineer . . . he's as near as your phone.

MINNEAPOLIS-HONEYWELL REGULATOR CO., *Industrial Division*, Wayne and Windrim Avenues, Philadelphia 44, Pa.—in Canada, Toronto 17, Ontario.

● **REFERENCE DATA: Write for Data Sheet No. 10.0-10a, "Adjustable Span Recorder."**

MINNEAPOLIS
Honeywell
BROWN INSTRUMENTS
First in Controls

Two Centralab Sub-Miniature Controls

for limited-space applications where only the very best will do

Model 1 with knob and switch

Actual size

Model 1 without knob and switch

As in all fine things, quality is the first consideration



Model 6 with switch enclosed

Write for new technical bulletins on Centralab Model 1 and Model 6 Sub-Miniature Controls.

Model 1-1/10 watt

Applications:	Hearing aids, military electronic devices, telephone equipment, sub-miniature radios, and a wide variety of other applications.
Size:	5/8" diam., without knob. 25/32" diam., with knob.
Resistance:	500 ohms to 10 megohms. Tested for 25,000 cycles. Seven standard tapers.

New! Model 6-1/10 watt

Has completely enclosed switch protected against dirt and other foreign matter.

Applications:	Designed especially for transistor applications.
Size:	1/2" diam.
Resistance:	500 ohms to 10 megohms. Tested for 25,000 cycles. Seven standard tapers.

More proof that if it's a job for electronic components, it's a job for Centralab

Centralab's advanced engineering continues to lead the component industry

VOLUME CONTROLS

CAPACITORS

SWITCHES



PACKAGED ELECTRONIC CIRCUITS

STEATITE INSULATORS

NEW 1956 Electroni-Kwiz!

1st Prize

Smith-Corona

Portable Typewriter

This is strictly a "do-it-yourself" proposition. You've got a good chance to win! It's easy — just answer this question in 50 words, more or less:

If you were given a free hand and purse to develop something new, in what realm would you concentrate your efforts — and why?

A leading editor will pick the winner of this month's prize. Mail your entry to us before January 31.

†Nothing to buy. Employees of Centralab and its advertising agency not eligible. Duplicate prizes awarded in case of tie. Entries become the property of Centralab — none can be returned.

Centralab

A DIVISION OF GLOBE-UNION INC.

914A E. Keefe Avenue • Milwaukee 1, Wisconsin
In Canada: 804 Mt. Pleasant Road, Toronto, Ontario

R-563

SINCE 1922, INDUSTRY'S GREATEST SOURCE OF STANDARD AND SPECIAL ELECTRONIC COMPONENTS

Simpson panel instruments...

VOLTMETERS, AMMETERS, MILLIAMMETERS, MICROAMMETERS, WATTMETERS, GALVANOMETERS, VOLUME LEVEL INDICATORS, SEALED & RUGGEDIZED METERS, METER RELAYS

800 STOCK TYPES

... plus HUNDREDS MORE, custom-built from standing tools ✻



YOUR ELECTRONIC PARTS DISTRIBUTOR HAS HUNDREDS IN STOCK!

✻ Send us your special meter requirements today. Let our top-flight engineers work out solutions or make recommendations *best suited* to your needs.

Simpson **INSTRUMENTS THAT STAY ACCURATE**

..sizes and types to meet your exact requirements!

5 ACCURATE METER MOVEMENT TYPES



(A) NEW CORE TYPE—A superb new movement that is *self shielded*, remarkably small and lightweight. Instruments now equipped with it meet the various Military Specifications for Sealed and Ruggedized Meters. Shallow, medium, and deep sizes.



(B) EXTERNAL MAGNET TYPE—The magnet structure of this time-proven movement is an independent part, permitting a choice of magnet material to match specific requirements.



(C) DYNAMOMETER TYPE—This fine movement features a high torque to weight ratio. With it, Simpson is the only manufacturer producing a two-inch wattmeter. Movement is air damped, sturdily built.

(D) MOVING VANE TYPE—The preferred movement for A-C measurement. Consumes remarkably little power. Features Simpson three-way balancing and patented balance weight locking clips.

(E) NEW BIFILAR SUSPENSION TYPE*— Represents a brilliant, new adaptation of the D'Arsonval principle with bifilar suspensions that *eliminates all friction due to pivots and jewels.*

*Simpson-Greibach Movement

Shunts and Current Transformers available to your specifications.

Send for Technical Manual 17

Simpson ELECTRIC COMPANY

5200 West Kinzie St., Chicago 44, Ill. Phone: EStebrook 9-1121
In Canada: Bach-Simpson, Ltd., London, Ontario

Want more information? Use post card on last page.

NOW PHELPS DODGE SODEREZE*

SUITABLE FOR ALL

First for Lasting Quality—from Mine to Market!

*Reg. U. S. Pat. Off.

GIVES HIGH "Q"...
CLASS "A" APPLICATIONS!

- **New materials assure high "Q".**
- **All essential properties equal or superior to existing film wires.**
- **Positive uniform soldering. No stripping or cleaning necessary.**



Phelps Dodge Sodereze represents a new advance in ready-to-solder magnet wire. It's a typical Phelps Dodge development designed to keep pace with industry's growing need for wires that handle easily, reduce over-all cost and satisfy a variety of operating conditions.

Phelps Dodge Sodereze offers a unique combination of improved chemical and mechanical properties with the advantage of high "Q". The versatility of Phelps Dodge Sodereze not only permits its use wherever solderable wires have been proven practical but suggests new applications, particularly in the finer sizes, to replace conventional wires.

Any time magnet wire is your problem, consult Phelps Dodge for the quickest, easiest answer!

support Junior Achievement
PUTTING YOUTH IN BUSINESS

PHELPS DODGE COPPER PRODUCTS CORPORATION
WIRE TO MEASURE

PHELPS DODGE COPPER PRODUCTS CORPORATION

INCA MANUFACTURING DIVISION
FORT WAYNE, INDIANA

Want more information? Use post card on last page.

TAYLOR Shop Talk

Laminated Plastics
Vulcanized Fibre

TAYLOR FIBRE CO.

Plants in Norristown, Pa. and La Verne, Calif.

PHENOL—MELAMINE—SILICONE—EPOXY LAMINATES • COMBINATION LAMINATES • VULCANIZED FIBRE • POLYESTER GLASS ROD

Tips for designers



Furniture can make good use of the mar-resistant, tough surface afforded by Taylor Vulcanized Fibre plywood combination table tops.

Terminal strips for high-precision electronic instruments benefit by the excellent insulating properties of Taylor XXXP-301 hot-punch phenol laminate.



Heavy bumper blocks for steel mill use, made of Taylor Built-Up Fibre several inches thick, give long service under severe shock and abrasion.

Selenium rectifier plates are insulated by washers made of Taylor Grade 353 phenol laminate . . . chosen for its dimensional stability and mechanical strength.

TAYLOR FABRICATING FACILITIES

Your production can be simplified . . . schedules safeguarded . . . inventory headaches cured . . . and overall costs reduced by having Taylor fabricate finished parts to your specifications. Efficient, modern facilities are ready to serve you. Get in touch with Taylor about your specific requirements.



High strength, light weight, excellent insulating and corrosion-resistant qualities make Taylor Epoxy Glass Base Laminate the ideal material for tubing in an aircraft fuel gage tank unit made by Avien, Inc.

When service conditions are tough— *use Taylor special-purpose laminates*

Designing for severe service? Then take a look at what Taylor special-purpose laminates can do. Taylor's resin chemists have developed special formulations of melamine, silicone and epoxy resins . . . for combination with a variety of base materials. The result is a line of laminates which offer the plus performance that your new designs may require.

Taylor epoxy laminates. Retain superior mechanical properties after exposure to high temperatures (above 430 F) . . . have outstanding electrical characteristics, moisture resistance and resistance to corrosive chemicals . . . setting these laminates apart as a means of solving difficult design problems.

Taylor melamine laminates. Excellent resistance to arcing, electrical corona, flame and chemical attack characterizes these materials . . . useful in many electrical applications.

Taylor silicone laminates. These withstand temperatures up to 500 F . . . provide insulation where other laminates thus far cannot be used. They also possess high mechanical strength, low power factor and low moisture absorption.

Sheets, tubes and rods of these materials are available in a range of sizes that will give you maximum economy of material in your manufacturing processes.

To help you in the application of these specialized materials to your specific product, Taylor offers the service of its experienced engineering staff. Call on Taylor for a consultation on your individual requirements.

Want more information? Use post card on last page.

REVOLUTIONARY REVOLUTIONS!



World's largest line of vacuum pumps — from 2 cu. ft. per min., ¼ h.p. to 780 cu. ft. per min., 40 h.p.

Vacuum pump performance standards were revolutionized when Kinney introduced the cam and piston design . . . establishing new criteria by which all other pumps are judged. Through continuing research, Kinney constantly adds more features to these superior basic designs . . . controlled gas ballasting . . . dynamic balancing for reduced vibration . . . consistently quick recovery of operating pressures, etc. . . . to make each revolution of a Kinney High Vacuum Pump an economy move in thousands of installations . . . in a wide variety of applications . . . throughout industrial America.

Competent vacuum engineers in all our district offices are ready to help you solve your particular problem. Send the coupon for details. Kinney Mfg. Division, Boston 30, Massachusetts.

KINNEY MFG. DIVISION
THE NEW YORK AIR BRAKE COMPANY
3565 WASHINGTON STREET • BOSTON 30 • MASS.
INTERNATIONAL SALES OFFICE, 50 WEST ST., NEW YORK 6, N.Y.

Please send Bulletin V54 describing the complete line of Kinney Vacuum Pumps.

Our Vacuum problem involves .....

.....

Name .....

Company .....

Address .....

City ..... State .....

Want more information? Use post card on last page.

For *more dependable* Switchgear, Specify

For *more dependable* Insulation, Specify

NATVAR 400

EXTRUDED VINYL TAPE



I-T-E MULTUMITE Switchgear is compact and efficient. It is designed and built to provide positive protection of secondary distribution systems with an extra margin of safety for uninterrupted service. Instrument transformers are designed specifically for switchboards.



Natvar 400 Extruded Vinyl Tape is used on this Type C-2, 5,000 volt, 600 amp. primary transformer coil to protect the instrument circuit, because it has good dielectric strength, requires fewer layers than VC, is flexible enough to conform to sharp bends without wrinkling, and because it has adequate heat resistance.

Natvar

Natvar Products

- Varnished cambric—cloth and tape
- Varnished canvas and duck
- Varnished silk and special rayon
- Varnished—Silicone coated Fiberglas
- Varnished papers—rope and kraft
- Slot cell combinations, Abaglas®
- Vinyl coated—varnished—lacquered tubing and sleeving
- Extruded vinyl tubing and tape
- Styreflex® flexible polystyrene tape
- Extruded identification markers

Ask for Catalog No. 23

For more than 60 years I-T-E has been known in the electrical industry for the *quality* of its products. This reputation has been maintained through sound engineering and manufacturing skill.

Component parts and materials that go into I-T-E Switchgear are the finest obtainable, and are carefully coordinated into efficient functional units. Natvar 400 extruded vinyl tubing and tape and other Natvar flexible insulations are used because they consistently meet I-T-E's rigid requirements.

Natvar 400 and other Natvar flexible electrical insulating materials are available for immediate delivery, either from your wholesalers' stocks or direct from our own.

NATVAR CORPORATION

FORMERLY THE NATIONAL VARNISHED PRODUCTS CORPORATION

TELEPHONE RAHWAY 7-8800 — CABLE ADDRESS NATVAR: RAHWAY, N. J.

201 RANDOLPH AVENUE • WOODBRIDGE, NEW JERSEY

TYPE P PORTABLE DYNOGRAPH

Single and Dual channel Units—all performance specifications are identical to those of the console model—Chart speeds from 1 to 100 mm. per second.



TYPE M CONSOLE

Six channels—accommodates up to six Type 146 amplifiers with input couplers, uses roll or folded charts—eight chart speeds, 1 to 250 mm. per second.

OFFNER DYNOGRAPH RECORDERS


Speed plus sensitivity —15 microvolts d-c per millimeter—1/120th second deflection time.
Large, easy to read permanent records—over 8 cm excursion.
No hysteresis—high-torque returns stylus to base line—even with paper stationary.
Completely stable—has absolute zero base line drift.

IF YOU COMPARE—YOU WILL SELECT THE OFFNER DYNOGRAPH!

Compare the direct writing oscillographs on the market today. If you do, you will select the Offner Dynograph because only the Offner Dynograph has these features:

15 microvolt per millimeter d-c sensitivity . . . Absolute *drift-free* stability . . . One amplifier for d-c amplification, resistance and reluctance gages . . . True differential input, isolated from ground . . . Rugged, low resistance movement.

No other direct writing oscillograph on the market has *any of these features!* The Offner Dynograph *has all these features and many more!*—because the Dynograph uses the exclusive patented Offner *chopper amplifier.* This amplifier must be distinguished from a chopper *stabilized* amplifier, which merely reduces, does not eliminate drift, and provides none of the other features of the Offner Dynograph.

If you want the widest versatility, highest accuracy, greatest reliability in direct writing high speed oscillographs—*compare them all!* You'll select the Offner Dynograph.



Write for your copy of Bulletin L-742. Get complete details and application information on both Portable and Console Models. Write for a demonstration by our Engineering Representatives in your area. Compare—and you will select the Offner Dynograph.

OFFNER ELECTRONICS INC.

5324 N. Kedzie Avenue, Chicago 25, U. S. A.

This year it's

KINGSBRIDGE 3

March 19-22
New York City

for the
Radio Engineering Show



For the third year in succession, the great annual IRE Radio Engineering Show will open its doors to the industry for four spectacular days at the Kingsbridge Armory and Kingsbridge Palace in New York City. As in the preceding years, the Show will be filled to capacity with 704 exhibits and displays of the latest and newest developments in radio-electronics.

Is it too big? Not as a true representative of this giant industry. More than 200 papers presented by 22 Professional Groups at the Convention's 55 technical sessions are an accurate index to new research and development . . . and the 704 exhibitors represent about 80% of the productive capacity of the industry . . . not one whit larger than necessary to keep pace with electronic America today!

Plan now to attend the industry's most vitally important Show where

Over 42,000* meet!

*At the 1955 Show, 42,133 men and women from coast to coast and every field of radio-electronics attended the Radio Show. This year, attendance is expected to go even higher. Don't miss it!

Over 700 Exhibitors will show all that is NEW in radio-electronic engineering!

THE INSTITUTE OF RADIO ENGINEERS
1 East 79 Street, New York

Leaders in Electronics *rely* on Good-All Capacitors

. . . whether for a critical fraction of a second or for a long life of trouble-free performance. Our technical and production people gain real satisfaction from working out capacitor problems with design and component engineers. The confidence of these engineers in Good-All "know-how" has contributed greatly to our rapid growth in the industry

GOOD-ALL

Our engineers are ready to work with you on special applications. Write, wire or phone for specifications and quotations.

MIL TYPES

Good-All produces a broad line of hermetically sealed tubular and bathtub capacitors to specifications MIL-C-25A. Custom designs of various metal enclosed styles can also be provided to your individual specifications.

MYLAR TYPES

The space-saving size and extremely high IR of Good-All Mylar* types are ideal for many special purpose applications. These are available in several metal enclosed designs as well as in ceramic or plastic impregnated tubes.

*DuPont's trademark for polyester film.

GOOD-ALL ELECTRIC MFG. CO. Goodall Bldg. • OGALLALA, NEBRASKA

HARNESSING THE POWER OF THE POLES...

Berkeley MAGNETICS



a totally NEW *concept of industrial instrumentation*

Berkeley FERRISTOR* Circuitry

Brings You High Speed Counting and Control Without Vacuum Tubes!

featuring

RELIABILITY—designed for *continuous* duty!

RUGGEDNESS—immune to shock, vibration, overload!

SIMPLICITY—installation, operation, maintenance by regular plant personnel!

Utilizing rugged BERKELEY Ferristors* to perform most vacuum tube functions, new BERKELEY industrial counting and control instruments offer electronic speed and precision **plus** the unfailing reliability, simplicity and long service life of electromagnetic devices:



"TUBELESS" Decimal Counting Unit (right) generates 1/5th the heat of vacuum tube model (left); no component in the Ferristor* DCU operates at more than 25% of its ratings.

- **CONTINUOUS-DUTY RELIABILITY**—rugged encapsulated Ferristors*, developed and manufactured by Berkeley, are immune to damage caused by shock, vibration, moisture and overloading. They're non-aging, require no filaments, operate at extremely low current and voltage levels; produce little or no heat.

- **INSTALLATION, OPERATION, SERVICING BY REGULAR PLANT PERSONNEL**—no electronic "experts" required! Connections made on clearly-marked terminal strips, with standard industrial wiring procedures. Simple tamper-proof adjustments; sturdy, easily-understood controls!

- **LONG COMPONENT LIFE**—circuits operate at a fraction of component ratings. Elimination of excessive heat ends heat-caused deterioration and instability, permits use of dust-tight enclosures (no ventilation needed).

*Trademark

a totally NEW concept of industrial instrumentation

Berkeley Series 5840 Long-Life MAGNETIC Dual Preset Controller



TAMPER-PROOF, dust-tight transparent cover can be locked to prevent re-setting by unauthorized personnel.



SWING-OUT chassis construction simplifies installation, inspection and servicing.

Counts at rates to 10,000 per sec, produces electrical output signals at any two preset totals. Absolute accuracy. Operates from photocells, magnetic pickups, electrical contacts. Built-in DPDT output signal relay operates solenoids, solenoid valves, power relays, other control devices. First signal may be used to slow down operation preparatory to stop at final (second) count, etc. Has only two vacuum tubes (vs. 54 in electronic model), both used in low-level rf oscillator-power supply. Simple marginal test indicates approaching tube failure, permits replacement before failure occurs.

BRIEF SPECIFICATIONS

Max. Count Rate: 10,000 counts per sec

Input Sensitivity: 0.1 ma p-p into 10k load

Output Signal: From built-in DPDT relays; contacts rated at 5 amps (non-ind.)

Accuracy: Absolute

Power Requirements: 105/130 or 210/230 v. 60 cycle, 85 w.

Dimensions, Weight: 18⅞"W x 8¾"H x 13⅜"D; 50 lbs.

Price (f.o.b. factory): Model 5846 (6 digit) $1,295.00.

APPLICATIONS

Control of counting, weighing, sorting, packaging, shearing, metal forming, coil winding equipment; cut-off of motors, turbines, jet engines at precise predetermined rev count or speed, computer timing, etc. Continuous-duty reliability makes new MAGNETIC Preset Controller ideal for all process and production control applications where elimination of costly downtime is a vital factor.

Berkeley Model 7650 Long-Life MAGNETIC EPUT* Meter

Measures events occuring during precise 0.1, 1 or 10 sec time interval, displays results in digital form. Operates from photocell, magnetic pickup or any suitable transducer to measure pressure, temperature, flow, velocity, viscosity, frequency, rpm, or to count events or objects at rates to 40,000 counts per second.

Only three vacuum tubes used (35 in comparable electronic model) in rf oscillator-power supply operating at low levels. Simple marginal test indicates approaching tube failure, permits replacement before failure occurs. Has digital "count-down" time base for precise gating; no adjustment of time base required.

BRIEF SPECIFICATIONS

Count Capacity: 5 digits

Counting Rate: 0 to 40,000 per sec

Time Base: 0.1, 1 or 10 sec

Accuracy: ± 1 event, ± 50 ppm

Input: 0.3 ma p-p into 10k load

Power Requirements: 105/130 or 210/230 v. 60 cycle, 100 w

Dimensions, Weight: 18⅞"W x 8¾"H x 14⅜"D (overall); 55 lbs.

APPLICATIONS

Aircraft, automotive, jet or piston engine test cells, dynamometer test stands; laboratory or production tachometry systems; process control systems; data reduction systems; hydraulic and pneumatic servo testing; acceleration-deceleration determination; measurement of linear or centrifugal speeds, forces, strains; measurement of any optical, electrical, mechanical or physical event occurring during a precise time interval.

BERKELEY Long Life Magnetic EPUT* Meters and Magnetic Controllers are ready now to serve in your laboratory, inspection rooms and test cells, on your production, processing or packaging lines. You'll be hours and dollars ahead to call your nearest BERKELEY representative or write us now for complete data. Please address Dept. G-1.

75

Berkeley *division*

BECKMAN INSTRUMENTS, INC.

2200 Wright Avenue • Richmond 3, California

Tests show two CATHALOYS most versatile cathode materials

New alloys from Superior Tube simplify selection, prolong tube life

Now the engineer's job of selecting the right cathode alloy for practically any electron tube can be a simple choice between two new CATHALOYS from Superior Tube.

CATHALOY A-32* is an active alloy characterized by rapid activation, high emission level throughout life, absence of interface impedance, and very low sublimation. These remarkable advantages are the result of using aluminum in place of silicon or magnesium as the reducing agent. The addition of a small percentage of tungsten also makes A-32 approximately 50% more shock resistant than cathodes without tungsten. Thus A-32 is suitable for virtually any active alloy application, including ruggedized tubes.

CATHALOY P-50 is a passive alloy of carefully controlled analysis that is commercially available in WELDRAWN† cathodes as well as Lockseam.‡ It can be made in WELDRAWN form because of its capacity to take much more severe reductions in cold drawing without rupture than other grades of passive alloys. P-50 is identical in composition with the well-known ASTM Grade 21. The important difference is in the method of melting which improves the uniformity and completeness with which deoxidation is accomplished. All heats are tested in Superior Tube's laboratory before being approved for production.

Ask for complete technical reports on both these new CATHALOYS. Write Superior Tube Co., 2500 Germantown Ave., Norristown, Pa.



ON TEST. Laboratory photo of test diodes used in Superior Tube's electronic laboratory. Under exhaustive tests, the new Cathaloys display performance characteristics not present in other alloys.

*Patent applied for †TM Reg. U.S. Pat. Off., Superior Tube ‡Manufactured under U.S. patents NOTE. Cathaloy is a trademark of Superior Tube Co., Reg. U.S. Pat. Off.



CATHALOY A-32—3750 psi **Tungsten-free cathode alloy—2500 psi**
50% STRONGER. High temperature tensile testing machine proves Cathaloy A-32 approximately half again stronger than tungsten-free cathode alloys.



WELDRAWN PASSIVE ALLOY. Typical uses for Cathaloy P-50 are in Weldrawn cathode sleeve shown at right and in disc cathode shank at left. Heretofore, passive alloys have not been commercially available for these applications.

Superior Tube
The big name in small tubing

All analyses .010" to ½" OD. Certain analyses in light walls up to 2½" OD.

Toroids, Subminiature

C-A-C®

Subminiature Package Types—Others Available





● Our Network Designers can solve your space problems in filters, discriminators and delay lines with the subminiature toroids.

Inquiries are invited.

C-101

COMMUNICATION ACCESSORIES COMPANY

HICKMAN MILLS, MISSOURI • PHONE KANSAS CITY, SOUTH 5528

a

WESTINGHOUSE

BALTIMORE DIVISIONS

opportunity

for experienced electronic engineers seeking long-range positions of responsibility and opportunity.

Current opportunity at the Westinghouse Baltimore Divisions combines most of the ordinary advantages— such as good income and employe benefits— with a foremost program of professional recognition, advanced education at company expense, and long-range development work that is creative and interesting. Work in modern facilities that are ideally located. Apply today!

OPENINGS EXIST IN THE FIELDS OF:

- *CIRCUITRY
- *MICROWAVES
- *SERVOMECHANISMS
- *MAGNETIC AMPLIFIERS
- *PACKAGING
- *DIGITAL COMPUTER PROGRAMMING
- *FIRE CONTROL SYSTEMS
- *ANALOG COMPUTER DESIGN
- *TRANSFORMERS
- *VIBRATION
- *RADAR DESIGN
- *FIELD SERVICE

TO APPLY

Send letter outlining your experience to—

Technical Director, Dept. 284
Westinghouse Electric Corp.
2519 Wilkens Avenue
Baltimore 3, Maryland

YOU CAN BE **SURE**...IF IT'S

Westinghouse





force!

When you want to measure it look to **Brush Recording Systems**



Torque of an engine balancer shaft is recorded by Brush instrumentation in this set-up at Caterpillar Tractor Co. Test data helped Caterpillar engineers reduce vibration, improve engine performance.

A boxer's punch, a heart's contraction, a piston's thrust—you can measure almost any form of force with Brush Recording Systems. These versatile instruments give you the answers in writing, charting instantaneously as phenomena occur. Brush offers a complete line of portable, console or rack mounting oscillographic systems for recording 1, 2, 4 or 6 channels of data.

These and other Brush instruments can help you in virtually any measurement problem involving electrical, mechanical, heat, light, sound or nuclear quantities. For complete information, call or write Brush Electronics Company.

BRUSH ELECTRONICS COMPANY

INDUSTRIAL AND RESEARCH INSTRUMENTS
PIEZOELECTRIC MATERIALS • ACOUSTIC DEVICES
MAGNETIC RECORDING EQUIPMENT AND COMPONENTS

BRUSH 6 ELECTRONICS

Division of Clevite Corporation

ELECTRICAL

MECHANICAL

LIGHT

HEAT

SOUND

NUCLEAR

NEW IDEAS IN MEASUREMENT FROM BRUSH

Chooses best recording speed.

Test engineer has a choice of up to 16 recording speeds on this Brush Recording System. Result—he can choose the best speed for the signal being measured for optimum accuracy and clarity of chart records. Wide speed range helps economize on chart paper too! Systems like this can record a wide range of electrical or mechanical variables.

How well does he breathe?

This diver is entering a pressure chamber for a "dry-land dive" at various simulated depths. Through strain transducers, Brush recording instruments chart the pressure of the diver's breathing and the rate of air flow. Tests help evaluate physical effects on the diver as well as performance of equipment.



Counts anything?

The "Countess"—Brush's outstanding digital counter—counts anything up to 100,000 pulses per second. Unit requires only one-half the voltage, one-fourth the power needed by conventional counters. The result is less heat, greater reliability. Use the Countess as a component in equipment: for testing, controlling, computing, etc.

Keeps the music sweet.

This test set-up at Hammond Organ uses a Brush Frequency Response Recorder to test the ringing time of tone generating circuits. Brush offers an integrated line of precision equipment for measuring sound, noise, vibration, analyzing frequency spectra, etc. Chart records simplify analysis and provide permanent records of tests.

Call BRUSH for the answer!

For help in your measurement problems, call your nearby Brush representative, or write Brush Electronics Company, Department 777, 3405 Perkins Avenue, Cleveland 14, Ohio. Your request will receive prompt attention!

BRUSH ELECTRONICS COMPANY

INDUSTRIAL AND RESEARCH INSTRUMENTS
PIEZOELECTRIC MATERIALS • ACOUSTIC DEVICES
MAGNETIC RECORDING EQUIPMENT AND COMPONENTS

BRUSH ELECTRONICS

Division of Clevite Corporation

Convenient, more compact portable radios for Motorola



Capacitors made with new Du Pont MYLAR* help Motorola obtain essential space savings

"In designing our top-selling portable radios, the essential element of compactness was achieved through the help of capacitors made with Du Pont 'Mylar,'" reports Motorola, Inc. "Smaller capacitors are possible because 'Mylar' is tough, thin, and has high dielectric strength. In addition, the moisture insensitivity of these new capacitors assures superior performance, whether on the hot, humid beach or in cool mountain air."

This successful product innovation is only one example of the way an imaginative industry is putting the unique properties of Du Pont "Mylar" polyester film to profitable use. From metallic yarns to smaller transformers for guided missiles, Du Pont "Mylar" is making possible better products at lower cost in a wide variety of fields. Here's why:

"Mylar" has a tensile strength of 20,000 pounds per square inch. It has greater dielectric strength than most known insulating materials, and an impact strength at least twice that of any known commercial film. What's more, Du Pont "Mylar" is resistant to moisture and solvents, and remains flexible and stable over a temperature range extending from -80°F. to 300°F.

How about your product? There may be a way "Mylar" can solve those knotty problems and improve over-all performance. Mail the coupon today for a fact-filled booklet telling you more about this new versatile film—"Mylar."

DU PONT

MYLAR®

DU PONT POLYESTER FILM

Better Things for Better Living...*through Chemistry*

*"Mylar" is the registered Du Pont trade-mark for its brand of polyester film.

E. I. du Pont de Nemours & Co. (Inc.)
Film Department, Room E-1, Nemours Bldg.
Wilmington 98, Del.

Please send me sample and further information on "Mylar" polyester film.

Name_____

Firm_____

Street Address_____

City_____ State_____

A Wide-Deviation *Crystal-Standardized* F. M. DEVIATION METER

MARCONI

F.M. DEVIATION METER

TYPE TF 928

Carrier Frequency Range:
20 to 100 Mc.

R. F. Input Level:
55 mv to 10 v.

Deviation Measurement Ranges:
100, 200 and 400 kc full-scale.

Accuracy of Deviation Measurement:
±3%



F.M. DEVIATION METER Type TF 928 accurately measures the frequency deviation of f.m. transmitters operating at carrier frequencies in the range 20 to 100 Mc.* Designed to accommodate wide-deviation systems employing modulation frequencies between 50 cps and 120 kc, the Meter has three deviation measurement ranges extending from 0 to 100, 200 and 400 kc respectively. A particularly valuable feature of the design is the inclusion of a self-checking arrangement introducing an oscillator crystal into the grid circuit of the second i.f. amplifier stage. At the same time, an alternating potential is impressed on the screen of the ensuing tube which suppresses the generated frequency at alternate half-cycles; this produces a test signal of constant effective deviation against which the deviation scale may be standardized.

** or 500 Mc using oscillator harmonics.*



MARCONI INSTRUMENTS

VACUUM TUBE VOLTMETERS · FREQUENCY STANDARDS · OUTPUT METERS
F.M. & A.M. SIGNAL GENERATORS · DEVIATION METERS · WAVEMETERS
WAVE ANALYSERS · Q METERS · BEAT FREQUENCY OSCILLATORS

Full data and prices will be mailed immediately on request

44 NEW STREET · NEW YORK 4

CANADA: CANADIAN MARCONI COMPANY, MARCONI BUILDING, 2442 TRENTON AVENUE, MONTREAL.

ENGLAND: Head Office: Marconi Instruments Ltd., St. Albans, Herts. Managing Agents in Export: Marconi's Wireless Telegraph Co. Ltd., Marconi House, Strand, London, W.C.2

TC74

Highway to automation

Engineered Wiring—*and why Rome Synthinol® protects it from heat, corrosion, solvents and moisture.*

You can avoid failure of hook-up and control wiring, because of inferior insulations or construction, by using Rome Hook-Up, Machine Tool and Control Wires. Rome wires are made to stand up under high-speed, automatic operation day after day.

Hook-Up Wires

Rome Synthinol is UL approved for 80°C.—has high resistance to acids, oils, alkalies, moisture and flame.

Rome Synthinol 901 is UL approved for 105°C.—has all the advantages of regular synthinol *plus* higher resistance to heat deformation, shrinkage and cracking, and improved solderability.

Also, Rome makes *Rome Hi-Temp*, a rubber insulation with great heat and moisture resistance—UL approved for 75°C. . . . and a full line of special and standard *commercial* and *military* hook-up wires.

Machine Tool and Control Wires

Rome insulates its machine tool and control wires with synthinol to proof them against high ambient temperatures and corrosive conditions. They conform to National Machine Tool Builders' Association Standards and are UL approved as Type TW with end use approval for 80°C. operation in air; and in oily, moist locations for 60°C. operation.

Rome Synthinol and *Synthinol 901* are thermoplastic compounds designed for exceptional resistance to high ambient temperatures, corrosion, oil and chemical solvents. Synthinol-insulated wiring is especially suitable for machine tool use. It is available in a variety of permanently clear colors, solid or with spiral markings.

Send for complete data and specifications on Rome Hook-Up Wires, Machine Tool and Control Wires. They're available in special and standard constructions.



Without this control panel, *equipped with dependable wiring*, relays, starters and limit switches, the machine operator would do most of the work. Automation takes the machine through complex cycles without operator attention.



Once the hopper is loaded, this machine automatically grinds roller bearing races to precision tolerances. The machine also trues and dresses the grinding wheel—automatically.



This machine is built for automatic machining of a specific automobile part. Machine tool and hook-up wires carry the power and signals which make its automation possible.

It Costs Less to Buy the Best

ROME CABLE Corporation
ROME · NEW YORK
and
TORRANCE · CALIFORNIA

PRECISION RESOLVERS



by Reeves INSTRUMENT CORPORATION

- ★ Accuracy better than 0.05%.
- ★ Maximum interaxis error as low as 1'.
- ★ Very low distortion.
- ★ 60 or 400 cps. or wide band.
- ★ With or without booster amplifier compensation.
- ★ Standard military frame sizes.

the HIGHEST PRECISION resolvers available

Reeves' many years of experience as a pioneer in the field has made it possible to manufacture these compact precision resolvers in quantity production to a functional accuracy of 0.05% without culling—or to an accuracy of 0.03% on special order. Harmonic distortion and null voltages are held below one-tenth of one per cent.

Reeves resolvers are primarily designed for 60 and 400 cps. operation, with or without booster amplifier compensation. Special units are available for use at over 100 kc bandwidth. The Reeves R600 series is the standard of comparison among precision resolvers. Miniature resolvers of highest precision are also available.

Write for the Reeves Resolver Handbook.

REEVES PRECISION RESOLVERS AND RELATED COMPONENTS

MINIATURE PRECISION RESOLVERS



BOOSTER AMPLIFIERS



PHASE SHIFTERS

CONTINUOUS RESOLVER CHECKER

Reeves INSTRUMENT CORPORATION

REEVES INSTRUMENT CORPORATION

A Subsidiary of Dynamics Corporation of America

201 East 91st Street, New York 28, New York

2RV56

Farnsworth . . . ***VISION*** *beyond the range of sight . . .*

Farnsworth

CLOSED CIRCUIT TV

"lets you see . . . where you can't be"



MODEL 600A
Consists of a compact light weight camera and portable monitor interconnected by multiconductor cable.

MORE THAN 30 YEARS

experience in electronic television

for defense and industry . . . bring you Farnsworth closed circuit television that is second to none! Engineered especially for industrial, educational and commercial use this new, economical medium is saving time, and money in countless applications.

Yours should be one of them . . . Get the facts from Farnsworth.

WRITE DEPT. CT-156 FOR COMPLETE DETAILS

FARNSWORTH ELECTRONICS COMPANY
a division of International Telephone and Telegraph Corporation
FORT WAYNE, INDIANA

Farnsworth
A DIVISION OF IT&T

Want more information? Use post card on last page.

The British Electronics Industry is making giant strides with new developments in a variety of fields. Mullard tubes are an important contribution to this progress.

EL34

Britain's foremost pentode for 25W high fidelity equipment

The Mullard EL34 can be rightly acclaimed as the most efficient high fidelity output pentode tube yet produced in Britain. It is being fitted in many of the British sound reproducing equipments which are becoming increasingly popular in the United States and Canada.

Used in push-pull ultra-linear operation (distributed load), two EL34 tubes will give 32 watts output at a total distortion of less than 1%. The application of negative feedback reduces distortion even further.

The EL34 is equally capable of supplying higher power outputs where an increased distortion level is acceptable. Under class B conditions, 100 watts are obtainable from a pair of EL34 tubes in push-pull for a total distortion of 5%.

Another significant feature of this tube is its high transconductance value of 11,000 μmhos, resulting in high power sensitivity and low drive requirements.

Supplies of the EL34 are now available for replacement purposes from the companies mentioned below.

Principal Ratings

Heater
6.3V, 1.5A

Max. plate voltage
800V

Max. plate dissipation
25W

Max. screen voltage
425V

Max. screen dissipation
8W

Max. cathode current
150mA

Base
Octal 8-pin

Available in the U.S.A. from:—
International Electronics Corporation,
Dept. E1, 81 Spring Street, N.Y.12,
New York, U.S.A.

Available in Canada from:—
Rogers Majestic Electronics Limited,
Dept. IE, 11-19 Brentcliffe Road.
Toronto 17, Ontario. Canada.

Mullard

ELECTRONIC TUBES

used throughout the world

MULLARD OVERSEAS LTD., CENTURY HOUSE, SHAFTESBURY AVE., LONDON, ENGLAND

Mullard is the Trade Mark of Mullard Ltd., and is registered in most of the principal countries of the world.

MEV35



In harness racing as in capacitors you pick the leader by looking at the record. That's why at Cornell-Dubilier, we're mighty proud of our record of new capacitor designs, consistent dependability and outstanding field performance —a record no other company can even come close to approaching. That's the record of

C-D...45 YEARS OF FAMOUS FIRSTS

Typical of these "Famous Firsts" are the examples shown here ... just three of the hundreds of money-saving answers in capacitors a C-D engineer can show you. Write to Cornell-Dubilier Electric Corp., Dept. K-16, South Plainfield, N. J.

CONSISTENTLY DEPENDABLE

CORNELL-DUBILIER CAPACITORS

PLANTS IN SO. PLAINFIELD, N. J.; NEW BEDFORD, WORCESTER AND CAMBRIDGE, MASS.; PROVIDENCE AND HOPE VALLEY, R. I.; INDIANAPOLIS, IND.; SANFORD AND FUQUAY SPRINGS, N. C.; SUBSIDIARY, RADIART CORP., CLEVELAND, OHIO.

THERE ARE MORE C-D CAPACITORS IN USE TODAY THAN ANY OTHER MAKE

NEW DOELCAM PROPORTIONAL AMPLIFIERS OFFER GREATEST VERSATILITY IN LOW LEVEL D-C SIGNAL APPLICATIONS

HERE ARE TWO PRECISION AMPLIFIERS incorporating the new *Doelcam Second Harmonic Magnetic Converter* as the input stage. This unique design concept makes possible low noise level, high sensitivity and linear output.

The Model 2HLA-3 is both a Linear Indicator and a Multirange Amplifier. The Model 2HLA-4 is a Single Range Amplifier with provision for interchanging range by plug-in units. Both are ideal for either laboratory or production use.





Laboratory Application



The fast thermal response of highly sensitive thermistors can be accurately measured and recorded.

Production Application



Measuring the dielectric leakage current of capacitors.

Production Application



Production testing of precision resistors or potentiometers in a balanced bridge circuit.

Write for Bulletin 1A-7 Write for Bulletin SRA6

WHETHER YOUR APPLICATION is in the laboratory or on the production line, one of these two instruments is ideally suited. Their versatility is illustrated in the diagrams shown here. The Model 2HLA-3 is both a precision measuring laboratory instrument and a rugged production test instrument. The Model 2HLA-4 is designed for rack mounting as a component part of a control or measuring system.

HERE ARE SOME PERFORMANCE CHARACTERISTICS:

- High Gain — 10^4 for 2HLA-3, 10^5 for 2HLA-4
- Low Noise — less than 5 microvolts equivalent input
- Linear Amplification—better than ± 1% on all ranges
- High Stability — zero drift less than 10 microvolts
- Rugged — withstands inputs of 1.5 volts

SPECIAL APPLICATIONS: These instruments can be easily adapted to provide linearity down to 0.1%, isolated input, multiple inputs, increased gain, increased power output and extended frequency response. Send us your complete requirements.

Laboratory Application



Dynamic stress measurements made with linear response up to 20 cps.

Control Application



Temperature control within a small temperature range.

Doelcam

A DIVISION OF MINNEAPOLIS-HONEYWELL

SOLDIERS FIELD ROAD
BOSTON 35, MASS.

Instruments for Measurement and Control

Synchros • Gyros • Amplifiers • Microsyns • Servo Motors

Want more information? Use post card on last page.



VARIABLE RESISTORS

EAST COAST OFFICE
Henry E. Sanders
130 N. Broadway
Camden 2, New Jersey
Phone: Woodlawn 6-1668
TWX No. Camden NJ 380
Phila. Phone: Market 7-3129

WEST COAST OFFICE
Robert A. Stackhouse
928 S. Robertson Blvd.,
Los Angeles 35, Calif.
Phone: Crestview 4-5931
TWX No. BEV H 7666

SOUTHWESTERN U.S.A.
John A. Green Company
6815 Oriole Drive
P.O. Box 7224
Dallas 9, Texas
Phone: Dixon 9918

CANADIAN DIVISION
C. C. Meredith & Co., Ltd.
Streetsville, Ontario
Phone: 310

SOUTH AMERICA
Jose Luis Pontet
Buenos Aires, Argentina
Montevideo, Uruguay
Rio de Janeiro, Brazil
Sao Paulo, Brazil

OTHER EXPORT
Sylvan Ginsbury
8 West 40th Street
New York 18, New York
Phone: Pennsylvania 6-8239



275,000 sq. ft. plant area . . . 1500 employees . . . making ALL TYPES of variable resistors by the million . . . for ALL TYPES of military and commercial applications.

Dependable delivery. Exceptionally good delivery cycle due to enormous mass production facilities.

A CTS control can be tailored to your specific requirement. Refer your control problems to CTS specialists today.

CTS

CHICAGO TELEPHONE SUPPLY
Corporation

ELKHART • INDIANA
FOUNDED 1896

The Exclusive Specialists in Precision Mass Production of Variable Resistors

BURTON BROWNE ADVERTISING



NEW **Printed Circuit Precision Resistors**

To meet the requirements for printed circuitry, RPC has developed Type P Encapsulated Wire Wound Precision Resistors. Miniature, single ended units designed for easy rapid mounting on printed circuit panels with no support other than the wire leads. Many newly developed techniques are employed in the manufacture of Type P Resistors. These units can be operated in ambient temperatures up to 125°C. and will withstand all applicable tests of MIL-R-93A, Amdt. 3. Available in 6 sizes, rated from 1/10 watt to .4 watt. ¼" diameter by ⅜" long to ⅜" diameter by ¾" long. Resistance values to 3 megohms. Tolerances from 1% to 0.05%.

Encapsulated Precision Wire Wound Resistors

RPC Type L Encapsulated Resistors will withstand temperature and humidity cycling, salt water immersion and extremes of altitude, humidity, corrosion and shock without electrical or mechanical deterioration. Type L resistors are available in many sizes and styles ranging from sub-miniature to standard with lug terminals, axial or radial wire leads. Available for operation at 105° C. or 125° C. ambient temperatures. These resistors will meet all applicable requirements of MIL-R-93A, Amdt. 3. Type L can be furnished with all resistance alloys and resistance tolerances from 1% to .02%.

Wire Wound Precision Resistors

Type A Precision Resistors are widely used for all general requirements. They are available in a wide variety of sizes, styles and terminal types. They can be furnished with all resistance alloys in tolerances from 1% to .02%. Type A will meet the requirements of MIL-R-93A, Amdt. 2, Characteristic B. Special winding techniques, impregnation and thermal aging result in resistors of exceptional stability. Matched resistors, networks and special assemblies can be supplied.

rpc

HIGH QUALITY RESISTORS FOR ELECTRONICS

RPC is a widely recognized supplier of high quality resistors to industry, Government Agencies and the Armed Forces. Advanced production methods, modern equipment and scientific skill enables RPC to manufacture resistors of *highest quality* in *large quantities* at *reasonable cost*. Modern manufacturing plant is completely air conditioned and equipped with electronic dust precipitators to insure highest production accuracy. RPC resistors are specified for use in instruments, electronic computers, radiation equipment, aircraft equipment and scientific instruments.

Test equipment and standards for checking and calibrating are equalled by only a few of this country's outstanding laboratories. Our ability to produce resistors of highest quality coupled with prompt delivery have established RPC as a leading manufacturer of resistors. Small or large orders are promptly filled.

Representatives in principal cities. For full information send for latest catalog.



Wire Wound Precision Meter Multiplier Resistors

Type MFA and MFB High Voltage Wire Wound Resistors are Hermetically Sealed in glazed steatite tubes with ferrule ends for maximum protection against all adverse environmental conditions. Fully meet all requirements of JAN-R-29. Special multi-section winding insures greatest safety factor due to low voltage gradient between sections. Standard resistors up to 6 megohms, 6 KV, 0.5% tolerance. Higher resistance and closer tolerances available. MFA 9-25/32 inches long x 1½ inches diameter. MFB 5½ inches long x 1½ inches diameter.

High Voltage Resistors

Type B Resistors are stable compact units for use up to 40 KV. These resistors are used for VT voltmeter multipliers, high resistance voltage dividers, bleeders, high resistance standards and in radiation equipment. They can be furnished in resistance to 100,000 megohms. Available as tapped resistors and matched pairs. Sizes range from a 1 watt resistor 1 inch long x ⅜ inch diameter rated at 3500 volts, to a 10 watt resistor 6½ inches long x ⅝ inch diameter rated at 40 KV. Low temperature and voltage coefficients. Standard resistance tolerance 15%. Tolerances of 10%, 5% and 3% available. Tolerance of 2% available in matched pairs.

High Megohm Resistors

Type H Resistors are used in electrometer circuits, radiation equipment and as high resistance standards. Resistance available to 100 million megohms, (10^{14} ohms). For utmost stability under adverse conditions Type HSD and HSK Hermetically Sealed are recommended. Eight sizes from ⅞ inch to 3 inches long are available. Voltage rating to 15,000 volts. Low temperature and voltage coefficients. Standard resistance tolerance 10%. Tolerance of 5% and 3% available. Also matched pairs 2% tolerance.

RESISTANCE PRODUCTS CO.

914 S. 13th Street
HARRISBURG, PA.

leadership in semi-conductors
from
Transitron

SILICON **GERMANIUM**

Transitron
SILICON POWER RECTIFIERS
Send for Bulletin TE-1321

Transitron
SUBMINIATURE GLASS GERMANIUM DIODES
Send for Bulletin TE-1319

Transitron
MEDIUM POWER SILICON RECTIFIERS
Send for Bulletin TE-1321 D

Transitron
GOLD BONDED GERMANIUM DIODES
Send for Bulletin TE-1300

Transitron
HIGH POWER SILICON RECTIFIERS
Send for Bulletin TE-1321 C

Transitron
MATCHED QUADS
Send for Bulletin TE-1310

Transitron
SILICON BONDED DIODES
Send for Bulletin TE-1308

Transitron
AUDIO TRANSISTORS
Send for Bulletin TE-1320

Transitron
SILICON JUNCTION DIODES
Send for Bulletin TE-1322

Transitron
POWER TRANSISTORS
Send for Bulletin TE-1320 C

All Transitron semi-conductors are produced to the most rigid military and commercial specifications to assure long life and complete reliability. They provide the trouble-free, dependable performance that is so essential in modern complex electronic equipment.

Whether your requirements are for Germanium or Silicon, the solution can be found in Transitron's diversified line of semi-conductors. A wide variety of standard types, along with over 300 special types, are available. Your inquiries are invited.

Transitron electronic corporation
melrose 76, massachusetts

Want more information? Use post card on last page.

*1/10 OF 1%...LABORATORY STANDARDS



the primary instrument standards the world over... for instrument checking and maintenance, and wherever measurements must be made to a high degree of accuracy. Available as D-C Voltmeters and D-C Ammeters, and as A-C and D-C Voltmeters, Ammeters, and Single Phase Wattmeters.

*1/4 OF 1%...PORTABLE STANDARDS

the portable reference standards, for checking instruments, certified test work, and laboratory measurements. Available as A-C and D-C Voltmeters, A-C and D-C Ammeters and Milliammeters, D-C and Single Phase A-C Wattmeters, Poly Phase Wattmeters, Power Factor Meters, Frequency Meters and Phase Angle Meters.

*ACCURACY RATED

Weston's comprehensive selection of accuracy ratings enables you to choose instruments which *exactly* meet your measurement needs from every standpoint...*conservatively rated accuracy, long life, low cost.* For literature, consult your local Weston representative, or write direct.

WESTON Instruments

WESTON Electrical Instrument Corporation

614 Frelinghuysen Ave., Newark 5 N. J. — *A subsidiary of Daystrom, Inc.*

*1/2 OF 1%...WORKING STANDARDS

the rugged portables for general test work where long, readable scales and high shielding are desired. Available as D-C Voltmeters, Ammeters, Milliammeters and Volt-Ammeters; and as A-C Voltmeters, Ammeters, Milliammeters, and multi-range Ammeters and Voltmeters; A-C and D-C Single Phase Wattmeters.

*1%...FIELD AND SHOP INSTRUMENTS

Miniature D-C portables for accurate measurements in shop or field. Available in all required ranges as D-C Voltmeters, Millivoltmeters, Ammeters, Milliammeters, and D-C Volt-Ammeters.

E-I OFFERS..

8 DESIGN ADVANTAGES

Cushioned Glass Construction
High Dielectric Strength
Design Standardization
Vacuum Tight Sealing
Vibration Resistance
Super Durability
Maximum Rigidity
Miniaturization



-and COMPLETE FACILITIES

MAIN PRODUCTION FACILITIES IN NEWARK, NEW JERSEY The Newark plant houses the main engineering and production facilities at E-I. Designing, tooling and assembly departments include the most modern methods and equipment known to industry, today.

CONTINUING RESEARCH KEEPS PACE WITH INDUSTRY'S NEEDS. The complete research laboratory located in Irvington-on-Hudson in New York assures products that anticipate the ever more critical requirements of the electronic industry.

THE HICKSVILLE PLANT ON LONG ISLAND IS EQUIPPED for all types of electronic production. The Hicksville facility is one of the oldest producers of transmitting tubes, x-ray tubes, magnatrons and all forms of glass-to-metal seals.

E-I HEADQUARTERS—for Compression Seals, Multiple Headers, Sealed Terminals, Condenser End Seals, Threaded Seals, Transistor Closures, Miniature Closures, Color Coded Terminals, etc.

One **dependable** source for **all** hermetically sealed terminal requirements!

ELECTRICAL INDUSTRIES

PATENTS PENDING
ALL RIGHTS RESERVED

Division of Amperex Electronic Corp. — 44 SUMMER AVE., NEWARK 4, N. J.



RCA "Special Reds" provide that extra "life-line" you need in industrial electronic equipment, air, marine, and land-mobile communications, and unattended relay and transmission circuits—that extra margin of safety and dependability that *keeps things going!*

RCA "Special Reds" feature remarkable *stability*, excellent resistance to shock and vibration, exceptional *uniformity* of characteristics from tube to tube—and are backed by RCA for 10,000 hours minimum life!

RCA "Special Reds" are recommended for initial designs in industrial electronic equipment. They are excellent as replacements in existing circuits where there is a prototype operating under conditions within the ratings of the "Special Reds."

CONTACT YOUR LOCAL RCA TUBE DISTRIBUTOR TODAY. Ask for your free copy of the booklet "RCA Receiving Type Tubes for Industry and Communications" (form RIT-104).

RCA-5690—Full-Wave Vacuum Rectifier with separate heaters and cathodes.

RCA-5691—High-Mu Twin Triode. Similar to the RCA-6SL7-GT, but has twice the heater current.

RCA-5692—Medium-Mu Twin Triode. Similar to the RCA-6SN7-GTB.

RCA-5693—Sharp-Cutoff Pentode. Similar to the RCA-6SJ7.

RCA ELECTRON TUBES
RADIO CORPORATION OF AMERICA

See why we don't use Automation?

It's not that we are old-fashioned, here at Karp. Far from it. We have one of the best tooled and equipped sheet metal fabrication plants in the world. Many of our machines, indeed, are equipped with electronic timing controls.

If the time ever comes when we feel that automation can give you finer work than our several hundred skilled craftsmen... we'll install automation. But that time is not now—nor in the foreseeable future.

You see, Karp was founded upon a perfectionist's idea about custom craftsmanship. Our methods are paying off because our painstaking work to exact specifications results in quality products to you, often at "ready-made" economies. And remember—our men who were skilled craftsmen ten or twenty years ago are even more highly skilled craftsmen today.

Let us quote you on your next requirement.

KARP METAL PRODUCTS CO.
Division of H & B American Machine Co., Inc.
214 63rd Street, Brooklyn 20, N. Y.

Custom fabricators of enclosures, chassis, panels in any metal • All welding facilities U. S. Air Force Certified • Air-conditioned spray room • Complete baking facilities • Over 3,000 dies available • Complete sub-assembly facilities

Want more information? Use post card on last page.



G-E Germanium Rectifier Production Breaks the 5 Million Mark

Customer requirements accelerate the production of a full line of highly reliable, long-life germanium rectifiers

THE NEW germanium rectifiers were introduced by General Electric in 1952 and since then more than 5 million units have been produced for industrial and military needs. In effect, this achievement represents more than *ten billion hours* of rectifier life—in hundreds of diversified commercial and military applications.

PROVED QUALITY! Of the 5,000,000 rectifiers produced, only a fraction of 1% have required adjustment under the terms of General Electric's full year warranty!

Wide Range of Designs. G-E rectifiers are available in a broad range of designs for many applications—for electronic computers, control equipment, power supply units, magnetic amplifiers; for military and industrial needs requiring custom designs; and for almost any application where DC power is required. G-E Germanium Rectifiers are more compact, and weigh less—as much as 75% less than comparable rectifiers of other types—and meet the rigid requirements for performance established by the U. S. Navy, Air Force, and Signal Corps. What's more, G-E Germanium Rectifiers are *warranted for one full year.*

Immediate Delivery. Mass production assures fast delivery on all G-E Germanium Rectifiers regardless of quantity. For complete information concerning your rectifier needs, contact your G-E Semiconductor Representative. Or, write: *General Electric Company, Semiconductor Products, Section X 416, Electronics Park, Syracuse, New York.*



Diffused Junction Germanium Rectifiers combine very high forward conductance with very high back resistance. The high temperature and magnetic amplifier rectifiers feature very low reverse current ratings at ambient temperatures of 85°C.



Power of the basic rectifier unit is boosted 5 times by adding a copper fin. Stacked one to twelve fins in series or parallel, the rectifier may be operated as half wave, full wave, or bridge circuits, and many other types of single or polyphase circuits. Typical power ratings are as high as 3 amps @ 190 volts; 1.3 amps @ 575 volts; 3.6 amps @ 140 volts, etc.



The Medium Power Rectifier has a 5 amp rating at 200 volts (55°C). At 85°C it is rated 2.5 amps at 100 volts. These rectifiers, stacked in series or parallel, have ratings in thousands of watts depending on the design of the circuit.

Progress Is Our Most Important Product

GENERAL ELECTRIC

UNLIMITED HORIZONS

THE NEW LIGHTWEIGHT U.S.A.F. J4 COMPASS SYSTEM PERMITS PRECISE FIGHTER NAVIGATION AT ALL LATITUDES

ANOTHER MAJOR GYRO PROBLEM SOLVED BY WEAPONS GUIDANCE LAB. U.S.A.F. AND KEARFOTT

This miniature Kearfott Directional Gyro is the heart of the U.S.A.F. J4 Compass System. The System provides both latitude corrected and magnetic slaved directional gyro heading information. Suitable output transmitters are incorporated to supply compass data to autopilots, course indicators, and other systems requiring this information. This system provides all the functions of the Kearfott designed U.S.A.F. N1 Compass System with little loss in accuracy despite a 66% reduction in weight. The J4 Compass System as designed by Kearfott was selected by the Air Force ". . . due to its adaptability to product improvement and Kearfott's ability to meet the urgent requirements of the Air Force."

U.S.A.F. J4 Directional Gyro
Random drift rate 3° per hour max.
Weight 7½ lbs.

OTHER KEARFOTT GYROS IN PRODUCTION

VERTICAL GYROS: Precise verticals with 2 mins. vertical accuracy (Bench) weigh 7 pounds and measure 5⅛" diam. x 6⅛" high. Miniature verticals with 15 mins. vertical accuracy weigh 3.5 pounds and measure 3" x 3" x 4" approx.

FREE GYROS: Designed specifically for missile applications with 1° per minute drift. Under 2000 cps vibration at 3G drift will not exceed 5°/ min. The gyro withstands 60G shock.

FLOATED RATE INTEGRATING GYROS: Designs include 2.5 x 10^6, 2 x 10^4 and 6 x 10^6 wheels. Representative random drift rate .25°/ hour on day-to-day basis. Standard deviation for one day run .05°/ hour.

STABLE PLATFORMS: 3 gyro, 3 and 4 gimbal designs now in development, flight test or production are suitable for primary gyro reference or for inertial applications.

There is a Kearfott Gyro suitable for every aircraft and missile application. Write today for detailed technical data.

KEARFOTT COMPANY, LITTLE FALLS, N. J.
Sales & Engineering Offices: 1378 Main Ave., Clifton, N. J.
Midwest Office: 188 West Randolph St., Chicago, Ill.
South Central Office: 6115 Denton Drive, Dallas, Texas
West Coast Office: 253 N. Vinedo Ave., Pasadena, Calif.

Kearfott

A SUBSIDIARY OF GENERAL PRECISION EQUIPMENT CORPORATION

Want more information? Use post card on last page.

WALKIEPHONE

PORTABLE RADIO TELEPHONE FOR PERSONAL CONTACT WITH KEY MEN

Policemen, Firemen, Foremen, Airfield Supervisors and many other key men are more effective when in constant radio contact with their headquarters. The Pye Walkiephone, which weighs only 10½ lb., is ideal for this purpose. An outstanding tribute to the Walkiephone was paid by Sir John Hunt, who praised the part it played in the victorious assault on Everest.

Telecommunications

CAMBRIDGE ENGLAND

Pye (New Zealand) Ltd.
Auckland C.I., New Zealand

Pye Radio & Television (Pty.) Ltd.
Johannesburg
South Africa

Pye Canada Ltd.
Ajax, Canada

Pye Limited,
Mexico City

Pye Pty., Ltd.
Melbourne, Australia

Pye Limited
Tucuman 829, Buenos Aires
Argentina

Pye (Ireland), Ltd.
Dublin, Eire

Pye Corporation of America
270, Park Avenue, Building A
New York 17. N.Y.

PYE LIMITED • • CAMBRIDGE • • ENGLAND

Phone: Teversham 3131

Cables: Pyetelecom, Cambridge

Want more information? Use post card on last page.

Over the twelve years that Fairchild has been making precision potentiometers — from our first unit (Type 736), on through the more than eighteen different types now in production — we have established and are carrying out a research and development program on new designs and materials, techniques and equipment that is constantly improving our potentiometer reliability. The results of this program are quickly applied to production units and these improved methods and designs are maintained by comprehensive quality control and type testing programs.

MAXIMUM RELIABILITY...

how do you get it?

Reliability in precision potentiometers resolves itself into three basic factors; longer shelf life, longer rotational life, and longer environmental life. Fairchild has increased the average shelf and rotational life expectancy of precision potentiometers far beyond usually expected life cycles, in one way, by compounding and using special potentiometer lubricants. Life expectancy and stability under abnormal operating conditions have been vastly increased through the use of precision-machined aluminum alloy case construction. Epoxy resin insulation, one-piece Paliney conductive springs and contacts, and precious metal alloy resistance elements, for certain applications, also contribute to increased life and functional reliability. Whether one or all of these factors of reliability are important to you, you'll do better to choose Fairchild Precision Potentiometers. For specific facts, write Fairchild Camera and Instrument Corporation, Potentiometer Division, 225 Park Avenue, Hicksville, Long Island, New York, Department 140-64A2.

FAIRCHILD
PRECISION POTENTIOMETERS

Want more information? Use post card on last page.

POTENT POWER + **SMALL SIZE**

Up to 5100 mmf at 300 vDCw
Up to 3900 mmf at 500 vDCw

(size) Length 3/4", average Width 7/16", average Thickness 3/16" DM-20 shown actual size

El-Menco Dur-Mica DM-20

DIPPED MICA CAPACITOR WITH PARALLEL LEADS

PEAK PERFORMANCE
ideal for new miniatured designs and printed wiring circuits

MEETS ALL HUMIDITY, TEMPERATURE AND ELECTRICAL REQUIREMENTS OF MIL-C-5 Specifications!

TEST IT AND COMPARE!

- El-Menco's Dur-Mica DM20 costs even less than our famous molded mica capacitors.
- Provides greater versatility — wider applications.
- Tougher phenolic casing assures *longer-life* and *greater stability* through wide ranges in temperature.
- Parallel leads simplify application in transistor and sub-miniature electronic equipment including printed circuits for military and civilian use.

For Extreme Miniaturization Use Our DM15

DM15 — Up to 510 mmf at 300 vDCw
Up to 400 mmf at 500 vDCw

Available in 125°C operating temperature. Minimum capacity tolerance available ±½% or 0.5 mmf (whichever is greater).



El-Menco Capacitors

to meet modern miniature requirements


Typical Capacitance Drift Limits — of DM20 DUR-MICA Capacitors after Temperature Excursion of 25°C to + 85°C to 25°C to -55°C to 25°C
April 14, 1955
CAPACITANCE DRIFT IN %
CHARACTERISTIC F LIMITS
DM20 DUR-MICA LIMITS
UNIT CAPACITY IN MMF


Typical Temperature Coefficient Range for DM20 DUR-MICA Capacitors
April 13, 1955
TEMPERATURE COEFFICIENT IN PARTS PER MILLION °C
CHARACTERISTIC C LIMIT
CHARACTERISTIC D and E LIMITS
MAXIMUM TEMP. COEF.
CHARACTERISTIC F LIMIT
MINIMUM TEMP. COEF.
UNIT CAPACITY IN MMF


Typical Temperature Coefficient Range for DM20 DUR-MICA Capacitors
April 13, 1955
TEMPERATURE COEFFICIENT IN PARTS PER MILLION °C
CHARACTERISTIC C LIMIT
CHARACTERISTIC D and E LIMITS
MAXIMUM TEMP. COEF.
MINIMUM TEMP. COEF.
CHARACTERISTIC F LIMIT
UNIT CAPACITY IN MMF

For your special requirements — we are pleased to offer information and assistance. Write for free samples and catalog on your firm's letterhead.

THE ELECTRO MOTIVE MFG. CO., INC.

WILLIMANTIC CONNECTICUT

• molded mica • mica trimmer
• tubular paper • ceramic

Arco Electronics, Inc., 103 Lafayette St., New York, N. Y.
Exclusive Supplier To Jobbers and Dealers in the U.S. and Canada



Two of the new Leesona No. 107 Automatic Coil Winders recently installed in the Clock and Timer Department of the General Electric Company, Ashland, Mass. The last word in automatic coil winder design, No. 107's wind paper-insulated coils in stick form. Automatic operation eliminates human error, reduces wire breakage to a minimum, cuts production time and costs. Inset shows a Type H3 Synchronous Motor, one of many Telechron timing units with coils precision-wound on Leesona No. 107 machines.

Clock and Timer Department, General Electric Company selects Leesona Coil Winders as standard equipment

General Electric Department adds No. 107 machines for proved production advantages

The synchronous timing motors made by the Clock and Timer Department of the General Electric Company are famous for accuracy and dependability.

One reason why is the high efficiency maintained by this department of the General Electric Company, in its wide range of coil winding operations. Leesona Coil Winders are standard equipment at General Electric Telechron plants — and during a recent expansion of production facilities, Leesona No. 107 Automatic Coil Winders were important new additions.

Leesona No. 107 machines are fully automatic. Every feature is designed to produce compact, uniform, paper-insulated coils — in fastest time — with minimum operator attention — at lowest cost. This General Electric department reports:

"The Short Paper Attachment on our Leesona No. 107 Coil Winders is a big advantage. Allowing an initial paper insert of 1 7/16", it eliminates the usual 2 3/4" insert when starting winding. On these particular coils the result is considerable savings in wire."

Get the Whole Story

on how Leesona No. 107 Automatic Coil Winders can bring new, profit-boosting efficiency to your own coil winding production. For complete details on this advanced machine — and other helpful coil winding information — check and mail the coupon today.

B.5.4



FOR WINDING COILS
IN QUANTITY...ACCURATELY
...AUTOMATICALLY...USE
UNIVERSAL WINDING MACHINES

UNIVERSAL WINDING COMPANY

P. O. BOX 1605, PROVIDENCE 1, RHODE ISLAND, Dept. 121

Please send me

- ☐ Bulletin on the Leesona No. 107 Automatic Coil Winder.
- ☐ Condensed catalog of Leesona Winders.
- ☐ Bulletin on the new Leesona *Pay-As-You-Profit Plans* for purchasing or leasing modern coil winding machinery.

Name.....*Title*.....

Company.....

City.....*Zone*....*State*.....

Want more information? Use post card on last page.

TRUFLEX® Thermostat Metal Coils Over ½ Mile Long in One Piece Simplify Fabrication and Reduce Costs in Thermal Element Manufacture

The problem . . . to obtain thermostat metal strip in a series of types having sufficiently uniform dimensional control and temperature response to be fabricated into finished parts on automatic machines.

The solution . . . Step 1; the consistent quality of each type of TRUFLEX tested quickly demonstrated that mass production by machine was fully practical for all types.

Step 2; General Plate Division then supplied the required types in long coils 3 feet in diameter with center hole to fit the customer's automatic machine arbors. Each coil is a continuous piece 1800 feet long, by 0.040″ thick and 0.250″ wide.

These coils save the customer many dollars by minimizing idle machine time and eliminating costly waste of material in fabrication.

If your products require temperature control . . . indication or compensation, the accurate performance and uniform high quality of TRUFLEX Thermostat Metals will save you money too.

Here's why! General Plate Division uses advanced production methods, combining the best equipment available with years of manufacturing "know how", to insure positive consistence in thermal and mechanical performance of TRUFLEX Thermostat Metals.

General Plate Division will fabricate parts from TRUFLEX to meet the specific mechanical and electrical performance demands of your particular applications. Or, if you prefer to make your own parts, General Plate Division will supply TRUFLEX Thermostat Metal in strip to meet your specifications.

Write today for your copy of the new TRUFLEX Thermostat Metal Catalog. Engineering assistance available without obligation.

GENERAL PLATE ELECTRICAL CONTACT KIT FOR LABORATORY AND DEVELOPMENT USE

Kit K11 contains a wide assortment of silver rivet contacts; Kit K12 has representative standard button contacts. Also included are metal strips for fabrication of contact parts. These kits are available at nominal cost.

METALS & CONTROLS CORPORATION
GENERAL PLATE DIVISION
111 FOREST STREET, ATTLEBORO, MASS.

You can profit by using General Plate Composite Metals!

MEMO

FROM: THE ENGINEERING STAFF AT NJE

TO: ENGINEERS INTERESTED IN HIGH VOLTAGE

SUBJECT: **What is Mature Design?**

Our "H-line" Industrial High-Voltage power supplies are a good example of mature design.

- 23 stock models blanket 95% of all applications.
- They are completely safe.
- They protect themselves against abuse and/or mishap.
- They are very flexible—reversible polarity, triple-range metering, 100% voltage control, wide-range trip-out adjustment.
- They are compact and relatively light. They mount in rack or cabinet. They make a striking appearance.
- Their simple, logical design uses the same circuit, the same components, the same techniques over and over again. This means purchasing and mass-production savings, which are reflected in our prices.

As we have said before, with the introduction of our H-line,

HIGH VOLTAGE COMES OF AGE!



Assembly of H-line control panels. All 23 stock models use the same chassis and circuit.

For our complete line of electronic power supplies See electronics BUYERS' GUIDE Pg. 113-120

Write for Catalog H-8 with complete prices and specifications of our H-line Industrial High Voltage Power Supplies.

NJE corporation

Electronic Development & Manufacturing

345 CARNEGIE AVENUE, KENILWORTH, NEW JERSEY

Competent Engineering Representation Everywhere | Rapid, complete, competitive custom quotes from 1000 Amperes (low voltage) to 250 KV (low current.)

POWER SUPPLIES UNLIMITED

MALLORY



SERIES 1800
shunt drive

SERIES 1850
separate drive

Two new Mallory vibrator models, developed for general commercial use, provide performance to meet military specifications . . . without extra cost!

New Mallory self-rectifying vibrators lead in long life, and dependable service

New construction. A new kind of leaf spring construction puts extra life and performance into the self-rectifying vibrators now available from Mallory. The contact arms attached to the vibrating reed are dual springs. This design effectively prevents "bounce" of the contacts to give clean make-and-break action, and provides dynamically balanced self alignment.

Count on them for longer life. Stopping of contact chatter eliminates a major source of contact wear . . . assures far longer service in every vibrator, minimizing danger of occasional early failure.

Engineered to fill the need for a premium-performance vibrator of this type for commercial power supplies, these new Mallory models are capable of meeting stringent military requirements. They can be relied upon to deliver the extra service you need . . . without premium price. For technical data, and for a consultation on your power supply requirements, write or call Mallory today.

New Heavy Duty Mallory Vibrator

The new 1700 series Mallory split-reed "communication type" vibrator* uses special alloy leaves which serve both as contacts and as springs . . . eliminating usual button contacts. Life is up to 100% longer, constancy of output improved, and driving power reduced. The new design is available both as a split-reed model for 6/12 volt service, and in a Duplex heavy-duty model without split-reed construction. For information, write or call Mallory.

*Patent applied for

Serving Industry with These Products:

Electromechanical—Resistors • Switches • Television Tuners • Vibrators
Electrochemical—Capacitors • Rectifiers • Mercury Batteries
Metallurgical—Contacts • Special Metals and Ceramics • Welding Materials

Parts distributors in all major cities stock Mallory standard components for your convenience.

Expect more . . . get more from

P. R. MALLORY & CO. Inc.
MALLORY
P. R. MALLORY & CO., Inc. INDIANAPOLIS 6, INDIANA

electronics

W. W. MacDONALD, Editor

JANUARY • 1956

CROSS TALK

► **FUTILITY?** . . . Referring again to the editorial entitled D.O.A., which appeared here in November and was followed up in December, it is interesting to note that several tv manufacturers reported unexpected increases in the sale of higher-priced sets in the last quarter.

There could be many reasons for this switch away from rock-bottom leaders on the part of the public. Among them, it is possible that people who have had their fingers burned by shoddy merchandise hope they can get good merchandise by paying more for it.

This may or may not be so at the moment, depending upon whether the additional dollar went into the chassis or into the cabinet. But it does indicate that the pendulum may be swinging back toward quality.

► **REVERSE ENGLISH** . . . As the trend toward greater automation continues, more and more manufacturers of machinery will get million-dollar orders largely on the strength of thousand-dollar electronic controls. And in many instances the controls will be made by somebody else.

Where the somebody else is an established maker of electronic equipment our industry will gratefully accept the new business and run. If history repeats there will be little thought on the part of the average electronics manufacturer about the relative size of the two orders, the thousand-dollar and the million-dollar package.

What prevents an occasional manufacturer of electronic controls from building or buying materials-handling, or production, or packaging machines for sale in combination with his controls? Must the tail always wag the dog?

► **UPSET THEORIES** . . . Up in the northland, near the spot where Marconi's first transatlantic wireless message was received 55 years ago, is a scatter-propagation station pushing radio signals hundreds of miles on a frequency believed for many years limited to just a little more than line-of-sight distances.

This reminds us that prior to 1901 many scientists thought that "magnetic signaling" would forever be limited to a maximum range of 165 miles.

► **NO SMUGNESS** . . . No industry is more reliant upon new technical developments for its future markets than the electronics industry.

The president of one of the largest companies in the field expressed this well in a recent speech in which he said "In our own company last year, forty-eight percent of our sales were in product lines which our research laboratories and engineers have developed within the past 10 years."

Even more significant because it promises continued growth was his statement that "There is no such thing as an entrenched and unassailable position in the electronics or appliance business."

► **CRYPTOGRAM** . . . One of our most cryptic critics says the word "reliability" is rapidly becoming as meaningful as the words "high-fidelity."

We'll be cryptic too, and leave it right there.

LOOKING AHEAD . . .

Rash of new-year market surveys, extreme activity of public-relations people, indicates increasing industry interest in commercial versus military business

Desire for shallower television-receiver cabinets points toward 110 or even 120-degree picture tubes; engineers are burning midnight oil to develop deflection circuits

Growing importance of electronics market to machine builders accustomed to leasing equipment could spread lease idea further as, for instance, in the instrument field

Electronics and other engineers are doing a lot of serious thinking about the nature of gravity; maybe it would help to think about it as a combination of centrifugal forces from outer space pressing upon the earth rather than as a pull from within the planet

Transistors Up Reliability

SUMMARY —— Four-channel broadcast remote pick-up amplifier similar to conventional equipment operates either from power line or internal batteries. Automatic cut-over relay prevents loss of program. Printed circuits help keep weight to 17 pounds

By PAUL G. WULFSBERG

Assistant Director
Research and Development
Collins Radio Co.
Cedar Rapids, Iowa

DEVELOPMENT of low-noise, low-cost, hermetically sealed transistors has opened the door to another area of products that can be transistorized. The broadcast remote amplifier is an example of a product in which transistors may be used exclusively without any sacrifice in cost or performance.

In addition, many new performance features may be achieved that were previously beyond the state of the art. Although little has been published on the use of transistors in high-fidelity audio circuits, they are well suited to this field, especially since they have the virtue of producing no microphonics. Reliability, which is important in broadcast equipment, is well served by the increased life of transistors and the fact that they are not susceptible to catastrophic failures but rather to a gradual decline in performance. This gradual decline is

Operating engineer using the self-contained transistor remote pickup broadcast and public address amplifier

# of Broadcast Remotes



Printed wiring boards shown as normally attached (left) and removed (right) to show components attached to underside

readily spotted in routine performance checks and does not cause program outages. This article describes the design considerations and details of an amplifier which takes advantage of new transistors now available in production quantities.

The broadcast remote amplifier is, in reality, a portable studio console. It permits the broadcast station to move the studio out to the program source and usually involves the use of several microphones. For example, a sporting event such as a football game may use as many as four microphones for full coverage of the event. The various microphone outputs are suitably mixed and amplified to a level of zero to +8 vu (+10 to +18 dbm) for transmission to the main studio over wire lines.

Customer Preferences

Design details of the remote amplifier were influenced by answers to a questionnaire mailed to a representative sample of broadcasting stations across the country. Among the features desired are a power source of both 115-v a-c and batteries with automatic power changeover when a-c power fails. Self-contained batteries with life of approximately 50 hours (25 hours minimum) are wanted. Maximum gain specified was 90 to 100 db. Also requested was a bridging volume control for public address feed and tone oscillator for line-level setup.

Preamplifier Problem

The first problem considered was suitability of transistors in low-level preamplifier service. After testing many transistors for noise figure, it was found that a preamplifier could be built with performance comparable to that of the best studio consoles. Figure 1 shows the curve of noise figure vs frequency for selected samples of type 2N106 units.



FIG. 1—Noise figure vs frequency for selected samples of 2N106 type transistors

Although the noise factor for frequencies below 1,000 cycles is not too impressive, the mean average noise for a 15-kc bandwidth is only about 3.6 db, which is considered acceptable. Noise power output of an ideal resistor of any resistance value for a bandwidth of 20 kc (typical for broadcast amplifiers) is −124.8 dbm.

The final design of this amplifier provides an equivalent noise input as low as −120 dbm (60 db below a −60 dbm input) which is only 5 db above the ideal amplifier. The input impedance of the grounded-emitter circuit used is about 1,000 ohms. Since it was found that the mismatch losses between the microphone and the transistor were only 1 to 5 db, as shown in Fig. 2, the usual input transformer was eliminated. This also eliminated the hum pickup and frequency-response problems associated with this transformer.

The weight and cost saved by eliminating the input transformer made practical high-level mixing through the use of individual microphone preamplifiers. In vacuum-



FIG. 2—Mismatch loss between microphone and transistor is slight enough to eliminate transformer



FIG. 3—Elements of the transistorized broadcast remote pickup amplifier. Detail of two input stages similar to others has been eliminated for simplicity. Complete circuit detail is given in Fig. 4

tube designs, high-level mixing is not nearly so easily attained since the battery drain for individual preamplifiers is high and multiple input transformers are heavy and costly.

As illustrated in Fig. 3 and Fig. 4, the individual preamplifiers are followed by ladder type input faders. Outputs from the four faders are paralleled and fed to the second preamplifier stage, which is nearly a duplicate of the input stage. The booster stage follows, using a less-expensive higher-noise transistor.

Owing to the high level from this point and on, noise is no longer



FIG. 4—Complete diagram of the remote amplifier shows that it can be operated from power line for best economy but switches automatically to batteries in event of power failure

a design consideration. This condition is indicated in Fig. 5, which shows typical operating levels throughout the amplifier. The booster stage is followed by the master gain control that is used for initial output level adjustment and is not normally varied during a broadcast. Both the input and master gain attenuators use a 2-to-1 step-down impedance for low insertion loss.

Output Circuits

The master gain control feeds the driver stage, which in turn drives the high-level push-pull output stage. Techniques for achieving the high-fidelity characteristics[1] of this section have been described. The output transformer feeds the line through suitable switching as shown in the diagrams. It has a second output winding for feeding a bridging load, normally the public address system often used for the audience present at the broadcast.

This eliminates the need for separate public-address microphones and gives the engineer better control of the local public address system, since it may be operated by another person not concerned with the broadcasting end of the program.

Other Circuits

A tone oscillator, employing a Colpitts circuit, is used to provide 400 cycles for advance circuit lineup to the main studio. It is fed through the TONE switch to the second preamplifier. The microphone circuits are cut when the tone oscillator is in use.

The power supply for the amplifier permits either a-c or battery operation. The a-c supply uses a full-wave circuit employing a pair of 1N48's to give an output of 22.5 volts at 15 to 20 ma. The total a-c power consumption from the line is 1.5 watts.

Emergency Battery

In case of a-c power failure, a relay automatically transfers to the battery supply, preventing program outages. Several instances have been reported in which this feature has been valuable in a previous design. However, in one case where the announcer was covering a collegiate basketball game, the power and light failure caused the game to be halted, leaving the announcer with an operating amplifier but no game to broadcast.



FIG. 5—Typical operating levels in dbm throughout amplifier



FIG. 6—Response and output level taken at 15 dbm output

As will be noted from the schematic diagram, extensive filtering is employed in the power supply to control hum and noise. One of the characteristics of transistors appears to be the need for well filtered supply voltages.

Battery power consumption is 350 milliwatts, which is only about one-third that of a typical heater-cathode tube filament. An additional 4.5-volt battery may be used if desired for vu meter illumination. An interlock switch prevents the power from being left on when the unit is in its carrying case.

Printed Circuits

Printed circuits are used extensively in the amplifier to reduce the space and cost factors. It is also expected that uniformity from unit to unit will be improved with printed circuits. For maximum strength and resistance to heat and humidity, glass-base epoxy resin type boards, shown in the photograph, are employed.

The remaining components are for the most part fastened directly to the chassis proper. The a-c power supply is, however, mounted on a separate bracket and may be seen at the lower center of the photographs. The batteries are mounted in such a way that they cannot be seated if they are reversed in polarity. This prevents damage to the transistors from operator error.

Performance Summary

The performance of the amplifier in its final form has exceeded expectations. Weight of the complete units including batteries is only 17 pounds. The carrying case, used like a portable typewriter case, adds five pounds additional weight bringing the total to 22 pounds. The height of the amplifier scarcely exceeds five inches, and the volume of the unit is half that of its predecessor.

Figure 6 shows the response and distortion taken at an output level of +15 dbm. The measured equivalent noise input is −116 to −120 dbm and the gain into the line pad is 96 db.

The amplifier shows that transistors have their place in high-fidelity circuits, particularly where portability and low battery power are important. In this particular unit, battery power was reduced by a factor of 15 over the previous design. The absence of microphonics in transistors is another advantage which in some applications, such as hearing aids, is important. This feature should make transistors useful in the preamplifier stages of studio consoles, especially since the noise factor has been recently improved.

Reference

(1) Robert L. Riddle, High Fidelity Transistor Power Amplifier, ELECTRONICS, p 174, Sept. 1955.



Top view of control relay shows arrangement of circuit components with explosive squib at lower right-hand corner

Fuel Cut-Off Control

SUMMARY — Low-frequency audio signal applied to relay cuts off missile fuel. Parallel-T feedback network provides stable, high-Q selectivity over 2-to-1 range of frequencies. Built-in low-power gamma-ray source stabilizes operating potential of neon voltage regulator

DESIGNED for use in conjunction with a radar-beacon system as as fuel cut-off control for guided missiles, frequency selectivity and stability of operating potentials were factors of prime consideration in the development of an audio-frequency operated relay.

Subminiaturization techniques were used to develop the unit shown in the photograph. The complete unit measures only 6¾ inches end to end.

Selective Circuit

By developing a tunable parallel-T feedback circuit, stable high-Q selectivity was obtained over a 2-to-1 range of audio frequencies.

Tunable from 88 to 154 cps, the input circuit in the schematic of Fig. 1 comprises a center-fed parallel-T network connected between the plate and grid of high-transconductance triode V_{1A}. By center feeding the network, several advantages are obtained. The R-C integrating network formed by the input circuit greatly reduces any response to noise and transients.

For maximum Q, a parallel-T network should feed into as high an impedance as possible. If the grid end of the network were used as signal input, the relatively low impedance of R_1 plus the generator impedance would shunt the output of the parallel-T. The resultant loss of Q would be detrimental to the performance of the circuit, especially when the center frequency is detuned from the point of best symmetry. This effect is substantially reduced by feeding the network at the center or low-impedance point. At the same time, a high degree of stability is obtained due to the integration of the input signal.

Oscillation will occur in all phase-shift networks whenever too much



FIG. 1—Selective a-f control relay. Radium-coated metal band encircles V_5 to stabilize its operating potential. Squib consists of carbon element, which when heated ignites a small explosive charge that propels a silver pin between two contacts



Bottom view of control relay shows arming pin inserted in switch (safe position). Neon regulator with radium band is at center

for Guided Missiles

By GERALD L. ZOMBER and DONALD MACMILLAN

Avion Instrument Corporation
Paramus, New Jersey

gain is applied for a given amount of feedback. Gain of the amplifier is controlled by R_2, which is adjusted for the desired Q. The circuit will provide stable Q values up to 100. Rheostat R_3 controls phase shift and sets the frequency of the selective circuit.

Voltage Regulation

Since variations in the plate supply could cause instability, voltage regulation of the input plate supply is essential. Therefore, tube V_{1B} is utilized as an open-loop shunt regulator, with an NE-2 neon lamp, V_5, serving as a voltage reference. It was found that the ionization and operating potentials of this neon tube could be stabilized by subjecting its elements to low-power gamma radiations. To effect this, a small precious-metal band containing a microgram of radium was glued around the envelope of the NE-2 using glyptal cement.

Resistor R_4 is selected to provide +128 v at the cathode of V_{1B}.

A conventional a-c amplifier having a gain of approximately 400 is used to bring the signal level up to an amplitude which, after rectification, is sufficient to cut off V_{2A}.

In the quiescent state, V_{2A} and V_{2B} conduct essentially equal currents. Since their plate voltages are nearly equal, no net potential exists between the plate and cathode of thyratron V_6, so that this tube is not conducting.

When a signal of proper amplitude and frequency is applied to the input, it passes through the selective portion of the circuit and is rectified by the 1U1. Resulting negative voltage drives the grid of V_{2A} to cutoff. This action causes the plate potential of V_{2A} to rise, thereby charging C_3. As this charging voltage reaches a level sufficient to fire neon lamp V_6, the consequent flow of current through R_6 increases the grid voltage of thyratron V_4 until it fires. This action permits C_1 to discharge through the squib, provided the switch is in the armed position (arming pin withdrawn). Ignition of the squib sets off a tiny explosive charge that closes the output circuit, thereby closing a solenoid valve to cut off the fuel supply of the missile in which it is installed.

Safety Feature

When the arming pin is inserted in the switch, resistor R_6 is substituted for the explosive relay and the latter is connected in series with B+ to apply voltage to the plate of V_{2B}. If the explosive squib should be open circuited, the anode of V_{2B} will be at or below ground potential, so that V_4 will have no cathode bias. In this case, it would fire before V_6 fires and V_5 would not glow. This indicates a defect in the squib circuit. Failure of any tube will cause the unit to remain inoperative, since C_1 will not be charged and the squib will not ignite. Also, in case of plate or heater voltage failures, the squib will not ignite.

Other Applications

Besides its application as a fuel cut-off control for missiles, this selective a-f control relay may be used, upon substitution of a suitable relay for the explosive squib, as a telemetering-switching-command detector in missiles, radiosondes, weather balloons and as a relay in other remotely controlled devices.

Development of this device was sponsored by the U. S. Army Signal Corps.

The authors appreciate the assistance and encouragement rendered them by the engineers of the GMI Branch, Radar Division, Evans Signal Laboratory, Belmar, N. J.

Solution of five-component chemical kinetics problem requires only five of computer's ten amplifiers

Ten operational amplifiers, power supplies and detachable problem board comprise a . . .

——Simplified Analog

FUNDAMENTAL BEHAVIOR of physical systems, whether electronic, aerodynamic, mechanical, acoustic or other, is best described by differential equations. With a simple computer, an unlimited number of practical system equations may be solved even more easily than setting down the explicit equations themselves.

Elaborate electronic computers are an indispensable aid in solving complicated problems like the stability of high-speed aircraft or the accuracy of fire-control systems. Appropriate emphasis is placed on accuracy and versatility so that the most complex problems can be handled. Economic considerations are entirely secondary.

By contrast, the computer in the photograph provides the same facility for solution of everyday problems in differential equations that the desk calculator gives for problems in arithmetic—with comparable investment and operating economy.

The computer is applicable to monitoring or control of industrial processes, solution of closed-loop problems in the laboratory and the analysis of regulating systems or devices. In addition, the computer provides an ideal means for study or demonstration of differential equations, Laplace transforms, exponential functions, modulation, oscillating systems, logarithmic decrements, damping factor and other aspects of mathematical or physical systems. Accessory equipment can adapt it for the solution of general nonlinear problems.

Theory of Operation

The computer is an electronic differential analyzer which solves physical or mathematical problems by analogy between two sets of equations. One set of equations expresses the problem which the computer is asked to solve. The second set is set up by the computer operator to form a consistent quantitative analogy between the two sets of equations.

The computer yields the time-dependent solution of differential equations automatically through the use of operational amplifiers. These units provide the fundamental functions of integration, multi-



FIG. 1—High-gain d-c amplifier



FIG. 2—Amplitude transfer characteristics of d-c amplifier

SUMMARY —— Everyday problems in differential equations yield to solution by compact analog computer that sacrifices extreme accuracy and elaborate design but is sufficiently versatile to handle the most complex problems

By VICTOR B. COREY

Technical Director
Donner Scientific Company
Berkeley, California

Computer

plication or division by a constant, addition, subtraction and sign changing required to reduce the differential equations to a closed representation in analog form. Rules of procedure permit progressive setup of the differential equations to be solved through repeated integration and summation of terms to find the variables of final interest.

Operational Amplifiers

The ten operational amplifiers in the computer are identical. Using the circuit of Fig. 1, each amplifier meets the requirements for reliable and accurate performance in an electronic analog computer intended for both repetitive and extended time solutions.

The amplifier employs a 6AU6 high-gain input pentode, V_1, and a direct-coupled 6BQ7A dual triode, V_2, operated as a cathode-follower output. The load impedance of the cathode follower is a series arrangement of an OA2 voltage-regulator, V_3, and one triode section of a 6BQ7A, V_4. Returned to a regulated source of −300 v, V_4 maintains essentially constant plate current over a wide range of plate voltage. An output voltage balanced about zero for zero input voltage is generated with respect to ground at point *A*. The second triode section of V_4 serves a duplicate function for an adjacent operational amplifier.

Coarse d-c balance potentiometer R_1 compensates for gross offset in output voltage at zero input voltage. The fine d-c balance potentiometer R_2 has a more limited range and is used for final setting of 6AU6 cathode potential to make zero output voltage correspond with zero potential on the input grid. Once this adjustment has been made, output voltage will be proportional to input voltage over an output range of ±100 volts.

The conductance through R_3 and R_4 changes the cathode potential of V_1 in the same direction as the output voltage. This is equivalent to an increase in the potential at the input grid and represents positive or regenerative feedback. Thus less signal is necessary at the input grid to obtain a given output voltage. Increasing the conductance of the feedback path by decreasing

R_s can increase positive feedback to the point of infinite gain so that the ratio of output voltage to the signal on the input grid increases without limit. Infinite gain can be achieved under one set of operating conditions, but the changes in tube characteristics over the operating range impose a practical limit on average gain at the extremes of the range.

Characteristics

Experimental measurements of output voltage versus input voltage for a typical amplifier are shown in Fig. 2. Infinite gain over the full operating range would be represented by a horizontal line through the origin extending from −100-v output to +100-v output. The curve for the unloaded amplifier ($R_L = \infty$) shows that a maximum grid signal of 5 mv is required for operation over the full ±100-v range and that average gain over most of the range is greater than 40,000. The lowest value of average gain under full load (R_L = 20,000 ohms) is 10,000 at +100-v output, where an input of −10 mv is required. Even under full load, average gain exceeds 30,000 over most of the operating range.

The amplifier of Fig. 1 is shown symbolically in Fig. 3A. Gain A is high and the input and output are of opposite polarity.

When a high-gain amplifier is used in an analog computer it is made an operational amplifier by adding two passive external impedances, as shown in Fig. 3B[1]. Impedance Z_i is connected in series with the input voltage e_i. Impedance Z_f is connected directly between output and input of the amplifier and introduces negative feedback. In Fig. 1, Z_f would be connected between point A and the grid of V_1.

The value of grid current for V_1 has been found consistently below 1 millimicroampere under normal operating conditions. Since currents in Z_i and Z_f of Fig. 3B will nearly always be between five hundred and five million times this value, the grid current may safely be neglected.



FIG. 3—High-gain amplifier (A) is converted to operational amplifier (B) by external impedances. Amplifier can be used for summation (C) and integration (D)

With the addition of Z_i and Z_f, the gain of the amplifier becomes independent of all circuit parameters except Z_i and Z_f. The general case is illustrated in Fig 3C where n separate voltages e_1, e_2, e_3, ..., e_n are fed to the amplifier through n input impedances Z_1, Z_2, Z_3, ..., Z_n. A single impedance Z_f is connected directly between input and output of the amplifier.

For algebraic summing of input voltages, sign changing and multiplication or division by a constant, impedance Z_f and all input impedances are resistances. In practical operation the ratio R_f/R_i is not allowed to exceed 50. For integration, impedance Z_f is a capacitance and the input impedances are resistances. The characteristic operation of such an arrangement can be seen in the simple integrator of Fig. 3D. Since $i_g \doteq 0$, the current through R_i is continuous with the charging current on C_f.

If the voltage across the capacitor is V and its instantaneous charge is $q(t)$, the charging current is

$$i(t) = dq(t)/dt = d(VC_f)/dt = C_f(dV/dt)$$

But the negative feedback operation of the high-gain amplifier keeps $e_g \doteq 0$ so that the input grid is held at ground potential for any normal value of output voltage. The current equation therefore becomes

$$e_i/R_i = C_f(dV/dt) = -C_f(de_o/dt)$$

It follows that

$$e_o = -\frac{1}{R_iC_f}\int_o^t e_i dt + e_o]_{t=o}$$

The arbitrary constant of integration $e_o]_{t=o}$ is supplied by the voltage across C_f when $t = 0$.

Differential Equations

By more complicated input and feedback impedances, single operational amplifiers may serve a variety of special functions such as the generation of the electrical analogs of Laplace transforms. However, the amplifiers' basic role in the computer involves their use in combination to solve differential equations.

To solve such a problem with the computer a formal procedure[3] may be adopted in which it is assumed that an input signal representing the highest derivative is available to a specified operational amplifier in the computer. If this amplifier is connected as an integrator, its output voltage will be proportional to the next lower derivative with sign reversed. This voltage may serve as input to the next operational amplifier, again connected as an integrator and the process repeated.

The highest derivative in the differential equation to be solved by the computer may be expressed

mathematically in terms of lower derivatives, the dependent variable itself and the driving function. As a final step in setting up the computer to solve the problem, the highest derivative is so expressed in circuit form. Lower order terms are taken from the operational amplifier outputs where they are assumed to be generated through integration.

The input driving function is supplied from an external function generator or synthesized by other operational amplifiers in the computer. All terms are combined in the proportions specified by the differential equation and fed into a summing amplifier. Any necessary changes of algebraic sign are introduced by additional operational amplifiers.

Output of the summing amplifier is connected to the amplifier input where the highest derivative was first assumed to exist. Alternatively, the summing operation can be combined with the first integration in a single operational amplifier. When the highest derivative is synthesized in the proportions specified by the differential equation, the unique requirements of the equation are imposed on the solution delivered by the computer. To generate the correct definite integral at the output of each operational amplifier connected as an integrator, it is necessary to apply the initial condition voltages which correctly define the various constants of integration. These voltages are maintained by separate sources until the time $t = 0$ when the voltage sources are simultaneously disconnected and the problem is released to the computer for solution.

Functional Arrangement

The computer comprises the amplifier section, power supply section, cabinet and problem board. The amplifier panel and power-supply panel are the upper and lower sections of the computer. The completely detachable problem board plugs into two multiconductor connectors near the bottom of the power-supply panel.

The amplifier section contains ten operational amplifiers, arranged side by side on a single chassis.

The front panel of the amplifier section is furnished with controls for both selection and adjustment and a 4½ in. zero-center meter. A row of lights near the top of the panel indicate actual or approaching overload for the operational amplifiers.

The power supply section contains the main regulated power supplies for the operational amplifiers, separate regulated initial-condition power supplies with their output controls, relays and connectors.

The two multiconductor connectors near the lower edge of the panel carry the amplifier and relay connections to the problem board. To minimize crosstalk between amplifiers, all the amplifier input wiring is routed through the connector at the left while the connector at the right carries the wiring from the amplifier outputs. For the same reason the ten compute-reset relay poles are divided into two equal groups which are routed separately through the two connectors.

The main positive and negative high-voltage power supplies for the operational amplifiers are individually electronically regulated to approximately 0.25 percent for line-voltages changes from 105 to 125 v and amplifier loads up to 5 milliamperes. The negative supply, which delivers a regulated voltage −300 v at 130-ma constant load current, is controlled with respect to the voltage drop across an OA2 voltage regulator operated at constant current. The positive voltage supply uses the regulated voltage of output of the negative supply as a reference and delivers 370 v at load currents up to 180 ma.

The problem board provides connections between operational amplifiers and external computing elements which generate the electrical analogs of differential equations.

Each problem board is furnished with a bottom cover plate which serves as a shield and reduces 60-cycle hum on any amplifier output to an unimportant level.

The compute-reset relays maintain an independent initial-condition voltage across the feedback capacitor of each operational amplifier used as an integrator until the problem is released to the computer for solution. Thereupon the compute-reset relays disconnect each integrating capacitor from its initial-condition power supply and connect the input of each operational amplifier used as integrator to the proper driving point in the circuit analog.

Hold-Operate Relays

During normal reset or compute operations the hold-operate switch is kept in the operate position. The hold-operate relays remain deenergized in this position. The center terminal of each relay group is directly connected to the pole of its compute-reset relay. However, when the switch is thrown to HOLD, the hold-operate relays are energized and the center terminal of each relay group is disconnected from its compute-reset relay pole.

The hold function is used when problem solution is to be interrupted temporarily for examination or change of parameters or scale and then resumed.

Two or more computers may be used as a single larger computer. To synchronize compute-reset operations the two-conductor compute-reset plugs at the lower rear of the computer cabinet are connected in parallel for all computers. Operation of the compute-reset switch of any one computer produces simultaneous operation of the compute-reset relays in all computers combined with it. A similar arrangement may be used to synchronize the hold-operate function.

Many design aspects of this computer are directly related to characteristics of simplified analog computers originated by the Systems Development Section, Aviation Ordnance Department, Naval Ordnance Test Station, Inyokern, California, and used there since 1949.

REFERENCES

(1) Dewitt H. Pickens, Electronic Analog Computer Fundamentals, ELECTRONICS, 25, p 144, Aug. 1952.
(2) R. C. H. Wheeler, "Basic Theory of the Electronic Analog Computer", Donner Scientific Co., Berkeley, Calif.



THE FRONT COVER—Tool setup for cutting intricate shape in aluminum oxide in a single operation, note finished workpiece

Ultrasonic Machining of

SUMMARY — Slicing or cutting germanium, silicon, quartz, ferrites, glass-bonded mica and other materials at high speed by impact grinding results in greater precision and makes possible a great variety of shapes

SEMICONDUCTOR DIODES and transistors, as well as complex ferrite and ceramic shapes, must be produced in volume and at minimum cost. Since no compromise in precision can be allowed, conventional machining methods are no longer adequate. All these requirements are met by ultrasonic impact grinding, with significant advantages.

The processing of germanium, silicon and quartz for diodes, transistors and frequency-control crystals is performed in two operations: slicing and dicing.

In the first operation, boules of the material, usually between 0.5 inch and 1.25 inches in diameter, are sliced into thin wafers.

After being sliced, the wafers are cemented flat onto a glass or ceramic block and cut into small squares or disks or into rectangular bars. This operation is called dicing.

Slicing and dicing have usually



FIG. 1—Tool for slicing quartz crystals showing quartz boule and wafers (A) machined ferrite core (B) and ceramic-spacer holes cut to close tolerances (C)

ULTRASONIC IMPACT GRINDING

- The cutting tools are rugged and usually inexpensive
- Attaching tools to the machine is simple. The setup is readily changed from one tool to another, providing great versatility
- The operating principle insures sharp edges on every cut, as well as perfect duplication of the tool shape in the workpiece
- Since tool shape is duplicated in the workpiece, there are no restrictions on the shape to be cut. Tools can be round, square, triangular or any other shape
- Because lapping grades of abrasive are used to do the cutting, a fine surface finish is produced which requires a minimum of subsequent surface lapping

By **MAURICE S. HARTLEY***

Director of Engineering
Sanborn Company
Cambridge, Mass.

Brittle Materials

been done by means of diamond wheels ganged on an arbor to give the desired wheel spacing. This method has several drawbacks: diamond wheels are costly, and very thin wheels are subject to breakage; much time and skill are required to assemble an arbor of precisely spaced wheels, thus restricting the versatility of the ganging setup; diamond sawing tends to leave rough edges at the edge of each cut, especially in deep cuts, so that extensive lapping is required to finish each wafer; a diamond wheel cannot be used for dicing round disks from the wafer.

Impact grinding offers a number of advantages, the most important of which are listed in the box.

In ultrasonic impact grinding, as with diamond-wheel cutting, there are limits to the area which can be machined in one operation. Also, it is not possible at present to slice wafers thinner than 0.015 inch with consistent results.

Figure 1A shows a multiple-blade cutting tool assembly, mounted on its supporting and driving tool cone, with typical crystal wafers.

Designers of magnetic cores for high-frequency transformers, electronic computer switches and microwave transmitting devices can now explore the advantages offered by the electrical and magnetic properties of ferrite crystals.

By means of impact grinding, this material can readily be shaped in one piece with sharp corners and precisely oriented sides. Moreover, the core is not subjected to stress during machining.

The ferrite core shown in Fig. 1B was cut from an 0.125-inch thick single crystal wafer in less than two minutes. The procedure, developed for the study of domain patterns in ferrite, involved six steps. Each ferrite crystal was first x-rayed to determine the orientation of its lattice structure, then mounted on a rectangular steel block with the edges properly located. The block was mounted on a rotary table which was placed on the worktable of the impact grinder. This arrangement permitted the crystal to be positioned at any desired angle with respect to the face of the soft-steel tool.

For each cutting, 600-grit boron-carbide abrasive in liquid suspension was dammed around the crystal with modeling clay. Grinding was accomplished without producing stresses that might have affected the internal structure of the crystal.

Glass-Bonded Mica

Glass-bonded mica, like other hard abrasive materials with a strong grain structure, is difficult to machine by conventional methods. The operator must take special care not to force the tool since the material is susceptible to internal damage from heat and pressure even when the cut looks perfect. By the use of impact grinding this material is readily machined with no danger of hidden damage.

Ceramics

When aluminum-oxide ceramic spacers are fired after the conventional molding process shrinkage occurs which makes it difficult to obtain the required shape. Each change in the location and shape of the holes requires expensive mold design and fabrication.

Simultaneous machining of multiple holes in finished blanks on the impact grinder was tried as an alternative to molding and proved to be an immediate success. Figure 1C shows a 0.030-inch-thick, 0.75 by 1.25-inch ceramic spacer produced at the rate of three per minute.

Not only are the tolerances uniform from piece to piece, but changes in location of the holes are made by positioning of the workpiece. Shape changes are also economically accomplished by conventional machining of the cold-rolled-steel tool tip, which is then easily soldered to the tool cone of the grinder.

The impact grinder, sketched in Fig. 2, comprises: a driver unit which serves as a source of ultrasonic (25-kc) electrical power for the cutting head; a pedestal unit that carries the cutting head and locates and feeds the work to it; an abrasive unit that circulates and feeds an abrasive fluid to the cutting tool; a head unit that sup-

* Work done while at Raytheon, Waltham, Massachusetts.

ports and drives the cutting tool; an interconnection unit that provides electrical services and interconnections to the various units; and a water-flow switch unit to prevent operation without cooling-water flow through the head unit.

Incorporated in the head unit is an electromechanical transducer which converts alternating current supplied by the driver unit into mechanical vibrations at 25 kc. These vibrations are amplified and transmitted to the cutting tool by means of a shaped tool cone. The cutting tool is secured to the tip of the tool cone and vibrates perpendicularly to the tool face (along the cone axis) without side-to-side motion.

The transducer, shown in cross-section in Fig. 3, is of the magnetostriction type and utilizes pure nickel laminations as the core material. Attached to the nickel is a mechanical-amplitude transformer, the transmitting cone, and the resonant support which is rigid at low frequencies but highly compliant at 25 kc. The resonant support is designed to hold the device securely but permit free vibration, while the transmitting cone drives the tool cone to relatively large longitudinal vibrational amplitudes at the resonant frequency. The tool cone is also a mechanical-amplitude transformer which supports and drives the cutting tool. Typical amplitude of vibration for a 0.5-inch-diameter cutting tool is 0.003 inch. Larger amplitudes may be obtained with smaller cutting tool diameters.

Table I—Impact Grinder Performance

Material	Ratio of Stock Removed to Tool Wear	Maximum Practical Grinding Area (sq in.)	Typical Grinding Rate ½"-dia. Tool, ½" Deep (in./min)
Quartz	50/1	1.4	0.045
Ferrite	200/1	3.1	0.075
Germanium and Silicon	200/1	3.1	0.075
Ceramic	150/1	2.4	0.060
Glass	200/1	3.1	0.100
Carbon	150/1	2.0	0.060
Glass-Bonded Mica	200/1	3.1	0.075
Synthetic Ruby	2/1	1.2	0.020
Mother of Pearl	200/1	3.1	0.075
Boron Carbide	3/1	1.1	0.015
Tungsten Carbide	1/1	1.2	0.009
Tool Steel	1/1	1.2	0.007

Impact grinder employs 320-grit boron-carbide abrasive and cold-rolled steel tool

Cutting Process

A small space filled with abrasive fluid develops between the vibrating tool face and the workpiece. Tiny particles of abrasive, accelerated by the motion of the cutting tool, are driven with tremendous impact against the work. Thereby an exact counterpart of the tool face is chipped or ground into the work. The work is fed up to the tool to maintain constant grinding force between the two.

Despite the fact that the abrasive particles strike the work with impact forces up to 150,000 times their own weight, the grinding force required seldom exceeds 10 pounds. This small force, together with the vibratory nature of the process, the absence of direct tool-to-work contact and the use of cool abrasive, combine to make impact grinding a cold-cutting and stress-free process.

The work material is not stressed or distorted and is not raised in temperature. It is normally unnecessary to clamp the work, and there is no tendency for the tool to wander. Existing or unfinished work may be taken up again with old or new tools without difficulty in recentering or relocation.



FIG. 2—Diagram of the impact grinder showing all units of the equipment

Design

The transducer design problem is the central one in impact grinding. Cutting rate varies directly with frequency and amplitude of vibration, and so it is desirable to have these as high as possible. The maximum useful amplitude is limited by the strength of available materials for the cutting tool, for the tool cone, and for joining these together, since vibration amplitude is largest for these parts. The cutting-tool face is limited in size to the maximum area which can be made to vibrate all as one piece. This sets an upper limit to vibra-

tion frequency for a given area. Inaudibility of the vibration is also desirable for physiological reasons.

A practical compromise among these considerations, together with transducer efficiency and reliability, results in the choice of the magnetostrictive transducer operating at 25 kc. For a given output power level at a set frequency, vibration amplitude of the parts coupled to the transducer varies inversely with their cross-sectional area. This means that small tools can be driven with high amplitude, large tools with smaller amplitude. The smallest useful tool size is therefore determined by material strength, the largest by lowest tolerable cutting rate.



FIG. 3—Cross-section of transducer assembly of the magnetostriction type

The choice of nickel for the transducer laminations is indicated by its availability, ease of fabrication, high fatigue strength, high tensile strength, ease of bonding to other metals, high Curie temperature and good magnetostrictive efficiency at convenient impedances.

Driver Circuit

As shown in Fig. 4, the driver unit is relatively simple and straightforward. The basic circuit consists of a 6C4 Hartley oscillator driving a pair of push-pull 813's operating class AB_2. A special output transformer matches the transducer load impedance to the power amplifier.

A tuning-indicator circuit is incorporated to enable the operator to tune the oscillator easily and reliably to the mechanical resonant frequency of the transducer. Although this resonant frequency does not produce a maximum or minimum electrical impedance that permits direct indication, it does produce a unique impedance value that can be measured.



FIG. 4—Circuit of driver unit incorporating tuning-indicator circuit

In effect, a sample of the current to the transducer and the voltage across the transducer are compared in magnitude and phase with values determined at the factory to exist at resonance. Correspondence of these values as they vary with tuning of the driver is indicated as a dip in the reading of the panel meter. This meter is actually backward-reading, so that the dip looks like a maximum. The tuning feature is valuable since it enables an unskilled operator to tune for maximum output without error.

The transducer requires a standing d-c bias current for proper operation. This is provided through an isolating network which prevents the d-c from saturating the output transformer. It also prevents the d-c source from shunting the ultrasonic output current.

Grinding Performance

Table I shows the effectiveness of the impact grinder in working with a variety of materials, using a cold-rolled-steel tool and 320-grit boron-carbide abrasive. These figures, while generally descriptive of impact grinding machinery, apply specifically to machines of the Raytheon Model 2-332 Series, which have 700 watts output.

In stock removal the abrasive grit, vibrating at ultrasonic rates, wears away both the tool and the workpiece. The work normally receives much greater wear, resulting in the desired stock removal. Some of the ratios shown in column 2 of Table I are as great as 200 to 1. Tool wear is confined mostly to the bottom face where dimensions are usually not critical. Because there is little lateral cutting action, the precise profile of the tool is maintained. Moreover, the soft cutting tool is usually inexpensive to replace.

For each tool and material combination there is a maximum grinding area which it is impracticable to exceed. These maximum areas are indicated in column 3 for the tool and abrasive specified. Impact grinding can be performed over larger surfaces but of approximately equivalent grinding area. Portions of stock can be removed by making several connected cuts with the impact grinder.

Column 4 shows conservative grinding rates for each material, using the tool and abrasive noted.

Further development of ultrasonic impact grinding equipment will be directed toward the achievement of higher machining speeds and larger areas.

Higher speeds will require higher power (more amplitude) which will require stronger materials. Larger areas will also require higher power, but may also enforce the use of lower frequencies. Sonic impact grinders operating at high power levels in soundproofed rooms may prove both necessary and entirely practical.

Much investigational work remains to be done on the actual mechanism of cutting, reduction of tool wear by variations in tool design, and methods of supplying abrasive.

Development work on the ultrasonic impact grinder was supported in part by the Signal Corps under Contract DA-36-039-sc-30282.

Servo Amplifier Uses

SUMMARY —— Power outputs of better than 5 watts obtained from servo power amplifiers using silicon power transistors in push-pull output stage. Amplitude distortion is under 10 percent measured at 3.5-watt output

EXPERIMENTAL power transistors have been used in several recent circuit designs. A typical application is a servo-motor drive amplifier which utilizes overall closed-loop negative feedback.

This unit was designed to drive the control phase of a 3,400-ohm split control-winding servo-motor. The amplifier is well stabilized and has a voltage gain of 400 at 400 cps.

At an operating power-output level of 0.115 watt, the output voltage would be approximately 20 volts. The characteristics of a resulting design are listed in Fig. 1.

A schematic of the amplifier is shown in Fig. 2. The unit uses type 904 silicon transistors in the low-level input and driver stages. The grounded-emitter input stage is current-stabilized by the 220,000-ohm resistor between collector and base.

The output stage uses two experimental silicon power transistors in push-pull. No output transformer is required because the control winding of the motor is center tapped. The d-c component of current flowing in the winding is small because the output stage is biased for class-B operation.

The feedback-loop stabilizing voltage is fed from the output of the amplifier through voltage divider $R_f - R_e$ to the emitter of the input stage. For degeneration, the voltage fed back across R_e must be in phase with the 400-cps signal input at the base of the first transistor. Approximately 0.24 percent of the output signal voltage is applied across R_e for stabilization.

Stability

The 4-μf capacitor in the emitter circuit of the second stage adequately bypasses the 680-ohm emitter resistor at the 400-cps operating frequency and at higher frequencies. However, at lower frequencies it has little effect. Hence, the circuit degenerates these frequencies and acts to stabilize the amplifier at lower frequencies.



FIG. 1—Specifications for servo-motor drive

Similarly, the 0.018-μf capacitor across the primary of the output-stage drive transformer and the R-C series network between the base and collector of the second stage stabilize the amplifier at higher frequencies.

The amplifier feedback voltage gain and phase-shift characteristics with the feedback loop closed are shown in Fig. 3. The gain is con-





Servo-motor drive amplifier at left is not much larger than a matchbook; power amplifier at right shows component mounting designed to give increased heat dissipation

Silicon Power Transistors

By J. W. LACY and P. D. DAVIS, JR.

Semiconductor Products Division Apparatus Division
Texas Instruments Incorporated
Dallas, Texas



FIG. 2—Circuit diagram of servo amplifier which uses two experimental silicon power transistors in push-pull

Table I—Servo Amplifier Data

Input impedance:	
Closed Loop	130K
Open Loop	5K
Output impedance:	
Closed Loop	Under 100 ohms
Open Loop	Approx. 10 K
Voltage gain:	
Closed Loop	Approx. 410
Open Loop	Over 10,000
Power gain:	
Open Loop	83.2 db
Ambient temp:	100 C Maximum 71 C Nominal operating



FIG. 3—Closed-loop characteristics of servo amplifier



FIG. 4—Voltage gain plotted as a function of power servo amplifier output



FIG. 5—Servo power amplifier with an output in excess of 5 watts

stant over a wide range of frequencies on either side of 400 cps. Also, the phase shift is near zero over the same range.

Although there are gain peaks at two points, 90 cps and 3,000 cps, outside of the desired operating frequency range, the phase shift at these points is still sufficiently low to eliminate any tendency toward oscillation. Additional data is shown in Table I.

Voltage gain characteristic as a function of power is shown in Fig. 4. The gain of the amplifier is constant for output signal levels up to about 2 watts and drops only slightly at 3 watts.

The output section of a servo amplifier, from which more power output is required, is shown schematically in Fig. 5.

To obtain power outputs greater than those of the amplifier previously described, it is necessary to have more drive signal current available than is practical for the type 904 transistor to supply. Higher driving currents require a higher-wattage bias supply for the power transistors. In this case high gain at low signals is not needed. Consequently, the power supply requirements are reduced by eliminating the bias. The output characteristics of the amplifier are shown in Fig. 6.

Due to the need for the a-c driving signal to swing well into the nonlinear region of the collector characteristic, an increase in output is accompanied by an increase in amplitude distortion. However, this distortion is not detrimental. Actually, in using the motor as a tuned load, the measured distortion is under 10 percent at 3.5 watts.

The authors thank the engineers at Texas Instruments for their assistance. Particular thanks go to C. De Weese, W. Jurek and E. Heckman.



FIG. 6—Output characteristics of servo power amplifier

Measuring Phase at R-F

SUMMARY —— Time delay or phase angle of two sine waves in the frequency range between 10 kc and 20 mc can be measured by comparison-type instrument with an accuracy of 0.1 degree or 1 percent of dial reading. Unaffected by tube variations or noise and harmonic content of input signals, it can measure 5×10^{-10} second delay

By Y. P. YU

President
Advance Electronics Co., Inc.
Passaic, N. J.

COMPARISON METHODS of measuring direct potential, using a standard cell and a linear potentiometer, are generally far more accurate than the direct indication of a voltmeter. Similarly, in measuring a phase angle between two alternating voltages, the comparison method is likely to be more accurate than the direct-indication method.

The instrument to be described is essentially a comparison device employing a continuously variable delay line as a standard phase shifter and a sensitive balanced phase detector to indicate the phase difference of the two input signals.

Continuous Delay

A continuously variable delay line is effectively a compressed radio-frequency cable with one conductor changed into a long thin coil and the other conductor spaced closely to the first, thus producing a large amount of time delay while maintaining a low attenuation at high frequencies. Figure 1A shows a schematic diagram of a continuously variable delay line.

The variable contact can be adjusted to travel from one end of the line to the other; thus the time delay between the output terminal and the input terminal can be varied from zero to the maximum time delay of the entire line. A dial can be made to measure time delay directly, or phase delay in degrees can be determined by multiplying the frequency of the signals and 360.

A balanced phase detector is a special type of peak rectifier capable of producing a direct potential at its output terminals, proportional to the vector difference of the two alternating voltages applied to its input terminals. Therefore, when the input signals applied to the balanced phase detector are in phase, the reading of the output d-c meter will be equal to zero when the amplitudes of both input signals are equal and equal to a minimum when the amplitudes of both input signals are unequal. Figure 1B shows a simple circuit diagram of a balanced phase detector.

The operation of the instrument may be explained with the aid of the block diagram of Fig. 1C. Both E_1 and E_2 may be introduced with two low capacitance probes. Potentiometer R_1 is used with the input capacitance of the amplifier to introduce a small lagging phase angle to E_1 channel in order that the phase difference caused by lead inductances and stray capacitances can be balanced out by the initial adjustment of the continuously variable delay line.

The differential tuned amplifier is used to increase the sensitivity and to reduce the effects caused by noise and harmonic contents of both signals. A gain control is installed in the differential tuned amplifier for balancing the difference in absolute amplitudes of E_1 and E_2.

First E_2 is disconnected and signal E_1 is applied to both input probes. Then the continuously variable delay line is adjusted until the meter reading becomes minimum. The reading of the continuously variable delay line is recorded



FIG. 1—Schematic of continuously variable delay line (A) and circuit of balanced phase detector (B) combined to form precision phase detector shown in block diagram form at (C)

and Video Frequencies



Delay line is coiled around a copper-plated ring. Moving contact is shown at left. Front of unit (right) gives delay in microseconds on direct-reading dial

as t_1 or θ_1. At this point, both input channels have equal time delay.

With E_1 and E_2 separately applied to the input probes the continuously variable delay line is adjusted until the meter reading again becomes minimum or zero and the dial reading recorded as t_2 or θ_2. The unknown phase angle θ is $\theta_2 - \theta_1$ in degrees or $t_2 - t_1$ in microseconds.

Circuit Description

In Fig. 2, V_3 is an amplifier feeding the continuously variable delay line. Amplifier V_1 is the input amplifier for E_1 channel. Potentiometer R_1 and the input capacitances of V_1 are used to introduce a lagging phase angle to the E_1 channel. The purpose of adjusting R_1 is to balance the difference in phase shift caused by lead inductance and stray capacitance of E_1 and E_2 input channels. Tubes V_3 and V_4 are connected as a differential tuned amplifier, in which a single tank circuit is connected between the two plates. Phase shift caused by off-resonance of the circuit will not affect instrument accuracy.

Switch S_1 selects the frequency band. Variable capacitor C_1 is used for tuning. In case the amplitude of E_1 is higher than E_2, both bias and screen voltages of V_3 can be adjusted by potentiometer R_2 and R_2' until the amplitudes of the output signals at the plates of V_3 and V_4 are approximately equal. Resistor R_2 is used for coarse adjustment and R_2' is used for fine adjustment. Diode D_1 is connected as a balanced phase detector. Duotriode V_5 is connected as a d-c amplifier.

Potentiometer R_8 is used for zero adjustment of the panel meter, and to supply a negative direct voltage to offset a part of the input d-c signal from the phase detector. The output of V_5 is used to excite the output meter. The power supply of this unit has 300 volts unregulated potential and a 150 volts regulated potential.

The continuously variable delay line unit illustrated is a ring with a layer of copper coated on a part of its surface. This form is wound toroidally with Formex magnet wire. Both the dimensions and the number of turns on the coil are very accurately controlled to obtain good linearity and precise time delay.

The time delay of the line can be accurately measured by the following procedure: (1) apply a single signal whose period T is shorter than the total time delay of the delay line to both E_1 and E_2 input terminals of the instrument; (2) adjust for minimum meter reading near the beginning of the dial and record the dial reading as t_1; (3) adjust for the second minimum meter reading near the middle or the end of the dial and record the reading as t_2. A correction factor C for the dial of this instrument may be found by using

$$C = T/(t_2 - t_1)$$

Another method for checking the value of time delay is to connect E_1 binding post to ground, short the END terminal to the GROUND terminal at the rear of the delay line unit and apply a signal with frequency f_s to the E_2 input binding post. Then the delay line dial is turned slowly from its end gradually to its beginning until the meter indication becomes maxi-



FIG. 2—Complete circuit of comparison type phase indicator

mum. The dial reading is recorded as t_a. Increasing the signal frequency to f_b, the delay line dial is again adjusted until the meter reading becomes maximum and the dial reading recorded as t_b. Correction factor C can be determined by

$$C = \frac{1}{4(t_b - t_a)} \frac{1}{(f_a - f_b)}$$

Both terminating resistors R_c from INPUT terminal and END terminal to GROUND terminal of the continuously variable delay line must be equal to the characteristic impedance of the line. Otherwise, standing waves will be introduced within the line, thus decreasing the accuracy of the instrument. The value of R_c can be determined by applying a single sine-wave signal to E_2 input binding post and rotating the delay line dial. If the line is properly terminated, no maximum or minimum reading can be found on the panel meter. If the meter reading decreases rapidly when the variable contact is being rotated away from its END terminal, the value of R_c is too high. On the other hand, if the meter reading increases rapidly, R_c is too low.

Meter Sensitivity

Maximum sensitivity for full-scale deflection is 0.01 volt rms in the instrument described. Since the phase detector is based on measuring the vector difference of the two input signals, the meter indication can be expressed in terms of the absolute amplitude of one signal, say E_2 and the phase angle θ when the absolute amplitudes of both signals are equal.

$$\text{Meter indication} = 2E_2 \sin(\theta/2)$$

To obtain an adequate minimum indication, the amplitude of the input signals can be calculated by using the above expression; the results are given in Table I.

This table shows that the required amplitudes of the input signals become larger when the phase angle is small. When the input signals are 0.5 volt, the panel meter has an indication of about 0.00087 volt when the phase angle θ is 0.1 degree according to the above expression. In other words, the deflection will be about 9 percent of full scale under this condition. Thus, 0.5 volt is recommended as the minimum input for detection of 0.1 degree to produce 9 percent of full-scale deflection.

The significance of minimum indication on the panel meter when the delay line dial is being rotated depends not only on the amplitude but also on the frequency of input signals. Therefore, it is desirable to consider the relationship between signal frequency and rotation of the delay line dial. For a 0-to-0.25 microsecond continuously variable delay line, the change in meter indication becomes full scale as the delay line dial is rotating from one end to the other when E_2 equals 0.01 volt at 2 megacycles.

Table I—Input Amplitudes Required for Full-Scale Deflection

Input amplitude in volts	Phase angle in degrees
0.01	180
0.014	90
0.01	60
0.115	10
0.286	4
1.15	1
2.3	0.5

This is found from the above expression by substituting 0.25 microsecond at 2 megacycles equal to 180 degrees. Similarly, the change in meter indication will be full scale as the delay line dial is rotating from one end to the other when E_2 equals 0.115 volt at 111 kc. Therefore, the significance of minimum indication becomes poor when the signal frequency decreases. To remedy this condition, it is possible to use longer delay lines for low-frequency signals. A variation of the circuit by addition of a step variable delay line of 5 microseconds total delay in steps of 0.05 microsecond connected in series with the continuously variable delay line has been built and tested. The results are satisfactory below 10 kc.

One of the advantages of this instrument is that stray capacitance and inductance of input leads and all circuit elements do not affect the accuracy of the measurement. Furthermore, the accuracy is completely independent of variations of tube factors, meter tolerance, and other circuit parameters, since the instrument is based entirely on a comparison principle. Because a continuously variable delay line is employed as a phase shifting element, the instrument can be used to measure very small time delay and phase angle of transmission networks at very high frequencies where other phase measuring devices fail.

Many instruments of this kind have been constructed and tested. It has been found that the accuracy is always better than ± 0.1 degree or ± 1 percent of the time delay indicated on the dial of the continuously variable delay line. The resolution time is 5×10^{-10} second or smaller; the smallest phase angle in degrees that can be read on the dial is aproximately equal to $5 \times 10^{-10} \times 360 \times$ frequency in cps. The practical frequency range can be from 10 kc to 20 megacycles. The indicator sensitivity is about 0.01 volt full scale.



Regulated bias supply uses two power transformers. Section at upper left supplies standby bias in case of failure of main supply. Lower section provides regulated voltage for control tube



Power supply as installed in linear accelerator. Standby supply is at left, with 845 tube used as grid-leak resistor at rear center. Small power supply for 6SL7 is at lower right

Biasing Large Amplifiers

SUMMARY —— Tube acting as variable grid-leak resistor provides constant grid bias to linear-accelerator amplifiers over a wide range of grid current demands. Supply will provide up to 100 ma at 1,000 volts

By W. G. WADEY
Yale University
New Haven, Conn.

MAINTAINING a constant bias on the twenty-two 6401 triode amplifiers used in the Yale linear accelerator normally requires a bias supply large enough to hold the bias steady regardless of variations in grid current.

The amplifiers operate at 600 mc and have a peak power output of 200 kw, which they deliver for 15 μsec at a repetition rate of 100 pps. At a plate voltage of 12 kv the required grid bias is about 600 volts, but it is convenient to be able to vary the bias up to 1,000 volts or more. The tubes draw grid current, but it is variable from tube to tube.

These conditions would require a large and costly supply since it is possible that all the tubes might draw the same sign of grid current. To avoid that, the circuit shown in the diagram was devised, which will supply 1,000-volts bias at currents up to 100 ma.

If bias were developed across an ordinary grid-leak resistor no bias supply would be needed, but the bias would vary with grid current. Replacing the fixed grid-leak resistor with a tube allows the resistance to be varied as the grid current changes thus keeping the bias constant.

In the circuit shown, the type 845 tube is the regulated grid leak. The grids of all the amplifier tubes are connected to the bias bus, $C-$, and the grid currents of all tubes flow to ground through the 845. The grid potential of the 845 is determined by a direct-coupled feedback amplifier consisting of both halves of a cathode-coupled 6SL7. The bias potential of the right-hand grid of the 6SL7 is picked off a potential divider connected from ground (positive) to a point 300 volts below the bias bus as maintained by the two 0A2 tubes. The 25,000-ohm potential divider across the lower 0A2 puts the left half of the 6SL7 in the proper range of its characteristics. The power supply at the lower right serves only thethe 0A2 tubes and the 6SL7.

Failure Protection

As with any grid-leak bias, if the r-f drive on the amplifiers fails, the bias fails and the tubes may be damaged. To prevent this a small back-up supply is provided. It is set with a variable transformer at some value less than the operating bias voltage. Normally, its only load is a voltmeter since the lower 3B24 tube is nonconducting.

If the r-f drive fails the bias will fall until the 3B24 conducts and then stay at the back-up voltage until the drive is restored. The back-up supply has no load, since no grid currents are drawn.

Scale Weighs Moving

SUMMARY — Highway trucks diverted to lane along edge of road are weighed while traveling at speeds up to 48 mph. Overweight vehicles set off preset alarm. Scale is operated at 400 cps and uses load cells bridge-connected to d-c amplifier. Dead weight is balanced with potentiometer

AN ELECTRONIC highway scale, recently installed on U. S. Highway 1 in Virginia, is capable of detecting overloaded trucks while they are in motion, recording the weight of all passing trucks and accurately weighing stationary trucks.

The scale operates at 400 cycles. Power is fed into the load cells, the zero-adjust potentiometer and the slide-wire circuit as shown in the block diagram. The voltage into the slide wire circuit and the zero-adjust potentiometer are in opposite phase to that fed to the load cells. The zero-adjust potentiometer is used to counterbalance load cell output owing to the dead weight of the scale platform.

When this equipment is used for static weighing, the circuit selector is connected to the balance meter, which is a zero-center, 100-microampere meter. With no load on the scale and the weight indicator dial at zero, there is no input to the amplifier and the meter shows a zero balance. When a load is placed on the platform, unbalancing the bridge network in the load-cell circuit, a voltage is applied to the amplifier and the meter goes off balance.

Static Weight

By turning the weight indicator dial, a voltage of opposite phase is introduced into the amplifier and this voltage is adjusted until its magnitude is equal to the load-cell output. The resulting amplifier input is zero and the meter returns to zero balance. The actual weight on the scale is indicated by graduations of the weight indicator dial on the shaft of the slide-wire control used to develop the balancing voltage.



Elements of highway scale that indicates static weight or signals and records overweight on basis of preset alarm



Alarm circuit of scale must be reset manually

Four load cells of this type are used under weighing platform

Trucks

By ARTHUR L. THURSTON

Consulting Engineer
Cox and Stevens Electronic Scales Division
Revere Corp. of America
Wallingford, Conn.

Weighing platform is set into roadway. Equipment is triggered by switch ahead of platform and shut off by another that follows. A permanent tape record shows the weight of each axle



Typical tape record of weights determined by automatic equipment from truck passing at 48 mph



Underside of platform shows support for electronic load cell. Four cells are used, one at each platform corner

When the scale is recording moving weights, the circuit selector switch is turned to the record position. The slide wire is not used and the weight indicator dial remains at zero. In this case, any load placed on the platform develops from the cells an output that is amplified and fed into the paper-tape recorder.

This recorder uses a heated stylus and sensitized paper for low-inertia, high-speed operation. To save tape, because it is used at the rate of 50 millimeters per second, a roadway treadle is placed just ahead of the scale to start the paper drive as a vehicle approaches the weighing platform. A second treadle shuts off the drive after the platform is cleared.

Overload Alarm

As an overload detector, the manual slide wire is set to the predetermined limit over which excess weights are to be detected. For a signal to trip the overload detector circuit, a voltage must be developed by load cells in excess of that voltage introduced by the slide wire. Any slight excess will trip the detector circuit and set off the alarm signal. In addition to the alarm, there would normally be a sign along the roadway to indicate to the driver of the overloaded truck that he is to pull off the highway and be weighed at a static scale operated by enforcement personnel.

Tandem Detection

As most states allow less weight on a tandem axle arrangement than on two single axles, two treadles are placed on the platform for tandem axle detection. If the contact strips in both treadles are closed at the same instant as by tandem axles, a high-speed switch circuit changes the amplifier output to a detector set to trip on a higher voltage. This detector, adjusted independently of the single-axle detector, is set to trip at a weight near the tandem axle load limit. In either case, the overload signal information is the same.

The oscillator and amplifier employ standard circuits, the amplifier having a gain of approximately 90 db. In addition, the amplifier contains a phase-detection circuit related to the 400-cycle supply, to provide a positive d-c output when the cell voltage exceeds the slide-wire voltage and negative for the reverse condition. The overload detector uses a standard d-c amplifier circuit with a relay in the plate circuit of the final stage. Only when the load cell output exceeds the slide-wire voltage will a grid voltage of the proper polarity be applied to the detector circuit. For the high weight limits of tandem axles, this bias voltage is increased so that a higher cell output to trigger the relay is required.

When the relay closes, a positive voltage from the power supply is applied to the grid of the output tube through the reset button on the panel and an external reset in series, should there be one. This locks in the relay to hold the alarm and roadway signs until the circuit is manually reset.



Spark (left) when 7-kv supply of tv transmitter with electronic-crowbar fault protection is shorted. Neither solder-wire loop nor aluminum foil are damaged. Effects of same test with overcurrent relay-magnetic switch type of fault protection are shown at right

Gas Tubes Protect

By W. N. PARKER and M. V. HOOVER

Tube Division
Radio Corporation of America
Lancaster, Pennsylvania

MOST POWER TUBES are subject at some time to a phenomenon known as the Rocky Point effect, which derives its name from experiences with power tubes in communications transmitters at Rocky Point, Long Island.

Nature of Effect

This phenomenon manifests itself as an internal flash-arc developing with little warning in power tubes which apparently are of good design and are operated in a conservative manner. Triggering sources range from cosmic rays to line-voltage transients, parasitic oscillations, spurious renegade primary and secondary electrons, material whiskers and photoelectrons.

The cause of this effect is not thoroughly understood and thus efforts to find a remedy are hampered. However, techniques have been evolved which protect power-tubes against Rocky Point effect. These circuits detect the development of fault conditions in a power tube and/or its circuitry and trigger a gaseous-conduction device connected in shunt with the d-c power supply, extinguishing the flash-arc in the power tube before serious damage results. The gaseous conduction device bypasses the rectifier output and filter-circuit energy until the rectifier is de-energized.

This protection system is known as an electronic crowbar.

Fault Protection

In the past, the chief technique available for minimizing the effects of flash-arc damage in power tubes has been the addition of resistance in series with the d-c supply to limit surge currents during faults. Figure 1 shows a circuit of this type in which R is the series limiting resistance. In high-power installations this type of circuit dissipates an objectionable amount of power in the series limiting resistance if even marginal protection is to be afforded.[1]

In 1951, it was suggested that an electronic crowbar be built and electronically slammed across the high-voltage-supply bus in event of a fault as a means of shunting the fault currents of a 2,000-kilowatt rectifier from the faulting tube.[2] This device placed a virtual short-circuit across the rectifier output, similar to that placed on the rectifier by the flash-arc, but transferred the short-circuit current to a device which was not damaged



FIG. 1—Simple r-f power amplifier has limiting resistance



FIG. 2—Basic electronic-crowbar fault-protection circuit

SUMMARY —— Microsecond-response fault-detection and protection circuit minimizes flash-arc damage to power tubes. Gas tube shunted across d-c supply extinguishes flash-arc before serious damage occurs. Systems handling up to 5 megawatts can be protected

High-Power Transmitters

by the momentary short-circuit condition.

Basic Circuit

A simple electronic-crowbar circuit is shown in Fig. 2. A fault in the protected power tube results in a sudden increase in current through cathode resistor R_k, producing a positive voltage pulse which is coupled by C_c to the grid of the thyratron. This impulse ionizes the thyratron and causes it to conduct damaging current away from the faulting tube.

The current through the crowbar tube energizes the coil of the overload relay, causing the circuit breaker to open, thus deenergizing the primary source of a-c power to the rectifier.

In the sequence of these operations, plate voltage across the faulting tube is quickly reduced to a value of 15 to 20 volts, which is the voltage drop across the ionized gaseous-conduction crowbar device. This low voltage starves and extinguishes the flash-arc in the protected tube before serious damage can result. A small series resistor, R, provides adequate voltage across the crowbar tube to insure its conduction despite severe low-impedance flash-arcs in the protected tube.

In a typical large-power-tube installation, the value of the series dropping resistor is only about 5 ohms.

Actuation Time

Measurements have revealed that the electronic-crowbar tube is capable of beginning its protective function within 1 to 5 microseconds after the fault has been detected. When vigorously triggered, hydrogen-thyratron crowbar tubes begin to conduct within approximately 1 microsecond and mercury-vapor devices within about 5 microseconds.

A simplified diagram of a crowbar protection circuit currently in commercial use is shown in Fig. 3. This circuit is employed in the RCA TTU-12, a 12.5-kilowatt uhf television transmitter.[2]

In the arrangement shown in Fig. 3, the series resistance corresponding to R of Fig. 2 consists of series resistors, R_1, R_2 and R_3.

Resistor R_2 also serves as a sensing resistor. In the event of a sudden overcurrent in the load circuit as a result of a fault, a steep-wavefront positive pulse is transmitted through the transformer to the grid of the thyratron crowbar tube, which is normally biased off by the bias source.

This pulse causes almost immediate ionization of the thyratron, which then conducts and forms an effective short-circuit in parallel with the load. Energy stored in reservoir capacitor C_r and that which is subsequently furnished from the power supply is dissipated in R_1 and R_2. Because R_3 has a large value compared to the resistance of the ionized thyratron, very little current flows to the faulting load.

The series resistance of R_1 and R_2 in combination with the impedance of the power supply limits the fault current to a value not exceeding the

peak-current rating of the thyratron. Conduction of the thyratron operates the overload relay, which ultimately interrupts the primary source of a-c power by the circuit breaker. Several other variations of this circuit also give effective protection.

Performance

When a wire having a diameter of 0.003 inch is placed directly across the energized 7,000-volt plate lead of the circuit shown in Fig. 3, the resulting arc is so slight that it produces only a small pit in the wire. However, a tremendous cone of fire results if the plate potential is short-circuited with the protective system disabled.

In another test of effectiveness, the positive power-supply lead is touched to a small sheet of thin metal foil at ground potential. The thin metal foil used in cigarette packages is quite satisfactory. If the protective circuit is operating properly, the foil will show no melting, pitting or burn marks. However, the foil will disappear in a cloud of vapor if the test is performed with the electronic protective circuits disabled. Results of such tests are illustrated in the photographs.

Equipment Installations

An electronic-crowbar system of protection has been employed in conjunction with the 1,700-kilowatt rectifier for part of Navy's Jim Creek million-watt transmitter.[5, 6] More recently, super-power transmitters for the Voice of America have used the electronic crowbar.[7] In these superpower installations, it is not uncommon to find rectifiers having fault-current capabilities of the order of 2,000 amperes.

The effectiveness of fault-protection circuits in these large systems may be demonstrated by a deliberate short-circuiting of the high-voltage bus or tube terminals with a movable horn gap in which one of the electrodes is a piece of conventional 0.060-inch-diameter rosin-core solder. A slight melting and pitting of the solder will result when the electronic crowbar is in operation.

When conventional breaker-protected rectifiers are used, however, the horn gaps will disappear in a frightening display of aural and visual fireworks. Although the use of grid-controlled rectifiers reduces tube damage significantly, experience has demonstrated that such rectifiers are also capable of damaging tubes and circuits.

Another advantage of rapid fault protection is that full power can be restored almost immediately when the damage due to the flash-arc is minimized. Operators of high-power transmitters are familiar with the lengthy aging process demanded by power tubes after a severe flash-arc.

These periods of operation at lower power level may require many hours or days. Furthermore, tubes which have suffered from severe flash-arc damage are often somewhat gassy and may produce a final and fatal flash-arc unless they are adequately protected during reaging.

Out of Service Time

Actual tests of electronic-crowbar circuits in super-power transmitters have demonstrated that full-power operation can safely be restored almost immediately after a flash-arc. When these protective circuits are operated in conjunction with grid-controlled rectifiers, the total down time due to a flash-arc is of the order of 50,000 microseconds, a period almost unobserved in most communications services. The down time is, of course, directly proportional to the severity of flash-arc damage.

High-speed fault protection is not limited to power tubes, but is equally applicable to circuitry associated with the tubes. Capacitors, inductors, insulation and the like can also be damaged by fault currents. Crowbar protection greatly enhances the possibility of survival of circuit components and of early restoration of normal full-power operation.

Fault Detection

The effectiveness of high-speed fault-protection circuits is contingent upon the early detection of a fault in the tube or in its associated circuitry.

In simple fault-detection systems, such as that shown in Fig. 2, the power tube is protected against faults, but the system is incapable of sensing fault conditions in the circuitry associated with the protected tube. This disavantage may be obviated by the use of a fault-detection system such as that shown in Fig. 3. In this system, any d-c fault in the tube or circuit on the load side of sensing resistor R_s triggers the protection system into action.

Several other fault-detection systems are available.[8] A differential system of fault protection has proven very successful.[9] The operation of the differential fault detector is predicated on the fact that a fault which develops in a vacuum tube operating as an oscillator or an amplifier causes the r-f output to decrease sharply and the d-c input to increase.

In the differential fault-detector circuit shown in Fig. 4, rectifier



FIG. 3—High-speed protection circuit used in 12-kilowatt ultra-high-frequency television transmitter. Resistor R_s acts as sensing element



FIG. 4—Differential fault detector in high-speed protection system

load currents manifest themselves as a negative voltage across R_1 in the negative return of the rectifier. A sample of the r-f power output from the protected tube is coupled by a link line from the tank circuit to the parallel resonant circuit in the diode plate circuit. Rectification by the diode develops a positive voltage across resistor R_2 having a magnitude directly proportional to the r-f amplifier output. Resistor R_4 may be adjusted until the differential voltmeter reads zero voltage with respect to ground, indicating balance between the sample of rectified r-f power output and the sample of d-c input from the negative return of the high-voltage rectifier. Because the r-f power output is approximately proportional to the d-c input, the null balance from point X to ground should be approximately maintained at all signal levels, despite 100-percent modulation of the protected tube.

It should be noted that the voltage from point X to ground is zero when the high-voltage rectifier and protected tube are idle. Consequently, under all normal circumstances the differential voltage is zero, resulting in zero-bias operation of the differential amplifier.

This amplifier normally draws plate current through resistor R_4 to produce a negative voltage at point Y with respect to ground. When all the circuit parameters are designed properly, the negative voltage across resistor R_4 is greater than the positive voltage across resistor R_5 produced by the battery. A resultant negative voltage is produced from point Z to ground which biases off the thyratron, as indicated by the bias voltmeter.

Circuit Operation

In the event of a fault, the rectified r-f voltage sample across R_2 decreases rapidly toward zero, while the d-c sample voltage across R_1 in the negative return of the high-voltage rectifier suddenly becomes increasingly negative. Either or both of these sample voltages produce a resultant voltage which is increasingly negative at point X as fault conditions develop. A negative voltage is thus produced from point X with respect to ground and the differential amplifier is biased off, reducing the negative voltage across R_4 to zero.

Point Z, which is positive with respect to ground because of the voltage divider across the battery, then triggers the thyratron electronic crowbar. In addition to its protective function, the thyratron also interrupts a-c power to the rectifier by the overload relay and the circuit breaker.

The tubes employed in electronic crowbar service must be reliable and rugged. They must also be able to conduct heavy surge currents for a short period of time after having been idle for a long period of time.

Tubes for Electronic Crowbar

In high-power installations, the type 5563A mercury-vapor thyratron has demonstrated its effectiveness in commercial equipment[5] with circuits similar to that shown in Fig. 3.

Hydrogen thyratron tubes are also reported to have been used effectively in connection with crowbar applications in super-power transmitters.[7]

From the standpoint of long life, dependability and ruggedness, the ignitron appears to be an ideal choice for super-power crowbar service. Absence of a hot cathode in this tube is an attractive feature.

Ignitrons appear to be almost indestructible in crowbar service. One tube has been in almost daily use in the protective circuits of superpower-tube test equipment for the past seven years. In the course of this activity, the ignitron crowbar has been operated in conjunction with a 5,000-kilowatt grid-controlled rectifier in which fault currents may approach several thousand amperes at output voltages of 27 kilovolts.

Because many flash-arcs are experienced during the early operation and aging of large power tubes, this particular ignitron has been subjected to an unusually rugged life. Since the electronic crowbar has been used, not a single protected tube has been seriously damaged by flash-arcs during testing.

References

(1) H. J. Dailey, The Surge Testing of High-Vacuum Tubes, *Proc NEC*, p 127, 1948.
(2) L. P. Garner, U. S. Patent No. 2,571,027, 1951.
(3) R. L. Meisenheimer, New 12½-Kilowatt UHF Transmitter, *Broadcast News*, 79, p 22, May-June 1954.
(4) RCA-6448 UHF Beam Power Tube Bulletin, Tube Division, RCA, Harrison, N. J.
(5) T. D. Hobart, Navy VLF Transmitter Will Radiate 1,000 Kw, ELECTRONICS, p 98, Dec., 1952.
(6) J. C. Walter, A Million-Watt Naval Communication Transmitter, *Communication and Electronics* (AIEE), p 369, Sept. 1953.
(7) H. D. Doolittle, "High Powered Hydrogen Thyratrons", Vol. I, p 6, Cathode Press, 1954.
(8) M. V. Hoover, U. S. Patent No. 2,673,952, 1954.
(9) W. N. Parker, H. C. Vance and M. V. Hoover, U. S. Patent No. 2,575,232, 1951.

Digital Presentation



FIG. 1—Resistance-capacitance network in preamplifier grid functions as modulator/mixer, derivative controller and noise filter

SUMMARY —— Servo-driven self-balancing potentiometer with counter coupled to servo shaft provides vacuum-tube voltmeter with digital presentation. Chopper samples potentiometer signal and compares it with input

LARGE-NUMERAL three-digit presentation displayed on the front panel of the vacuum-tube voltmeter avoids parallax errors. Polarity is indicated by a sign before the digits, and the decimal point is indicated in the display. The instrument is insensitive to line-voltage variations, and has no warmup drift when used as a d-c voltohmmeter.

Presentation accuracy for direct voltage is dependent only upon the linearity of the self-balancing potentiometer and the potential of the mercury-cell reference battery, modified slightly by the precision input attenuator. As an ohmmeter, the intrinsic accuracy is limited only by potentiometer linearity.

All measurements are accomplished by a null techique. Voltage measurements employ a self-balancing potentiometer, which has a basic range of 1 mv to 1 volt. High voltages are measured after division in a self-contained voltage divider. Resistance measurements employ a self-balancing Wheatstone bridge.

Alternating-voltage measurements are effected by peak-to-peak detection with a compensated 6BC7 detector, and measurement with the basic direct-voltage servo.

Accuracy

The instrument has a minimum accuracy of plus 1 percent of full scale on direct volts and ohms and plus 2 percent on alternating volts.

Repeatability of reading is approximately one part in one thousand obtained by high gain without compromising dynamic stablity. A derivative controller in the servo feedback loop, a low-pass filter for attenuating noise and 60-cycle hum, a d-c heater supply for the preamplifier, and means for preventing potentiometer noise from being introduced into the servo amplifier contribute to freedom from zero drift and calibration errors and to critically damped dynamic response. Because of the stability of the servo, no damping control is necessary.

As a d-c voltmeter, the digital presentation permits reading to one millivolt on the one-volt scale and to 1,000 volts with four decade

Vacuum-Tube Voltmeter

Front panel of voltmeter



Chassis and servo gear train

By AUGUST NUUT and CLARENCE MUNSEY

Hycon Manufacturing Company
Pasadena, California

ranges. On all ranges, the input impedance is 11 megohms.

Resistance values range from 1 ohm to 10 megohms. The presentation is linear. Accuracy may be expressed as a percentage of full scale, and compares favorably with laboratory-type resistance bridges.

The digital voltmeter is a servo-driven self-balancing potentiometer with a counter coupled to the servo shaft. The motor is coupled by spur gears to a shaft which positions the mechanical counter through two beveled gears. The potentiometer is operated from this shaft by a worm gear.

The life of the mercury-cell batteries is approximately equal to the shelf life, due to the less-than-50-microampere current drawn. These batteries need to be replaced approximately once a year.

The feedback potentiometer has a linearity of $\frac{1}{4}$ percent and a resolution of $\frac{1}{2}$ digit. Potentiometer noise has little effect on the balancing servo because of the chopper used for sampling the signal and comparing it with the input.

Circuit

Capacitor C_1 (Fig. 1) samples the potentiometer voltage. As a result, spike noise from the potentiometer is eliminated from the input to the low-level preamplifier.

Inverse feedback is used in two places in the servo amplifier for setting and stabilizing gain. Feedback resistor R_1 stabilizes the gain of the second 6AU6, and R_2 stabilizes the gain of the entire phase-inverter and power-amplifier loop in addition to lowering the output impedance of the power amplifier.

The amplifier loop included by R_1 contains a direct-coupled phase amplifier for stability. The direct-coupled phase inverter saturates at a peak swing which is slightly less than that required to cause the 6AQ5's to draw grid current. The only grid-current-limiting resistor used is R_3 at the input of the 12AT7. In spite of the 60-db range of inputs that can be applied, this high-gain amplifier cannot be blocked.

Although the motor is direct-coupled to the 6AQ5 output tubes, no d-c component flows through the motor winding. This reduces motor noise. Little signal power is lost in the transformer. Most of it is absorbed by the motor. Thus a small transformer with the secondary winding used for feedback may be used without compromising efficiency or smooth operation.

R-C Network

The network R_5, C_2 and R_6 when used with the chopper and C_1 functions not only as the modulator and mixer, but also functions as a derivative controller and potentiometer noise filter. Capacitor C_2 is smaller than C_1 and R_4 is much larger than R_5. Thus the voltage of C_1 is constant during the period that the chopper arm is connected to the right-hand contact. Assuming a constant signal input to R_4 and a step change of voltage to the left-hand contact of the chopper; the charging time constant through the choppers and the right-hand contact consists of C_2 and R_5. This time constant is shorter than that of C_2, R_5, R_4, R_3, plus the resistance of the input dividers.

As a result of a step change of the feedback signal, the initial error voltage coupled to the grid of the preamplifier is equal in amplitude to the magnitude of the step change. After a period of time, however, C_2 accumulates a charge which opposes the potential of the step change. The difference potential is smaller and the amplitude of the error voltage to the preamplifier is smaller. Figure 2 illustrates the process.

The counter was designed by Warren White and Warren Malcher. The contributions of coworkers including Edward M. Boughton, Jr., who reviewed the material, are acknowledged.



FIG. 2—Simulated potentiometer step function (A), error signal to preamplifier (B) and general form of derivative controller transfer function

Magnetic-Switch

SUMMARY —— High accuracy of response time measurements in testing high-speed magnetic amplifiers is provided by frequency tripler and magnetic switch. Phase shifter permits varying of switch firing point in relation to test voltage waveform



Breadboard model of magnetic-amplifier analyzer. Magnetic switch is on right and magnetic frequency tripler is at left

SYNCHRONOUSLY operated mechanical switches have proved to be a valuable tool for experimental studies on the dynamic properties of high-speed magnetic amplifiers. Application of such equipment is limited to power-supply frequencies where a mechanical switch can be used.

Analyzer performance can be considerably improved by providing a magnetic switch which consists of a saturable-reactor circuit producing an auxiliary current with nearly rectangular waveshape. The amplifier under test is supplied from a magnetic frequency multiplier which produces an exact multiple of the frequency of the a-c power supply.

When applying a frequency tripler, as illustrated in the typical example of Fig. 1, the magnetic switch makes and breaks alternately in a sequence of three half-cycles.

Figure 1 shows an arrangement of operation from a three-phase, 400-cps power supply in connection with a three-phase type of magnetic frequency tripler providing the frequency ratio 400-to-1,200 cps.

The amplifier under test is connected with the 1,200-cps output of the tripler. The 400-cps tripler input is supplied through a phase shifter with the magnetic-switch circuit. This circuit produces an auxiliary current I_x with nearly rectangular waveform and corresponding unidirectional square wave pulses representing the variable signal voltage E_s for controlling the amplifier input circuit.

Magnetic-Switch

The waveform of the output current I_x of an ordinary saturable reactor with high-permeability core material having series-aiding-connected a-c load windings N_1', N_1'' and series-opposing-connected d-c control windings N_2', N_2'' is nearly rectangular. This assumes that the control-circuit loop carrying constant direct current I_A represents a very high impedance (choke coil L_C) with regard to even-harmonic currents. These even-harmonic currents are suppressed and the saturable reactor operates under forced magnetization conditions.

To derive corresponding unidirectional square-wave pulses (signal voltage E_s) from the square-wave alternating-current I_x, a splitting



FIG. 1—Transient analyzer using magnetic switch is shown with circuit of high-speed magnetic amplifier under test

Transient Analyzer

By W. A. GEYGER

U. S. Naval Ordnance Laboratory
Silver Spring, Maryland

circuit is provided which consists of two half-wave-rectifiers D' D'', a potentiometer (first-half-cycle pulses I_D') and a fixed resistor (second-half-cycle pulses I_D'').

Magnetic Frequency Tripler

A simple arrangement for producing third-harmonic frequency power from a three-phase, four-wire power source contains three Y-connected saturable reactors *SR* with series-connected linear reactors, *LR*. The load consists of the magnetic amplifier under test and a variable transformer.

Introduction of the phase shifter offers the possibility of varying the actual time interval between the instant of firing of the saturable-reactor switch and the instant supply voltage E_P of the magnetic amplifier goes through zero.

Choke coil L_c carries the constant direct current $I_s = 0.6$ amp which is supplied from a storage battery or a full-wave rectifier. The splitting circuit consists of 2 rectifiers, each made up of 12 1-sq-in. selenium plates.

Table I—Core and Winding Data for Magnetic Switch and Tripler

Core		Winding			
No.	Material and Size	No.	Function	Turns	Wire Size
Magnetic Switch					
2	¼ in. by 2 mil Orthonol tape coil, 1¼ in. i-d, 1½ in. o-d	1 2	a-c load d-c control	1,700 500	No. 28 No. 28
Frequency Tripler Saturable Reactor					
3	¾ in. by 2 mil Orthonol tape coil, 1⅛ i-d, 1⅜ o-d	1		380	No. 23
Linear Reactor					
3	2-stacked Permalloy dust cores, Western Elect. No. 467585	1		300	No. 23

When supplying a 400-cycle voltage of about 110 to 130 volts rms, the average value of the full-wave-rectified load current is

$$I_N = I_A \frac{N_2}{N_1} = 0.6 \frac{500}{2{,}000} = 0.15 \text{ ampere,}$$

The average value of unidirectional current components is $I_D' = I_D'' = 0.075$ ampere. Thus, the average value of the unidirectional square-wave signal voltage E_s may be varied within the limits of from zero up to a maximum value of $E_{s_{max}} = I_D'R_D' = 0.075 \times 200 = 15$ volts.

Figure 1 shows the circuit diagram of a high-speed magnetic amplifier of the self-balancing potentiometer type. This single-ended external-feedback circuit contains two equally rated saturable-reactor elements with load windings N_L', N_L'', d-c control windings N_C', N_C'', and external-feedback windings N_F', N_F''. Positive feedback produces an effectively infinite gain and 100-percent negative voltage feedback. Signal voltage E_s is balanced automatically by the opposing average voltage drop $E_N = I_LR_s$, and the average control-winding current I_c flowing through the moving-coil microammeter is substantially zero. There is a linear relationship between I_L and E_s, and $1/R_s$ is the transconductance of the self-balancing magnetic-amplifier circuit.

Voltage drop I_LR_s, produced by load current I_L across compensating resistor R_s, is applied to the one channel of a dual-beam oscilloscope. Meanwhile the square-wave signal voltage E_s, synchronous with supply voltage E_P of the amplifier, is applied to the second channel.

The oscillograms of Fig. 2 show the transient response of the magnetic amplifier circuit of Fig. 1. The lower trace of each oscillogram shows the square-wave signal voltage E_s derived from the magnetic-switch circuit. The upper trace shows the transient response of compensating voltage E_s across compensating resistor R_s.

In oscillogram Fig. 2A, the response time of the amplifier is one half-cycle of the 1,200-cps power-supply frequency. The amplifier reaches 100 percent of its final steady-state output-current value 0.417 millisecond after the transient signal voltage E_s is applied to the control circuit.



FIG. 2—Oscillograms of magnetic amplifier transient response show effect of changing time interval between firing of magnetic switch and time when magnetic amplifier voltage goes through zero point

Analog-to-Digital

SUMMARY — Gating variable-frequency pulse oscillator into fixed-interval counter converts analog voltage into digital quantity over four-decade range. Output pulses, 20 volts at ½ μ sec into 100 ohms, are suitable for driving counter. Stability and repeatability are better than 0.1 percent of maximum frequency

By SHERMAN RIGBY
Johns Hopkins University
Operations Research Office
Chevy Chase, Maryland

ONE METHOD of converting an analog voltage to a digital quantity is to generate a pulse frequency that is proportional to the voltage to be converted. This frequency is then gated into a counter for a fixed time interval. At the termination of the gating interval the number left in the counter is the digital representation of the voltage. This article describes a variable-frequency pulse oscillator possessing a range of over four decades and an accuracy of 0.1 percent. Previous attempts[1] have been limited to about one decade.

The basic mechanism of oscillation is a pair of saw-tooth waveforms produced by integrating a control voltage E_c. Termination of one saw tooth causes the other to start; return to the initial voltage being accomplished during the active time of the other integrator as shown in Fig. 1. Output pulses are emitted at the termination of each saw-tooth waveform. The time between pulses is proportional to the total height of a saw tooth, $E_c - e_g$, and inversely proportional to its slope, $(E_c + e_g)/(RC)$. The pulse repetition frequency, the reciprocal of this time, is

$$f = \frac{(E_c + e_g)}{(E_c - e_g)} \frac{1}{RC} \qquad (1)$$

Hence, a frequency is linearly related to a d-c voltage E_c.



FIG. 1—Saw-tooth waveforms (A) and (B) control output pulses (C)

Fig. 2 is the block diagram and Fig. 3 the circuit diagram of the converter. The actual d-c input is negative voltage $-E_c$.

Operation

In Fig. 2, assume that gate diode *A* is conducting, sending current into the summing junction of integrator *A*. This causes the output of integrator *A* to integrate downward until clamp diode *A* conducts, passing just sufficient current to make the net current into the junction zero. The cycle of operation is started by reversing the flip-flop which causes gate diode *A* to be cut off.

Output from integrator *A* rises linearly. When this output voltage reaches E_s, Schmitt trigger *A* trips reversing the flip-flop and sending



FIG. 2—Variable-frequency pulse oscillator uses Schmitt trigger circuits

Data Converter



FIG. 3—All supply voltages for converter except two must be regulated to 0.1 percent. The +150 and +90 voltages are derived from voltage regulators V_{13} and V_{14}

a pulse into the pulse amplifier. This reversal of the flip-flop causes gate diode *A* to conduct, returning integrator *A* to its initial condition, and also cuts off gate diode *B* which starts integrator *B*. When integrator *B* reaches E_s, Schmitt trigger *B* trips again reversing the flip-flop and sending another pulse to the output circuit via the amplifier, pulse-former and output tubes. The entire circuit can be thought of as a multivibrator with linear timing waveforms.

Diodes *D* in Fig. 2, V_{12} in Fig. 3, are used to send current into both integrator junctions simultaneously to give external start-stop gating control of the pulses. This method is used rather than gating in the output tubes to obtain phase coherence between the pulses and the gating signal.

Integrator

An upper limit of 200 kc on the output pulse frequency implies a square-wave input to the integrators of 100 kc. Significant harmonics of this waveform extend well into the megacycle region. Conventional analog-computer-integrator designs do not even approach this bandwidth.

Theoretical considerations[6] indicate that multiple-tube operational amplifiers cannot be constructed to handle large bandwidths. Hence a single amplifying stage is indicated. However, a large gain is needed to produce the required accuracy of integration.

Positive feedback applied from the output to the cathode of amplifier V_a is employed. Potentiometer R_1 is adjusted to make the overall gain of the amplifier infinite. This is accomplished by adjusting R_1 for zero amplitude of the triangular waveform at the grid of V_a, as indicated by a oscilloscope. As the proper setting of R_1 depends on the g_m of the tube, it must be readjusted whenever V_a is replaced. A 50-$\mu\mu$f capacitor provides high-frequency compensation of the feedback network but is not made adjustable since the value is noncritical. Omission of this capacitor produces a square wave at the summing junction.

The transfer function of this integrator obtained from the equivalent circuit of Fig. 4A is

$$\frac{e_o}{E_i} = \frac{1}{RCp}\left\{\frac{\gamma g_m}{\left[\left(\frac{C_i}{C}+1\right)C_o p+\left[\frac{C_o}{C}\frac{1}{R}+\left(\frac{C_i}{C}+1\right)\frac{1}{R_L}+\gamma g_m\left(1-B\frac{C_i+C}{C}\right)\right]+\frac{1}{RCp}\left[\frac{1}{R_L}-\gamma g_m B\right]\right\}} \qquad (2)$$

where γ is fraction of V_a plate swing appearing at the output of the cathode follower, C_i and C_o are input and output parasitic capacitances of V_a, B is fraction of



FIG. 4—Equivalent circuit (A) of V_3 and V_{5A} in Fig. 3 and response (B)



FIG. 5—Converter performance with correction for —3.286 zero-frequency voltage



FIG. 6—Saw-tooth waveforms at 88 kc and saw-tooth and output pulses (B) at frequency of 10 kc



FIG. 7—Analog-to-digital converter includes pulse generator, variable-frequency pulse oscillator and counter

output voltage fed back to the cathode of V_3 and p is $j\omega$. The coefficient of the brace represents pure integration. If the quantity within could be made a constant, the integration would be perfect for all frequencies. By adjusting B to the value

$$B = \frac{1}{(g_m R_L \gamma)} \qquad (3)$$

this is best approximated. This value of B is the critical amount of regeneration, which makes the open-loop gain of the amplifier infinite at d-c. Using this appropriate value of B, Eq. 2 represents a pure integrator followed by a single-section low-pass R-C filter as illustrated in Fig. 4B where the 3-db cutoff frequency is

$$f_c = \frac{\gamma g_m}{2\pi(C_o + \frac{C_o}{C} C_4)} + \frac{1}{2\pi R(C_i - C)} \qquad (4)$$

If the output of this integrator were inverted and added in a resistive network to the output of a conventional R-C integrating circuit, the overall effect would be perfect integration at all frequencies.

As with any single-ended amplifier, an equivalent drift of e_g of about 0.3 volt changes the current flowing through R and hence the frequency[5]. This would, if uncorrected, cause excessive frequency drift at the low-frequency end of the range where the current through R is small. Push-pull amplifiers operating at low plate currents maintain grid stabilities of about 0.02 volt.[8] By using such a push-pull amplifier in a negative-resistance circuit V_1 or V_2, the current into the integrator junction is made independent of changes in e_g. The denominator of Eq. 1 also contains an e_g term since the initial clamp point of the integrator output is e_g, which is not corrected by this circuit. However, this represents only a given percentage change in frequency and therefore does not become more troublesome as the frequency is decreased. Better overall stability for both e_g terms in Eq. 1 could be obtained by chopper stabilization of the integrators if accuracy considerations warrant.

Differential adjustment of the bias on drift-compensator tubes V_1 and V_2 with R_2 equalizes the integrating rates of the integrators for low values of E_c. At high values of E_c, the integrating capacitors are adjusted to equalize rates. The setting for R_2 should be readjusted if V_3 or V_4 is replaced.

Other Components

Each Schmitt trigger detects the instant when the integrator waveform reaches the voltage E_s. It then delivers a negative pulse which reverses flip-flop V_{13}. The other Schmitt trigger does the same when the other integrator reaches E_s.

Both Schmitt triggers send negative pulses through mixing diodes CR_3 and CR_4 to pulse amplifier V_{14}. Here the pulse is sharpened and clipped at its most rapidly changing level by biased diode CR_5 in the output circuit of V_{14}. This sharp negative waveform cuts off pulse-forming tube V_{15}. An inductance in the plate of V_{15} rings for one-half cycle, which is about ½ microsecond in duration. Ringing after one-half cycle is damped out by diode CR_6. Pulse output tube

V_{1B} amplifies this shaped pulse and delivers an output to a low-impedance line.

The entire circuit was designed to make stability a function of voltages rather than a characteristic of tubes and passive components. Examination of Eq. 1 will show how far this has been accomplished. Since a basic component of frequency is time, it was necessary to use an R-C time constant. These components must be kept stable, but most of the other components have only secondary effects upon the frequency.

Variations of e_g have been discussed. Variations of E_s must now be considered. Although V_7 and V_8 in Fig. 3 are operated at high currents they are push-pull operated at the tripping point and hence have better voltage stability than single-ended pick-off circuits.[5]

Other major factors affecting E_s are the 400-volt supply for the Schmitt triggers and the resistor-divider ratio supplying the normally conducting triode grid.

The Schmitt triggers are fast but not instantaneous. This delay in starting the saw tooth causes nonlinearity in the frequency-versus-control voltage curve. This is compensated by slightly changing E_s with changes in E_c with R_z and R_c.

Since most of the important factors have been referenced to voltages it is necessary to regulate the supplies to 0.1 percent if this is the expected accuracy and stability of the overall circuit. However, the +150-volt screen supply and the +90-volt supply are not so critical and hence are derived from cathode-follower regulators V_{5B} and V_{5B}.

Performance

Figure 5 shows the performance expressed as a plot of pulse repetition frequency as a function of the control voltage corrected for the 3.286-volt offset. Although the design goal was about three decades final performance indicates four decades are available. The high-frequency limitation is the rapidity with which the integrators can return to the clamping point. This could be speeded up by increasing the current sent into the integrator summing junctions through gate diodes V_{9A} and V_{10B}.

Figure 6A shows the two saw-tooth waveforms produced by the integrators operating at a frequency of about 88 kc.

Figure 6B shows one saw tooth and the output pulses at a frequency of about 10 kc. The flyback time on the saw tooth is a much smaller percentage of the total cycle because of the lower frequency. Zero output frequency would be at a voltage of −3.286 volts. Hence this offset must be supplied by the device producing voltage E_c.



FIG. 8—Setup for converting product of two voltages into digital quantity

Applications

The block diagram of Fig. 7 shows the oscillator used to convert a voltage into a digital quantity.

Sometimes it is desired to convert the product of two voltages X and Y into a digital quantity. This can be accomplished by combining two methods of analog-to-digital conversion. One voltage, X, controls the frequency and the other voltage, Y, controls the time of counting. Figure 8 shows the block diagram. The phantastron[4] produces a waveform proportional to the plate-catching voltage, Y. A trigger resets the counter and starts the phantastron. During rundown a positive waveform appears at the screen, which is inverted and applied as the gating waveform of the variable-frequency oscillator. At the termination of the rundown, the count left in the counter is proportional to the product XY. If the grid return voltage of the phantastron is considered as another variable, Z, this product can be divided by a third voltage. The device then yields the digital conversion of XY/Z. By its nature, the phantastron limits the range of Y and Z to about two decades each.

REFERENCES

(1) D. J. Grey, V. P. Gurske and W. E. Morrow, Wide-Band Data Transmitter, ELECTRONICS, p 168, Sept. 1953.

(2) H. W. Bode, "Network Analysis and Feedback Amplifier Design", D. Van Nostrand Co., Inc., New York, N. Y., 1945.

(3) I. A. Greenwood, J. V. Holdam and D. Macrae, "Electronic Instruments", MIT Rad Lab Series, Vol. 21, p 513, Table 15.2, McGraw-Hill Book Co., Inc., New York, N. Y., 1948.

(4) B. Chance, et al., "Waveforms", MIT Rad Lab Series, Vol. 19, p 195, McGraw-Hill Book Co., Inc., New York, N. Y., 1948.



Top and bottom views of variable-frequency pulse oscillator

Phase Shifter Circuits



FIG. 1—Components of meter tester. Top row of blocks supplies potential-coil voltage; bottom row supplies current-coil current. Substandard meters have permissible error of less than 0.3 per cent. Input is a-c line voltage

NEED for portable universal equipment for testing meters is keenly felt in the laboratories of engineering firms and utility companies. The electronic meter tester to be described has been designed to fill this need.

Design of the equipment is based on the principle of phantom loading.[1] Test loads are simulated by applying rated voltages to the potential coils and variable current loads to the current coils.

System Theory

A two-stage phase-shifting network provides smooth control of the phase angle between the current and voltage vectors, particularly in the zero and unity-power-factor regions.

In the block diagram of Fig. 1, a low-voltage winding of the transformer supplies the current coil of the meter under test, the substandard wattmeter and a substandard ammeter; the value of the current is adjusted by a limiting resistor. Another secondary winding applies a voltage to a phase shifter capable of shifting the phase of the a-c input voltage up to 360 degrees. To keep the load impedances on the phase-shifting circuits extremely large, cathode followers have been interposed as shown in the diagram.

The final phase-shifted voltage is applied to a cathode-follower power amplifier which drives the requisite current through several meter potential coils ordinarily met with in practice.

Phase Shifting

Voltage AB, shown in Fig. 2, from the secondary of input transformer T_1 is applied to the first phase shifter in Fig. 3 consisting of C_1 and R_1. Voltage CO is applied to cathode-follower V_{1b} which serves as an impedance-matching device. This voltage is constant in magnitude for any value of R_1 and its position in the vector diagram is fixed by the setting of R_1. The output of the cathode-follower is slightly less in magnitude than, but in phase with, CO and is applied to the second phase-shifting network consisting of C_2 and R_2.

Point E, like O, moves on the second semicircle on CO. The double phase shifter is thus capable of rotating the voltage vector through 360 degrees. The magnitude of the output voltage, however, is a little less than a quarter of the input voltage.

The first phase shifter insures that the voltage and current vectors are in phase with each other. The second phase shifter is calibrated to read the power factor directly on the dial setting.



FIG. 2—Vector representation of two-stage phase shifter

The output of the second phase shifter is applied to the primary of T_2, which is used to obtain a grounded signal to the succeeding stages of the meter-testing equipment.

Potentiometer R_3 across the secondary of the interstage transformer provides smooth control of the magnitude of the power-amplifier output. The output of voltage amplifier V_3 is applied to the grid of the triode-connected cathode-follower driver amplifier, V_{2a}.

A small voltage of the order of 9 volts is fed back from interstage transformer T_2 to V_3 to improve stability of operation.

The power amplifier is of the cathode-follower type with two EL37 pentodes in class AB push-pull. The primary of output transformer T_3 is connected between the cathodes and the center tap of

Test Power Meters

SUMMARY —— Device permits testing and calibration of wattmeters, watt-hour meters and power-factor meters at line frequencies of 40 to 60 cps. Actual loads are simulated by phantom loading

By P. VENKATA RAO

Department of Power Engineering
Indian Institute of Science
Bangalore, India

the primary is grounded through the biasing resistors.

To keep the screen-grid voltage constant with respect to the cathode at the quiescent value, a separate winding of the same number of turns as the primary is provided on the output transformer. The ends of this secondary winding are connected to the two screen grids, with the center tap connected to the positive supply of the plates.

This amplifier is capable of delivering about 35 watts of undistorted output at any of its secondary taps.

To permit frequent checking for the correct initial phase alignment, a test wattmeter is incorporated in the equipment.

The first phase shifter is adjusted until a maximum reading is obtained on the wattmeter under test or on the panel wattmeter, when the power factor is set at unity. The phase angle can be smoothly varied through ± 90 degrees by the second phase shifter. In actual testing, the potential coil voltage wave can be smoothly varied through 180 degrees with reference to the current through the current coil of the meter under test. The wattmeter can be compared with a standard wattmeter for calibration purposes.

For the energy meter, however, a standard ammeter and a standard voltmeter are included in the current and potential circuits; power factor is indicated by the setting of R_2 of the second phase shifter.

The author is indebted to C. S. Ghosh for his encouragement and constant help, and to the Director, Indian Institute of Science for his permission to publish this paper. The assistance of G. Krishna is also acknowledged.

REFERENCE

(1) A. E. Knowlton, "Electrical Power Metering", p 159, McGraw-Hill Book Co., Inc., New York, N. Y., 1934.



FIG. 3—Phase is shifted over range of 360 degrees by combination of R_1C_1 and R_2C_2. Output voltage is adjusted by variation of R_3

Electrically Variable

By JAMES F. GORDON

Chief Development Engineer
Helipot Corp.
Division of Beckman Instruments, Inc.
South Pasadena, California



FIG. 1—Experimental variable gas-dielectric capacitor (A) and structure using 15 NE-2 glow tubes (B)



FIG. 2—Capacitance versus ionizing current at various frequencies for the single glow-tube unit (A) and the multiple glow-tube unit (B)



FIG. 3—Schematic of the variable capacitor unit showing circuit simplicity

THIS CONTROLLABLE capacitor exhibits a usably high ratio of capacitance change to total capacitance.

Although its dielectric constant is not appreciably greater than 1, the capacitance change is sufficient to provide frequency modulation and control of self-excited oscillators, see Fig. 1 and 2.

Circuit

A diagram of the capacitor circuit is shown in Fig. 3. The capacitor consists of a pair of plates with a glass envelope placed between the plates. Within the glass envelope are two electrodes and neon gas of suitable density and ionizing characteristics.

The gas within the envelope forms an appreciable part of the space between the two plates. Under the condition of no ionization, the aggregate dielectric constant will be slightly greater than one owing to the glass envelope and the negligible amount of neon.

That portion of the dielectric which is air and that portion which is glass will remain relatively constant, as will the insignificant amount of neon. When an ionizing potential is applied to the electrodes that part of the dielectric which consists of ionized neon will have acted to alter the aggregate dielectric constant.

An increase in capacitance takes place when gas ions are generated between the two electrodes. The greatest capacitance change takes place between the condition of no ionization and maximum ionization. There are applications for such abrupt capacitance changes. However, the use of the capacitor as a frequency modulator or similar proportional control requires that the ionizing current be maintained at some controllable level above the extinguishing point.[1]

With n gas ions present a certain fixed value of capacitance will result and with $n + 10$ or $n - 10$ gas ions a proportional increase or decrease in capacitance will take place. With the standard neon tubes used, the capacitance change for a linearly increasing current change is exponential.

A linear current-controlled variable capacitor should conform to the expression $C = Ik$, where C represents the capacitance and I the ionizing current; k defines the relative current-capacitance sensitivity. For frequency-modulator applications the ideal capacitor should agree with the expression $C = I\epsilon k$ where $\epsilon = 2$ defines conformity to the capacitance change in a resonant circuit to create a frequency change linear with current.

Neglecting inductance and resistance which must necessarily exist in a practical structure, such a capacitor will always appear as a variable capacitance in shunt with a fixed one. If C_s represents the fixed shunt capacitance, the expression becomes $C = Cs + I\epsilon k$.

To make the variable section as effective as possible a maximum



FIG. 4—Effective frequency sensitivity of the assembly using a single NE-51 glow tube. A reduction in Q is noted wherever the current increases

Gas-Dielectric Capacitor

SUMMARY —— Neon diode between plates of air capacitor varies dielectric constant in proportion to diode current, giving variation in capacitance between plates. Applications include frequency control of self-excited oscillators and potential use in other low-power circuits

ratio of variable capacitance to fixed capacitance must be accomplished.

The experimental units were designed to have low inductance and have worked satisfactorily through the test ranges shown. They should work effectively up to field frequencies of several hundred megacycles, although the effective current capacitance sensitivity k for a given current increment decreases as the field frequency increases, as shown in Fig. 4.

Limitations

One might expect the gas tube capacitor to be sensitive to ambient light, heat and stray electrical fields.[2] Such effects are almost negligible once ionization has taken place. The NE-51 and NE-2 bulbs are of the negative-glow type in which light is produced by the ion activity surrounding the cathode. The direct-current flow through such tubes may be considered as closely following statistical laws and might be expected to contribute noise in frequency-modulator applications. A realistic determination of noise contribution was made by utilizing the multiple tube capacitor to modulate an oscillator.



Single-tube capacitor showing NE-51 glow tube glass envelope

The oscillator output frequency was multiplied and applied to an f-m receiver. A modulating voltage was applied to the capacitor sufficient to create approximately 10 percent of the maximum capacitance variation available. The results are shown in Table I.

The rms f-m detector output was measured under conditions of no modulation at the received frequency. It was then compared with the residual noise when the gas capacitor was extinguished. No significant noise change was found.

Two possible ionization modes were noted where a sufficiently strong field exists to create a second ionization independent of the

Table I—Performance Data on the Variable Multiple Glow-Tube Capacitor

Static current	0.005 amp
Static capacitance at 0.005 amp	11.2 $\mu\mu f$*
Maximum capacitance change	± 1 $\mu\mu f$*
Capacitance change for $\pm$ 10% peak current change	± 0.125 $\mu\mu f$*
RMS Level of contributed noise with respect to RMS test receiver output created by $\pm$ 10% peak current change	< -60db**

When multiple glow tubes are used it is desirable to apply the modulation in series in order to eliminate the use of a separate coupling capacitor for each glow tube. Noise measurements were made by substituting this capacitor for the single unit in the circuit of Fig. 5.

* At 1.75 mc
** Audio bandwidth of receiver output held to 10 kc



FIG. 5—Frequency-modulated oscillator circuit at right with which modulation measurements of Table I were made

d-c ionization. The first of these modes is the one under which all of the measurements shown were made and is the condition created by the d-c ionizing current with negligible contribution by the field between the plates.

If, under the conditions of this first mode, the field strength between the plates is increased to a high enough value the second additional ionization will take place. This is characterized by the familiar blue-violet glow which diffuses throughout the bulb. A sudden increase in capacitance accompanies this change.

The d-c ionizing current still exhibits some control over the effective capacitance. A different situation exists here since the capacitor can be expected to exhibit a resistive component of impedance which will absorb appreciable energy from the circuit.

If the field strength should increase, so will the extent of this secondary ionization up to the saturation point. If such a condition occurs, where the capacitor is applied as an oscillator control, the amplitude changes will usually degrade the frequency stability and the performance may be erratic.

This difficulty is not present if the field strength is maintained at a low level. The gas-dielectric capacitor should be operated in a sufficiently weak field in frequency modulator use to assure that the second mode will not be triggered by peak-modulation currents.

Frequency Modulator Applications

The circuit of Fig. 5 meets the general requirements for a frequency-modulated oscillator. Ionization is held to the first mode where the field between the capacitor plates is suitably low. The frequency swing versus the rms modulating voltage is uniform throughout the audio range.

An experimental four-band r-f exciter unit was constructed utilizing four separate oscillators each on a different frequency. The NE-51 bulbs were placed behind windows in the front panel and served as indicators of the band selection in addition to their capacitor function.



FIG. 6—Curves show linearizing effect of resistance in series with glow lamp



FIG. 7—Curves show frequency stabilizing effect of gas tube on 300-mc oscillator

No measurable degradation of oscillator stability due to the use of the neon capacitors was experienced over the range 3 to 30 mc during 1,000 hours of test service.

The upper effective modulation-frequency limit will occur at the point where the ionization delay reaches a maximum. This takes place well above the audio range, however. It is characterized by a gradual increase in internal gas resistance as the modulating frequency is increased.[3]

Reference to Fig. 2 will indicate that some amplitude distortion of the demodulated wave must occur, since the capacitor does not exactly meet the $C = Iek$ requirement for a perfect modulator. This distortion will increase with the deviation requirement and will be largely second harmonic in order. It is typical of neon glow tubes that their terminal resistance decreases as the voltage increases.[4]

If one assumes a zero impedance modulating source, a condition will exist where the ionizing current will rise to a higher value during positive voltage increments than would be the case if the glow tube exhibited a constant impedance. This positive nonlinear resistance characteristic may be used to cancel the nonlinear capacitance characteristic. Thus distortion is reduced by placing resistance in series with the modulating source, see Fig. 6, or by suitable choice of modulation-source impedance.

The second mode of operation has been used to advantage experimentally to stabilize a h-f oscillator against changes resulting from plate-supply variations. In this case a circuit similar to that shown in Fig. 5 was used except that no d-c ionizing current was present and the capacitance was controlled by the field strength between the plates.

The test results[5] are shown in Fig. 7. This suggests a means of frequency stabilizing an a-m self-excited oscillator. The multiple-bulb coaxial-type capacitor shown in Fig. 1B provides greater capacitance changes than are possible with the single unit.

The variable gas-dielectric capacitor is a simple, efficient and reliable device having applications in frequency control of self-excited oscillators. It is potentially useful in other low-power circuits where small changes in capacitance are required to be controlled at rates to at least 20 kc.

While the glow tubes shown provide creditable performance, they show considerable variations between individually available commercial types. With particular attention to structure and type of gas, a group of gas tubes may be designed to take fuller advantage of the method described.

The writer wishes to express his appreciation to R. F. Smeltzer of the Bendix Radio Division; A. B. Meador, Melpar Corporation; W. G. Chenoweth and T. C. Fletcher of the Shasta and Beckman Divisions, respectively, of Beckman Instruments, Incorporated.

References

(1) Murray G. Crosby, U. S. Patents 2,127,486, 2,077,223; Hollmann 2,123,242; Weighton 2,446,118.
(2) R. M. Strassner, Gas-Diode Electronic Organ, ELECTRONICS, p 70, Jan. 1951.
(3) Mackay and Morris, Transient Response in Glow Discharges, *Proc IRE*, p 961, June 1954.
(4) Maxfield and Benedict, "Theory of Gaseous Conduction and Electronics," p 348, McGraw-Hill Book Co., Inc., 1941.
(5) Some preliminary investigations were made in the Research Department of the Bendix Radio Division on this control means in 1950.
(6) Linder and Wolff, Note on an Ionized Gas Modulator for Short Waves, *Proc IRE*, 22, p 791, June 1934.

Transistor Characteristics for Circuit Designers

SUMMARY——Tables indicate physical properties, maximum electrical ratings, small-signal low-frequency parameters and average characteristics for grounded-base, grounded-emitter, grounded-collector and switching circuits for 218 transistor types: 106 junction triodes, 46 high-frequency triodes, 6 tetrodes, 23 high-power units, 25 point-contact and 12 phototransistors

By SEYMOUR SCHWARTZ

Lincoln Laboratory
Massachusetts Institute of Technology
Lexington, Massachusetts

SUCCESSFUL transistor circuit design requires not only familiarity with transistor equivalent circuits and characteristic curves but also an understanding of the behavior of the parameters describing the transistor and the variation of these parameters with bias and temperature. Tables I to VI have been compiled as a systematic presentation of data necessary for transistor circuit design.

Each of the charts presents physical properties, maximum electrical ratings, typical small-signal low-frequency parameters, average characteristics for grounded-emitter, grounded-base and grounded-collector circuits and switching characteristics. Figure 2 illustrates the circuits referenced in Tables II and III.

Small-signal parameters are expressed as resistances. This permits a familiar physical representation of the transistor in circuit design. Box on p 171 enables transformation between h and r parameters.

All the characteristics are for fixed-bias conditions. However, these values vary with operating conditions. Examples of these variations are shown in Fig. 1A, 1B, 1C and 1D.

Figure 1A illustrates how collector capacitance C_c varies with collector voltage V_c. In designing an i-f tuned circuit, the tuning capacitor must be large enough to swamp out the effects of the variation of collector capacitance. If the i-f stage is a grounded-emitter rather than a grounded-base stage, the collector capacitance is magnified by the base-current amplification factor, β.

In i-f stages where neutralization is used to maximize gain by balancing out C_c, instability may occur when the battery voltage decreases. This variation of C_c with V_c permits use of the transistor as a reactance element in f-m applications.

At low current bias, Fig. 1B, 1C and 1D, the noise factor of the transistor decreases and emitter resistance r_e, base resistance r_b and collector resistance r_c increase, providing increased power gain and larger values of input and output impedance. This is advantageous in hearing aids where low bias currents are used.

Temperature Effects

In the germanium transistor, noticable changes in α, β and I_{co} take place at approximately 60 C as shown in Fig. 1E. These changes can lead to instability at high temperatures by α becoming equal to or greater than unity or by I_{co} increasing and causing a collector runaway effect due to self heating.

Temperature problems are minimized in silicon transistors as seen in Fig. 1F. The value I_{co} becomes almost negligible in design consideration as the upper limit or temperature range is above 100 C. In such special applications as d-c amplifiers, the slightest change in α over the normal temperature operating range can produce a significant change in d-c current gain of the grounded-emitter stage.

The low-frequency low-power triode junction transistor, Table I, is most commonly used. The majority are utilized in hearing aids audio systems, low-power control systems

ABBREVIATIONS USED IN TABLES

α	Current gain
β	Base-current amplification factor
BW	Bandwidth
C_c	Collector capacitance
$f_{\alpha c o}$	Alpha cutoff frequency
g-b	Grounded base
g-c	Grounded collector
g-e	Grounded emitter
I_b	Base current
I_{b2}	Second base current (tetrode)
I_c	Collector current
I_{co}	Collector cutoff current
I_e	Emitter current
I_{eo}	Emitter cutoff current
NF	Noise figure
r_b	Base resistance
r_c	Collector resistance
r_e	Emitter resistance
R_g	Generator resistance
R_i	Input resistance
R_L	Load resistance
R_o	Output resistance
V_c	Collector voltage

TABLE I—JUNCTION TRIODE LOW-POWER TRANSISTORS

Manufacturer	Type No.	Type	Max Coll Power (mw)	Max Coll Voltage (v)	Max Coll Current (ma)	Max Ambient Temp (degC)	Small-Signal Low-Frequency					
							Bias					
							V_e (v)	I_e (ma)	β	r_e (ohms)	r_b (ohms)	r_c (meg)
Amperex Electronic Corp.	OC70	*pnp* fused[1]	25 (45C)	−10	−10	45	−2	0.5	30	39	1,000	1.43
230 Duffy Ave.	OC71	*pnp* fused[1]	25 (45C)	−10	−10	45	−2	3	47	6.5	500	0.625
Hicksville, N. Y.												
CBS-Hytron	2N36	*pnp* fused	50	−20	− 8	50	−6	1	45	30	450	0.95
Danvers, Mass.	2N37	*pnp* fused	50	−20	− 8	50	−6	1	30	30	350	0.55
	2N38	*pnp* fused	50	−20	− 8	50	−6	1	15	25	350	0.5
	HA-1	*pnp* fused	50	−20	− 8	50	−3	0.5	40	24	700	1.7
	HA-2	*pnp* fused	50	−20	− 8	50	−3	0.5	30	35	350	0.8
	HA-3	*pnp* fused	50	−20	− 8	50	−3	0.5	35	30	450	0.6
	HC-1	*pnp* fused	50	−20	− 8	50	−6	1	45	30	450	0.95
Germanium Prod. Corp.	NPN-3/ 2N103	*npn* grown	50 (25C)	35	10	75	4.5	−1	4	25	100	2.0
26 Cornelison Ave.	RD2517A/ 2N97	*npn* grown	50 (25C)	30	10	75	4.5	−1	13.3	25	100	3.0
Jersey City, N. J.	RD2518A/ 2N97A	*npn* grown	50 (25C)	40	10	85	4.5	−1	13.3	25	100	10.0
	RD2521A/ 2N98	*npn* grown	50 (25C)	40	10	75	4.5	−1	40	25	150	5.0
	RD2522A/ 2N98A	*npn* grown	50 (25C)	40	10	85	4.5	−1	40	25	150	10.0
	RD2523A/ 2N99	*npn* grown	50 (25C)	40	10	75	4.5	−1	40	25	150	5.0
	RD2525A/ 2N100	*npn* grown	25 (25C)	25	5	50	4.5	−1	140	25	400	5.0
General Electric Co.	2N43	*pnp* fused	150 (25C)	−45[5]	−50	100	−5	1	49	32	400	1.0
Electronics Park	2N44	*pnp* fused	150 (25C)	−45[5]	−50	100	−5	1	21.2	26.5	300	1.0
Syracuse, N. Y.	2N45	*pnp* fused	150 (25C)	−45[5]	−50	100	−5	1	11.5	20	250	1.0
	2N43A	*pnp* fused	150 (25C)	−45[5]	−50	100	−5	1	43.4	15	575	1.43
	2N43A USAF	*pnp* fused	150 (25C)	−45	−50	100	−5	1	43.4	15	575	1.43
	2N76	*pnp* fused	50 (25C)	−20[5]	−10	60	−5	1	19	17	300	1.0
General Transistor Corp.	GT-14	*pnp* fused	70 (50C)	−25		85	−4.5	1	28	30	800	1.5
95–18 Sutphin Blvd	GT-20	*pnp* fused	70 (50C)	−25		85			45	30	800	1.5
Jamaica, N. Y.	GT-34	*pnp* fused	70 (50C)	−25		85			15	30	800	1.5
	GT-81	*pnp* fused	70 (50C)	−25		85			65	30	800	1.5
	GT-83	*pnp* fused	70 (50C)	−25		85			45	30	800	1.5
	GT-87	*pnp* fused	70 (50C)	−25		85			28	30	800	1.5
	GT-88	*pnp* fused	70 (50C)	−25		85			65	30	800	1.5
	2N34	*pnp* fused	70 (50C)	−25		85	−4.5	1	40	30	350	2.0
	2N36	*pnp* fused	70 (50C)	−25		85	−4.5	1	45	30	850	2.0
	2N37	*pnp* fused	70 (50C)	−25		85	−4.5	1	30	30	600	2.0
	2N38	*pnp* fused	70 (50C)	−25		85	−4.5	1	15	30	400	2.0
	2N39	*pnp* fused	70 (50C)	−25		85	−4.5	1	45	30	850	2.0
	2N40	*pnp* fused	70 (50C)	−25		85	−4.5	1	28	30	600	2.0
	2N42	*pnp* fused	70 (50C)	−25		85	−4.5	1	13	30	400	2.0
Hughes Aircraft Co	HA5001	*npn* alloyed	500 (25C)	30	100	85	5	1	65.6	16.5	900	2
Culver City, Calif.	HA5002	*npn* alloyed	500 (25C)	20	100	85	5	1	27.5	16	400	1
	HA5003	*npn* alloyed	500 (25C)	20	100	85	5	1	99	26	400	1
Hydro-Aire Inc.	J-1	*pnp* fused	150 (25C)	−40	−10	50	−6	1	34	30	400	1.0
Burbank, Calif.	J-2	*pnp* fused	150 (25C)	−40	−10	50	−6	1	15	30	300	0.7
	J-3	*pnp* fused	150 (25C)	−40	−10	50	−6	1	9	30	300	0.5
	HA-1	*pnp* fused	100 (25C)	−20	−10	50	−6	1	40	30	350	0.75
	CQ-1	*pnp* fused	150 (25C)	−40	−10	50	−6	1	9	30	200	0.5
Nat'l Union Electric	2N39	*pnp* fused	47 (25C)	−27	−12	60	−4.5	1	32.4			1 to 2
350 Scotland Rd.	2N40	*pnp* fused	47 (25C)	−27	−12	60	−4.5	1	15.7–32.4			1 to 2
Orange, N. J.	2N42	*pnp* fused	47 (25C)	−18	−12	60	−4.5	1	9			0.5 to 2
	T34D	*pnp* fused[1]	56 (25C)	−27	−12	70	−4.5	1	32.4	20		1 to 2
	T34E	*pnp* fused[1]	56 (25C)	−27	−12	70	−4.5	1	15.7–32.4	20		1 to 2

Parameters				Grounded-Emitter Connection					Grounded-Base				Grounded-Collector			
$f_{\alpha c o}$ (mc)	C_c ($\mu\mu$f)	I_{co} (μa)	NF (db)	I_b (ma)	R_i (ohms)	R_L (ohms)	R_g (ohms)	Gain (db)	R_i (ohms)	R_L (ohms)	R_g (ohms)	Gain (db)	R_i (ohms)	R_L (ohms)	R_g (ohms)	Gain (db)
		− 8	10													
		− 8	10													
0.5						30,000	1,000	40								
0.5						30,000	1,000	36								
0.5						30,000	1,000	32								
		−12	12			30,000	1,000	30								
		−12	27			30,000	1,000	30								
						1,200	1,000	35								
0.7		−12				30,000	1,000	40								
0.75	20	5	22	0.25	225	100,000	matched	33	45	250,000	matched	30	2,500	500	matched	7
1.0	19	2	20	0.07	400	100,000	matched	38	35	250,000	matched	32	7,000	500	matched	11
1.0	19	2	15	0.07	400	100,000	matched	38	35	250,000	matched	32	7,000	500	matched	11
2.5	14	2	20	0.025	850	100,000	matched	47	35	250,000	matched	35	20,000	500	matched	15
2.5	14	2	15	0.025	850	100,000	matched	47	35	250,000	matched	35	20,000	500	matched	15
3.5	10	2	15	0.025	850	100,000	matched	47	35	250,000	matched	35	20,000	500	matched	15
5.0	14	2	20	0.007	3,500	100,000	matched	53	45	250,000	matched	35	70,000	500	matched	20
1.0	40	−10	22		1,000	30,000	600	39	60	50,000	100	28	30,000	600	30,000	15
1.0	40	−10	22		700	30,000	600	38	55	50,000	100	28	15,000	600	15,000	12
1.0	40	−10	22		450	30,000	600	36	50	50,000	100	28	7,500	600	7,500	11
1.0	40	− 5	10		1,000	30,000	600	39	60	50,000	100	28	30,000	600	30,000	15
1.0	40	− 5	30		1,000	30,000	600	39	60	50,000	100	28	30,000	600	30,000	15
1.0	10	− 5	18		1,000	30,000	600	38	55	50,000	100	28	15,000	600	15,000	12
0.65		−10	16													
0.65		−10	16													
0.65		−10	16													
0.65		−10	16													
0.70		−10	16													
0.50		−10	16													
1.0		−10	16													
		−15	24													
		−15	24													
		−15	24													
		−15	24													
		−15	24													
		−15	24													
		−15	24													
2.5	15	5														
0.8		12	15													
1.5		10	15													
1.0		−10	11					40								
0.5		−15	22					35								
0.5		−20	33					30								
		−10	20													
0.5		−20	33													
		−10	20			30,000	500	39								
		−10	24			30,000	500	38								
		−20	28			30,000	500	36								
		−10	20			30,000	500	39								
		−10	24			30,000	500	38								

and low-speed computing circuits. Present units are available in the *pnp* and *npn* fused germanium, the *npn* grown germanium and *npn* grown silicon types. Of the fused type of transistor, the *pnp* is more available commercially and consequently has found a wider range of applications. The *npn* fused type is suitable for complementary symmetry circuitry. The grown silicon type is used for high temperature and low I_{co} applications.

The germanium and silicon grown transistors are used in almost the same manner as the fused transistor. Frequently, the grown types, owing to their lower value of collector capacitance and higher value of α cutoff, may be employed as

TRANSISTOR CHARACTERISTICS

Table I (cont)

Manufacturer	Type No.	Type	Max Coll Power (mw)	Max Coll Voltage (v)	Max Coll Current (ma)	Max Ambient Temp (degC)	Small-Signal Low-Frequency					
							Bias		β	r_e (ohms)	r_b (ohms)	r_c (meg)
							V_c	I_e				
Nat'l Union (cont)	T34F	*pnp* fused[1]	56 (25C)	−18	−12	70	−4.5	1	9	20		0.5 to 2
Philco Corp.	2N47	*pnp* fused[1]	50 (25C)	−35	−20		−5	1	39	25	600	1.0
4700 Wissahickon Ave.	2N49	*pnp* fused[1]	50 (25C)	−35	−20		−5	1	39	25	600	1.0
Philadelphia, Pa.												
RCA	2N104	*pnp* fused[2]	110 (25C)	−30	50	85	−6	1	44	24.5	750	2.25
Harrison, N. J.	2N77	*pnp* fused[1]	35 (25C)	−25	15	50	−4	0.7	40	36	560	2.3
Raytheon Mfg Co.	CK721	*pnp* fused[3]		−15[6]	−10	70	−6	1	45	25	700	2.0
55 Chapel St.	CK722	*pnp* fused[3]		−22[6]	−10	70	−6	1	22	25	250	2.0
Newton, Mass.	CK725	*pnp* fused[3]		−12[6]	−10	70	−6	1	90	25	1,500	2.0
	CK727	*pnp* fused[3]		− 6[6]	−10	70	−1.5	0.5	35	50	500	2.0
	2N63	*pnp* fused		−22[6]	−10	85	−6	1	22	25	350	2.0
	2N64	*pnp* fused		−15[6]	−10	85	−6	1	45	25	700	2.0
	2N65	*pnp* fused		−12[6]	−10	85	−6	1	90	25	1,500	2.0
Sylvania Electric	2N34	*pnp* fused	50 (25C)	−40	−10		−6	1	40	26	800	2.0
1740 Broadway	2N35	*npn* fused	50 (25C)	−40	−10		6	−1	40	26	800	2.0
New York, N. Y.												
Texas Instruments	200	*npn* grown	50 (25C)	30	5	50	5	−1	9	22	150	0.4
6000 Lemmon Ave.	201	*npn* grown	50 (25C)	30	5	50	5	−1	19	22	170	0.4
Dallas, Texas	202	*npn* grown	50 (25C)	30	5	50	5	−1	49	35	200	0.4
	206S	*npn* grown[1]	50 (25C)	30	5	50	2.5	−0.5	35			
	207S	*npn* grown[1]	50 (25C)	30	5	50	2.5	−0.5	19			
	208S	*npn* grown[1]	50 (25C)	30	10	50	2.5	−10	19			
	300	*pnp* fused	50 (25C)	−30	−10	50	−5	1	9		550	0.4
	301	*pnp* fused	50 (25C)	−30	−10	50	−5	1	19		1,000	0.4
	903	*npn* grown	150 (25C)	30	10	150	5	−1	9–19	150	500	0.5
	904	*npn* grown	150 (25C)	30	10	150	5	−1	19–39	150	1,250	0.5
	905	*npn* grown	150 (25C)	30	10	150	5	−1	≧39	150	2,500	0.5
	904A	*npn* grown	150 (25C)	30	10	150	5	−1	≧19	150	1,250	0.5
	210	*npn* grown	50 (25C)	30[7]	5	50	22.5	−2				
	302	*pnp* fused	50 (25C)	−30	−10	50	−5	1	44			
	350		50 (25C)	−12								
Transitron	2N85	*pnp* fused	750	−45	−100	100	−12	10	40	2.5	300	0.16
407 Main St.	2N86	*pnp* fused	750	−60	−100	100	−12	10	20	2.5	300	0.125
Melrose, Mass.	2N87	*pnp* fused	750	−30	−100	100	−12	10	20	2.5	300	0.125
	2N88	*pnp* fused[1]	25	−12	−10	85	−1.3	0.5	25	50	1,000	0.5
	2N89	*pnp* fused[1]	25	−12	−10	85	−1.3	0.5	25	50	1,000	2.0
	2N90	*pnp* fused[1]	25	−12	−10	85	−1.3	2.5	40	10	600	0.5
	2N91	*pnp* fused	125	−15	−500	85	−3	30	25	1.5	50	2.0
	2N92	*pnp* fused	125	−25	−200	85	−3	5	30	5	500	1.0
	2N34	*pnp* fused	125	−25	−20	100	−6	1	40	18	600	1.0
	2N36	*pnp* fused	125	−25	−20	100	−6	1	45	18	700	1.0
	2N37	*pnp* fused	125	−25	−20	100	−6	1	30	20	500	1.0
	2N38	*pnp* fused	125	−25	−20	100	−6	1	15	20	250	1.0
	2N43	*pnp* fused	375	−45	−50	100	−6	1	33	20	500	1.0
	2N44	*pnp* fused	375	−45	−50	100	−6	1	16	20	300	1.0
	2N45	*pnp* fused	375	−45	−50	100	−6	1	9	20	250	1.0
	2N63	*pnp* fused	125	−25	−20	100	−6	1	20	20	350	2.0
	2N64	*pnp* fused	125	−25	−20	100	−6	1	30	20	700	2.0
	2N65	*pnp* fused	125	−25	−20	100	−6	1	50	18	1,500	2.0
Tung-Sol Electric	DR126	*pnp* fused[4]	50 (25C)	−10[7]		85	−1.5	0.5	24	26	900	1.5
100 Eighth Ave.	DR128	*pnp* fused[4]	50 (25C)	−10[7]		85	−1.5	0.5	49	34	1,400	2.0
Newark, N. J.	DR129	*pnp* fused[4]	50 (25C)	−25[7]		85	−1.5	0.5	32.4	26	1,200	2.0
	DR130	*pnp* fused[4]	50 (25C)	−25[7]		85	−1.5	0.5	13	20.5	650	1.3
	DR154	*pnp* fused[4]	50 (25C)	−25[7]		85	−1.5	0.5	124	55	600	1.2
Western Electric	2N27	*npn* grown	50 (60C)	30	5	85	4.5	−1	19–198	50	700	2.0
120 Broadway	2N28	*npn* grown	50 (60C)	30	5	85	4.5	−1	5–198	125	1,000	1.0
New York, N. Y.												
Westinghouse	2N54	*pnp* fused[1]	200 (25C)	−45	−10	60	−6	1	33	25	400	1.0
Box 284	2N55	*pnp* fused[1]	200 (25C)	−45	−10	60	−6	1	20	20	400	1.0
Elmira, N. Y.	2N56	*pnp* fused[1]	200 (25C)	−45	−10	60	−6	1	13	5	400	1.0

high frequency transistors.

The maximum power ratings on most of the low-power transistors are of the order of 50 milliwatts collector dissipation at room temperature. Some of these units have external heat sinks and are able to dissipate considerably more power.

The rating most commonly em-

Parameters				Grounded-Emitter Connection					Grounded-Base				Grounded-Collector			
$f_{\alpha co}$ (mc)	C_e ($\mu\mu$f)	I_{co} (μa)	NF (db)	I_b (ma)	R_i (ohms)	R_L (ohms)	R_g (ohms)	Gain (db)	R_i (ohms)	R_L (ohms)	R_g (ohms)	Gain (db)	R_i (ohms)	R_L (ohms)	R_g (ohms)	Gain (db)
		−20	28			30,000	500	36								
1.0	49	−10	15		1,000	50,000 matched		42								
1.0	49	−10	12		1,000	50,000 matched		42								
0.7		−10	12		1,200	50,000 matched		43	140	400,000 matched		32.8	500,000	20,000 matched		13.9
0.7		−10	9		1,350	50,000 matched		42.6	130	400,000 matched		33.2	10,000	300 matched		16.2
		− 6	22		1,500	20,000 matched		41	70	100,000 matched		31	600,000	20,000 matched		15
		− 6	25		500	20,000 matched		36	45	100,000 matched		32	200,000	20,000 matched		10
		− 6	20		2,700	20,000 matched		42	110	100,000 matched		30	1,000,000	20,000 matched		16
		− 6	12			20,000	1,000	36		200,000	100	28	540,000	10,000	100,000	14
		− 6	25		800	20,000 matched		39	50	100,000 matched		32	350,000	20,000 matched		13
		− 6	22		1,500	20,000 matched		41	70	100,000 matched		31	600,000	20,000 matched		15
		− 6	20		2,700	20,000 matched		42	110	100,000 matched		30	1,000,000	20,000 matched		16
0.6	15	− 5	18	−0.03	1,200	30,000	500	40					20,000	500 matched		16
0.8	18	5	16	0.03	1,200	30,000	500	40					20,000	500 matched		16
0.9	15	10	26		480	20,000	500	37	35	100,000	60	30	9,500	500	15,000	12
1.1	17	10	23		970	20,000	500	40	40	100,000	60	30	15,500	500	15,000	14.5
1.3	19	10	20		1,250	20,000	1,250	43	45	100,000	60	31	32,000	500	15,000	17
		3	14			20,000	1,000	32								
		3.5	21			20,000	1,000	29								
		4	26			300	1,000	26								
		−10	25													
		−10	20													
3		1 (25C)	23													
3		1 (25C)	23													
3		1 (25C)	23													
≧8		1 (25C)	23													
		50 (25C)				10,000	500	39								
		−10														
0.8		−10	20			1,000	500	30								
0.8		−10	20			1,000	500	26								
0.8		−20	20			1,000	500	26								
0.5		−10	10			20,000	1,000	36								
0.5		−10	20			20,000	1,000	36								
0.5		−10	20			600	1,000	26								
		−15														
		−10														
		−10	20			30,000	1,000	40								
		−10	20			30,000	1,000	40								
		−15	22			30,000	1,000	36								
		−25	24			30,000	1,000	32								
		−15	20			30,000	1,000	40								
		−15	22			30,000	1,000	37								
		−15	22			30,000	1,000	33								
		−10	25			30,000	1,000	38								
		−10	22			30,000	1,000	39								
		−10	20			30,000	1,000	41								
0.9		− 9	14	−0.006		30,000	1,000	33								
0.9		− 8	18	−1.5		300		24								
0.7		−10	18	−0.006		30,000	1,000	35								
0.5		−14	21	−0.006		30,000	1,000	27								
0.7		−10	18	−0.006		30,000	1,000	40								
2	17	10	30													
0.95	25	10	30													
0.5		− 6			700	50,000	700	39.5	125	300,000	125	31	35,000	1,000	35,000	15
0.5		− 6			550	67,000	550	39	125	300,000	125	31	27,000	1,000	27,000	13
0.5		− 6			450	85,000	450	37	125	300,000	125	31	20,000	1,000	20,000	11

All sockets A to H except where otherwise noted
[1] Socket type A
[2] Socket types B to H
[3] Socket types A, I and J
[4] Socket type not given

Characteristics measured at 25 C unless otherwise noted
[5] Characteristics measured at 30 C
[6] Characteristics measured at 27 C
[7] Temperature not given

ployed is the maximum power rating. Maximum current and maximum voltage ratings cannot be achieved simultaneously because the product of these two ratings usually exceeds maximum rating. The maximum voltage rating is set at a value safely below the collector voltage breakdown value while the max-

TABLE II—HIGH-FREQUENCY TRANSISTORS

Manufacturer	Type No.	Type	Max Coll Power (mw)	Max Coll Voltage (v)	Max Coll Current (ma)	Max Ambient Temp (degC)	Storage Temp (deg C)	Typical Small-Signal				
								Bias		β	r_e (ohms)	r_b (ohms)
								V_e (v)	I_e (ma)			
General Electric	2N78	*npn* rate grown	50 (30C)	15	20	100	100 max	5	−1	27.5		
	2N123	*pnp* fused	150 (25C)	−15	150		85	−5	1	30–150		
	2N135	*pnp* alloyed	100 (25C)	−20	−50		85	−5	1	20		
	2N136	*pnp* alloyed	100 (25C)	−20	−50		85	−5	1	40		
	2N137	*pnp* alloyed	100 (25C)	−10	−50		85	−5	1	60		
Germanium Prod.	RD2523A (2N99)	*npn* grown	50 (25C)	40	10	75		5	−1	40	25	150
	RD2525A (2N100)	*npn* grown	25 (25C)	25	5	50		5	−1	100	25	400
	RD2521A (2N98)	*npn* grown	50 (25C)	40	10	75		5	−1	40	25	150
	RD2517A	*npn* grown	50 (25C)	30	10	75		5	−1	13	25	100
Hydro-Aire	HF-1	*pnp* fused	35 (25C)	−15	− 5	55		−4.5	1	25	30	500
	IF-1	*pnp* fused	35 (25C)	−15	− 5	55		−4.5	1	20	30	500
Philco	SB-100	surface barrier[1]	10 (40C)	− 4.5	− 5		−55 to 85	−3	0.5	19	50	
Raytheon	CK-760	*pnp* fused		− 6[2]	− 5		−55 to 85	−6	1	45	22	70
	CK-761	*pnp* fused		− 6[2]	− 5		−55 to 85	−6	1	50	22	70
	CK-762	*pnp* fused		− 6[2]	− 5		−55 to 85	−6	1	60	22	70
Sylvania	2N94	*npn* alloyed	50 (25C)	20	10		−55 to 85	6	−0.5	30	52	500
	2N94A	*npn* alloyed	50 (25C)	20	10		−55 to 85	6	−0.5	30	52	500
Texas Inst.	220	*npn* grown[1]	50 (25C)	30	5	50		22.5				
	221	*npn* grown[1]	50 (25C)	30	5	50		22.5				
	222	*npn* grown[1]	50 (25C)	30	5	50		22.5				
	223	*npn* grown[1]	50 (25C)	30	5	50		22.5				
	904A	*npn* grown	150 (25C)	30	10	150		5	−1	≥19	150	1,250
	224–1											
	2											
	3											
	4											
	5											
	225–1											
	2											
	3											
	4											
	5											
	226–1											
	2											
	3											
	4											
	5											
	227–1											
	2											
	3											
	4											
	5											
Tung-Sol	DR-155	*pnp* fused[2]	50 (25C)	−10		85	−55 to 85	−1.5	0.5	32		
	2N112	*pnp* fused	50 (25C)	−10	− 8	85	−55 to 85	−6	1	32	31	110
	2N113	*pnp* fused	50 (25C)	−10	− 8	85	−55 to 85	−6	1	32	31	110
Western Electric	2N27	*npn* grown	50 (60C)	30	5	85		4.5	−1	20–198	50	700

Socket types A to H unless otherwise noted
[1] Socket type A only
[2] Socket types A and J

Low-Frequency Parameters						H-F Parameters	High-Frequency Circuit Conditions					High-Speed Switching Characteristics			
r_e (meg)	$f_{\alpha e}$ (mc)	C_c ($\mu\mu$f)	I_{co} (μa)	I_{eo} (μa)	NF (db)	$r_b C_c$ ($\mu\mu$ sec)	Application	R_i (ohms)	R_o (ohms)	Power Gain (db)	Circuit	Rise Time (μsec)	Fall Time (μsec)	Reverse Emitter Voltage (v)	Circuit
	5.5	6	1		14		r-f amp	1,000	6,000	20					
							i-f amp	1,500	10,000	30					
	7.5	14	−2	5	10	1,000	switching					0.1	0.2	5	
	4.5	14	5				r-f/i-f amp			29					
	6.5	14	5				"			31					
	10	14	5				"			33					
5.0	3.5	10	2		15		i-f amp unneut	500	10,000	22		<0.2	<0.3		
5.0	5.0	14	2		20		"	750	10,000	23		<0.2	<0.3		
5.0	2.0	14	2		20		"	500	10,000	22		<0.2	<0.3		
3.0	1.0	19	2		20		"	350	10,000	20		<0.2	<0.3		
1.0	5.0	10	−10												
1.0	2.0	10	−10												
0.4	30 (osc)	2.2	−0.5	0.5		800									
1.0	5	14	−2	2	25	1,000									
1.0	10	14	−2	2	25	1,000									
1.0	20	14	−2	2	25	1,000									
2.0	3.5	10	3	−3	15	1,000	i-f (g-b)	80	100,000	25[4]	C	0.15	0.15	≥0	F
							i-f (g-e)	500	25,000	32[4]	D				
2.0	6.0	10	3	−3	15	1,200	i-f (g-b)	80	100,000	25[4]	C	0.1	0.1	≥0	
							i-f (g-e)	800	25,000	35[4]	D				
							r-f (g-b)	80	15,000	20[5]	E				
			50				262-kc (g-e) i-f	750	70,000	31	A				
			50				"	750	70,000	33	A				
			50				"	750	70,000	35	A				
			50				262-kc conv	300	60,000	20	B				
0.5	≥8		1												
							neut 262-kc g-e i-f	600	70,000	26	H				
										28					
										30					
										32					
										34					
							neut 455-kc g-e i-f	500	50,000	24	H				
										26					
										28					
										30					
										32					
							neut 262-kc g-b i-f	65	120,000	18	I				
										20					
										22					
										24					
										26					
							neut 455-kc g-b i-f	65	150,000	18	I				
										20					
										22					
										24					
										26					
1.0	1.4		−15		28										
1.2	5		−10		28		i-f	600	25,000	32	G				
1.2	10		−10		28		i-f	600	25,000	33	G				
2.0	2	17	10												

Characteristics measured at 25 C unless otherwise noted

[3] Characteristics measured at 27 C

[4] Bandwidth 12 kc

[5] Bandwidth 25 kc

TABLE III—GROWN *NPN* JUNCTION TETRODE TRANSISTORS

Manufacturer	Type No.	Max Coll Power (mw)	Max Coll Voltage (v)	Max Coll Current (ma)	Max Base-to-Base Current (ma)	Application	Small-Signal Low-Frequency				
							Bias		I_{b2} (ma)	α	r_e (ohms)
							V_e (v)	I_e (ma)			
Germanium Prod.	RDX-302/ 3N23	50(25C)	30	5	5	video amp, switching 10-mc osc	4.5	1	0	0.95	30
	RDX-301/ 3N23A	50(25C)	30	5	5	video amp, switching 20-mc osc	4.5	1	0	0.97	30
	RDX-300/ 3N23B	50(25C)	30	5	5	video amp, switching 35-mc osc 20-mc i-f	4.5	1	0	0.98	30
	RDX-300A/ 3N23C	50(25C)	30	5	5	video amp, switching 50-mc osc, 20 to 30 mc i-f	4.5	1	0	0.99	30
Texas Inst.	700	50(25C)	30	5	5	low-level, low-freq age	5	−1	0	0.95	30
Western Electric	3N22	30(25C)	12	5	5	video amp, r-f	9	−2	−4.5	0.90	25
							9	−2	0	0.975	25

All sockets A, F, G, H and M

TABLE IV—POWER TRANSISTORS

Manufacturer	Type No.	Type	Max Power Output (w)			Max Coll Power (w)	Max Coll Voltage (v)		Max Coll Current (amp)	$f_{\alpha co}$ (kc)	Small-Signal		
			Class A	Class B (push-pull)	D-C Switch		Circuit				Bias		β
							g-e	g-b			V_e (v)	I_e (ma)	
Amperex	2N115	*pnp* fused[1]	1.5	2.5		2(45C)	−12(B) −6(A)		−1	300			
	2-OC72	*pnp* fused[2]				0.045(45C)	13(B)		0.045	10			
CBS-Hytron	HD-197	*pnp* fused[1]				0.5(25C)	−40			150	−10	50	10
Hydro-Aire	JP-1	*pnp* fused[2]	0.45	0.9	1.5	0.5(25C)		−45	−0.1	50	−22.5	20	9
Minneapolis-Honeywell Regulator Co.	H-1	*pnp* fused[1]	5	10	40	20(21C)	−30	−60	−0.8	20	−2		
2753 4th Ave. S Minneapolis, Minn.	2N57	*pnp* fused[1]	6	12	48	20(21C)	−30	−60	−1	20	−2		
	H-2	*pnp* fused[1]	8.5	18	68	20(21C)	−30	−60	−1.4	20	−2		
	H-3	*pnp* fused[1]	2	4	16	5(21C)	−30	−60	−0.35	20	−2		
	H-4	*pnp* fused[1]	2	6	16	5(21C)	−30	−60	−0.5	20	−2		
Sylvania	2N68	*pnp* alloyed[3]	0.75	10		4(25C)		−25	−1.5		−6	50	40
	2N95	*npn* alloyed[3]	0.75	10		4(25C)		25	1.5		6	−50	40
	2N101	*pnp* alloyed	electrically identical to 2N68										
	2N102	*npn* alloyed	electrically identical to 2N95										
Texas Inst.	X-2	*npn* grown						35	0.075	225	5	−1	9

Parameters			Typical Operation	
r_b (ohms)	r_c (megohms)	I_{co} (μa)	Freq (mc) Circuit *J*	Power-Gain at 5mc Circuit *K*
70	2	10	10 to 20	12
100	2	10	20 to 35	14
200	2	10	35 to 50	15
300	2	10	50 to 80	17
1,000	1	10		
100	1	10	15	
1,000	1			

Characteristics measured at 25 C

imum current is selected where β has not decreased to too low a value.

Table II, high-frequency transistors, includes *pnp* and *npn* fused junction, *npn* grown junction and *pnp* surface-barrier units. Except for the *npn* grown type, which is of either germanium or silicon, all of these units use germanium.

Physically, one of the main distinctions between these units and the low-frequency units is the closer spacing between emitter and collector junctions. Electrical characteristics are higher alpha cutoff, lower collector voltage breakdown and in many units lower collector capacitance and lower base resistance. The widest application is in radio receivers and high-speed switching circuits.

In selecting a high-frequency transistor for a grounded emitter i-f amplifier, note that the β cutoff frequency of the amplifier is equal to α cutoff frequency divided by β.

Table III lists tetrode junction transistors which are high-frequency triode *npn* grown junction transistors with an extra base lead and a narrower base region. The electrical characteristics of the grown tetrode transistor are almost identical to the grown triode transistor except for a lower value of base resistance and higher value of α-cutoff frequency. The extra base lead makes the tetrode applicable in specialized control circuits and avc applications. Bias for the extra base lead is usually obtained from a bleeder across the main supply.

High-Power Units

The high-power transistor, Table IV, is in most cases the largest of all transistors. One element is attached to the container. In most units the case may be connected to the chassis either directly or

Low-Frequency Parameters						Typical Operating Conditions										
r_e (ohms)	r_b (ohms)	r_c (ohms)	C_c ($\mu\mu$f)	Rise Time (μsec)	I_{co} (μa)	Class & Circuit	Supply Voltage (v)	Coll Current (ma)	Base Current (ma)	Zero Signal Current (ma)	Power Output (w)	Power Gain (db)	Driving Power (mw)	R_s (ohms)	R_L (ohms)	R_g (ohms)
						B(g-e)	−6	−1,280		−5	5[4]	27				
						B(g-e)	−6				0.2[4]	27				
	70	5,000				A		−50				30			5,000	100
2	150	100,000			−500	B(g-b)	−22.5	−40			0.7[4]	20				
				1.5	−8,000	A(g-e)	−28	400	50		5	15	158	20	70	4
						B(g-e)	−28	510		4	10[4]	12	630	100	140	4
				1.2	−8,000	A(g-e)	−28	500	45		6.25	16	156	35	56	4
						B(g-e)	−28	640		4	12.5[4]	13	625	140	128	4
				0.5	−8,000	A(g-e)	−28	600	30		7.5	20	75	40	47	4
						B(g-e)	−28	890		4	17.5[4]	16	440	100	80	4
				1.2	−1,000	A(g-e)	−28	150	15		1.9	16	48	100	187	4
						B(g-e)	−28	220		0.5	4.4[4]	12	278	240	320	4
				0.6	−1,000	A(g-e)	−28	150	10		1.9	21	15	60	187	4
						B(g-e)	−28	318		0.5	6.25[4]	14	250	200	224	4
1	30	100,000	300		−100	A(g-b)	−12	−150			0.6	23		75	100	50
						B(g-e)	−12	−550		−1	5[4]	15		50	12	50
						B(g-c)	−12	−550		−1	5[4]	10		250	12	100
						B(g-b)	−24	−950		−1	10[4]	10		2	24	2
1	30	100,000	300		100	A(g-b)	12	150			0.6	23		75	100	
						B(g-e)	12	550		1	5[4]	15		50	12	
						B(g-c)	12	550		1	5[4]	10		250	12	
						B(g-b)	24	950		1	10[4]	10		2	24	
25	0.75	200,000			25	B(g-b)	22.5	40			0.5[5]	9.5			1,000	
						B(g-b)	22.5	40			0.5	22.7			1,000	

Table IV (cont)

Manufacturer	Type No.	Type	Max Power Output (w)			Max Coll Power (w)	Max Coll Voltage (v)		Max Coll Current (amp)	$f_{\alpha co}$ (kc)	Small-Signal		
							Circuit				Bias		
			Class A	Class B (push-pull)	D-C Switch		g-e	g-b			V_c (v)	I_e (ma)	β
Texas Inst. (cont.)	951	*npn* grown silicon		0.45(25C) 0.3(100C) 0.15(150C)		1(25C) 0.5(100C) 0.15(150C)	50		0.06				
	952	*npn* grown silicon		0.6(25C) 0.4(100C) 0.15(150C)		1(25C) 0.5(100C) 0.15(150C)	80		0.05				
	953	*npn* grown silicon		1(25C) 0.5(100C) 0.15(150C)		1(25C) 0.5(100C) 0.14(150C)	120		0.04				
Transistor Products	X-107	*pnp* fused[1]	1			2(25C)	−30	−60	−1		−24	80	22
241-251 Crescent Ave. Waltham, Mass.	X-120	*pnp* fused[1]	7.5			15(25C)	−30	−60	−4		−28	360	20
Transitron	2N83	*pnp* fused[2]	5	15	40	10(25C)	−30	−45	−1	200	−20	100	8
	2N84	*pnp* fused[2]	5	10	30	10(25C)	−22	−30	−1	200	−20	100	12
Tung-Sol	DR-150	*pnp* fused		1	3.5	5(25C)		−25	−1	250	−15	10	33
Western Electric	2N66	*pnp* fused[1]				5(25C)	−40	−60	−0.8	500	−4.5 −40	100 0	45

[1] Type A sockets

[2] Socket types A to H

TABLE V—POINT-CONTACT TRANSISTORS

Manufacturer	Type No.	Application	Max Coll Power (mw)	Max Coll Voltage (v)	Max Coll Current (ma)	Max Reverse Emitter Voltage (v)	Max Emitter Current (ma)	Max Emitter Power (mw)	Small-Signal			
									Bias		$-\alpha$	r_e (ohms)
									V_e (v)	I_e (ma)		
Hydro-Aire	A-0	amp, osc	0(25C)	−20	−8				−8	0.3	2	425
	A-1	amp, osc	50(25C)	−20	−8				−8	0.3	2	425
	A-2	amp, osc	50(25C)	−20	−8				−8	0.3	2	375
	A-3	amp, osc	50(25C)	−20	−8				−8	0.3	2	350
	S-0	switching	50(25C)	−40	−8	−30						
	S-1	switching	50(25C)	−40	−8	−30						
	S-2	switching	50(25C)	−30	−8	−30						
Sprague Electric	5A	switching	80(25C)	−50	−10	−50			−10	1	3	
Transistor Prod.	2A	amp, osc, sw	120(25C)	−50	−8	−50						
	2C	switching[1]	100(25C)	−50	−8	−50						
	2D	amp, osc[1]	100(25C)	−50	−8	−50						
	2E	amplifier[1]	100(25C)	−50	−8	−50						
	2G	switching[1]	120(25C)	−50	−8	−50						
	2H	amplifier[1]	100(25C)	−50	−8	−50						
	2L	switching[1]	50(25C)	−50	−8	−50						
	2N32	switching[1]	50(25C)	−40	−8	−40						
	2N33	switching[1]	30(25C)	−8.5	−7							
	2N50	switching[1]	50(25C)	−15	−1	−15						
	2N51	sw, osc[1]	100(25C)	−50	−8	−50						
	2N52	amp, osc[1]	120(25C)	−50	−8	−50						
	2N53	switching[1]	120(25C)	−50	−8	−50						
Western Electric	2N21	switching	120(25C)	−100	−60	−100	60	80(25C)[2]	−10	1	2.5[3]	200
	2N21A	amp, osc, sw	120(25C)	−100	−60	−100	60	80(25C)[2]	−10	1	2.5[3]	200
	2N110	switching	200(25C)	−100	−75	−100	75	100(25C)[2]	−10	1	2.5[3]	200
	2N67	hi-speed sw	100(25C)	−100	−60	−100	60	60(25C)[2]	−10	1	3	900

Socket types A to H unless otherwise noted

[1] Socket types A and L

Maximum ambient temperature 50 C unless otherwise noted

[2] Maximum ambient temperature 85 C

Characteristics of A-0, A-1, A-2, A-3, 2N21, 2N21A, 2N110 and 2N67 measured at 25 C

Low-Frequency Parameters						Typical Operating Conditions										
r_e (ohms)	r_b (ohms)	r_c (ohms)	C_c ($\mu\mu$f)	Rise Time (μsec)	I_{co} (μa)	Class & Circuit	Supply Voltage (v)	Coll Current (ma)	Base Current (ma)	Zero Signal Current (ma)	Power Output (w)	Power Gain (db)	Driving Power (mw)	R_s (ohms)	R_L (ohms)	R_g (ohms)
					5	B(g-e)	28	30			0.45(25C)[4] 0.15(150C)	20			1,500	1,000
					6	B(g-e)	45	25			0.6(25C)[4] 0.15(150C)	21			4,000	1,000
					8	B(g-e)	67.5	20			1(25C)[4] 0.15(150C)	23			8,000	1,000
0.85	12	50,000			−120	A(g-b)	−28	−80			1	24	4	1.5	375	
0.65	1	10,000			−200	A(g-b)	−28	−360			5	20	50	0.8	100	
0.3	15	20,000	400	1.5	−100	B(g-e)	−30	−160			2.5[4]	24			600	100
0.3	15	20,000	400	1.5	−100	B(g-e)	−20	−160			2.0[4]	22			400	100
		30,000														
			400		75											
					300											

[3] Socket types A and K

[4] Push-pull connection

Low-Frequency Parameters						Large-Signal Parameters						
r_b (ohms)	r_e (ohms)	$f_{\alpha co}$ (mc)	C_c ($\mu\mu$f)	Nf (db)	I_{co} (μa)	Rise Time (μsec)	Turn-Off Time (μsec)	Off I_c (ma)	On V_c (v)	Emitter Rev Resist. (ohms)	α (at max rise time)
200	13,000	3			−1,200						
200	13,000	2			−1,500						
175	13,000	1			−2,000						
150	13,000	0.3			−2,000						
						0.2[3]		−1	−2	50,000	
						0.5[4]		−1	−2	50,000	
						1[5]		−1	−2	50,000	
		5		43		0.12	0.5				
90	10,000	2		45	−1.1	0.2	1.3	−1.1	−1	200,000	5
90	10,000	2		45	−1.1	0.2	1.3	−1.1	−1	200,000	5
90	15,000	1.5			−0.9	0.3	1.3	−0.9	−1	200,000	4
500	20,000	20			−0.9	0.02	0.9	−0.9	−0.8	2,000,000	7

[3] Fall time = 1 μsec
[4] Fall time = 2 μsec
[5] Fall time = 6 μsec
[6] Large-signal α = 2.4

PARAMETER CONVERSION FORMULAS

$$H_{11} = \frac{R_{11}}{R_{22}} = -\alpha$$

$$H_{11} = R_{11} - \frac{R_{12}R_{21}}{R_{22}} \doteq r_e + (1-\alpha)r_b$$

$$H_{12} = \frac{R_{12}}{R_{22}} \doteq \frac{r_b}{r_c}$$

$$H_{21} = \frac{1}{R_{22}} \doteq \frac{1}{r_c}$$

$$r_c = \frac{1}{H_{22}}$$

$$r_b = r_c H_{12}$$

$$|\alpha| = |H_{21}|$$

$$r_e = H_{11} - r_b(1-\alpha)$$

TRANSISTOR SOCKETS

Code	Manufacturer	Type
A	Solder connections	———
B	Elco Corp.	3-pin polarized 3-pin printed-circuit
C	Cinch Mfg. Corp.	3-pin polarized
D	Super-Ear Prod. Co.	3-pin polarized
E	Mycalex Tube Socket Corp.	3-pin polarized
F	Elco Corp.	4-pin polarized 4-pin printed-circuit
G	Super-Ear Prod. Co.	5-pin
H	Elco Corp.	5-pin 5-pin printed-circuit
I	Super-Ear Prod. Co.	5-pin equal spacing
J	Cinch Mfg Corp.	5-pin
K	Amphenol Co.	———
L	Cinch Mfg Corp.	———
M	Cinch Mfg Corp.	4-pin polarized

TABLE VI—PHOTOTRANSISTORS

Manufacturer	Type No.	Type	Max Coll Voltage (v)	Max Coll Current (ma)	Max Coll Power (mw)	Max dark Current (μa)	Max Ambient Temp. (deg C)	Cutoff Freq. (kc)	Noise (ft-candles)	Sensitivity (μa/ft-candles)
General Transistor	GT-66	fused, 3 lead[1]	12	20	50(25C)	15		750	6×10^{-4}	25
Texas Inst.	800	grown, 2 lead[2]	20	20	50(25C)	250	40	20		35
Transistor Prod.	1N188	grown, 2 lead	100		40(25C)		50		3 to 10 μv	10 μa/millilumen
	1N189	nonrect, 2 lead			30(25C)	20	50			0.08%/ft-candle
	10A	grown, 2 lead	15		100(25C)	500	50		15 to 100μv	4ma for 300 ft-candles
	10B	grown, 2 lead	15		100(25C)	50	50		15 to 100μv	50% for 10 ft-candles
	5B	grown, 2 lead	50		100(25C)	20	50		3 to 10μv	1ma for 300 ft-candles
	5C	grown, 2 lead	50		100(25C)	5	50		3 to 10μv	50% for 40 ft-candles
	11A	nonrect, 2 lead	15		50(25C)	4,000 ohms	50			2,000 ohms for 300 ft-candles
	11B	nonrect, 2 lead	15		50(25C)	4,000 ohms	50			3,000 ohms for 300 ft-candles
	17A	grown, 2 lead							below 1μv	
Western Electric	1N85	grown, 2 lead[1]	90	1	50	20	85	25	$2\times10^{-6}\mu$a	0.35μa/μw

[1] Socket type A
[2] Socket type A to H

through a thin mica spacer. The types used as power transistors are the germanium *pnp* fused and silicon *npn* grown.

The *pnp* fused transistors are usually the high-power units whose larger physical size provides collector power dissipation up to 20 watts. The larger physical size also contributes a higher collector capacitance and lower α-cutoff frequency. Medium power *pnp* and *npn* fused units which retain their smaller physical size and most of the electrical characteristics of the low-power transistors are used in applications requiring collector power dissipation below $\frac{1}{2}$ watt.

The characteristics peculiar to the high-power transistor are the lower values of input resistance, output resistance and α, resulting from the higher values of bias currents employed. Bias stability tech-



FIG. 1—Variation of transistor parameters with operating point (A to D) and ambient temperature (E, F)

NOW...QUICK... EASY

ASSEMBLY WITH

CINCH EDGE CIRCUIT

(PATENT PENDING)

CONNECTOR–

(SHOWN ENLARGED) ▷

The CINCH EDGE CIRCUIT CONNECTOR provides quick, easy assembly. Eliminates moisture trap. Allows more flexible tolerances. Lower cost. Available in materials for both Military and Commercial use.

PRINTED WIRE BOARD

. . . high quality etched circuit boards with 5, 6, 7, and 8 pin subminiatures as well as 7 and 9 pin standard CINCH sockets. Provide flexibility of design and application.

Graphik Circuits reduce wiring costs, reduce assembly time • eliminate errors • miniaturize •

GRAPHIK CIRCUITS Division of Cinch Manufacturing Corporation

221 South Arroyo Parkway, Pasadena 1, California

Sockets, terminals and other hardware installed to specifications



CINCH will design, or redesign, components to fit specific needs, and will assist in the assembly of components through proven automation technique.

CINCH components are available at leading electronic jobbers—everywhere.

CONSULT CINCH

Centrally located plants at Chicago, Shelbyville, Pasadena and St. Louis.

CINCH MANUFACTURING CORPORATION

1026 South Homan Ave., Chicago 24, Illinois

Subsidiary of United-Carr Fastener Corporation, Cambridge, Mass.

niques are used to minimize the effect of runaway due to self-heating of the collector.

The point-contact transistor, Table V, is limited to high-speed switching circuitry. Phototransistor devices, Table VI, are divided into two basic types: the two-lead and three-lead devices. In the two-lead unit, one lead is attached to the base and the other to the collector. The three-lead device has leads going to the emitter, base and collector respectively.

The two-lead device is used in circuits providing d-c amplification for unmodulated light while the three-lead device can be used in circuits employing a-c amplification for modulated light.

Acknowledgment is given to Ann M. Field and Elizabeth A. Sewell for their assistance in compiling data.



FIG. 2—Typical circuits for high-frequency transistors (A to I) and junction tetrode transistors (J, K) referred to in Tables II and III

MALLORY

FP Capacitors withstand high ripple currents . . . are ideal for use with selenium rectifiers, doubler or tripler circuits, especially at high ambients.

High ripple currents...high temperatures... call for Mallory FP Capacitors

Higher ripple currents in color television circuits emphasize the importance of ripple current rating in choosing electrolytic capacitors.

To see how Mallory FP Capacitors compare in this quality, take a look at the table at the right. The figures are based on extended life tests in our laboratories.

Uniformly higher in ripple current rating than other standard types of electrolytics, FP's often can carry *double* the current rating expected for a given capacitance and voltage rating. The reason for this superiority is the unique FP construction. The fabricated plate compresses a lot of effective area into minimum volume . . . so that more electrolyte and more capacitance can be placed in a smaller size container. This compact construction has improved heat dissipation. In addition, separator, etched cathode, end seal and air space are designed for 85° C. operation.

The same characteristics which give Mallory FP's their superior ability to handle high ripple current also permits them to operate effectively in auto radios, sealed military units and other equipment where high ambient temperatures are a problem.

The Mallory FP is a capacitor that needs no de-rating at 85° C., and that can take heavy ripple current without overheating and with normal life expectancy. A Mallory capacitor specialist will be glad to consult on the use of FP capacitors in your specific circuit . . . or to send you detailed technical data.

Typical Ripple Current Ratings for FP Capacitors

The following ratings represent values obtained by tests on single section units at 85° C. ambient, on 120 cycle ripple.

Capacitance	Voltage	Ripple Current Rating	
		Mallory FP	Usual Industry Expectation
80 mfd	450 VDC	670 MA	480 MA
60	450	620	440
100	350	820	500
200	150	1290	525
150	250	1030	515

Serving Industry with These Products:

Electromechanical—Resistors • Switches • Television Tuners • Vibrators
Electrochemical—Capacitors • Rectifiers • Mercury Batteries
Metallurgical—Contacts • Special Metals and Ceramics • Welding Materials

Parts distributors in all major cities stock Mallory standard components for your convenience.

Expect more . . . get more from

P. R. MALLORY & CO. Inc.
MALLORY
P. R. MALLORY & CO., Inc., INDIANAPOLIS 6, INDIANA

Want more information? Use post card on last page.

Electrons At Work

Edited by ALEXANDER A. McKENZIE

Wrist Receiver Circuit Uses Three Transistors



Highly efficient detector and two a-f stages comprise the LEL wrist radio

COMPLETE CIRCUIT of the wrist radio receiver (ELECTRONICS, p 10, Dec. 1955) is shown in the diagram.

The tap on the input inductance is adjusted for best impedance match and selectivity. The low loading of the input circuit by the transistor allows a frequency coverage of over 3-to-1 ratio with conventional slug tuning.

Regeneration is provided by the tank circuit in the emitter circuit of the r-f stage. This is tuned to a frequency below the broadcast band, thus presenting a capacitive reactance at all frequencies within the band.

Reduction of the time constant in the base circuit of the r-f stage will result in oscillation when the base current control is advanced beyond the point of stability. In strong signal areas, it is not necessary to operate the base current control close to the point of instability. However, as the distance from the station increases and low signal energy results, it is necessary to operate the control closer to threshold, as is common with regenerative receivers.

The collector circuit of this stage is bypassed to ground by the 2,000-$\mu\mu$f capacitor.

The low base current provides operation in the nonlinear portion of the transistor ΔI_b, ΔI_c characteristic, resulting in good detection characteristics. As regeneration is advanced, the input circuit losses are decreased and sufficient signal energy is supplied to the base emitter circuit.

The higher efficiency that results permits reception of much weaker signals than would be possible with a diode detector. The balance of the receiver is a two-stage audio amplifier. The overall signal gain of these stages exceeds 70 db.—V.Z.

Breakdown In Gas Tubes

OF PERENNIAL surprise to young physicists and engineers is the effect of light on the breakdown voltage of glow-discharge tubes. This interdependence is spelled out in an unpublished National Bureau of Standards report on characteristics of cold-cathode glow-discharge tubes by Eugene J. Hebert, Jr., quoted here with permission.

"The d-c breakdown voltage is greatly affected by light or rather the lack of it. Experiments of the present study indicate that the breakdown voltage, after a tube has been in complete and total darkness for 24 hours or more and then fired in complete and total darkness, may vary from 100 to 200 percent of the breakdown voltage at general room illumination (20 to 50 foot-candles).

"The effect is not consistent; a particular tube may display this variation only at intervals and then again may or may not display it for a considerable number of tests. Some tubes show little variation at all. The intensity of the light seems to be of little importance, the main factor being just that some light be present.



Influence of temperature and light on direct breakdown voltage

"The light from a nearby tube is usually sufficient to bring the breakdown voltage back to that under general room illumination. This effect is illustrated in the graph where V_1 is the breakdown voltage under room illumination and V_2 that under total darkness."

One experimenter in early cosmic-ray sounding utilized a neon-bulb relaxation oscillator to key a radio transmitter. When the keying circuit was sealed in a metal can, it failed to operate. With a tiny window set into the wall of the can in the general vicinity of the neon tube, normal operation was restored. This was true when the window passed any degree of daylight or even artificial light from an electric bulb. Intensity of illumination appears uncritical.—A.A.McK.

(Continued on Page 178)

kepco

NEW!
1.5 Ampere
KR SERIES

VOLTAGE REGULATED POWER SUPPLIES

for powering electronic equipment

Model KR-18

Model KR-18MC

FEATURES:

- Fast Recovery Time, Suitable for Square Wave Pulsed Loading.
- Voltage Range continuously variable without Switching.
- Either Positive or Negative may be Grounded.
- Oil Filled Condensers.
- Wire Harness and Resistor Board Construction.
- Power Requirements 105-125 volts, 50-60 cycles. Units operate up to 400 cycles.
- Terminations on rear of unit.
- Locking type voltage control, AC, DC Switches, Fuses, and Pilot Lights on Front Panel.
- Color Grey Hammertone.
- Guarantee One Year.

Build these compact Power Supplies into your equipment!

KR Voltage Regulated Power Supplies are conservatively rated and are designed for continuous duty at 50°C ambient.

REGULATION: Less than 0.2 volts for line fluctuation from 105-125 volts and less than 0.2 volts for load variation from 0 to maximum current.

RIPPLE: Less than 3 mv. rms.

To include 3" Current and Voltage Meters, Add M to Model number (e.g. KR 16-M) and Add $30.00 to the Price.
To include Dust Cover and Handles for Table Mounting, Add C to Model number (e.g. KR16-C) and Add $10.00 to the Price.
To Include Meters, Dust Cover and Handles, Add MC to Model number (e.g. KR-16-MC) and Add $40.00 to the Price.
PRICES F.O.B. Flushing.

1.5 Amp. KR SERIES

Model	Volts	6.3V AC	Rack Mount W	H	D	Price
KR16	0-150	Each supply	19"	12¼"	17"	$625
KR17	100-200	has two	19"	12¼"	17"	$625
KR18	195-325	15 Amp.	19"	12¼"	17"	$695
KR19	295-405	outputs	19"	12¼"	17"	$695

The KEPCO KR SERIES in the above voltage ranges are available in 600 Ma. — 300 Ma. — 125 Ma. series.

A LINE OF 50 MODELS
Available from Stock – Catalog on Request

RESEARCH • MANUFACTURING
KEPCO Laboratories

KEPCO LABORATORIES
131-38 SANFORD AVENUE • FLUSHING 55, N.Y. • INDEPENDENCE 1-7000

Computer Stored Program Alters Itself



Memory section has space for 4,096 instructions and numbers. Since instructions are stored in the memory, the program can alter itself



Plug in units based upon mechanized wiring facilitate servicing in new Librascope computer. Logic section (right) can be removed

Total access time is 2 millisec minimum and 17 millisec maximum. Addition time is 0.26 millisec, division and multiplication are 17 millisec

Transistors Lighten Field Telephone Repeaters

Transistorized version of telephone repeater enables a combat soldier to talk more than 30 miles. Total weight of the unit is 3.5 pounds



Amplifier uses transistor shown at the middle left of unit

RANGE of the average Army field telephone line is 6 miles. Repeaters, or amplifiers, increase the talking distance to 30 miles, but normally require 15 vacuum tubes powered by a special 24-volt jeep battery or a small power generator.

The new repeater, using a transistor audio amplifier, is some 40 times smaller and 20 times lighter than the multitube version of the equipment.

Batteries for the new Signal Corps device last 90 days and cost $6 a year. For an obsolescent World War II repeater, batteries had to be changed every two weeks and cost $105.

The repeater circuit is printed on a card and sealed in a plastic case. It is expected to last 10 to 15 years in field service and needs no adjustment.

(*Continued on Page* 180)

Look mom...no hands!



Mom died a thousand deaths when Junior free-wheeled his two-wheeler down Deadman's Hill... no hands, yet!

Despite dire predictions, Junior grew up... but he didn't change a bit.

True, he's outgrown his bike... more complex machines are his meat today. He's designing industrial indicators, recorders and computers... automatic machine tools... six-figure process controllers. Tomorrow, his dream of automation will come true in the completely automatic factory.

Yes, Junior's grown up, but his war-cry is the same..."look mom, no hands!"

Junior outgrew his bike when he discovered HELIPOT ® *precision potentiometers. If you're still riding in circles, join Junior! You'll find that Helipot makes the most complete line... linear and non-linear... in the widest choice of sizes, mounting styles and resistances ...that our engineers will gladly adapt standard models to your requirements... even design entirely new ones for you. For information and specifications... write for data file 101.*

Helipot

first in precision potentiometers
Helipot Corporation/South Pasadena, California
Engineering representatives in principal cities
a division of Beckman Instruments, Inc.

BECKMAN

422® REG. U. S. PAT. OFF.

American Transistor Broadcast Receiver



Broadcast receiver employs five transistors

BROADCAST receiver using transistors is being produced by General Electric. It is powered from a d-c supply of 13.5 volts and uses a plated wiring chassis. Tuning between 540 and 1,620 kc, the circuit employs a 455-kc intermediate frequency.

There are five hermetically sealed transistors, including oscillator-converter, detector, audio amplifier and two i-f amplifier stages. Power output is 40 milliwatts at 10-percent distortion.

Frequency Diversity Gives Reliable Signals



Diversity microwave terminal uses two transmitters and two receivers

FAILURE of microwave equipment to furnish consistent communication may be caused, not by malfunctioning of the gear, but by refraction in the atmosphere. Equipment recently developed by Motorola for special applications requiring maximum possible reliability uses two beams at different frequencies.

Two separate transmitters are required as well as two receivers. Only one receiver output is used at a time. Received signal strength of both beams is monitored by a signal comparator circuit. If the level of one beam falls significantly below the other, receivers are automatically switched in a period of only a few milliseconds.

Scatter Symposium

PROPAGATION experts gathered during November for a two-day session in Washington. Their symposium on communication by scatter techniques was sponsored by the Institute of Radio Engineers (acting through professional groups on antennas and propagation, and communications systems) as well as by the George Washington University.

Besides addresses that were essentially nontechnical, 21 formal papers were presented ranging from theory and experimentation to communications practice. Both vhf propagation by ionospheric scattering and uhf beyond-horizon tropospheric transmissions were described.

Commissioner E. M. Webster of FCC discussed the allocations problems inherent in a new technique and pointed out that so far no new allocations have been made to accommodate scatter circuits. Allen B. DuMont reviewed propagation mechanisms and urged the establishment of live television hookups between North America, Europe and South America.

▶ **Auroral**—H. G. Booker reviewed the propagation phenomenon by which signals are returned from a northerly direction. J. H. Chisholm described wartime propagation anomalies and indicated that diversity techniques in modern transhorizon circuits may increase effective bandwidth as well as improving s-n ratio. Experimental ionosphere scatter paths studied by R. C. Kirby showed a maximum Doppler shift of 6 kc. The role of meteors in extended vhf propagation was discussed by O. G. Villard.

J. R. McNitt, in describing the Maine to Greenland vhf circuits said that the Loring AFB-Goose Bay link, which is too short for satisfactory service, will be extended to 900 miles. K. A. Norton, who discussed the scatter mode, relied upon meteorological data previously presented in a paper by B. R. Bean. F. J. Altman described a simplified diversity system using two planes of polarization to obtain quadruple diversity, and W. E. Morrow presented a plan for parallel connection of equipment to effect greater equipment reliability.

▶ **By request**—T. J. Carroll of MIT Lincoln Lab, departed from his role as moderator to explain the controversy between two theoretical groups in the field of over-horizon propagation. One camp

A COMPLETE LINE OF DEPENDABLE ENCAPSULATED RESISTORS

PERMASEAL®

PRECISION WIREWOUND RESISTORS FOR 85C AND 125C AMBIENTS

When you have applications requiring accurate resistance values at 85C and 125C operating temperatures, in units of truly small physical size—you'll find the resistor you want is one of the 46 standard Permaseal designs in tab and axial lead styles.

They meet or exceed requirements for all types of military and industrial electronic apparatus and instruments. They are "extra-protected" by a special Sprague-developed plastic embedding material that performs beyond the severe humidity resistance specifications of MIL-R-93A and Proposed MIL-R-9444 (USAF).

Permaseal winding forms, resistance wire and embedding material are matched and integrated to assure long term stability at rated wattage over the operating temperature range.

These high-accuracy units are available in close resistance tolerances down to ±0.1%. They are carefully and properly aged for high stability by a special Sprague process.

SPRAGUE

FOR COMPLETE DATA WRITE FOR COPY OF SPRAGUE ENGINEERING BULLETIN NO. 122A

SPRAGUE ELECTRIC COMPANY • 35 MARSHALL ST. • NORTH ADAMS, MASS.



INCREASE COMPUTER RELIABILITY

WITH **AMPHENOL**

RACK & PANEL CONNECTORS



RELIABILITY in computer programs is first attained through the use of top quality components. And the finest rack and panel connectors for subassembly plug-ins are made by AMPHENOL. Check these types and features!

BLUE RIBBONS. For quick, positive connect/disconnect there are no finer connectors than AMPHENOL Blue Ribbons. The self-wiping, self-cleaning "ribbon" type contacts work smoothly and efficiently. The tough diallyl phthalate dielectric combines high electrical quality with high impact strength In 8, 16, 24 and 32 contacts. With or without shells and latch-lock fittings.



PRINCIR. These new printed circuit connectors have as a design basis a contact with exceptionally long spring base and a circle-lip for good wiping action. Because of this contacts can't be "set" and provide extremely long life. Available with 6, 10, 15, 18 and 22 contacts. Diallyl phthalate dielectric; gold-plated contacts.

PIN & SOCKET TYPES. Three connector designs are available in this versatile group: hex miniatures, rectangular miniatures and standard rectangulars. With a wide choice of contact arrangements and accessory hardware they provide dependable service in hundreds of computer applications.





AMPHENOL

AMERICAN PHENOLIC CORPORATION • chicago 50, illinois

AMPHENOL CANADA LIMITED • toronto 9, ontario

believes in the concept of a blob in which occurs fine scale microturbulence that produces extended-range signals. Carroll himself believes that the mode theory is adequate by which stratified air, affected by gravity, produces something akin to optical twilight.

H. V. Cottony described a series of experiments using rhombic, corner-reflector and Yagi antennas. T. Moreno and F. A. Speaks listed existing and preproduction models of high-power klystrons useful for transhorizon transmitting equipment. J. R. Day outlined the design considerations for Pole Vault and White Alice communications equipment. The ionospheric scatter equipment used at vhf was described by R. M. Ringoen. The Montreal-Riverhead experimental circuit was handled by H. H. Beverage and L. C. Simpson.

A brief run-down of the Booker-Gordon theory was given by W. E. Gordon. T. E. Rogers commented upon sensible circuit design based upon some 220 mc transmissions over water from Scituate, Mass. Kenneth Bullington reviewed experiments carried out along the coast of Newfoundland using 505 and 4,090 mc. Preliminary measurements over the 468-mc Montreal-Riverhead path were evaluated by G. S. Wickizer. W. A. Whitcraft, Jr. reviewed backscatter and suggested that the technique could be used to communicate between two stations within the skip zone. Signal fluctuations in overwater propagation at 3 and 9 cm received comment from W. S. Ament.

It is expected that transactions of the symposium will be published by IRE.

Interaction Between Antennas

FOR MANY YEARS it has been known that the loop patterns of marine radio direction finders are affected by proximity of other wires, particularly those antennas resonant at, or connected to, equipment tuned to the desired frequency of d-f reception.

It is customary to break up guy wires with insulators so that reradiation of radio signals will occur



(ACTUAL SIZE PHOTO)

. . . and this amazing sensitivity is only one of many outstanding characteristics of the entirely new DuMont Type 324 cathode-ray oscillograph. New standards of stability, low noise and hum level assure full use of the Type 324 for d-c to 300 kc measurements even in the microvolt region. Furthermore, the Type 324 is completely calibrated to read time and amplitude directly. There are so many features incorporated in this new instrument we can't begin to give you the whole story here. Write us for complete specifications, or better still, ask for a demonstration of the

NEW DUMONT TYPE 324

For further information write to:

Technical Sales Department • ALLEN B. DU MONT LABORATORIES INC. 760 Bloomfield Ave., Clifton, N. J.

HOW ACCURATE

can a wavemeter be...?

DE MORNAY-BONARDI

model DB-715

cavity wavemeter

You'll find DeMornay-Bonardi wavemeters so accurate that they may be used as secondary standards. Advanced design is responsible. These units offer extremely high Q, and a high resolution micrometer which permits precise determination of plunger position. Backlash is eliminated. Micrometer readings are plotted on a multi-page, high-resolution calibration chart for maximum accuracy.

TEMPERATURE COMPENSATED



SEALED AGAINST ATMOSPHERIC CHANGES

DeMornay-Bonardi units are effectively sealed against changes in atmospheric pressure and humidity. A metal-to-glass window seals off the cavity . . . a bellows construction seals the plunger area. Pressurizing the cavity with inert gas further assures the maintenance of dielectric constant. These features, plus the use of ball bearings, keep accuracy high for many years without service.

FEWER INSTRUMENTS NEEDED

Each DeMornay-Bonardi instrument covers an unusually wide segment of the total range, and measures the entire frequency band within that range. Only eleven sizes serve from 2.6 KMC to 90 KMC. You save capital outlay on the number of sizes needed.

REACTION TYPE CAVITY WAVEMETERS

Calibrated Freq. Band KMC	Calibration Accuracy Min ± MC	Cat. No.	Price
60-90	40	DBA-715-1	$460
50-75	30	DBB-715-1	460
33-50	10	DBC-715-1	460
26.5-40	6	DBD-715-1	460
18-26.5	3	DBE-715-1	460
12.4-18	1.5	DBF-715-1	430
8.2-12.4	0.75	DBG-715-1	415
7.05-10	0.60	DBH-715-1	450
5.85-8.2	0.35	DBJ-715-1	485
3.95-5.85	0.15	DBK-715-1	530
2.6-3.95	0.075	DBL-715-1	735

Model DB-715 units are available in Reaction, Absorption or Transmission types. Prices average around $460. Thirty-day deliveries on all sizes. Write for complete data.

DE MORNAY BONARDI

DE MORNAY-BONARDI
780 SOUTH ARROYO PARKWAY
PASADENA, CALIFORNIA



Minimum error occurs when the down lead is 60 feet from the d-f loop

only at frequencies well above those used for direction finding.

Since reradiation on the d-f frequency results in large and unpredictable bearing errors, it is usual to disconnect receiving and transmitting antennas while using the d-f loop. However, the need for maintaining watch on the distress frequency (500 kc) has resulted in a recent evaluation by J. H. Moon in the *Marconi Review*, No. 113.

The errors found among ships with different spacings of antennas is shown in the graph. The spacing shown on the abscissa is that between the d-f loop and the down lead of a ship's main antenna when the latter is tuned to 500 kc. Loop reception is likewise on 500 kc.

The pure quadrantal error that originates in the solid mass of the ship's structure is not considered here.

It has been concluded by the author of the original paper that many ships with some 500 feet of separation between antennas might safely use the d-f equipment without isolating the receiving antenna during the operation.—A. A. McK.

Paging Receiver Uses Two Tubes

GROWTH of one-way signaling and also one-way reception of communications signals has led to an increased number of receivers for the purpose. A recent design employs only two tubes and is packaged in a styrene case.

The receiver comprises a superregenerative detector followed by a single audio stage that drives a magnetic speaker. Each stage uses a subminiature pentode, which together with all other parts is

Will this blot spread... or shrink?

NOTHING STRIKES so brutally at human lives as a slum.

Yet of America's many millions of homes, the blot that is a slum covers more than 1 out of every 10 . . . and nearly one-half of all our homes are urgently in need of repair and basic improvements.

Will the blot go on spreading? Or will a concerted, nationwide attack on the causes of slums shrink it, year by year, until it is wiped out? Today, this is a challenge to every American . . . a challenge that *must* be met.

Your community . . . your problem!

A slum reaches across blocks, across miles, to sit on your doorstep and demand a price.

You pay it in the threat of crime and juvenile delinquency to your family. You pay the price in higher personal property taxes to fight the disease and crime and poverty that are slum-bred. You pay personally when the value of your home sinks as community deterioration takes another step closer.

Your *firm* pays when the community where you do business goes downhill. Slums automatically mean lower purchasing power and less effective labor.

Good citizenship is good business

It's good citizenship and good business both for your firm to join efforts to check housing decay . . . to stop slums before they start. In fact, it's the *responsibility* of every business, as it is of every other good citizen, to support community improvement efforts.

Some slums are beyond repair. They should be torn down and a fresh start made. Others can be remodeled, made to conform to better living standards. So it is up to you to get behind every sound program which seeks to provide adequate housing for all our people.

Adding your support to the efforts of the millions already attacking the problem, your firm can help stop slums cold and put America's housing standards at a new height.

How to get into action

A group of Americans from every walk of life has formed a new, non-profit organization to help combat home and community deterioration — The American Council To Improve Our Neighborhoods . . . A.C.T.I.O.N.

Send for a free copy of "ACTION." It explains what A.C.T.I.O.N. is and proposes to do. It also lists booklets, research reports, check-lists, and other material which can help you protect the housing health of your community. Address P. O. Box 500, Radio City Station, New York 20, N. Y.

ACTION

American **C**ouncil **T**o **I**mprove **O**ur **N**eighborhoods



AN INSPIRING ADVANCE IN MINIATURE RATE GYRO DESIGN

LEAR

AN INSPIRING

ADVANCE

IN MINIATURE

RATE GYRO DESIGN

MODEL 2157-F

Peak Accuracy in a Capsule—Weighs only .7 pound, measures only 1½" by 3", yet resolution and threshold levels of new 2157-F gyro approach zero.

"Stiff-Cross-Axis" Torsion Bar—Radically improved torsion bar provides frictionless suspension, adds new stiffness to eliminate cross-axis flexure inaccuracies.

No Thermal Null Wander—Use of thermally compatible materials for all associated parts eliminates inaccuracies due to differing expansion qualities. Null doesn't vary with temperature.

Uniform Damping—Same temperature-conscious approach includes a greatly superior new method of damping the output axis to assure uniform dynamic performance from −65°F through +165°F. Twin compensating plungers operate in a special fluid within tiny steel cylinders in such a way that the relative thermal expansion of the parts compensates the thermal characteristic of the viscous fluid to provide uniform, frictionless damping throughout the temperature range. No heating of any kind is required.

Immeasurably Sensitive—With no frictional restraints of any kind on the output axis sensitivity is maximized.

No Wiping Contact—Electro-magnetic pick-off of output axis motion eliminates friction of conventional wiper-contact potentiometer for better resolution.

Rugged and Durable—Designed with partially floated gimbal for a guaranteed life of 1000 hours minimum, meets all applicable military specifications.

For complete engineering data write Lear, Inc., Grand Rapids Division, Grand Rapids, Michigan.

LEAR



Circuit of the one-way signaling receiver uses a superregenerative detector



Upper model of the receiver shows speaker ports (right)

mounted on a phenolic board.

Gummed aluminum foil is applied to the inside of the case and provides an inexpensive but excellent low-loss r-f shield. The units are pretuned to either 35.58 or 43.58 mc, the standard one-way signaling frequencies, by proper choice of C_1. Final tuning is accomplished with adjustment of L_1.

The unit, with its short, single-wire antenna weighs less than 6 oz. Technical information on this receiver was kindly furnished by the manufacturer, West Coast Electronics Co., of Los Angeles, Calif.

Single-Sideband Mobile Radio

FEDERAL COMMUNICATIONS COMMISSION has gone on record as looking towards establishment of single sideband transmission in radiotelephone stations below 25 mc. Presently, this includes stations in the fixed service except Alaskan and maritime. Because of special technical problems, there are no immediate plans for extension of ssb to mobile, Alaskan and maritime fixed stations.

Radiotelephone stations customarily employ double sideband transmissions on the frequencies in question although ssb has been used for years in international radiotelephone service. Elimination of the extra sideband offers means of reducing bandwidth for each station, probably resulting in additional channels being made available.

FCC expects users, manufacturers and professional groups to conduct tests and studies to serve as technical background for future consideration.

Citizen Radio Evaluation

USE OF Citizen Radio frequencies has failed to live up to early plans, but the facilities are being increasingly employed by those prepared to purchase commercial equipment that can be tuned to frequencies between 460 and 470 mc.

An evaluation recently made has been published as Bulletin No. 9 of the Engineering Experiment Station of the University of Idaho in Moscow, Idaho. Retuned commercial equipment was used in the class A bands, 460-462 and 468-470 mc. Hand portable, class B, equipment was used at 465 mc.

In the Idaho terrain it was found that the class A equipment had a minimum range about 3 miles and maximum range over 60 miles. The class B equipment operates satis-

Radar Data Via Wire

Bandwidth of radar ppi signals is compressed by an optical-electronic scanning device in a ratio of 100 or greater. After transmission over a telephone line or radio link, the signals are used to recreate a facsimile of the original radar picture. The Rafax system is manufactured by Haller, Raymond & Brown

GOT A RELAY PROBLEM?

USE R-B-M

GENERAL PURPOSE RELAYS

Low in Cost – Small in Size – Dependable in Performance – AC or DC

For industrial smoke detectors

For radio transmitter panels



For television screen enlargers

For auxiliary gas engine generators

For photoelectric street lighting control



For automatic furnaces

For jet aircraft preheaters

IN ADDITION R-B-M General Purpose Relays are used on X-Ray apparatus, permanent wave machines, wire recorders, automotive radio telephone communication equipment, vending machines, coin operated phonographs and many other applications.

Let R-B-M engineering and production facilities serve you. Contact us immediately—Phone 5121

R-B-M DIVISION
ESSEX WIRE CORPORATION
Logansport, Indiana

Controls for Electronic, Refrigeration, Industrial, Appliance, Communication and Automotive Industries

RBM

factorily between 300 yards and 10 to 20 miles. Class C equipment used for remote control and utilizing a frequency of 27.255 mc was not tested.

Summaries of a large number of tests are given in the 35 pages.

Photocontrol Prevents Motorist Blindness

TUNNEL ENTRANCE lights must be switched to high intensity during periods of bright external sunlight so that drivers' eyes will have necessary time to accommodate to less illumination within the tunnel.

The photoelectric control used for this application differs from the more usual type of device that operates with failing sky light. It is essentially a two-stage photorelay using a 1P39 vacuum phototube, a 6SQ7 buffer amplifier and a 6SJ7 output tube to energize the pilot relay. This relay, in turn, actuates a power contactor.

The phototube directly controls the buffer amplifier. The power amplifier is controlled through a time-delay network that provides a 4 to 6-second delay at turnoff. False operation that might be caused by transient artificial light sources is thus prevented.

A small portion of the p-a output is fed back in series with the phototube-buffer tube signal circuit. This feedback causes a regenerative or trigger action. The circuit becomes unstable and snaps over when the operating points are reached. Because the turn-off point is fixed at a foot-candle value higher than the



Circuit of photocontrol adapted from street-light device

NEW HUDSON STANDARD CASES

Available From Stock!

STANDARD RECTANGULAR SIZES

HU—688:
DIMEN. A—⅝"
DIMEN. B—1 5/16"
LENGTH—⅝"

HU—734:
DIMEN. A—11/16"
DIMEN. B—1 9/32"
LENGTH—1 27/64"

HU—736:
DIMEN. A—¾"
DIMEN. B—15/16"
LENGTH—⅞"

HU—745:
DIMEN. A—¾"
DIMEN. B—15/16"
LENGTH—1⅛"

HU—750:
DIMEN. A—⅞"
DIMEN. B—1 1/16"
LENGTH—1⅛"

HU—796:
DIMEN. A—⅝"
DIMEN. B—1 5/16"
LENGTH—2½"

HU—826:
DIMEN. A—11/16"
DIMEN. B—1 9/32"
LENGTH—1⅝"

HU—844:
DIMEN. A—11/16"
DIMEN. B—1 9/32"
LENGTH—1¼"

STANDARD ROUND SIZES

HU—727:
OUTSIDE DIA.—1¼"
LENGTH—½"

HU—728:
OUTSIDE DIA.—1 1/16"
LENGTH—2¼"

HU—737:
OUTSIDE DIA.—1 15/64"
LENGTH—1 13/32"

HU—760:
OUTSIDE DIA.—21/32"
LENGTH—5/16"

HU—771:
OUTSIDE DIA.—.742"
LENGTH—¾"

HU—773:
OUTSIDE DIA.—1 1/16"
LENGTH—1"

HU—806:
OUTSIDE DIA.—1 9/64"
LENGTH—1⅞"

HU—819:
OUTSIDE DIA.—49/64"
LENGTH—2 1/64"

STANDARD SQUARE SIZES

HU—709:
DIMEN. A—1"
LENGTH—2⅛"

HU—789:
DIMEN. A—1"
LENGTH—1½"

HU—793:
DIMEN. A—1"
LENGTH—1 19/32"

HU—808:
DIMEN. A—1 1/64"
LENGTH—1 25/32"

HU—810:
DIMEN. A—4 5/64"
LENGTH—7/16"

HU—847:
DIMEN. A—1"
LENGTH—2¼"

File This Page for Future Reference



3 FULLY-EQUIPPED PLANTS

Offering the Most Complete Line of Precision Drawn Cases and Covers in the Industry!

...THREE COMPLETE SERVICES!

Hudson Standard Metal Closures

Over 1000 economical standard types mean HUDSON can supply precision components at commercial prices. A wide variety of optional features make it possible to solve all but the most unusual closure requirements with standard types selected from HUDSON stocks.

Hudson Quality Metal Stampings

Metal parts produced to your exact specifications at prices that reflect the economies of mass production methods. Hudson can work to close tolerances and maintain uniformity throughout production runs. Quotations supplied promptly on receipt of drawings.

Hudson Sheet Metal Facilities

Depend on HUDSON for expert fabrication of simple or complex sub-assemblies. Facilities include certified welding of alloys, silver soldering, brazing and chrome plating.

NEW CATALOG READY, NOW!

The Hudson story is contained in one handy catalog. Full descriptions of all standard items and complete information on Hudson metal working facilities. Call or write for your copy, now!

Precision Components of Steel, Aluminum, Copper, Brass, Mu Metal

HUDSON TOOL & DIE COMPANY • INC

118-122 SOUTH 14th ST., NEWARK 7, N. J.

NOW! MEASUREMENTS' MEGACYCLE METER

Gives You Extended Coverage from 100 Kc to 940,000 Kc



MODEL 59-LF OSCILLATOR UNIT
Frequency Range: 100 Kc to 4.5 Mc.
Price - Oscillator Unit (Head) only $98.50

MODEL 59 OSCILLATOR UNIT
Frequency Range: 2.2 Mc to 420 Mc.
Price - Oscillator Unit (Head) only $98.50

MODEL 59-UHF OSCILLATOR UNIT
Frequency Range: 420 Mc to 940 Mc.
Price - Oscillator Unit (Head) only $123.00

PRECISION GRID-DIP METERS

The Power Supply is a compact, lightweight portable unit consisting of a full-wave rectifier with voltage regulator tube—designed for use with any of the oscillator heads illustrated.

PRICES:

Power Supply only $75.00
Model 59-LF Head with Power Supply $168.00
Model 59 Head with Power Supply $168.00
Model 59-UHF Head with Power Supply $198.00

Prices FOB. Boonton, N. J.

Measurements' Megacycle Meter is now available in a choice of three oscillator heads providing frequency range coverage from 100 Kc to 940,000 Kc. Thus, the utility of this versatile instrument has been extended, making it, more than ever, indispensable to anyone engaged in electronic work; engineer, serviceman, amateur or experimenter.

Laboratory Standards — MEASUREMENTS CORPORATION — BOONTON · NEW JERSEY

Photocontrol is housed in meter-type glass enclosure

turn-on point, cycling is prevented.

The turn-on point can be adjusted over a range and the turn-off point follows it, but always at a fixed differential. The on and off designations used above refer ultimately to the condition of the pilot relay, which is energized during daylight. The contacts of the power contactor can be used to close or open the external circuit during either daylight or dark periods.

For tunnel applications, the daylight-closed circuit would be used. The information abstracted here comes from a maintenance manual furnished by The Fisher-Pierce Co., Inc., of South Braintree, Mass.

Hawaii Cable Authorized

AUTHORIZATION permitting American Telephone and Telegraph Co. to construct and operate twin submarine cables between the United States and Hawaii has been granted by FCC.

The new cable system, designed for telephone and telegraph communication from Point Reyes, Calif. to Koko Head, Oahu, Hawaii, will cost about $35 million. When completed in 1957 the cable will be the world's longest telephone-telegraph span. With a length in excess of 2,000 miles it will exceed those of the Newfoundland-Scotland and Alaskan cables.

FCC Mobile Monitor

BECAUSE fixed monitoring stations cannot receive distant television transmissions, Federal Communications Commission has developed a

how to reduce costs with WESTERN GEAR rotary electrical equipment

We have more than 50 basic prototype motors, fans, blowers, converters, alternators and generators. Motor designs range from 1/500th to 4 HP, 50 to 1,000 cycles in frequency, any desired voltage. Extensive line enables economic modification to your requirements or special design. Complete engineering service gladly offered for help on any rotary electrical equipment problem. Write for new catalog No. 254-A.



Precision fine pitch gears, constructed to the highest specifications for electronics use, available from 200 to 6 diametral pitch and from .125" to 10" diameter. Complete engineering and manufacturing facilities for the application of high precision gearing and gear drives in electronics equipment. Ask for help on your problem. No obligation!

"The difference is reliability" • Since 1888

Detail your requirement on any electronic problem. Utilize Western Gear's production facilities to cut your product costs. Our engineers will give their recommendations promptly. Address Western Gear Corporation, Electro Products Division, 132 W. Colorado St., Pasadena 1, Calif.

WESTERN GEAR Corporation
ENGINEERS AND MANUFACTURERS

PLANTS AT LYNWOOD, PASADENA, BELMONT, SAN FRANCISCO (CALIF.), SEATTLE AND HOUSTON — REPRESENTATIVES IN ALL PRINCIPAL CITIES

LAPP INSULATION FOR WATER-COOLED SYSTEMS



For carrying cooling water which must undergo a change in potential, use of Lapp porcelain eliminates trouble arising from water contamination and conductivity, sludging and electrolytic attack of fittings. Permanent cleanness and high resistance of cooling water is assured with the completely vitrified, non-absorbent Lapp porcelain.

PORCELAIN WATER COILS

Twin hole or single hole models to provide flow of cooling water from 2 to 90 gallons per minute. Each assembly includes ceramic coil, aluminum mounting base, nickel plated brass attachment fittings . . . and is proof-tested to 100 lbs. per square inch water pressure.

PORCELAIN PIPE

Practically any piping layout can be made with these pieces . . . swivel flanges provide automatic alignment. Straight pipe up to 60" lengths, 90° and 180° elbows, fittings for easy attachment to metal pipe; matching support insulators. Inside diameters ¾" to 3".



WRITE for Bulletin 301 containing complete description and specification data. Lapp Insulator Co., Inc., 245 Sumner Street, Le Roy, New York.

Lapp

mobile monitoring unit that will operate in the various field engineering districts where it is needed.

Measurements to be made include frequency of the sound and picture carriers, color subcarrier, line scanning and field scanning repetition rates, modulation percentage and waveform observations. Distribution of the elements of the television signal over the assigned channel will be determined by spectrum emission analysis.

South Africa Time Signals

ESTABLISHED in 1949, station ZUO is now one of the six stations in the world transmitting standard frequency and time signals in accordance with standards of accuracy set up by CCIR (International Consultative Committee for Radio).

Operation is continuous except between the hours 0630 and 0700 Universal Time. Output power is 100 watts on 5 mc from Johannesburg, South Africa.

Modulation for time signals is one impulse a second, each consisting of 10 cycles of 1,000 cps tone (10 milliseconds duration.) The first im-

Microwave Facsimile

Photograph of the Chicago terminal of Texas Illinois Natural Gas Pipeline Co. microwave link to Houston, Texas was sent over the system and the result reproduced above. Copy was scanned at drum speed of 100 rpm with a definition of 100 lines to the inch. A temporary channel 7½ was inserted between two of the 12 channels in regular use. Microwave antenna in foreground has protective cover against weather

NIXIE

Newest STAR IN THE ELECTRONIC GALAXY

SOME TYPICAL NIXIE APPLICATIONS

1. DIGITAL VOLTMETERS
2. COUNTERS
3. CALCULATORS
4. ALTIMETERS
5. RADAR
6. DIAL SYSTEMS
7. REMOTE POSITION INDICATORS

Haydu's 10 digit in-line numerical indicator!

Small, electronic indicating tube uses the direct read-out method which clearly displays the digits at top surface of tube. This method assures the highest readability from a wide angle . . . speeds work, reduces errors, cuts costs in hundreds of diversified applications.

NOTE THESE OUTSTANDING ADVANTAGES:

- Small, simple plug-in tube
- Uses standard sockets
- Vivid numbers for highest visibility
- Low power required
- Operates directly off Beam Switching Tubes or any voltage source
- Radical Simplification of circuitry
- Long life
- Rugged construction



Write to Haydu Tube Division, Dept. 10, Plainfield, N. J., for complete information on your applications.

HAYDU

BROTHERS OF NEW JERSEY

PLAINFIELD, NEW JERSEY

SUBSIDIARY OF BURROUGHS CORPORATION

AUTOMATIC PRODUCTION AND QUALITY CONTROL TESTING

with the CTI Supertester

The CTI Supertester is an automatic, precision instrument for production testing, fault analysis, and preventive maintenance. It checks electronic and electrical products more completely and in a fraction of the time required by present methods.

Providing complete flexibility and rapid interchangeability between products, the Supertester can be programmed for any combination or sequence of the following measurements:

Impedance	A-C Voltage	Leakage
Resistance	D-C Voltage	Continuity

REDUCE TEST COSTS

Requiring only an untrained operator, the Supertester frees valuable technical personnel for specialized work. One Supertester is the equivalent of a series of custom built, single product testers, or a benchful of precision bridges and meters.

SPEED PRODUCTION

Complex circuits, gain and frequency measurements, involved relay operations — all are checked at the rate of 180 tests per minute. Hours of manual test procedure have been reduced to minutes. Time is not wasted checking good units.

INCREASE PRODUCT QUALITY

Accurately checking every production unit against design values and tolerances, the Supertester does not overlook tests or pass questionable circuits. Original specifications are tirelessly and rigidly adhered to. Instead of checking only the essential circuit parameters, the Supertester tests equipment completely, quickly, and at far less cost.

Proved in Use!

The Supertester is being used daily by a number of the nation's leading manufacturers. Their testing applications include printed circuits, telemetering units, guided missile circuitry and pre-flight tests, and aircraft electronic equipment.

Whatever the problem, rigid test specifications, high production rates, or reducing test costs, automatic testing is the solution, and the CTI Supertester has proved itself to be the efficient, money saving means to this solution.

COLOR TELEVISION INCORPORATED — CTI — SAN CARLOS 1, CALIF.

pulse in each minute is prolonged to about a half second.

Announcements are made ahead of each quarter-hour minute using Morse code. For example, the announcement between 4.14 and 4.15 pm would be sent:

ZUO ZUO ZUO 1615

Since the maximum oscillator drift is less than 1 part in 10^9 a month, frequency accuracy is $\pm$ 2 parts in 10^9. If necessary, signals are phased in steps of 20 milliseconds or multiples thereof on the first Monday of the month. The maximum value of steps of frequency adjustment is 1 part in 10^9.

Accuracy of time intervals is $\pm 2 \times 10^{-6}$ ($\pm$ 1 microsecond). A quarterly bulletin is published by The Union Astronomer, Union Observatory, Johannesburg, South Africa.

Gamma Rays Preserve Meat

PASTEURIZATION by gamma rays has been suggested as a public health measure for fresh meat and seafoods. It would have the further advantage of making available to the small market the method of packaging cuts of meat in the manner employed in very large markets. The ultimate effect would be to confine the butchering operation to the slaughter and packing house. Gamma radiation might destroy

Tiny Loudspeaker



Small loudspeaker for use in pocket-size transistor radio receivers is only 2½ inch in diameter and about a half inch thick. Magnetic structure that projects from the rear of conventional speakers is contained within the shell surrounding the vibrating cone. Unit was developed by RCA engineers



Designed for Application

Grid Dip Meters

Millen Grid Dip Meters are available to meet all various laboratory and servicing requirements.

The 90662 Industrial Grid Dip Meter completely calibrated for laboratory use with a range from 225 kc. to 300 mc. incorporates features desired for both industrial and laboratory application, including three wire grounding type power cord and suitable carrying case.

The 90661 Industrial Grid Dip Meter is similar to the 90662 except for a reduced range o 1.7 to 300 mc. It likewise incorporates the three wire grounding type cord and metal carrying case.

The 90651 Standard Grid Dip Meter is a somewhat less expensive version of the grid dip meter. The calibration while adequate for general usage is not as complete as in the case of the industrial model. It is supplied without grounding lead and without carrying case. The range is 1.7 to 300 mc. Extra inductors available extends range to 220 kc.

The Millen Grid Dip Meter is a calibrated stable RF oscillator unit with a meter to read grid current. The frequency determining coil is plugged into the unit so that it may be used as a probe.

These instruments are complete with a built-in transformer type A.C. power supply and internal terminal board to provide connections for battery operation where it is desirable to use the unit on antenna measurements and other usages where A.C. power is not available. Compactness has been achieved without loss of performance or convenience of usage. The incorporation of the power supply, oscillator and probe into a single unit provides a convenient device for checking all types of circuits. The indicating instrument is a standard 2 inch General Electric instrument with an easy to read scale. The calibrated dial is a large 205° drum dial which provides seven direct reading scales, plus an additional universal scale, all with the same length and readability. Each range has its individual plug-in probe completely enclosed in a contour fitting polystyrene case for assurance of permanence of calibration as well as to prevent any possibility of mechanical damage or of unintentional contact with the components of the circuit being tested.

The Gride Dip Meters may be used as:

1. A grid Dip Oscillator
2. An Oscillating Detector
3. A Signal Generator
4. An Indicating Absorption Wavemeter

The most common usage of the Grid Dip Meter is as an oscillating frequency meter to determine the resonant frequencies of de-energized tuned circuits.

Size of Grid Dip Meter only (less probe): 7 in. x 3 1/16 in. x 3 1/2 in.

JAMES MILLEN MFG. CO., INC.

MAIN OFFICE AND FACTORY

MALDEN, MASSACHUSETTS, U.S.A.

for insulated wire, one source Continental

For the run-of-the-mill wiring problems—or the hundreds of specials—the one source for practically all types of permanently insulated wire—is Continental. Whether it's electronic hook-up wire, military hook-up wire or cable, switchboard AVB—TA—SHFS Cable or Wire . . . Asbestos, Glass, Nylon, Varnished Cambric, Polyethylene, etc. . . . the **Always Correct Source** is Continental Wire Corporation. Refer your special wiring problems today to Continental's Wire and Cable specialists.

*A.C. Source

Contact: Continental Sales, Box 363, Dept. C
Wallingford, Conn., Phone COlony 9-7718

POWER and RHEOSTAT CABLE—TYPE AIA
available in Sizes 18 AWG—2,000,000 CM inclusive.



Stranded copper conductor, asbestos insulation, asbestos braid. Heat, flame, moisture resistant impregnation and finish.

For open installation in high operating temperatures, oil, grease, corrosive vapors or moisture. Maximum temperature 257° F.

Continental
WIRE CORPORATION
WALLINGFORD, CONNECTICUT • YORK, PENNSYLVANIA

about 99 percent of the microorganisms without developing off-flavors and also increase refrigerator shelf life. Refrigeration would still be necessary.

Electrostethograph Measures Heart Sounds

ADAPTATION of a surface roughness measuring gage (ELECTRONICS, p 181, Nov. 1953) to measurement of heart sounds has extended the range of cardiographic equipment. Using a stethoscope diaphragm coupled directly to the anode of a movable anode transducer tube, frequencies as low as one cps can be recorded. The output of the device can be observed on a conventional cro or a recording oscillograph and can also be recorded on tape for reference.

High directional selectivity of the cardiograph pickup head permits observation of the vibrations produced in different areas of the heart. Study of these localized vibrations may lead to more accurate diagnostic techniques. With the accumulation of a large library of recordings from normal and defective hearts, the value of the instrument will be increased as a supplement to conventional electrocardiograph and stethoscope techniques.

Development of the stethograph was done at the Medical College of South Carolina by Dr. Dale Groom,

Multimegawatt Fluorescent



Fluorescent tubes fastened to inside of radome used in arctic service are lighted by power in beam from Air Force FPS-6 height-finder radar on test by General Electric engineers

fast deliveries!

price savings up to 300%!

SAVE! and IMPROVE with

STACKPOLE "EE" CORES

Leaders in Engineering core Economy

Preferred-type Stackpole "EE" iron cores meet 8 out of 10 engineering needs . . .

They are stocked for immediate delivery in any quantity . . .

Cost savings amount to as much as 300% less than custom-engineered cores that entail set-up charges . . .

Equally important, new Stackpole core types are constantly being added to the "EE" list to keep abreast of new engineering and production requirements.

Write for latest Stackpole "EE" Core list.

Electronic Components Division

STACKPOLE CARBON COMPANY, St. Marys, Pa.

In Canada: Canadian Stackpole Ltd., 550 Evans Avenue, Toronto 14, Ontario

LAB PULSESCOPE

by Waterman

MODEL S-5-C

Size:
13" x 16½" x 14⅛"

ANOTHER EXAMPLE OF Waterman PIONEERING...

The LAB PULSESCOPE, model S-5-A, is a JANized (Gov't Model No. OS-26) compact, wide band laboratory oscilloscope for the study of all attributes of complex waveforms. The video amplifier response is up to 11 MC and provides an equivalent pulse rise time of 0.035 microseconds. Its 0.1 volt p to p/inch sensitivity and 0.55 microsecond fixed delay assure portrayal of the leading edge when the sweep is triggered by the displayed signal. An adjustable precision calibration voltage is incorporated. The sweep may be operated in either triggered or repetitive modes from 1.2 to 120,000 microseconds. Optional sweep expansion of 10 to 1 and built-in markers of 0.2, 1, 10, 100, and 500 microseconds, which are automatically synchronized with the sweep, extend time interpretations to a new dimension. Either polarity of the internally generated trigger voltage is available for synchronizing any associated test apparatus. Operation from 50 to 400 cps at 115 volts widens the field application of the unit. These and countless additional features of the LAB PULSESCOPE make it a MUST for every electronic laboratory.

WATERMAN PRODUCTS CO., INC.

PHILADELPHIA 25, PA.
CABLE ADDRESS: POKETSCOPE

MEMO... Write for details today!

WATERMAN PRODUCTS

WATERMAN PRODUCTS INCLUDE

S-4-C SAR PULSESCOPE®
S-5-A LAB PULSESCOPE
S-6-A BROADBAND PULSESCOPE
S-11-A INDUSTRIAL POCKETSCOPE®
S-12-B JANized RAKSCOPE®
S-14-A HIGH GAIN POCKETSCOPE
S-14-B WIDE BAND POCKETSCOPE
S-15-A TWIN TUBE POCKETSCOPE
RAYONIC® Cathode Ray Tubes and Other Associated Equipment



Electronic stethoscope using a movable anode transducer

aided by Joseph Bidwell of the General Motors Research Laboratories, where the original surface roughness gage was developed.

Delay-Line Pulse Generator

By IRVING BARDITCH
Baltimore, Md.

A VARIABLE-WIDTH high-precision pulse is simply produced by the circuit shown in the diagram. The width is continually variable, jitter-free and as accurate as the delay-line being used. A trigger pulse is used to initiate one tube of a bistable multivibrator; the same pulse is then passed through a variable delay line and used to initiate the other tube of the multivibrator.

As a consequence, the output pulse is jitter-free, continually variable within the resolution limits of the delay line and independent of any R-C time constant or other source of instability. The rise time and minimum width of the pulse



Simple delay-line circuit can generate pulses of less than 1-μsec duration

Save, save, save . . . time, trouble, money . . . when purchasing molybdenum permalloy* Powder Cores, for there can be no waste when you buy from Magnetics, Inc. Exclusively *Performance-Guaranteed*, these cores are also graded according to inductance, and color-coded so your assemblers *know* how many turns to put on without special testing. Write today for full details . . . Bulletin PC-103 and your Color-Coding Card . . . and remember . . .

PERFORMANCE-GUARANTEED

Permalloy Powder Cores

COST NO MORE-

WHY TAKE LESS?

MAGNETICS inc.

DEPT. E-23, BUTLER, PA.

*Manufactured under a license agreement with the Western Electric Co.

A. W. HAYDON PRECISION

Governed D. C. Motors like the 5600 series insure unfailing performance of America's perimeter defenses. They are an integral part of "Hogan's Fence" — Guided Missiles and Launching Apparatus.

The 5600 series motor incorporates a 900 beat governor movement which corrects the motor speed at the rate of 900 times per minute or 15 times per second. Corrections are made as ripples in motor speed caused by the pulsing of contacts or as phase shifts due to a change in load or voltage.

Windings are available for nominal voltages of 6, 12, and 25 volts D. C.; however motors may be operated on higher voltages by means of a voltage divider resistor. Output speeds from 900 RPM down to 1 revolution in 2 hours can be provided.



SPECIFICATIONS

1. Voltage range nominal ± 20% at 68°F.
2. Ambient temp. range minus 65°F to plus 165°F.
3. Vibration 5-55 cycles per sec. with 10g max. accel.
4. Tolerance on escapement rate:
   (a) ± 0.1% under condition 1
   (b) ± 0.3% under condition 2
   (c) ± 0.5% under condition 3
5. Shock — per MIL-E-5272A, Proc. 1 (50g for 11ms)



Rated 30 oz. — in. full load torque at 1 RPM. Torque is limited by materials used in gear train to 20 oz. — in. intermittent or 5 oz. — in. continuous duty at 1 RPM. Special gear trains are available.

WHEN TIMING POSES A PROBLEM CONSULT . . . .

The A. W. HAYDON Company

235 NORTH ELM STREET, WATERBURY 20, CONNECTICUT

Design and Manufacture of Electro-Mechanical Timing Devices

(General Catalog Sent on Request)

are limited only by the capabilities of the tubes. This circuit allows the generation of variable-width pulses below one microsecond, a region in which the cathode-coupled multivibrator will not function.

PERTINENT PATENTS

By NORMAN L. CHALFIN
Hughes Aircraft Co.
Culver City, Calif.

SIGNALING methods and oil prospecting are two diverse but important applications of the electronic technique. Considerable space has been given below to a French invention describing the former, since it appears to have high interest.

Coded Pulse Device

A circuit shown in Fig. 1 defines a "Method and device for decoding groups of coded pulses representing an intelligence wave". This is the invention of A. P. Pages and G. H. L. Dureau of Paris, France. They have assigned their patent No. 2,685,647 to Societé Alsacienne de Constructions Mecaniques of Paris.

This invention, provides a method of translating successive groups of coded recurrent electric pulses of time period T, comprising an integral number n of coded pulses, each of which may be of one or another of two possible signaling conditions, into a variable amplitude intelligence wave. This method comprises the steps of creating, on re-



FIG. 1—Successive groups of three coded pulses applied to input

For greater economy...

wider design flexibility...

UNEXCELLED PERFORMANCE!

Miniaturized Hi-Voltage

QUALITY CARTRIDGE RECTIFIERS BY

International

Manufactured under the United States Army Signal Corps Reduced Inspection Quality Assurance Program

RIQAP

A WORLD OF DIFFERENCE THROUGH RESEARCH

The higher voltage ratings of International selenium rectifier cells result in a 30% shorter length cartridge! These miniature-size rectifiers permit greater design freedom where space is at a premium. They are available in numerous terminal types, circuits, cell sizes and protective coatings to meet your specific needs. International—leader in the field—sells more selenium cartridge rectifiers than all other manufacturers combined! As a result, your special cartridge rectifier requirements may be standard at International. A wire, letter or phone call will bring immediate and experienced recommendations for your application.

International Rectifier

CORPORATION

EXECUTIVE OFFICES: 1521 E. GRAND AVENUE, EL SEGUNDO, CALIFORNIA • PHONE OREGON 8-6281
NEW YORK: 501 MADISON AVE., PLAZA 3-4942 • CHICAGO: 205 W. WACKER DR., FRANKLIN 2-3869
IN CANADA: ATLAS RADIO CORP., LTD., 50 WINGOLD AVE., W., TORONTO, ONTARIO, RU 1-6174

WORLD'S LARGEST SUPPLIER OF INDUSTRIAL METALLIC RECTIFIERS

an important new drafting technique
24 COLORS—$1.50 PER DOZEN, LESS IN QUANTITY
possible only with
MARS-LUMOCHROM
All colors blueprint perfectly, making color-drafting possible.
MARS-LUMOCHROM does not fade
. . . does not smear . . . is waterproof
. . erases perfectly . . . keeps finest point
Send for free sample
STAEDTLER also proudly introduces the Mars-Pocket-Technico for field use, the Mars "Draftsman's" Pencil Sharpener with the adjustable point length feature, and the efficient, clean Mars lead sharpener. All available—along with the established standards: Mars-Lumograph black graphite drafting pencils, Mars-Technico lead holder and leads, and Tradition-Aquarell painting pencils—at all leading art material and drafting supply dealers.
J.S. STAEDTLER, INC. HACKENSACK, NEW JERSEY

ceiving each one of the successive groups and storing for a time at most equal to T, a group of n electrical voltages.

Each voltage corresponds to one pulse in one of the groups and has one or another of two predetermined constant values according to the signaling condition of the corresponding pulse, rapidly producing, during a time interval at most equal to T, a sequence of 2^n different permutation groups of n voltage pulses in which each individual pulse has one or another of the two predetermined constant voltages.

All of the permutation groups have the same duration and follow each other at uniform time intervals of duration t. Each of the $(n\text{-}1)$ first pulses in each of the permutation groups is thereby delayed respectively by such an amount that 2^n different groups of n simultaneous pulse voltages successively appear at n terminals at 2^n different instants within the time interval at most equal to T. Each one of the n voltages appearing at said n terminals is then compared with one of the n voltages of the stored-group of n electric voltages.

► **Equal Voltages**—When all compared voltages are equal a derived pulse of short duration is emitted at that instant. The time position of the derived pulse within the time interval at most equal to T thus depends upon the composition of the stored electrical voltage group. Successive derived pulses so obtained from successive groups of coded pulses are demodulated by their time position with respect to fixed reference instants whereby they are transformed into an intelligence wave of variable amplitude.

Another feature of the invention provides a device for translating into a variable amplitude intelligence wave, periodic electric synchronizing signals of period T and recurrent groups of electric coded pulses of recurrence period T including an integral number n of pulses. Each of the integral pulses may be one or another of two possible signaling conditions. The device comprises a generator of periodic voltage pulses of period T, synchronized by the periodic electric synchronizing signals, with

Added Evidence that —

Everyone Can Count on VEEDER-ROOT

This Veeder-Root Reset Magnetic Counter (AC or DC) is actuated through electromagnets. And it may be connected in series with any device having a contact arrangement . . . like the specially designed Veeder-Root Electrical Contactor at the left, which insures positive operation of the counter, either in oscillation or connected directly to a revolving shaft . . . with the counter placed at *any* distance from the machine or process on which the count is required.

This is another one of the hundreds of Veeder-Root Standard and Special Counting and Computing Devices developed for every conceivable counting duty, in every field from atomics to electronics.

What do *you* need to count? Just write:

VEEDER-ROOT INCORPORATED
HARTFORD 2, CONNECTICUT

Chicago 6, Ill • New York 19, N. Y. • Greenville, S. C.
Montreal 2, Canada
Offices and Agents in Principal Cities
"The Name that Counts"

Want more information? Use post card on last page.

General

mercury batteries can add sales appeal to your products

The miniature size and high energy output of General Mercury Batteries are giving many products the added sales appeal of smallness and better performance.

For instance, the radio industry is using these qualities of General Mercury Batteries to produce a truly portable radio. They are small enough and light enough to be carried conveniently and comfortably in a coat pocket or purse. Yet these new radios provide excellent tone and trouble-free operation.

If small size, without sacrifice of efficiency, is important to your products, it will pay you to investigate the advantages offered by General Mercury Batteries. They have exceptionally long shelf and operating life, and supply a constant source of current. General Mercury cells are available in "power packs" in an unlimited number of series, parallel or series-parallel combinations. General "power packs" are made up of individual cells permanently joined together by General's exclusive surge-weld process. You may be interested to know that a great many of these mercury cells are being used on Government scientific developments.

We would appreciate an opportunity of discussing the individual battery needs of your products. We will be glad to send you complete data.

General
DRY BATTERIES, INC.
13000 ATHENS AVE., CLEVELAND 7, OHIO
BOulevard 2-0030



FIG. 2—Voltage storing device is one of three used

provision for creating and storing a group of n electrical voltages on receiving each one of said groups of coded pulses.

Each voltage corresponds to one pulse in one of the groups and has one or another of two predetermined constant values according to the signaling condition of the corresponding pulse. There is also a device controlled by the generator for creating, during a time interval at most equal to T, a series of 2^n electric voltage pulses spaced in time at uniform intervals of duration τ and an arrangement controlled by the generator, which generates at the same time a sequence of coded pulses successively reproducing each one of the 2^n possible permutation groups of n voltages in the form of pulses having one or another of the two predetermined voltage values.

A chain of delay networks in cascade is provided having a total delay time at least equal to $(n\text{-}1)\ \tau$ and with n connection points spaced along the chain in such a manner that the propagation time from one point to the next is equal to said duration τ. There is an arrangement for applying the sequence of coded pulses at one end of the chain and an impedance for terminating the chain at its other end to avoid pulse reflections at that end. A voltage comparator compares each of the n voltages that appear at the n connection points to one voltage of above-mentioned stored voltage group.

The comparator is controlled by pulses from the series of 2^n electric voltage pulses. The comparator controls a generator of a derived pulse when the voltage values in each compared pair are equal. Successive derived pulses are demodulated as derived from successively received coded pulse groups with respect to their time position in relation to fixed reference times established by the generator. Signals received at



"System-designed" Leach relays serve all three

Yes, the missile age is the toughest challenge yet for electronic components . . . and supersonic inhabited aircraft aren't far behind in their demands for reliability. Just meeting specifications is no longer enough. In this newest family of electronic-aircraft-missile relays, LEACH does more, offers reliability *beyond* specs . . . dependability based on design and manufacturing experience second to none.

These relays were *system designed* . . . Leach Engineers started with the framework of today's *system* demands, they built a family of relays not merely to satisfy specifications but *to do a job*. Here are some of the features that help insure *system reliability* in your electronic, aircraft and missile work . . .

HERMETIC SEALING – *every relay checked by mass spectrometer*

OPTIONAL LEADS – *solder terminals, potted leads or plug-in bases*

SQUARE CANS – *20% more relays in the space required by round cans*

SHOCK RESISTANCE – *vibration and shock properties exceed MIL specs*

HIGH-TEMPERATURE – *dependability assured at 120°C ambient*



	9220	9226	9230
Contact arrangement	4PDT	6PDT	4PDT
Operating voltage	18-30 VDC	18-30 VDC	18-30 VDC
Contact rating at 28 VDC Resistive Inductive	 5 amp 1.5 amp	 5 amp 1.5 amp	 10 amp 7 amp
Coil resistance	250 ohms	200 ohms	150 ohms
Duty	Continuous	Continuous	Continuous
Weight	.25 lb.	.25 lb.	.5 lb.

COMPLETE SPECIFICATIONS on these three new relays will be sent on request. *Write for them today.*

LEACH CORPORATION / LEACH RELAY DIVISION

5915 AVALON BOULEVARD, LOS ANGELES 3, CALIF.

DISTRICT OFFICES AND REPRESENTATIVES IN PRINCIPAL CITIES OF U. S. AND CANADA

QUAKER CITY GEAR..

• For complete gear assemblies . . Hardened and Ground Gears . . Master Gears and Involute Spline Gauges . . Thread Ground Worms . . Coniflex and Spiral Bevel Gears . . . .



We invite your inquiry

QUAKER CITY GEAR WORKS
INCORPORATED
RED LION AND PHILMONT ROADS
BETHAYRES, PA., CHAPEL HILL 0800

the output of the demodulator are applied to a utilization circuit.

Groups of binary pulses may be arranged in 2^n different ways to represent 2^n different amplitude values. A basic sequence of N bivalent symbols may also be written, provided N be large enough, in such a way that 2^n different groups of n bivalent symbols are successively found at regular intervals in the sequence. A most economical way of doing so is to write $2^n + (n\text{-}1)$ bivalent symbols in such an order that all the 2^n possible permutation combinations are successively found by shifting the rank of the group in the sequence by one unit.

While the application of the principle of the invention is not limited to the use of a basic sequence of the latter type, it will be assumed in the following description that this is the case for greater simplicity and because one of the simplest embodiments of the invention is thus effected.

To simplify the description, there is considered below the particular case when $n = 3$, that is, when the groups of coded pulses each comprise three pulses each capable of assuming two values that will be represented respectively by the figures 0 and 1. It is assumed that one of the values of the pulses is effectively zero—the pulses may each be either absent (value 0) or present (value 1).

Groups of three binary pulses may be arranged in eight different ways and consequently represent eight distinct amplitudes. For instance, to represent eight distinct amplitudes of an intelligence wave, corresponding to the integral numbers from 1 to 8, the eight groups may be 000, 001, 011, 111, 110, 101,



FIG. 3—Pulse generating system produces coded and noncoded signals



UNITS SHOWN HALF-SIZE

Target... RELIABLE CIRCUIT MINIATURIZATION

NEW ASTRON ET ELECTROLYTICS SAVE SPACE AND WEIGHT ...PERFECT FOR PRINTED CIRCUITRY

THEY'RE A HIT! Astron's newest capacitor design puts miniaturization directly in your sights . . . now it's possible to reduce overall equipment size, significantly—without impairing quality. New *ET* Electrolytics, available in *industry's widest range* of values, incorporate Astron's exclusive "SM"* Safety Margin Construction for the extra stamina to withstand surge voltages, ripple currents and high temperatures.

TINY, BUT TOUGH, *ET* Electrolytics offer a new designing approach whether you're working with printed circuitry, miniature tubes or transistors because here's a unique capacitor that matches their compactness. Long life . . . dependable 85°C operation and good capacitance stability result from meticulously controlled production techniques. Surgically-clean assembly of specially etched high purity foil . . . "regulated" electrolyte formulas for long life under varying conditions . . . positive hermetic sealing in metal cans for absolute environmental protection.

NEW *ET* ELECTROLYTICS utilize low-resistance terminal tab construction and exhibit exceptionally low current leakage over their entire operating range. Multiple production tests and 100% final inspection are your guarantee against costly rejects.

EVER BEEN ON A SPOT for chassis space? You'll want full engineering and application information — please request Bulletin AB-22.

PERFECT FOR CONVENTIONAL ..... OR PACKAGED CIRCUITRY ..... WITH MINIATURE TUBES ..... OR TRANSISTORS .....



Export Division: Rocke International Corp., 13 East 40th St., N. Y., N. Y.

In Canada: Charles W. Pointon, 6 Alcina Ave., Toronto 10, Ontario

*Trademark

ASTRON CORPORATION

255 GRANT AVENUE, E. NEWARK, N. J.

ADDED SAFETY
for the Skyways

RCA's new C-Band air-borne weather mapping radar unit marks a big-step toward all-weather commercial air transport service . . . a major contribution to added efficiency, safety and comfort in flight.

Efficient and safe, too, are the Camloc quarter-turn fasteners that hold the C-Band's electronic assemblies firmly in place. A quarter-turn and the Camloc fastener is opened fast. A quarter-turn and the Camloc fastener is closed fast—to hold fast!



Electronic components in this RCA C-Band radar accessory unit are assembled in groups for quick and easy servicing. Camloc quarter-turn fasteners provide the fast-acting, firm-holding means of insuring quick accessibility on the ground, vibration-proof operation in the air.

Camloc fasteners and latches are serving the aircraft and electronics fields in hundreds of ways. There's a Camloc device to meet your fastening needs, too. Write for complete information.

CAMLOC®
FASTENER CORPORATION
75 Spring Valley Road, Paramus, N. J.
WEST COAST OFFICE: 5410 WILSHIRE BLVD., LOS ANGELES, CAL.

010, 100. These groups may be formed by extraction, from the sequence 0001110100111 . . . successive three-figure groups obtained by shifting one figure from one group to the next one.

If there is produced, by any means, a series of ten two-valued pulses, the composition of which is represented by the basic sequence, all possible permutation groups will be successively found in each permutation group appearing once. This occurs if it is assumed the production of the sequence begins at a time that varies according to the particular composition of the considered group.

▶ **Sequence**—In the practice of the invention, the above-mentioned series of at least 2^n pulses and the whole sequence of N coded pulses will be produced during a time interval at most equal to and preferably slightly less than T. Designating the repetition period of the pulses in the series by τ, such arrangements will be taken that the product $2^n\tau$ be less than T and that changing from one coded pulse group (permutation combination) to the next different group will be effected in a sequence at regular time intervals also equal to τ.

Circuits can be arranged such that, at 2^n recurrent instants separated by time intervals equal to τ and defined by the pulses of the abovementioned series, a received coded pulse group may be compared with every possible group present in the sequence, any one of the comparisons will show identity. The received group is thus identified by the rank of the identical group of the sequence; 2^n comparisons will thus be made during each time interval T, at 2^n instants corresponding to 2^n pulses of the series. Some of the pulses may possibly be unused if, as in certain embodiments of the invention, the series includes more than 2^n pulses.

As already mentioned, it is possible to build a sequence of coded pulses fulfilling the required conditions by taking N equal to $2^n + (n\text{-}1)$.

Figure 1 illustrates an arrangement wherein successive groups of three coded pulses are applied to

. . . what we mean is a promotion package of 12 REGULAR ISSUES OF ELECTRONICS *plus the* BUYERS' GUIDE

Whatever other dilemma the advertising budget planner may be in, he is in agreement on one salient point: *advertising, to develop maximum effectiveness, must be continuous.* Nothing, absolutely nothing, pays off on the long run more than getting potential buyers familiar with your product and trade name by way of consistent, all-the-year-'round advertising. Once ascertaining what your market is, the logical approach is to keep your product in view of this market through continuous, consistent advertising.

For instance, the value of continuity in advertising was demonstrated by a series of surveys conducted by McGraw-Hill's Research Department. It was found through the results of these surveys that continuity in advertising increased the recognition of an electronic firm's products 26% in nineteen months.

For the budget planner with an electronic account, there is a ready-made promotion package for the consistent, continuous year 'round advertising program. That program is 12 regular issues of ELECTRONICS plus the 1 issue of the ELECTRONICS BUYERS' GUIDE . . . 13 insertions for 1956! Here you will reach more than 40,000 subscribers who *pay* to get ELECTRONICS – owners, partners, corporate officers, managers, department heads, chief engineers and especially: electronic, electrical, design and research engineers; in brief, the people of the industry who are responsible for buying the products you promote in the sales pages of ELECTRONICS and the buying reference pages of the "Guide." With a consistent, continuous advertising program in 13 issues of ELECTRONICS (12 regular issues plus the "Guide") manufacturers have discovered that they get the greatest return from their advertising dollar investment because ELECTRONICS reaches the men who influence purchasing.

BUDGET NOW FOR 13 INSERTIONS IN '56!



Up here

Only the Best is Reliable Enough

G-V Thermal Time Delay Relays have won the confidence of the country's major manufacturers of aircraft and airborne electronic equipment. More than a quarter million of them are now giving dependable service in over 500 different applications.

Timings of 1/10 to 300 Seconds

Precision of operation, unobtainable elsewhere, is made possible by the G-V design. Hermetic sealing, field adjustability and temperature compensation make closer settings and accurate repeatability inherent in G-V Thermal Time Delay operation.

A well-qualified G-V representative is ready to serve you. Write for complete data.

G-V CONTROLS INC.
24 Hollywood Plaza, East Orange, N. J.

G-V

the input from an external source. This may be a card or other system. They follow through a chain of delay networks with time delays equal to that occupied by a complete group of coded pulses divided by a number n of pulses that are received by and fully dissipated in a terminating network.

Three voltage-storing devices such as shown in Fig. 2 are timed at a recurrent rate T by appropriate



FIG. 4—Output and input devices are connected through phase control

control pulses and separated from the coded groups by a synchronizing selector.

A generating system shown in Fig. 3 produces the series of $2^n + (n\text{-}1)$ noncoded and two sequences of $2^n + (n\text{-}1)$ coded pulses, using the same recurrent pulse generator as supplies control pulses T, which are used as directing pulses for the system. The noncoded pulses are applied to a second system of delay networks as described above having delay times such that they are totally dissipated in the termination device.

It will be assumed that pulses representing the combination 101 are received at the input of Fig. 1.

These three pulses are propagated in the first delay networks and are positioned in the storage devices according to the delays at the same instant when the recurrent pulse generator puts out a pulse. This pulse is under the control of the synchronizing selector to allow only the synchronizing pulses through. The synchronizing pulse turns on the storage devices to receive a present pulse and an absent or no pulse. The present pulses are in devices I and III while the absent pulse is in device II. They thus store the 101 input.

During the next phase of the operation the generating system supplies a sequence of 10 coded

ACTUAL SIZE

complete with selector switch...

TRIPLETT

ELECTRICAL INSTRUMENT CO.
Bluffton, Ohio



- 5,000 ohms per volt. A.C.
- 20,000 ohms per volt. D.C.
- BANANA-TYPE JACKS—positive connection and long life.
- EXCLUSIVE SELECTOR SWITCH speeds circuit and range settings. The first and only miniature VOM with this exclusive feature for quick, fool-proof selection of all ranges.

CARRYING CASE

Handsome leather carrying case with adequate space for Model 310 tester and accessories. Trouser belt slips through loop on back of the case for out-of-the-way carrying. MODEL 369 CASE—U.S.A. Dealer Net..... **$2.90**

Model 310 MIGHTY MITE

the only complete miniature V-O-M (AC-DC)

LOOK AT ALL THESE RANGES

DC VOLTS: 0-3-12-60-300-1200 at 20,000 Ohms/Volt.
AC VOLTS: 0-3-12-60-300-1200 at 5,000 Ohms/Volt.
DC MICROAMPERES: 0-600 at 250 Millivolts.
DC MILLIAMPERES: 0-6-60-600 at 250 Millivolts.
OHMS: 0-20,000-200,000 (200-2000 at center scale).
MEGOHMS: 0-2-20 (20,000-200,000 Ohms at center scale).
OUTPUT: Convenient chart in instruction book.

SEE IT AT YOUR JOBBER
AND IT'S ONLY ONE OF TRIPLETT'S MIGHTY NINE VOM LINE!

ONLY **$29.50** Dealer Net



631 Combination V-O-M—VTVM

630-NA For Best Testing Around The Lab, Production Line or Bench

630 The Popular All-Purpose V-O-M

630-A A Good Lab and Production Line V-O-M

630-T For Telephone Service

666-HH Medium Size For Field Testing

625-NA The First V-O-M With 10,000 Ohms/Volt AC

666-R Medium Size With 630 Features

Boston Business Advertising

Want more information? Use post card on last page.

"THE COUNTREY MOST OVER GROWNE WITH PYNES"
...is still rich in resources for your plant

CAPTAIN JOHN SMITH REPORTED from Virginia in 1608 "the countrey most over growne with pynes." That year, the Colony exported "pitch, tarre, clapboard and waynscot"... items still on the modern list. But today Virginia forests have reared new industries of which Captain John never dreamed.



CHEMICALS, CARTONS, RAYON as well as furniture and paper now roll from Southside Virginia's modern plants. If you, too, can profit from abundant, nearby supplies of resin, fiber, pulp, lumber . . . you will find many other advantages in this new industrial area.

PLUS FACTORS FOR YOUR PLANT range from conservative Southern manpower to a mild, no-shut-down climate. You're central to the East Coast, with favorable rail rates to Mid-west markets. A host of truck lines, plus five main-line railroads, bring coal, chemicals, soybeans and other materials at short-haul cost.

AMPLE LOW-COST ELECTRICITY flows from VEPCO's modern power network. Generating capacity in 1955 was stepped up by 300,000 kilowatts, with 300,000 more authorized and ready soon. For more facts . . . and confidential help with your industrial home hunting, write or telephone VEPCO—serving THE TOP OF THE SOUTH.

VIRGINIA ELECTRIC and POWER COMPANY
Walter I. Dolbeare; Vice President—Area Development
Electric Building, Richmond 9, Virginia • Phone: 3-4261

pulses, 000, 111, 01, 00, which are applied to a chain of delay networks IV, V and VI. At the appropriate times these pulses are applied to the three amplifiers and to the voltage comparators.

The amplifier supply to the comparators a present or absent pulse in accordance with the code. Only one of the eight possible groups will coincide with the stored information in storage units I, II and III or 101. When this group passes, the voltage comparators are balanced and no output appears at the grid of the nonconducting biased amplifier tube.

While the coded sequence is being applied from coded pulse amplifier to delay networks IV, V, VI noncoded pulses are being applied to another grid of the biased amplifier tube and tend to make it conducting except that when noncoincident pulses from the comparator devices are applied this conductive condition is inhibited.

Thus when the coincidence of the 101 of the coded sequence occurs and no signal appears at the grid of the biased amplifier, a pulse appears at the anode, is detected and may be used to control other circuits. A similar condition would occur for any other coincidence.

Pulse Prospecting

A technique for "Geophysical Exploration by Electric Pulses" has resulted in the grant of patent 2,685,058 to W. J. Yost of Dallas, Texas. The patent is assigned to Socony-Vacuum Oil Company, of New York.

According to Yost's patent as illustrated in Fig. 4, when a commutated d-c potential e of alternate polarity is applied through input electrodes to a particular ground area, at a distance s a particular signal will be picked up that it has been found varies in phase and amplitude in accordance with the geophysical conditions of the ground. The electric field picked up at the output electrodes depends upon the resistivity of the earth.

The field decreases with increasing values of distance s as the cube of s. In practice, s is a great distance and so this factor is ignored since there will be only the minutest field owing to direct flow between

Keith Alderson (above) is Traffic Co-ordinator for Sportsvision, Inc., in Hollywood. He says,

"I'm the Sunday morning quarterback!"

"When the final gun sounds on Saturday's football games," says Keith Alderson of Sportsvision films, "cameramen rush their film to us.

"By Sunday morning, we've got finished prints of Pacific Coast Conference games into the hands of the coaches. They call me their 'Sunday morning quarterback'!

"But that's the easy part of the job.

"By evening, we've edited all the games into three half-hour TV shows—Big Ten, PCC games, and the All American Game Of The Week. Out they go to 150 television stations for immediate showing.

"How do we do it? Air Express, across the board!

"Nobody else can meet our schedules. Yet Air Express saves us money! Austin, Texas, to Hollywood, for instance, costs $8.03 for 15 lbs. That's $1.68 less than the next lowest priced air service."

Air Express

GETS THERE FIRST via U.S. Scheduled Airlines

CALL AIR EXPRESS . . . *division of* **RAILWAY EXPRESS AGENCY**

Want more information? Use post card on last page.

TRAGEDY
IN TWO CHAPTERS

I

Once there was a happy band of people called *Project Engineers*. Mostly human, they had carefree spirits and careworn bodies. Among their number were many with the magical ability that most of us lost when we passed nine years old.

In large and small industrial plants they could be found, dreaming impossible castles and making the dreams come true. How sadly this happy picture was to be shattered, we shall soon see.

The attack was launched insidiously, by The Forces of Darkness, who easily captured citadels of management by firing terms like "specialized knowledge" and "departmental responsibility." Always noted for an open unsuspicious outlook where *animate* objects are concerned, the Project Engineers saw no bad omen and did their best to cooperate. Specifications of all sorts began dropping around them. Small thick Military ones on white paper; large limp Departmental ones in purple hectograph; and superlarge Wrinkled ones on single sheets of blue print. The P. E.'s struggled to give each its due. The result, but for the aforesaid trusting natures, should have put them wise.

Equipment started passing more and more specifications, and doing less and less useful work. The P. E.'s realized vaguely that all was not right in Denmark. They lost their carefree spirits and their faces bowed down to match their already laboring shoulders.

The F. of D. chose this as the time for the next ploy. "Complexity!", they chortled. "That's the thing — yuk!" And now equipment blossomed forth in cancerous fashion with thousands and thousands of parts in each set. The F. of D. rubbed their hands! "With three thousand parts (= chances-to-fail), we'll have things g-r-r-round to a standstill in no time."

II

And now comes the real Drama. A small gallant few P. E.'s still with some old time spirit locked horns with a vicious case of complexity. Mercilessly they tortured components piece by piece eliminating each one destined to fail early. As mercilessly they treated finished equipments. They beat the percentages, and made the equipment work; — but at what cost!

They tried to tell others of what they had done, in the city of brotherly love.

But as in any real tragedy, the F. of D. had the inexorable vote of destiny. They made their final overwhelming attack. "We must keep these insufferable undoers of our dastardly doings in the dark. Insulate them from germinal contact with the outside world! Withhold from them the wisdom available by playing intellectual ping pong with suppliers! Cause them to wither from within by starvation of ideas!"

In no time flat a host of New Harpies were drawn up in cobwebby cadaverous cacophony just out of reach of the Project Engineers. They had names like "Standards Department"— "Qualified Products List"—"Vendor History File"—"AQL"

The last employed survivor of the original happy band resigned last month to join three cronies in a secluded nut hatchery featuring do-it-yourself therapy.

For us, all this is a great shame. We are, as usual, out of step. While we should have been setting up QPL's, we have been doing things like finding out if our hot new little telegraph relays * would *work*. (Not *pass*.) It takes time even on a telegraph set to run up half a billion operations. We are now getting back (as exhibits only!) relays which customers have operated in printers (.06 amp. 110 VDC inductive) that many times and more, without even availing themselves of the built-in-ingeniously-easy-maintainability.

If only we had been in time, we might have helped reprieve a few survivors of the above unequal struggle.

SIGMA

SIGMA INSTRUMENTS, INC.
62 Pearl Street, So. Braintree, Boston 85, Mass.

input electrodes and output electrodes. If the earth is considered homogeneous the signal at the detecting electrodes may be only boundary wave energy traveling at speeds approaching the speed of light.

Where the earth is not homogeneous, detecting electrodes will



FIG. 5—Typical signals resulting from geophysical soundings

pick up a combination of the signal of the air-earth boundary wave and subsurface reflections from discontinuities and resistive interfaces. At the detector a commutator similar to that at the transmitter is employed. In the presence of discontinuities an original signal as shown at (A) in Fig. 5 is received as at (B) or in the presence of severe discontinuity as at (C).

Considerable subsurface structure results in a received pattern such as shown at (D).

A phase shift of 40 deg in a tangential received wave is reported from certain subsurface interfaces compared to others. These measurements may be made by the technique shown to depths greater than 1,000 feet.

By standards developed from measurements made in areas well-known as to the subsurface geophysical structures, the invention has provided means for prospecting as yet untapped areas.



FERRITES *by Moldite* . . .

Whatever you need in Ferrites

Antenna Rods — Sleeves
Toroids — Threaded Cores
Cups — Coil Forms
Cores

There is a MOLDITE quality engineered product perfect for your application.

also Magnetic Iron Cores
Molded Coil Forms
(iron & phenolic)

Send for our catalog NM No. 110

. . . and backed by MOLDITE'S reputation for highest quality and guaranteed uniformity from first to last.

The use of a MOLDITE ferricore properly designed into a specific coil has the following advantages.

- Lower losses (eddy current)
- Smaller sizes for more compact construction
- Higher efficiency
- Higher permeability
- Lower operating temperatures
- Less corona effect
- Lighter weight
- Lower cost

NATIONAL MOLDITE COMPANY

1410 CHESTNUT AVE., HILLSIDE 5, N. J.

Robert T. Murray Co.
604 Central Avenue
East Orange, N. J.

Jerry Golten Co.
2750 W. North Ave.
Chicago 22, Ill.

William A. Franklin
3 Holly Road
North Syracuse, N. Y.

Perlmuth-Colman & Assoc.
2419 South Grand Ave.
Los Angeles Cal.

Jose Luis Ponte
Cardoba 1472
Buenos Aires

John S. Plewes Co.
52 Humbercrest Blvd.
Toronto 9, Ontario

Want more information? Use post card on last page.

Production Techniques

Edited by JOHN MARKUS

Eight Captive Screwdrivers Align Video I-F Strip

Method of sliding finished board into alignment fixture. Right hand of operator is on lever attached to cam that moves contacts up to board, making test connections for energizing all circuits on board automatically

ETCHED wiring boards serving as video i-f amplifiers in Westinghouse television receivers are accurately aligned with the aid of a bench fixture that automatically makes all necessary connections and provides the required aligning tools. The operator merely slides a board vertically into the fixture, up against a stop, then pulls a lever to press spring-loaded contacts against the required terminals on the dip-soldered wiring pattern.

Using both hands, the operator then adjusts captive screwdrivers for each of the four transformers in turn, while watching indications on the scope over the bench. The screwdrivers are spring-loaded so that they move back out of the way automatically when released. A pushbutton under the left wrist of the operator is pressed between transformer adjustments, to actuate a five-position attenuator controlled by a stepping switch. After the fourth and last transformer on a board is aligned, the next push on the button brings the attenuator back to its original setting in readiness for the start of the next board.

Boards awaiting alignment are placed in a rack at the right of the operator for preheating tube filaments, so that no time is lost in waiting for them to warm up in the alignment fixture. After a board is taken from the preheating rack and transferred to the alignment fixture, the operator places a cold board in the empty position. The time for this operation is sufficient for the tubes to recover the heat lost during transfer.

FOR most work with etched wiring boards in Convair's Pomona, Calif. missiles plant, three sizes of holes have proved adequate for leads of components, namely 0.053, 0.063 and 0.094 inch. Clinching of leads against the etched wiring permits considerable clearance of leads in these holes, simplifying assembly operations.

Wood Pallet Aids Insertion of Parts in Wiring Boards



Inserting seven-terminal Couplate in etched wiring board for radio. Tuning capacitor and volume control have special terminals that permit manual insertion in much the same manner, for automatic anchoring and connecting by dip soldering

MANUAL insertion of components in four-tube radio etched-wiring boards is accomplished efficiently on moving conveyor lines in the Metuchen, N. J. plant of Westinghouse Electric Corp. with the aid of simple wood pallets, each holding three wiring boards. The three-up arrangement of pallets gives sufficient weight and bulk so that the relatively light boards do not move around on the belt during assembly work.

Pallets are loaded simply by dropping the boards into position on sawed-out shelves. Each operator on the line inserts her assigned



KESTER "44" RESIN, PLASTIC ROSIN AND "RESIN-FIVE" FLUX-CORE SOLDERS are tried-and-proved remedies for almost every production situation where soldering time gets out of hand. Kester's great adaptability to widely divergent soldering requirements has time and again helped so many manufacturers combat rising production costs. It could be the solution you've been looking for!

THIS IS IT . . . *the informative 78-page free Kester textbook "SOLDER . . . Its Fundamentals and Usage." Send for your copy today!*

KESTER SOLDER

COMPANY 4204 Wrightwood Avenue, Chicago 39, Illinois; Newark 5, N. J.; Brantford, Canada

Want more information? Use post card on last page.

quota of parts. Punched holes are almost double the lead diameter in most cases, making manual insertion easy. Leads are not clinched. When all parts have been inserted, the board is carefully lifted out without tipping and transferred to a metal pallet for dip soldering.

Cutouts along the front edge of the wood pallet enable the operator to grip the front of the board readily when lifting it out of the pallet.

Machines Speed Cutting of Resistor Leads for Etched Wiring

ALTHOUGH intended for handling individual components, the motor-driven lead cutter developed in Emerson's Jersey City plant (ELECTRONICS, page 258, May 1952) has been found suitable for cutting two or three ¼-watt resistor leads at a time. Because of their small body diameter, these resistors can be readily loaded into the slots of the projecting sprockets on the endless chain. The chopping blades can cut two or three leads just as readily as one while moving up and down under cam action.

This type of machine has stood up well in actual use now for over 3 years. Its settings can be changed to provide different equal or unequal lead lengths simply by loosening two captive Allen wrenches at the rear. The only drawback is the necessity for hand loading, though this is at the same time an advantage because a human operator can load bent leads just as easily as straight leads.

The loading problem is partially solved by the IRC automatic lead cutter, an early version of which has been under test in the Emerson plant for a number of months. This does not have the latest automatic feed and hence the resistors must be dribbled down into the hopper a handful at a time by the operator. Though giving many times the cutting speed of an individual-resistor-loading setup, this machine does not begin to approach the ultimate cutting capacity of 60,000 resistors per hour that can be achieved with fully automatic feed of the hopper.

From the hopper, the resistors drop down a zig-zag path, achieved by having zig-zag slots for the leads in the two vertical side-plates between which the bodies of the resistors pass. This prevents the resistors from cocking at too great an angle and jamming as they go down. A Syntron electric vibrator bolted to the back of this slide-down plate helps to keep resistors moving without jamming.

At the bottom, the resistor leads pass between two pairs of rotating cutters, each pair individually adjustable as to position, to give any desired equal or unequal lead lengths. The cutters are geared together and driven by an electric motor through a reduction gear ar-

Loading resistors manually two at a time on motor-driven cutter

Loading resistors a handful at a time into IRC lead cutter



In Electronic Fan Design Only JOY AXIVANE® FANS Offer All These Advantages



PRECISION CONSTRUCTION

Precision construction insures performance that gives you great power in so compact a unit.

COMPACT DESIGN

Joy's axivane design permits installation of Axivane fans as part of the duct . . . requires no extra space.

LIGHT WEIGHT

Axivane fans are light in weight as well as compact because they are built from precision aluminum or magnesium castings produced in our own foundry under JOY engineering supervision.

AERODYNAMIC ENGINEERING

The airfoil blades and stationary vanes of JOY fans are made with power-saving, efficient airfoil cross-section. AXIVANE design provides equal pressure and velocity distribution across the fan outlet . . . eliminates turbulence . . . and produces the greatest cooling effect with the least expenditure of power.

MAXIMUM STRENGTH

Joy AXIVANE fans are durable because the outer casing, stationary vanes, and inner casing are precision-cast as a single unit, giving extra strength and maximum resistance to shock.

UNMATCHED EXPERIENCE

Joy's unmatched experience as the world's largest manufacturer of Vaneaxial fans and blowers is a bonus that costs you nothing extra . . . JOY'S leadership is due solely to the multitude of customers who are now enjoying the benefits of outstanding engineering. Why not join the number of satisfied JOY customers . . . you'll be in the best company.

COMPLETE LINE

Joy offers a large selection of fans in the standard line . . . as well as custom-designed types that are available to your specifications. The Joy line includes fans for all purposes ranging from 1/500 HP to 3000 HP. You'll find a fan to suit your needs in the JOY line. Let us work with you. ***Joy Manufacturing Company, Oliver Building, Pittsburgh 22, Pa.*** In Canada: *Joy Manufacturing Company (Canada) Limited, Galt, Ontario.*

Write for FREE Bulletin 15-39

W&O I 5627-15

Consult a Joy Engineer

For VANEAXIAL FANS • COMPRESSORS • VACUUM PUMPS and BOOSTERS
OXYGEN GENERATORS • HYDRAULIC FITTINGS • ELECTRICAL CONNECTORS

JOY

WORLD'S LARGEST MANUFACTURER OF VANEAXIAL-TYPE FANS

SCIENCE AND ENGINEERING

AT LOCKHEED MISSILE SYSTEMS DIVISION

THE OPERATIONAL APPROACH TO RELIABILITY

Reliability is the root of operational effectiveness, seeking out and solving failure before it occurs. The end result of Reliability is a missile system able to perform its mission successfully at a time dictated by military necessity.

To achieve that high standard, scientists and engineers at Lockheed Missile Systems Division apply an operational approach to Reliability in all phases of missile systems research, development and operation.

Under the Lockheed philosophy of Reliability, scientists and engineers combine their talents to study:

Human factors; training; design and operational safety; ground support and maintenance systems; airborne systems reliability; statistical methods; components application, including electronic, electrical, electromechanical and mechanical systems and environmental conditions.

Those possessing a high order of ability applicable to these areas of endeavor are invited to write:

Dr. Richard R. Carhart, Carl D. Lindberg, Reliability Staff Dept. Engineer, and Dr. O. B. Moan evaluate the functional and operational reliability effects of proposed revisions in the electrical power supply of a missile.

Lockheed

MISSILE SYSTEMS DIVISION

research and engineering staff

LOCKHEED AIRCRAFT CORPORATION

VAN NUYS, CALIFORNIA

rangement. The rear cutter of each pair has small gear teeth so as to grip resistor leads, while at the same time serving as a shearing anvil against which the sharply beveled front cutter can work to give a shearing cut.

In the fully automatic version of the machine, the box of resistors is unloaded automatically under photoelectric feed control, so that the operator needs only to remove empty boxes and put in full boxes from time to time.

Blower-Cleaned Tote Trays for Tube Grids



Construction of dust-repelling trays for small and critical grids used in miniature tubes

SPECIAL perforated metal trays are used for tube grids in the Bloomfield, N. J. tube plant of Tung-Sol Electric Inc. to insure cleanliness during assembly. Loaded trays are placed in recesses in a slanting box, at the rear of which is mounted a small centrifugal blower. The blower keeps a steady stream of air coming up through the trays past the grids to keep dust from settling on them.

The nickel-plated trays are designed to be self stacking. The slots also permit quick drainage of degreasing solution when entire trays of grids are immersed for cleaning.

Fluorescent Lamps Aid Inspection of Wiring

SHIELDED fluorescent lamps mounted directly on the rails of a pass-along assembly line provide glareless low-angle lighting that aids inspectors in detecting and repairing defects in dip-soldered wiring for a large etched-wiring board used in Westinghouse tv sets. Bad joints and shorts between wiring lines are easily detected. Shorts are cleared immediately with the tool used for probing joints. Locations requiring hand soldering are marked for later correction by putting on a small

Clearing short between leads with probe tool at inspection position illuminated by fluorescent lamps above and below wiring board. Operator's right hand rests on shield of lower lamp while holding etched wiring board in pass-along line

McGRAW-HILL MAILING LISTS WILL HELP YOU

- Merchandise your advertising
- Conduct Surveys
- Get leads for your salesmen
- Get inquiries about your product or service
- Pin-point geographical or functional groups
- Sell Direct
- Build up weak territories
- Aid Dealer Relations

Direct Mail is a necessary supplement to a well rounded Business Paper Advertising program.

600,00 actual names of the top buying influences in all the fields covered by the McGraw-Hill publications make up our 150 mailing lists. These lists are built and maintained primarily for our own use, but they are available to you for Direct Mail purposes. Pick out a list of YOUR prospect from our Industrial Direct Mail Catalogue.

More and more, progressive companies are using Industrial Direct Mail regularly as an advertising medium. They effectively allocate a portion of their concentrate on the best business publication.

For complete, detailed information about our service, fill in the coupon or write for your copy of our free Business and Industrial Direct Mail catalogue.

Direct Mail Division,
McGraw-Hill Publishing Co., Inc.
330 West 42nd St., N. Y. 36, N. Y.

Please forward my free copy of the McGraw-Hill "Industrial Direct Mail Catalogue."

Name _____

Company _____

Address _____

City _____ State _____

alligator clip to serve as indicator.

The 18-inch fluorescent lamps are mounted in plain white fixtures of the type having an adjustable metal shade. This shade is covered with black tape to eliminate reflections from overhead lighting. The inspector adjusts each shade so looking directly at the lamps will be avoided.

To prevent warping of such a large wiring board during dip soldering, a heavy punched metal stiffening strip is plugged into the center holes of the six-in-line tube sockets running across the center of the board. Three of the punched pegs on the strip, one at each end and one at the middle, are undercut. The operator crimps the socket tubulations over these to give the mechanical holding required to prevent the board from curling when immersed in the molten solder. The solder itself provides increased holding ability afterward, so there is no give when tubes are plugged in or removed.

Conveyorized Oven Bakes Resist on Boards

Silk-screen printing setup for etched wiring boards, with inspection position at right

SILK-SCREEN stenciling positions are located on both sides of a moving-belt conveyor running through a baking oven in RCA's Indianapolis plant. After placing a sheet of XXXP copper-clad phenolic in position on the worktable, the operator brings down the hinged silk-screen holder and forces the etching resist through the screen with one slow movement of a wide rubber squeegee. This applies the resist to protect the copper in regions where a wiring pattern is desired. The operator then transfers the board carefully to the conveyor, for transport through the oven to bake the resist.

Fiber Tote Tray Is Experimental Chassis

By GEORGE H. AMBER

Professional Engineer
Jam Handy Organization, Inc.
Detroit, Mich.

SMALL fiber tote trays reinforced with metal-edge corners have proved ideal as bases for day-to-day breadboard setups and for experimental lab checkouts of analytical designs. The inexpensive and expendable trays serve the same function as a metal chassis but are much easier to prepare.

Conventional metal-working techniques were applied to the fiber box at first, these being drills, a socket punch and a key-hole hacksaw for large rectangular holes. However, it was soon found that drills were not needed, for screw and wire holes could be readily pierced through the fiber with a scriber or awl. For potentiometer shafts and switch barrels, a small hole could be worked up in size with a center punch or screwdriver. Also, aviation-type

PRECISION-EERING

THE DIFFERENCE IN ATLAS DIFFERENTIALS

● Every tooth a masterpiece in finish, fit and motion. Atlas differentials are "precisioneered" to provide Nth degree accuracy in addition, subtraction and other electro - mechanical applications. The high sensitivity and minimal lost motion of precision Zerol gears ... plus corrosion and wear resistance assure long life in every assembly. Atlas gears and assemblies are made to meet your design and specifications. Have proved themselves by their acceptance and constant reorders from the world's largest users of electro-mechanical equipment. From drawing board to production line Atlas design, production and methods engineers and skilled toolmakers work with you on a job basis. Let them help you. Write for your copy of "Precision-eering Electro-mechanical Equipment" to Atlas Precision Products, Philadelphia 24, Pa.

FROM DRAWING BOARD TO PRODUCTION LINE

SERVICE ATLAS QUALITY

ATLAS Precision Products

Want more information? Use post card on last page.



Thermally Similar



RESISTOR ASSEMBLIES BY CLAROSTAT

Another example of *imagineering* at Clarostat—Two or more deposited carbon resistors encapsulated in a common potting compound to provide highly similar thermal conditions.

Designed to fill the needs of critical circuitry, the Clarostat thermally similar resistor assemblies are made up of deposited carbon resistors approved under MIL-R-10509A specifications. Resistance, or voltage ratio change from that of room temperature is less than 0.1% throughout the range of −55° C to +85° C.

Write for complete technical information on this latest product of the House of Resistors.

CLAROSTAT

CONTROLS AND RESISTORS

CLAROSTAT MFG. CO. INC., DOVER, NEW HAMPSHIRE

In Canada: Canadian Marconi Co., Ltd., Toronto 17, Ont. Manufactured under license in Great Britain by A. B. Metal Products Ltd., 17 Stratton St., London W. 1, Concessionaires for British Commonwealth except Canada.

CODE MARK Anything! WITH

★ CODE MARKING INKS
For Resistors and Capacitors.
For Machine or Hand Application.

Whatever the substance, Phillips has an ink to mark it permanently and legibly—or can make one. Marking experts insist on "Clear Print" Wood Block Stamp Pads and Opaque Inks. They get clear, sharp, fast-drying impressions. Also inks for brush, pen, stencil or machine application available in a variety of colors and quantity containers.

★ Quick Laboratory Service On Your Problem Markings.

★ To Permanently Mark . . . Metals, Plastics, Glass, Wood, Paper, Leather, Ceramics—glazed, varnished or lacquered surfaces and virtually every other known material.

WRITE FOR FREE BOOKLET

L. A. PHILLIPS, President
PHILLIPS PROCESS CO. INC.
192 MILL STREET
ROCHESTER 14, N. Y.

Want more information? Use post card on last page.



Punching screw and wire holes in 4 × 10 inch tote tray with ordinary awl

sheet metal snips replaced the hacksaw for rectangular holes.

The fiber tote trays are manufactured by National Metal Edge Box Co., Philadelphia, Pa. The two smallest sizes of trays (5.5 × 5 × 2.75 inches deep and 11.25 × 5 × 2.75 inches deep) are most frequently used as a chassis. Cost in quantities of twenty-five or more is under 20¢ each.

In working on the fiber chassis, a yellow china marking pencil makes a contrasting layout on the blue surface. Binder-head sheet metal screws and flat speed nuts are used instead of machine screws when mounting components, brackets, sockets or clamps. The pointed screw is compatible with a pierced hole, and the broad speed-nut offers ample backing to resist pull.

United-Carr snap fasteners are used as electrical lead connectors



Making socket hole with Greenlee punch after making pilot hole with awl and enlarging with center punch



Cutting transformer hole with aviation-type metal snips



WHY USE 1945 SYNCHROS IN 1956 DESIGNS?

Available in all Types!

ACCURACY 7 MINUTES

Function	Type Number	Primary Element	Excitation Voltage 400 cy.	Input Current (ma.)	Input Power (Watts)	Primary Impedance Secondary Open (Phase)	Primary Resistance (Ohms)	Secondary Element	Output Voltage	Secondary Impedance Primary Open (Phase)	Secondary Impedance Primary Shorted	Secondary Resistance (Ohms)	Phase Shift Degrees	Sensitivity mv./deg.	Accuracy Minutes Max.
Transmitter	CGC-8-A-7	Rotor 1 Phase	26.0	100	.50	54+ j260	37.0	Stator 3 Phase	11.8	12+ j45	15+ j3.5	11.8	8.0	200	7
Control Transformer	CTC-8-A-1	Stator 3 Phase	11.8	90	.23	28+ j110	24.7	Rotor 1 Phase	23.6	220+ j740	246+ j60	143	8.5	400	7
Control Transformer	CTC-8-A-4	Stator 3 Phase	11.8	37	.09	67+ j270	59.5	Rotor 1 Phase	24.0	508+ j1680	640+ j190	381	9.2	400	7
Resolver	CSC-8-A-1	Stator 2 Phase	11.8	84	.27	38+ j136	27.0	Rotor 2 Phase	23.2	280+ j600	344+ j75	230	11	400	7
		Rotor 2 Phase	26.0	39	.43	280+ j600	230	Stator 2 Phase	10.6	38+ j136	70+ j29	27.0	20	180	7
Repeater	CRC-8-A-1	Rotor 1 Phase	26.0	100	.50	54+ j260	37.0	Stator 3 Phase	11.8	12+ j45	15+ j3.5	11.8	8.0	200	30*
Differential	CDC-8-A-1	Stator 3 Phase	11.8	85	.21	27+ j120	25.0	Rotor 3 Phase	11.8	38+ j122	47+ j14	36.0	9.0	200	7 Rotor 7 Stator

Total Null max. 30mv for each unit

Also available in 115v 400 cy. primary, 90v secondary Transmitters, C.T.'s, Receivers

*Torque 2600 mg.-mm./degree from CGC-8-A-7

LOOK TO **cppc** FOR SYNCHRO PROGRESS

In equipment which must be flown, why load on extra weight? Clifton's new Size 8 Synchros can take the place of larger units at very significant saving in bulk and weight. These new Size 8's are now in use in some of the latest and lightest avionic equipment. Samples are available from stock, quantities from the production line.

CLIFTON PRECISION PRODUCTS CO. INC.
CLIFTON HEIGHTS PENNSYLVANIA

Want more information? Use post card on last page.

28 foot TRANS-HORIZON ANTENNAS available NOW

Field proven for two years in over 50 installations, this versatile, rugged antenna is currently available *from stock.*

more **KENNEDY** *equipment*

This typical SCATTER installation shows three 28-foot trans-horizon antennas. D. S. Kennedy & Co. not only furnished the "dishes", but also all of the waveguide components which included diplexers, bends, horns, transitions, etc.

From design and development through production of **complete antenna systems** Kennedy has your answers. And when time is an important factor, Kennedy is unmatched.

ANTENNA EQUIPMENT

D. S. KENNEDY & CO.

COHASSET, MASS. — TEL: CO4-1200

Mounting United-Carr snap fastener on top of fiber chassis for use as battery connection

and to connect separate units together. For example, a power supply is snapped onto one side of a summing amplifier chassis and a 6.3-v filament transformer is snapped onto the opposite side of the summing amplifier. Some B batteries, such as the 67½-v size, come with snap terminals so they can be snapped directly to a fiber chassis.

The fiber chassis is tough and strong, so that it springs back from a severe stress rather than becoming permanently deformed. Heavy components, such as magnetic amplifiers and transformers, are best mounted at a corner for stiffness.

While tubes can be mounted upright in a conventional manner, the trend in the test laboratory is to mount the tubes upside down. This permits components to be readily changed, and makes readily available all tube socket pins for point-to-point measurements and waveform checks. Most GT series tubes, such as the 6SN7 type, and all miniatures can be mounted upside down in any of the trays. Hot tubes, such as rectifiers and power pentodes, belong on top.

In addition to the tangible advantages of reduced shop time and



Appearance of ring oscillator as wired on fiber chassis for experimental work

Using Ceramic Capacitors? Specify RMC DISCAPS

Temperature Compensating

These DISCAPS meet all electrical specifications of the RTMA standard REC-107-A. Small size, lower self inductance and greater dielectric strength adapt them for VHF and UHF applications. Type C DISCAPS are rated at 1000 working volts providing a high safety factor. Available in six sizes in all required capacities and temperature coefficients.

Heavy-Duty

RMC Type B "Heavy-Duty" DISCAPS are designed for all by-pass or filtering applications and meet or exceed the RTMA REC-107-A specifications for type Z5Z ceramic capacitors. Rated at 1000 V.D.C.W., Type B DISCAPS cost no more than lighter constructed units. Available in standard capacities between 470 MMF and 40,000 MMF.

Type JL

Type JL DISCAPS afford exceptional stability over an extended temperature range. They are especially engineered for applications requiring a minimum capacity change as temperature varies between −60°C and +110°C. The maximum capacity change between these extremes is only ±7.5% of capacity at 25°C.



Wedg-loc

The exclusive wedge design of the leads on these DISCAPS lock them in place on printed circuit assemblies prior to the soldering operation. "Wedg-Loc" DISCAPS are available in capacities between 2 MMF and 20,000 MMF in TC, by-pass and stable capacity types. Suggested hole size is an .062 square.

High Voltage

Special high voltage DISCAPS are available in a wide range of capacities for color television and other electronic applications. RMC DISCAPS for deflection yokes insure the voltage safety factor required in this application. They are available in all capacities between 5 MMF and 330 MMF.

Plug-in

RMC Plug-in DISCAPS will speed up production time in printed circuit operations. Leads are constructed of No. 20 tinned copper (.032 diameter) and are available up to 1½" in length. Manufactured in TC, by-pass and stable capacity types, Plug-in DISCAPS have all the electrical and mechanical features of standard DISCAPS.

Write today on your company letterhead for expert engineering help on any capacitor problem.

DISCAP CERAMIC CAPACITORS

RMC

RADIO MATERIALS CORPORATION

GENERAL OFFICE: 3325 N. California Ave., Chicago 18, Ill.

FACTORIES AT CHICAGO, ILL. AND ATTICA, IND.

Two RMC Plants Devoted Exclusively to Ceramic Capacitors


Precision Components
for Microwave Systems
Unequalled experience in the design and manufacture of both simple and complex test components makes Technicraft your best and most economical source of supply.
Technicraft research has led to the development of new and better designs for such equipment as traveling detectors, slide tuners, movable shorts, stub tuners, VSWR calibrators and oscillating joints.
Our field representatives will be glad to provide assistance or information to help solve your microwave problems — contact us at Thomaston.
For complete details and characteristics ask for our specification sheets.
TECHNICRAFT LABORATORIES
INCORPORATED
1550 THOMASTON RD. • THOMASTON, CONNECTICUT
Designers and Manufacturers of Rigid and Flexible Waveguide Assemblies, Microwave Test Plumbing and Components, Waveguide Systems.

reduced chassis cost, these simplified fiber-chassis experimental techniques brought about unexpected intangible advantages at the Jam Handy Organization. Most electronic engineers are eager to prove out their paper designs, but are intimidated at times by the prospect of the time and metal work involved

Wien-bridge oscillator mounted on bottom of small fiber tote tray

Underside of Wien-bridge oscillator, showing potentiometers and tube

in working up a conventional chassis. Many a good idea thus cools off and many a poor one is carried into the prototype and pilot model, because it was never adequately breadboarded.

Designers are less reluctant to try out a circuit idea when it is easy to whip together functional hardware. Checking out each design change saves engineering time and reduces the need for last-minute re-designs and field modifications.

A shielded chassis is often desirable for high-frequency applications. It is planned to try out a copper-laminated fiber chassis that would permit point soldering of brackets and ground return leads.

A further experiment would in-

VOLTABLOC®

the most VERSATILE BATTERY ever built!


SMALL DIMENSIONS BUT BIG RATINGS
PEAK DISCHARGE RATES UP TO 20 TIMES CAPACITY
VERY FLAT DISCHARGE CURVE
OUTLAST CONVENTIONAL BATTERIES 5 to 1
UNHARMED BY VIBRATION, SHOCK, SHORT-CIRCUITS
WITHSTANDS TEMPERATURES −40°C to +160°C
NO MAINTENANCE
VOLTABLOC®
AMERICA

OUTPERFORMS ANY BATTERY AVAILABLE IN U. S. TODAY

For the first time VOLTABLOC'S® hermetically sealed cells make practical the application of rechargeable batteries in electronic design.

VOLTABLOC'S patented construction of sintered, nickel and cadmium plates compressed tightly in a hermetically sealed, metal case is the secret. They cannot leak or gas—can be stored indefinitely in any state of charge or discharge.



Their high quality and outstanding characteristics have introduced new standards of battery performance and economy. Send today for complete information on your specific applications. Write to SAFT Corporation of America, 2 Gregg St., Lodi, N. J.

A COMPLETE LINE FROM 0.8 a.h. TO LARGEST PEAK DISCHARGE REQUIREMENTS.

SAFT AMERICA

VOLTABLOC®—
THE HERMETICALLY SEALED BATTERY

ERIE FIRST AGAIN!
electronics

TEMPERATURE STABLE
Hi-K DISC CERAMICONS®
TYPE "H-A"

A NEW HIGH IN STABILITY

NOT 7½%—NOT 5%
ERIE OFFERS 3%
MAXIMUM CAPACITY CHANGE over temperatures ranging from +10° to +85°C. on this new Hi-K dielectric.

As a result of ERIE's continued basic research in Ceramics, another outstanding Hi-K ceramic dielectric has been created from ERIE laboratories known as TYPE "H-A". *This dielectric exhibits the flattest temperature characteristic Hi-K material ever offered to industry at non-premium prices.*



TYPICAL TEMPERATURE CHARACTERISTIC

TYPE "H-A" Temperature Stable Ceramicons are available in production quantities in any nominal capacitance value ranging from 150 mmf. to 4,250 mmf. with tolerances of ± 10% and ± 20%. Diameters of the "H-A" Ceramicons range from 5/16" to 3/4". Maximum thickness on all units is 5/32". Available in 22 gauge wire leads; also with 20 gauge wire leads or spade leads for automatic insertion in printed circuit boards.

Because of their small size and convenient shape, the TYPE "H-A" disc is ideally suited for critical applications that formerly required the use of expensive capacitors of other types.

For further information write for ERIE Bulletin 449.

ERIE electronics
ERIE ELECTRONICS DIVISION
ERIE RESISTOR CORPORATION
Main Offices and Factories: ERIE, PA.
Manufacturing Subsidiaries:
HOLLY SPRINGS, MISSISSIPPI • LONDON, ENGLAND • TRENTON, ONTARIO

volve combining etched circuit techniques with the fiber chassis. In this way, the advantages of low cost, easy workability, shielding and printed circuit simplicity may all be possible at the same time.

The fiber chassis is even being seriously considered for use as a permanent chassis. Its resilience makes it extremely resistant to shock damage and the inherent internal damping of the fiber resists vibration.

Producing Inkless Drawings for Etched-Wiring Patterns

By Donald F. Pennie
Electrical Engineer
Minnesota Engineering Co.
Minneapolis, Minn.

In testing various units of automatic assembly systems, etched-wiring layouts are often needed for test purposes. Where high accuracy is not necessary, engineers themselves can produce a satisfactory master drawing by applying Scotch electrical tape to a sheet of glass. This eliminates a costly drafting operation and saves considerable time. Furthermore, changes can be made in a few seconds, as compared to the hours required to move ink blots around on Bristol board or make new drawings.

To make a typically simple circuit by the tape method, the necessary tools are several sheets of ¼-inch to ½-inch plate glass, a few china marking pencils, Scotch tape (No. 471 and No. 33 work satisfactorily), a sharp cutting edge such as a razor knife and a paper punch. Even more convenient are the strip and circle preforms recently made available for this purpose by W. H. Brady Co. of Milwaukee.

A scale is selected (usually two times actual size). Paper cut-outs


Example of paper cutouts for three-tube amplifier having power transformer and selenium rectifier

INDIANA PERMANENT MAGNET DESIGN INFORMATION

published for industrial and consumer product engineers and designers

HOW TO MAGNETIZE PERMANENT MAGNETS



Magnetizing permanent magnets after assembly into the product offers several advantages. Higher field strengths are obtainable. The magnetic field produced in a loudspeaker, for example, using an Alnico V permanent magnet that has been magnetized after assembly, is about three times as great as the field obtained when the same magnet is magnetized before assembly.

The unmagnetized magnets are easier to handle and to assemble with other parts of the assembly. There is less contamination due to pick-up of magnetic particles.

Magnetizing after assembly is also advantageous in such applications as watt hour meters, polarized relays, and permanent magnet motors.

Using the Magnetizer

Most commonly used magnets are of simple bar or "U" shapes, which may be magnetized with an electromagnetic magnetizer in the user's plant.

Fig. 1-A shows how a bar magnet should be positioned between the magnetizer's pole pieces. The square ends of the pole pieces are used toward the gap. The space between the pole pieces is adjusted so the magnet can be easily inserted and removed. Normally, only one to two seconds are required to fully magnetize the magnet.

An assembly consisting of a bar-type magnet and soft-steel pole pieces should be placed with the magnet between the magnetizer pole pieces as shown in Fig. 1-B. Positioning the assembly as shown in Fig. 1-C will not fully saturate the magnet.

"U" shaped magnets and assemblies should be positioned as shown in Fig. 2, with the tapered ends of the magnetizer pole pieces used toward the gap. A meter or separator assembly would be placed on the magnetizer as shown in Fig. 2-B.



When a "U" shaped magnet is tall or larger than the generally accepted setting of the magnetizer, the field produced at point "X" (see Fig. 2-C) may not be sufficient to saturate the magnet. In this case there are two acceptable methods of magnetization. One is to place the magnet with its side on the pole pieces as shown in Fig. 2-D. This allows the yoke of the magnet to become magnetized. The magnet is then raised to the position in Fig. 2-C and again magnetized.

The other procedure is to stand the magnet on the magnetizer pole pieces with one or two steel blocks against each of its legs as shown in Fig. 2-E. The magnet (or assembly) is then magnetized three times: first, with both pairs of blocks in place; second, with blocks (a) removed; and third, with blocks (b) also removed.

For a complete discussion of how to magnetize permanent magnets by the electro-magnetic method, write for a copy of *Applied Magnetics*, Vol. 2, No. 3.

Chesterfield?

Cigarette manufacturers invest a great deal of time and money to bring you the best smoke possible.

Chesterfield is no exception . . and strangely enough, behind some of their recent efforts is an Indiana Permanent Magnet. You've probably read dozens of ads which say, "Chesterfield . . made the modern way . . with AccuRay."

AccuRay is a machine, made by Industrial Nucleonics Corp., that checks and controls the making of Chesterfields. One of the basic parts of this machine is a contact meter-relay, manufactured by Assembly Products, Inc. And the heart of this relay is an Indiana Hyflux Alnico V magnet!

Report on Indox I Ceramic Permanent Magnets

This recently published four-page technical bulletin, "Indox I Ceramic Permanent Magnets," suggests factors to be considered during design calculations, and discusses possibilities for new applications or improvements of existing ones.

Also discussed are some 30 representative sizes and shapes available in sample quantities for immediate shipment. Ask for price list and Catalog 15-A-1.

THE INDIANA STEEL PRODUCTS COMPANY
Valparaiso, Indiana

WORLD'S LARGEST MANUFACTURER OF PERMANENT MAGNETS

INDIANA PERMANENT MAGNETS


What are YOUR paper tube requirements?
• Special size or shape
• Critical tolerances
• High dielectric strength
• High tensile strength
• Dimensional stability
• Low unit cost
• Prompt delivery in any quantity

PRECISION *can*

meet your exact specifications

You can order from Precision in an infinite variety of sizes, shapes, I.D.'s or O.D.'s and be sure of the finest quality and construction, plus uniformity throughout. You can specify kraft, fish paper, acetate, combinations, phenol impregnation, etc., whichever material is best suited to your particular application.

Precision's modern high production facilities and rigid manufacturing control bring you all these advantages at lowest possible cost!

Request samples and Arbor List of over 2000 sizes.

PRECISION BOBBINS CUT COIL COSTS



Eliminate rejects, waste, loss of time. Order in any size or shape, plain or fitted with leads, slots or holes. Flanges cut to your specification. Ask for samples and bulletin.

Sales Representatives in:

New England: Framingham, Massachusetts, Trinity 3-7091
Metropolitan New York, New Jersey: Jersey City, New Jersey, Journal Square 4-3574
Upstate New York: Syracuse, New York, Syracuse 4-2141
Northern Ohio, Western Penn.: Cleveland, Ohio, Atlantic 1-1060
Indiana, Southern Ohio: Logansport, Indiana, Logansport 2555
California: Pasadena, California, Sycamore 8-3919
Canada: Montreal, Quebec, Canada, Walnut 0337

PRECISION

PRECISION PAPER TUBE CO.

2041 W. CHARLESTON ST. CHICAGO 47, ILL.

Plant No. 2: 79 Chapel St., Hartford, Conn.

Crayoned wiring layout on glass



Taped wiring layout on glass

of the components are made to this scale and shifted about on a flat surface within the limits of the desired board size until an optimum arrangement is achieved. The cutouts are then tacked to the drafting board surface with masking tape, a clean plate of glass is placed over them and a china-marking pencil is used to sketch possible wiring routes. Different colors are sometimes helpful for signal, d-c and 60-cps paths. The work then becomes a game of moving or rotating tube sockets and shifting resistors and capacitors to minimize the number of jumpers. The pencil lines are easily wiped off with cleaning tissue to make changes.

When satisfied with the component positions and interconnections, the penciled plate glass is removed and a fresh glass placed over the paper cutouts. Component terminations cut from plastic tape (or preforms) are now placed on the fresh glass over the final component layout. For example, ¼-inch terminal circles of No. 33 Scotch tape are placed over the ends of all resistor, capacitor and other axial-lead components. Small resistor and capacitor terminations are spaced on centers ½-inch apart or more, as required for Minn-A-Matic insertion machinery. Squares or rectangular terminations are used for larger parts such as potentiometers and transformers.

When all tape terminals are in place, the connecting strips are cut

project for '56

join the A-MP® taper parade



Are you in step with the more progressive manufacturers of BUSINESS MACHINES—AIRCRAFT—GUIDED MISSILES—ELECTRONIC EQUIPMENT—who have approved and are profiting by the use of A-MP TAPER TECHNIQUE?

There is still room on the A-MP TAPER TECHNIQUE Band Wagon for you to join the leaders. You, too, can increase speed of assembly, improve reliability, and save money by using A-MP TAPER PINS, TAPER TAB RECEPTACLES, TAPER BLOKS and TAPER TIPS.

And you'll be "cheered on" by the many alert manufacturers of electrical and electronic components who have modified their standard products to help you enjoy the advantages of A-MP TAPER TECHNIQUE.

Make it a *MUST* to specify A-MP TAPER TECHNIQUE in your PROJECTS for 1956.

A-MP

AIRCRAFT-MARINE PRODUCTS, INC.

GENERAL OFFICES: HARRISBURG, PA.

A-MP of Canada, Ltd., Toronto, Canada
Aircraft-Marine Products (G.B.) Ltd., London, England
A-MP—Holland N.V.'s-Hertogenbosch, Holland
Societe A-MP de France, Courbevoie, Seine, France

Want more information? Use post card on last page.

SILVER

FOR ELECTRICAL AND ELECTRONIC USES...

SILVER—because of its superior electrical conductivity, its equally superior thermal conductivity, its excellent resistance to corrosion and its ready workability—is used in many different forms on a wide variety of applications in the electrical and electronic industries.

As a leading fabricator of silver and its alloys, Handy & Harman has developed silver in many forms to meet the industries' needs.

The list at the right is typical of the silver products readily available for your use. In addition, we are equipped to produce special silver alloys to meet special requirements. Our engineering and research departments are always ready to cooperate in solving your particular problems.

Write us if you want information about the uses of silver and its alloys.

- Fine silver (wire & strip)
- Silver anodes and grain for plating
- Silver contact alloys
- Silver powders
- Silver flakes and paints
- Silver brazing alloys
- Special electronic solders
- Solder-flushed silver alloys
- Silver chloride and oxide
- Special silver alloys to your requirements

PRECIOUS METALS SINCE 1867

HANDY & HARMAN

General Offices and New York Plant

82 Fulton Street • New York 38, N. Y.

OFFICES and PLANTS
BRIDGEPORT, CONN.
PROVIDENCE, R. I.
CHICAGO, ILL.
CLEVELAND, OHIO
DETROIT, MICH.
LOS ANGELES, CALIF.
TORONTO, CANADA
MONTREAL, CANADA

from tape with the razor and added. Spacing and minimum width of these strips of tape depend on the current to be passed, coupling, efficient use of resistors for bridging and the necessary spacing to avoid bridging in the solder-dip operation.

Scotch No. 33 electrical tape is easy to cut and work with, but is

Examples of finished boards

too stiff for sharp radii. Scotch No. 471 tape may be easily used for sharp radii, but bleeds if the tape is allowed to get too warm and may slip on the glass plate if laid down in a stretched position.

During the final routing of cir-

Finished amplifier after soldering

cuits the china-marking pencil sketch serves as a good guide. It will be found that a ½-watt resistor will nicely bridge two or three ⅛-inch parallel conduction paths. Ground paths serve as fairly good shields and unfortunately also as efficient ground loops. If the china-marking pencil sketch has been correctly drawn, rotation or shift of components rarely needs to be made in this third step.

When conduction paths are complete, extra tape can be added where grounding is thought to be necessary or to widen areas which might become points of poor pattern adhesion. Tape wiring is

new digital magnetic tape transport →

the **AMPEX FR200** for digital handling provides new performance standards, new convenience features and an unmatched excellence of design

NEW EASE OF TAPE CHANGE...
The time saving feature of single loop threading is provided by a lever which moves the idlers into a straight line. This arrangement eliminates chance of faulty threading by unskilled personnel.

NEW MACHINE-TO-MACHINE TAPE COMPATIBILITY...
All Ampex FR200 Tape Transports are manufactured to exact standards that permit tapes recorded on one to be reproduced on any other. Ampex-to-Ampex compatibility is guaranteed — *and at no extra cost.*

NEW PLUG-IN HEADS TO MATCH OTHER TAPE TRANSPORTS...
The Ampex FR200 uses self aligning plug-in head assemblies. These can be furnished to match other digital or analog tape recorders to permit tape interchange. A second head stack for monitoring or "off-tape" parity checking can also be added if desired.

HIGH-SPEED START AND STOP...
On the Ampex FR200 the tape attains full speed or full stop within less than 5 milliseconds to provide high information storage density. A remote control provision is provided, as well as pushbuttons on the topplate.

NEW STANDARD OF EXCELLENCE...
The FR200 brings to digital applications the reliability, durability and adherence to specification that have made Ampex Tape Recorders the most widely used in instrumentation.

NEW LOW PRICES BEGINNING AT $2675
The base price of $2675 is for a complete FR207-TB tape transport, with 7-track head, for ½-inch tape operating at 30 ips tape speed. Prices will be quoted on machines with other tape speeds, multiple speeds, other tape widths and other heads.

FULL SPECIFICATIONS ON THE FR200 *and description of its features and accessories are given in descriptive literature. For your copy, write Dept. E 2539.*

AMPEX CORPORATION
934 CHARTER STREET
REDWOOD CITY,
CALIFORNIA

DISTRICT OFFICES: New York; Chicago; Atlanta; Dayton; Redwood City; Silver Spring, Maryland (Washington D.C. Area)
DISTRIBUTORS: Radio Shack, Boston; Bing Crosby Enterprises, Los Angeles; Southwestern Engineering & Equipment, Dallas and Houston; Ampex-American in Canada.

PRINT ELECTRONIC CIRCUITS AUTOMATICALLY BY SILK SCREEN

GENERAL DECORATOR PRESSES-SERIES B

■ The Silk Screen method is being widely accepted for preparing copper laminated plastic panels prior to etching printed circuits. General Decorator Presses put printed circuits on an automatic, high production basis. Bowed panels are held flat by vacuum. Line contact impression and accurate register give clean, sharp reproduction of fine lines. Controlled inking lays down a thick, uniform layer of resist.

Model No.	B1224	B1824	B1836
Sheet Size	13x25"	19x25"	19x37"
Speeds Up To	1000 per hr.	800 per hr.	800 per hr

ThermoJet DRYER Utilizes a new system for high speed drying of inks, resists and coatings by greatly accelerated evaporation of solvents.

GENERAL

Write for complete information
RESEARCH AND SUPPLY COMPANY
572 S. Division Avenue
Grand Rapids 3, Michigan

—they're dependable!

DKE

precision, deep drawn

KOVAR PARTS

—from 1/4" dia. and 3/4" deep, .025" thickness

Consult the Engineering Company for quality parts or sub-assemblies of steel, aluminum, copper, brass, kovar, nickel and monel. Fast, economical service on long or short runs. The most modern machines and micro-precision tools assure highest accuracy.

WRITE TODAY for quotations, sending your sketches or blueprints; no obligation

THE engineering CO., 27 WRIGHT ST., NEWARK 5, N. J.

easily removed or added at this stage.

The finished drawing is removed, clamped in a frame against a white background and photographed conventionally for the production of etched wiring boards.

Under-Bench Wire Bins

Floor-level view of under-bench wire-storing tubes

METAL tubes holding a complete selection of wires needed in Martin electronic assembly operations are fastened under the work tables. They provide a conveniently available stock of wire for the operators on both sides of the tables. These simple aids have saved operators many useless trips to stock bins.

Pre-Tinning Techniques for Etched Wiring

By L. J. MARTIN and M. J. VAVRA
Weapon Systems Development Laboratories
Hughes Aircraft Co.
Culver City, Calif.

ONE operation which subjects an etched wiring board to chemical contamination is that of plating the etched circuit. Gold, nickel, rhodium and solder plating have been used on etched circuits to facilitate soldering or improve contacts.

As a test of the effect of plating, comb test patterns were prepared on phenolic boards and subjected to solder plating in a lead-tin-fluoroborate bath, followed by normal washing. After exposure to humidity, resistivities were similar to those of unplated control samples, indicating negligible contamination from plating. It should be pointed

America's Most Complete Line of Instrument Calibration Standards!

Meets our need for GREATER ACCURACY!

FROM ACTUAL EXPERIENCE BY

International Business Machines Corp.

Poughkeepsie, New York

The increased usage of electronics in the computing machine industry has resulted in a greater need for accuracy in electrical testing equipment," according to the manager of test equipment maintenance of IBM's Poughkeepsie plant.

"Because our specifications require that any test equipment shall have twice the accuracy of the unit being tested, the finest meters have to be used, and these meters are constantly calibrated with the help of the two RFL Model 260B and 262B Calibration Standards in our testing department. We've used them steadily since 1952 both for inspecting meters and making up correction data for such test instruments as polyrangers, laboratory standards, secondary standards and electric dynamometers."

The advantage gained by in-plant calibration of electrical instruments using these console type Standards, which encompass the full range of testing instruments, under controlled laboratory conditions, goes beyond mere convenience. Their ease of operation, consistent calibration and high accuracy over wide current and voltage ranges are impossible to duplicate using individual testing equipment which must be moved from job to job throughout a manufacturing plant.

In addition to accuracy, each RFL Standard has many features which make rapid calibration procedure possible. Where many instruments must be tested, it can be demonstrated that an appreciable cost saving over older calibration methods will soon result.



Model 260C

Calibrates DC electrical measuring instruments to direct reading accuracies of 0.5% (0.25% using calibration charts) through voltages ranging from 1 millivolt to 1500 volts and currents ranging from 1 microampere to 150 amperes.

Net price $8,975.00 f.o.b. Boonton.



Model 261B

Calibrates all types of AC meters to direct reading accuracies of 0.5% (0.25% using calibration charts) over frequency range of 50 to 1600 cps. Current range from 1.5 milliamperes to 200 amperes; voltage range from 75 millivolts to 1500 volts. Output of electronic power oscillator has less than 5% total harmonic content at 60 cycles.

Net price $9,250.00 f.o.b. Boonton.



Model 262B

Calibrates DC electrical measuring instruments to direct reading accuracies of 0.1% (0.05% using calibration charts) through voltages ranging from 1 millivolt to 1500 volts and currents ranging from 1 microampere to 150 amperes.

Net price $14,300.00 f.o.b. Boonton.

Write for technical data and application information.

RFL

Radio Frequency

LABORATORIES, INC.

Boonton 3, New Jersey, U.S.A.

DESIGNERS AND MANUFACTURERS OF ELECTRICAL EQUIPMENT SINCE 1922

Radio Frequency Laboratories, Inc.
Boonton 3, New Jersey

Please send me complete information on all Instrument Calibration Standards.

Name_____ Title_____

Company_____ Phone_____

Address_____

City_____ State_____

HYCON EASTERN

a complete facility for

DESIGN • ENGINEERING • PRODUCTION



CRYSTAL FILTERS



FREQUENCY RANGE: 10 kilocycles to 10 megacycles for all types of filters.

BANDWIDTH RANGE: 0.01% to 14% of center frequency.

APPLICATIONS: Carrier Communication Systems: Telephone Channel Filters, Pilot Selection Filters, Telemetering Channel Filters, Teletype Channel Filters, Other Frequency Multiplexing Systems. Single Side Band Filters. High Selectivity Amplifiers. Noise and Sound Analysers. Carrier Current Systems. Harmonic Selection.

ANNOUNCEMENT is made of a new technique for the synthesis of crystal filters which resolves many of the problems heretofore associated with their design and production. High initial cost and long lead time have been eliminated. System design no longer need be compromised because of the limited number of existing filters. Filters can be produced on short notice in large or small quantities to meet *exact* performance requirements. Curves shown above suggest the wide variety of characteristics. *Your inquiry is invited.*

HYCON EASTERN, INC.

75 Cambridge Parkway, Dept. A, Cambridge 42, Massachusetts

out, however, that these boards did not have holes drilled in them which might have permitted entry of the electrolytes. The only machined surfaces were the outside edges, far removed from the circuit.

► **Dip-Soldering Isn't Easy**—One naturally thinks of dip-soldering in connection with etched wiring as a means of soldering many connections at once, without dependence upon a girl with an iron, as an attractive economic prospect. Reliable dip-soldering, though, is easier talked about than done. One can't just stick component leads into an etched circuit with partially oxidized copper conductors, apply a safe flux, dip it in solder and hope for 100 percent reliable joints. Either a dangerously active flux must be used or other steps to insure wetting the etched conductors must be taken, such as pretinning or plating.

Some workers have found a thin gold plate, a flash, to be adequate to insure tinning. Others prefer solder plating at least 0.001 inch thick. Though it has been shown that adequate washing avoids contamination from plating electrolytes, plating tends to be objectionably expensive, if for no other reason than the difficulty of interconnecting the many isolated conductors on a board.

► **Fluxing Problems**—Pretinning with molten solder has obvious advantages over plating, but fluxes are required and so must be considered as possible contaminants. The important differences between using fluxes for pretinning or for soldering components directly to untinned conductors are: the pretinning may be done with a heated roller or other similar applicator, which aids in breaking through the oxide better than with dipping; flux residues may be washed away more effectively after simple tinning than after covering a board with components.

In general, the more active the flux the greater is its help in soldering. However, unless the residues of active fluxes can be removed, their corrosive effects are intolerable. Many so-called noncorrosive fluxes have been tested. In one set

BEYOND THE HORIZON TRANSMISSION



Photograph of the earth from 100 mile altitude — Courtesy U. S. Air Force

M. M. Hubbard, President, Hycon Eastern, Inc.

Formerly Assistant Director, Lincoln Laboratory, M.I.T. Participated in Lincoln 1952 Summer Study and made preliminary designs for detection and communication systems for the Distant Early Warning Line, utilizing scattering techniques. Participated in Projects Hartwell, Charles, Beacon Hill and Lamp Light studies.

A. J. Pote, Vice Pres., Chief Engineer, Hycon Eastern, Inc.

Formerly Group Leader (Communications), Systems Engineering Lincoln Laboratory, M.I.T. Completed detail system design of long range scatter communications for experimental Early Warning Trial; specified communication system details for operational Distant Early Warning Line. Participated in Projects Troy, Charles and Lamp Light studies.

A TECHNOLOGICAL BREAKTHROUGH

Not since the end of the 19th century when Marconi signalled a few miles over a radio circuit has any development in the field of communications had the far-reaching significance of ionospheric and tropospheric "Scatter" transmission . . . "Beyond the Horizon" circuits. Signals as far as several hundred miles beyond the horizon exhibit properties which make possible in long distance radio circuits, for the first time, degrees of reliability equal to or better than wire circuits afford.

EXPERIENCE IN A NEW FIELD

To successfully exploit this new technique in practical applications, fundamental knowledge and experience is imperative. The Communications Engineering Team at Hycon Eastern, Inc. has had precisely this experience working with experimental and operational circuits and in the planning of complete communications systems.

HYCON EASTERN OFFERS AN INTEGRATED SERVICE

Within the areas of Hycon Eastern, Inc. and its associates, Hycon Manufacturing Company and Hycon Aerial Surveys, Inc. can be found complete facilities not only to design, engineer and specify equipment for Beyond the Horizon Transmission Systems, but to design Central Offices, Connecting Wire Networks, perform Communication Traffic Density Surveys, Aerial Surveys and Mapping to determine the most efficient routes for land lines and for various radio links such as UHF/SHF line of sight. After the necessary facts have been gathered there further exists the experience to evaluate them and to specify practical equipment with complete independence of judgment necessary to create a complete communications system capable of fulfilling present and projected needs.

A COMPLETE FACILITY FOR DESIGN OF INTEGRATED COMMUNICATIONS SYSTEMS

HYCON EASTERN, INC.

75 CAMBRIDGE PARKWAY • DEPT. A, CAMBRIDGE 42 • MASSACHUSETTS



New!

subminiature magnetic storage elements by

EPSCO

small size • low power • rugged • reliable

New Epsco Magnetic Storage Elements Type SR-11 are designed for airborne and missile applications. Due to their extremely low power requirement, they may be driven by either subminiature tubes or transistors.

Measuring only ¾" x ¾" x 7/16", these new subminiature units are entirely suitable for mounting on etched wiring boards. Epsco SR-11 storage elements also offer the advantages of high ratio of storage elements to drive tubes. Wide operating limits and encapsulated packaging insure the ultimate in reliable performance.

SR-11 elements have an information rate design center of 10 kc, with a practical upper information rate of 15 kc. Peak power per shifted "one" at design center is only 0.5 watts.



Circuit Schematic



Typical Output Voltage Waveform



Typical Drive Current Operating Limits

For full information on Epsco Magnetic Storage Elements, write for Engineering Data Sheets.



EPSCO INCORPORATED

588 Commonwealth Avenue, Boston 15, Mass.

of experiments these fluxes were applied to comb pattern test boards, a dip or roll tinning performed and the boards subjected to humidity exposure. Except when these boards were thoroughly cleaned after tinning, serious insulation leakage was measured and visible corrosion generally was evident. This indicated, contrary to a general belief, that these fluxes are not completely volatilized or decomposed to noncorrosive residues by the heat of soldering. Accelerated corrosion tests also were made by applying the fluxes to parallel windings of bare copper wire on glass rods and subjecting these to direct voltages and humidity. Corrosion was evidenced by the formation of copper salts.

Stearic acid-toluene and rosin-alcohol were found to be free of contaminating residues and therefore safe to use without subsequent cleaning to remove all traces of their residues. Though the residues of corrosive fluxes can be removed by thorough washing, one is inviting trouble from careless work. One also should beware of using these active fluxes with eyelets because of the danger of trapping corrosive residues beneath their heads.

▶**Roller-Type Soldering Iron**—Pretinning may be performed with a heated solder-coated roller, either used manually or mechanized for volume production. The construction of a hand-roller containing a regulated heating element is shown. A thin uniform film of solder is applied and rolled onto the fluxed boards, the conductors picking up this solder film as they are heated



Hand roll tinner. Cord does not kink because soldering iron is locked in fork of handle; copper roller rotates on and is heated by heating element of iron

...adapted by Admiral®
to rise above present flight ceilings

When present flight ceilings of military aircraft are again elevated, the fire control radar apparatus will be ready to rise with the planes. Admiral's development work on the basic unit has eliminated the need for pressurization to prevent voltage break-downs at extremely high altitudes. In solving this central problem, a host of vexing collateral problems have been eliminated. As developed and built by Admiral, the unit is compact, lightweight, and needs no bulky, expensive cooling system to dissipate internal heat.

Here is another example of Admiral's many contributions to the science of military electronics. Exceptional facilities are available for research, development and production of electronic or electro-mechanical equipment. Address inquiries to:

Admiral Corporation
Government Laboratories Division, Chicago 47, Illinois

NOTE: NEW COLOR SOUND FILM on Admiral Automation available for showing to technical or business groups. Address requests to Public Relations Director, Admiral Corporation, Chicago 47, Ill.

LOOK TO *Admiral* FOR RESEARCH • DEVELOPMENT PRODUCTION

In the fields of:

COMMUNICATIONS, UHF AND VHF, airborne and ground.
MILITARY TELEVISION, receiving and transmitting, airborne and ground.
RADAR, airborne, ship and ground.
RADIAC • MISSILE GUIDANCE • TELEMETERING
• DISTANCE MEASURING • TEST EQUIPMENT
• CODERS AND DECODERS

FACILITIES BROCHURE describing Admiral plants, equipment and experience sent on request.

ENGINEERS: The wide scope of work in progress at Admiral creates challenging opportunities in the field of your choice. Write Director of Engineering and Research, Admiral Corporation, Chicago 47, Ill.

Want more information? Use post card on last page.

Comar Plug-In Relays simplify replacement, speed up servicing, permit faster assembly, eliminate wiring error. Safety covers protect against shock and dust. Ideal for use in vending machines, mobile communications equipment, electronic computors, automatic pin-spotters, testing apparatus, etc. Maximum standard contact combinations up to 3PDT, (up to DPDT, UL). Also available without covers. Relays used are standard Comar components. Our engineers will show you how these plug-in types can best be applied to your requirements. No obligation.

Send for details now!

Comar
ELECTRIC COMPANY
3349 ADDISON STREET
CHICAGO 18, ILLINOIS

RELAYS • SOLENOIDS • COILS • TRANSFORMERS • SWITCHES • HERMETIC SEALING

by the roller. This tinning operation should be performed as soon as possible after the boards have been etched, cleaned and dried, so as to minimize oxidation prior to tinning. Subsequently, the tinned boards may be dipped in stearic acid, to provide flux for subsequent dip-soldering and to protect the tinned conductors from oxidation, if stored.

For successful dip-soldering, it is essential that the solder wet the component leads, as well as the board conductors. Consequently, it is desirable to have these leads tinned with an eutectic solder and then coated with stearic acid. Component leads thus treated have dip-soldered well, even after two years of open storage.

Split Induction Coil Heats Silicon Crystals

By J. Soled

Signal Corps Engineering Laboratories
Fort Monmouth, New Jersey

Split induction coils are needed when the work piece is so shaped that it cannot be inserted into the coil. The usual design utilizes separate water cooling paths for each half, with a rubber connecting tube joining them. The halves are hinged to facilitate opening and closing. Such a design results, however, in a heavy assembly.

▶**Construction Details**—The split induction coil was designed to maintain the close coupling and narrow heating zone of the regular single-turn coil. A three-piece inner copper ring, silver-soldered to the split copper tubing, supplies the current path. A slight bowing out of the copper tubing at both sides provides room for sleeve joints, which take ☆ inch thick, ⅜ inch



Disassembled work coil, with O-ring seals attached to fixed ends



EARLY RESEARCH AND DEVELOPMENT EXPERIENCE with electronic location equipment at G.E. began in 1935 when this first system, with an output of 1½ watts, located planes up to five miles away.

IN USE TODAY, this huge nodding height finder was designed and developed by General Electric to be used with powerful search radar systems and is a major contribution to long-range aircraft location.

How G.E.'s 20-year antenna background can help make your radar system more effective

6 examples show experience in all areas of land- and ship-based antenna work

To give you an outstanding source for reliable, precision radar antenna equipment, General Electric backs modern facilities with the know-how that comes from many years of research, engineering, and manufacturing experience.

For example, early research in electronic location equipment at G.E. began in 1935 and engineering and manufacturing experience includes these six major areas:

1. **Stabilized bases** to compensate for ship pitch and roll were built in large quantity with Navy antennas in World War II.
2. **Small, portable systems** for weather balloon tracking were developed and produced for the Army and Navy in 1948.
3. **Powerful heightfinding antenna,** FPS-6XW1, developed by G.E. for USAF in 1949, was an advancement in long-range detection.
4. **Giant shipboard search antenna,** largest in use today, was G-E developed and produced for Navy early-warning ships.
5. **Long-range search antennas** (FPS-7) were designed and built by G.E. using advanced construction techniques.
6. **One of the first combination antennas** (allows both search and elevation detection), the Navy's SPS-8 was designed and produced to give a precise beam pattern.

This extensive background enables clearer perception of special engineering and manufacturing problems. It is the element that helps give G-E precision antenna equipment the efficiency and reliability to help make your radar system more effective. For more information, contact your G-E Apparatus Sales Office or use coupon below.

Mail to: General Electric Company, Section A223-2
Schenectady 5, N. Y.

Please send me these two bulletins:

GEA-6279, Radar Antennas, Mounts, Components, and Accessories

GED-2494, G.E.'s Naval Ordnance Department Offers *Complete* Engineering and Manufacturing Services

☐ For immediate project. ☐ For reference only.

Name .....
Position .....
Organization .....
Address .....

Progress Is Our Most Important Product

GENERAL ELECTRIC



● Springs and wireforms take on some pretty queer shapes at times. They're designed that way to do unusual jobs. However, many springs are unnecessarily complex in design —they may do the job, but they cost too much. Here's a good suggestion:

When you have an unusual or "tricky" spring application let Lewis Engineers work with you. They have a wealth of experience to offer in helping you find the simplest, lowest cost answer to your spring problem.

Lewis engineering experience is just one of the many "extras" you get when you make Lewis your source for springs. Whether it's help in spring design, packaging springs for efficient assembly line handling, or simply a case of getting top quality springs at competitive prices—call on Lewis . . . springs and wireforms are our business.

LEWIS SPRING & MANUFACTURING COMPANY
2656 W. North Avenue, Chicago 47, Illinois

Lewis PRECISION SPRINGS

The finest light springs and wireforms of every type and material



Coil in operation on floating-zone equipment for growing silicon crystals

outer-diameter rubber O rings for effective water sealing.

In the floating-zone technique for growing single crystals of silicon a necked quartz tube is employed, around the necked section of which a separate induction coil was formed.

Small triangular copper projecting ears are gripped by beryllium copper clips to develop pressure contact of the inner silver-plated conducting path. These clips slide on and off with finger pressure.

The heating characteristics of the split coil are equal to that of the original single-turn coils. The prin-

Twisting Insulated Wire

A MECHANICAL wire twister which can be operated by one worker is used in Martin's Baltimore plant. The device consists of a driving head powered by a slow-speed motor, a stationary head with rotating pins for attaching the wires and a comb for leading the wires as they are being twisted.

One end of each wire to be twisted



Extremely long life . . . with no maintenance problems. Thousands of voltage/amperage combinations available. Sizes from 11/16" square cells to giant 6" x 10" plates . . . Federal can provide a power rectifier for almost every type of industrial and military equipment.

Encapsulated Rectifiers



Maximum resistance to impact, acceleration, and vibration. Complete protection from harmful atmospheric conditions. Other electronic components may be encapsulated with rectifier to form a rugged, replaceable "potted" circuit.

High-Voltage Stacks

250 to 5000 volts/5 to 40 milliamps. Encased in paper, glass, Bakelite, nylon, or metal tubes. Simple fuse-clip mounting of ferrule terminal types. Also, hermetically-sealed types. Uses: CRT high-voltage supplies, photoflash, insulation testers, etc.

Why INDUSTRY and DEFENSE LOOK TO Federal FOR THE FINEST IN SELENIUM RECTIFIERS

High-Temperature Stacks



For maximum operating life at ambient temperatures up to 150° C. A full range of voltage/current combinations for medium and high temperatures. Ideal for aircraft and military equipment.

Selenium Contact Protectors



Extend contact life by over 1000 times. Used in inductive circuits to prevent erosion of switch contact surfaces . . . to suppress arcing and rf transients. Minimum effect on release time. Hermetic sealing meets JAN specs. For relays, electromagnets, and telephone systems.

Magnetic Amplifier Rectifiers

Selenium cells and stacks precisely manufactured, tested, and selected to assure a high degree of stability and very low reverse current. For use with saturable reactors, regulated DC power supplies, etc.

Pioneering Leadership

Federal is the *original* supplier of selenium rectifiers in the United States . . . leading the field in research, development and production.

Facilities and Service

Federal's facilities can handle the largest and most complex orders ...satisfy the rush requirements of customer production peaks. Every order—large or small—is processed through a skilled engineering staff.

Quality and Economy

Federal's modern fabrication methods, mass production, intensive quality control, and rigid testing assure a product of highest quality and greatest economy.

LET US KNOW your AC-to-DC conversion problems. For further information on Federal Industrial Rectifiers, call NUtley 2-3600, or write to Dept. F-813

Federal

A DIVISION OF IT&T

Federal Telephone and Radio Company

A Division of INTERNATIONAL TELEPHONE AND TELEGRAPH CORPORATION

COMPONENTS DIVISION • 100 KINGSLAND ROAD • CLIFTON, N. J.

In Canada: Standard Telephones and Cables Mfg. Co. (Canada) Ltd., Montreal, P. Q.
Export Distributors: International Standard Electric Corp., 67 Broad St., New York

Custom Iron Cores to your Specifications





Regardless of your requirement, we can supply a full line of custom iron cores in a variety of sizes and shapes for many applications . . . designed for your needs. Send us your problems.

RADIO CORES, INC.

has Everything in Iron Cores

***The Original* Engineered Economy* Iron Cores**

We originated the ways and means of providing ENGINEERED ECONOMY*IRON CORES at money saving prices and from stock. Over 14 types are available to cover most insert and threaded applications.

* TRADEMARK

Complete Engineering Service

We are the world's largest producers of iron cores because we employ the largest, most experienced and most efficient engineering department to enable us to design, produce and suggest iron cores which will do the best job for you.

Write today . . . tell us your problems . . . you'll be glad you did.

Radio Cores, Inc.

MEMBER mpa METAL POWDER ASSOCIATION

9540 Tulley Avenue Oak Lawn, Illinois



Operator holds motor switch in left hand and comb in right hand as she walks ahead of twists

is attached to the driving head. The other end is fed through the comb and attached to the pins on the stationary head. The operator starts the mechanism with a remote-control switch carried in one hand and leads the wires with the comb held in the other hand while walking ahead of the twists. At the end of the wire the motor is turned off and the twisted group removed from the machine.

The device has saved 75 percent of production costs over hand-twisting operations.

Self-Insulating Aluminum for Transformer Coils

DEVELOPMENT of a method of winding coils with aluminum foil or sheet which is insulated only with aluminum oxide has been announced by Reynolds Metals Co., Louisville, Ky. A special anodizing process provides excellent insulation, making possible the new system of winding coils for use in power transformers and solenoids.

The coils are wound spirally with the anodized aluminum foil or thin aluminum sheet instead of with conventional wire. Minimum winding radius recommended is ½ inch. Sheet thicknesses currently being considered are 0.008 inch and 0.015 inch, with 0.004 inch as a minimum for anodized insulation.

In addition to cost savings, the method offers important advantages in reduction of size, weight and resistance to heat.

Aluminum can now be used as a conductor with no increase in equipment size. Spiral winding of the coils subjects the conductor in-

ANOTHER FIRST BY Amperex®

High-Power RF Oscillator Triodes SPECIFICALLY DESIGNED as INDUSTRIAL POWER OSCILLATORS

for INDUCTION HEATERS
for DIELECTRIC HEATERS

Designed to end the practice of forcing communications-type oscillator tubes into heavy-duty industrial service, these new AMPEREX triodes are engineered from the ground up to the specific requirements of RF power oscillator circuitry in industrial induction and dielectric heating installations. Their performance is virtually independent of the wide variations in load impedance encountered in industrial applications.

Outstanding Electrical Characteristics—

- **low plate impedance**
- **low mu**
- **hi h transconductance**
  fo ..
  .. superior "loadability"
  ... high efficiency under all loaded conditions
  ... greater power into hard-to-heat loads
  ... simpler circuitry eliminating special grid-current regulation devices

Outstanding Physical Characteristics—

- **thoriated tungsten filament ..**
  ... for maximum life
- **extra-heavy-wall copper anode ...**
  ... to absorb short-term overloads of double the maximum ratings
- **platinum-clad grid ...**
  ... for stable grid-current operation
- **coaxial grid construction** and **powdered-glass stem ...**
  ... for maximum mechanical strength
- **permanently bonded, flexible, heat-dissipating filament leads**
  ... to eliminate failures due to contact resistance at terminals

FOR OPTIMUM PERFORMANCE WITH FLUCTUATING LOADS



Type 6756
WATER-COOLED
20 kw dissipation
$435.00
Grid Connector included
Accessory: Water Jacket (Type S-15096)

Type 6757
FORCED-AIR-COOLED
15 kw plate dissipation
$535.00
Grid Connector included
($75.00 allowance for return of radiator with order)



TYPICAL OPERATING CONDITIONS
TYPES 6756 and 6757

Oscillator, Class C — Three-Phase, Full-Wave Supply (Per Tube)

	CCS Full Load	CCS 2A Load	CCS No Load
DC Plate Voltage	12000	12000	12000 volts DC
DC Plate Current	3.5	2.0	0.430 amps DC
DC Grid Voltage	—1220	—1380	—1710 volts DC
RF Grid Voltage	2050	2030	_____ volts
DC Grid Current *	**0.210**	**0.238**	**0.295 amps DC**
Grid Resistor	5.8	5.8	5.8 kilohms
Plate Input	42.0	24.0	5.16 kw
Plate Dissipation	11.25	4.9	_____ kw
Efficiency	73.30	79.4	_____ percent
Load Impedance	1755	3120	_____ ohms
Plate Power Output	30.75	19.1	_____ kw

*Note flat grid current characteristics, no load to full load, without external grid stabilization circuitry

Detailed data sheets and application information available on request.

***Retube with* Amperex**

AMPEREX

Available At Your Local Parts Distributor

AMPEREX ELECTRONIC CORP.
230 Duffy Ave., Hicksville, Long Island, N. Y.

In Canada: Rogers Majestic Electronics Ltd.
11-19 Brentcliffe Road, Leaside (Toronto) 17

20
TO
200 D.P.
SEND YOUR PRINTS FOR QUOTATION



SPURS • HELICALS • WORM AND WORM GEARS • STRAIGHT BEVELS
LEAD SCREWS • RATCHETS • CLUSTER GEARS • RACKS • INTERNALS • ODD SHAPES

THE *Finest* IN GEARS

Beaver Gear Works Inc.
1021 PARMELE STREET, ROCKFORD, ILLINOIS

unique in design — rugged in construction

GREEN
PANTOGRAPH
ENGRAVERS

THE NEW
HEAVY-DUTY MODEL D-2

THE FAMOUS
MODEL 106

The three-dimensional bench Model 106 cuts costs — engraves, routs, models and profiles, giving you expert results even by unskilled workers.

The Model D-2 heavy-duty two dimensional Pantograph is a precision machine with a multitude of new features. Open on three sides, it permits complete freedom for engraving, milling, profiling large panels (up to 30" in diameter) or bulky pieces. Single, micrometer adjustment controls vertical depth of cut, automatically adjusting copy table with pantograph. Range of reduction ratios from 2-to-1 to infinity! Vertical range over 10 inches!

For complete information, write to

GREEN INSTRUMENT COMPANY
363A Putnam Ave. Cambridge, Mass.

sulation to turn voltage only, and accordingly normal layer insulation can be eliminated. This saving in space, coupled with that derived from the use of the very thin anodic films for insulation and the lack of voids in the completed windings, accounts for the compactness of the coils.

Further space savings are afforded by the excellent heat transfer characteristics of the coils. Since every turn of the coil is exposed to the outside, no hot spots are encountered and cooling ducts can be eliminated.

The anodic coating, consisting of aluminum oxide—a chemically inert material and an excellent electrical insulator—reduces the possibility of a coil's burning out, since the melting point of the anodic coating is higher than that of aluminum itself.

Appreciable weight savings also are afforded by the new aluminum coils. In most cases, the coil weight is approximately one-half that of a comparable copper unit.

Basing Pencil Triodes with Epoxy Resin

By David Lichtman
and
Byron G. Wells
Applied Physics Staff
Airborne Instruments Laboratory
Mineola, N. Y.

Flexible wire filament leads on various uhf triode tubes were found to break easily and required soldering or elaborate terminations in order to connect to them. Leaving the leads too long resulted in the possibility of short circuits; on the other hand, clipping them short caused difficulty in making connections. For these reasons it was decided that a means of basing these tubes be devised.

▶ **Use of Sleeving as Mold**—The first attempts consisted merely of



Example of unbased tube

When you can buy

this



Relay Headers Ready for Assembly

This newly developed Relay Header Assembly introduces a new high in simplified production techniques by eliminating these costly steps: buying or producing square cover plates with studs attached; stamping the hole in the cover plate for the hermetically sealed header; attaching and shaping pigtails; soldering or brazing the mounting bracket to the cover plate; mounting the seal in the cover plate.

To the manufacturer, this means a profit increase . . . *to the engineer,* a new horizon in design simplification . . . *to the purchasing agent,* a reduction of orders placed and attendant paper work . . . *to production control,* a reduction of parts inventoried and stocked.

Whatever the problem in mechanical assemblies, whether it be complex Relay Headers, Multi-Headers specially shaped to fit enclosures or cans, or Color-Coded Terminal Plates with studs attached—you'll find the most economical solution to your assembly problem at HERMETIC.

Write for engineering assistance, data, prices and your FREE copy of "Encyclopedia Hermetica"—a handy, desk-top reference guide.

Hermetic Seal Products Company

31 South 6th Street, Newark 7, New Jersey

California Associate: Glass-Solder Engineering, Pasadena

FIRST AND FOREMOST IN MINIATURIZATION

Here is the most compact centrifugal blower unit made . . . EAD's high-velocity subminiature centrifugal blower is only 2⅞" long, weighs only 6 ounces, yet it can move 13 cfm of air at a velocity of 3,000 feet per minute—and the volume holds up at high static pressures. It is driven by EAD's new one-inch diameter motor. The metal blower housing can be rotated to any position desired for maximum efficiency in cooling radar equipment, amplifier units, transmitter equipment, oscillators, and in other applications where high temperatures in confined areas demand miniaturized blowers with the highest possible performance characteristics. EAD's subminiature blower units meet all applicable MIL specification, and low temperature rise makes them suitable for high altitude and high ambient temperature operation.

CFM	13 @ 0" SP 10 @ 1.0" SP	7 @ 0" SP 5 @ .2" SP
MAX. SP.	2.5	0.6
RPM	20,000	11,000
AMPS	0.1	0.06
WATTS	10.0	6.0
CAPACITOR Mfd/Volts	0.25/220	0.1/220
WEIGHT (OUNCES)	6	6
MODEL NO.	B2GIQ-C	B2HIY-C

Modifications of standard models or completely new designs can be engineered to meet your special cooling needs. Write for complete information.

EASTERN AIR DEVICES, INC.

SOLVING SPECIAL PROBLEMS IS ROUTINE AT EAD



387 CENTRAL AVENUE • DOVER, NEW HAMPSHIRE

slipping a piece of Teflon sleeving over the end of the tube and filling the sleeving to the proper level with Araldite No. 502 (CIBA Co.). After the Araldite had set, the Teflon sleeving was removed, leaving a plastic base with the two filament leads projecting beyond it. Clipping the leads to a suitable length and tinning added to their rigidity.

Better rigidity and mechanical strength were obtained when a pair of specially constructed tube pins were spotwelded to the shortened filament leads before basing. The heavier pins were stronger and looked better.

►**Use of Brass Mold**—When it was decided that the overall appearance and strength would be improved by the addition of a shoulder on the base, a new mold was designed. The new mold, which incorporated the shoulder design, had to be made of



Based tube, with matching socket alongside

a flexible material that could be slipped over the base once the base had hardened. The mold material decided upon was Arcoflex-B (Applied Resins Co.). A brass mold was prepared to cast the Arcoflex mold.

It was found that careful handling of the Arcoflex was required; furthermore, to secure a clear, bubble-free mold, the Arcoflex had to be subjected to partial vacuum before it was poured.

►**Pouring Precautions**—In pouring the liquid from the can to a suitable container for pumping, care must be taken to pour it down one side of the container to avoid trapping any air. After pumping, the same care should be exercised when pouring the liquid into the mold. A slow, careful curing process will result in a mold that can be used again and again.

The new Arcoflex mold was set in place over the filament end of the

Electro-Snap Switches Can Be Adapted to Almost Any Job — Quickly, Easily, Economically

Just choose the Electro-Snap Basic Switch that meets your electrical requirements, add the proper actuator — and presto! — you have a tailor-made precision switch that exactly fits your application. Electro-Snap makes a wide variety of stock actuators to fit almost any requirement. And our engineering department is at your service if a standard combination "won't fill the bill."

For prompt action on your switching problems, send us a brief description and rough sketch of the switch you need.

Switching Problem?



SUB-MINIATURE SWITCHES TYPE E-4

S.P.D.T., 1 circuit; 5 amps, 125/250 v. AC Operating force 150 grams max. Exceptionally vibration-resistant. Special model E4-7 is stabilized for — 65° to + 350° F. operation.

Push Button Actuator

Toggle Actuator (Momentary or Constant Contact)

Double Toggle Actuator

Roller Leaf Actuator

Leaf Actuator

Extension Leaf Actuator


Ganged Interlock

TYPE S SWITCHES Series S1



S.P.D.T., 2 circuit; 10 amps, 125/250 v. AC/ 30 v. DC. Ind. Screw or solder terminals on ends or one side of switch. Also available with reset button at bottom of switch or in Type S-100 Make-Before-Break Series where switch completes a new circuit before interrupting old one.

Write for Data Sheet STN-1


Roller Lever Actuator


Roller Actuator

Push Button Actuators (Various button sizes available)

Toggle Actuator (momentary or constant contact)


Extension Leaf Actuator

Special Push Button Actuator designed for fire control system



DOUBLE-POLE SIMULTANEOUS ACTION TYPE D-8

D.P.D.T., 4 Circuit
15 amps, 125/250 v. AC.
10 amps, 30 v. DC Ind.
Eight terminals and four separate circuits which operate simultaneously permit switch to reverse 3-phase motors, replace expensive relays, etc.

Write for Data Sheet DN-1

Roller Leaf Actuator


Roller Lever Actuator

Leaf Actuator

Extension Leaf Actuator


Push Button Actuators (Various button sizes available)

HERMETICALLY-SEALED DOUBLE-POLE SWITCH

Write for Data Sheet HJN-1

Type J2-4

Toggle Actuator for J2-4

D.P.D.T., 4 circuit 10 amps, 125/250 v. AC/30 v. DC.

ELECTRO-SNAP SWITCH & MFG. CO. 4220 West Lake Street, Chicago 24, Illinois

MANUFACTURERS OF A COMPLETE LINE OF PRECISION SWITCHES FOR INDUSTRY AND AVIATION

ELECTRO SNAP

FOR COMPLEX AUDIO FILTERS LIKE THIS CALL ON



CHICAGO STANDARD

• Because Chicago Standard design and production engineers have built so many audio filters . . . of all types . . . they can quickly solve your filter problem with a unit **built to meet your exact specifications.**

Chicago Audio Filters are known for their sharp discrimination, low loss, maximum output and unusually compact construction. They are effectively shielded in drawn steel cases, hermetically sealed, or with the famous Chicago "Sealed-in-Steel" construction.

Write Today outlining the specifications you require. Your inquiry will receive prompt attention.

a typical unit is
LOW PASS FILTER LPF-2



A *stock* unit for aircraft, amateur, police and other voice communication equipment.
Cut-off frequency, 3000 cps;
Input impedance, 50,000 ohms;
Output impedance, 50,000 ohms;
Insertion loss 0.8 db.;
Maximum input signal, 10 volts RMS;
Dimensions, 2⅛" x 2¼" x 1⅜"
Weight, 6½ oz.

CHICAGO STANDARD TRANSFORMER CORPORATION
ADDISON & ELSTON • CHICAGO 18, ILLINOIS

Export Sales:
Roburn Agencies, Inc.
431 Greenwich St.
New York 13, N. Y.

Tube in socket

tube. The tube was then mounted, anode down. The Araldite was weighed out with 1-percent black coloring (No. E-340) and allowed to set at room temperature until all trapped air bubbles worked their way to the surface. Then, 10-percent hardener (HN-951) was added and carefully stirred into the Araldite mixture, in order not to induce further bubbling.

The Araldite mixture was then poured carefully down one side of the mold (again, to avoid trapping air); when the desired level was reached, the tube and mold were baked at 70 C for one-half hour. The unit was then removed from the oven and allowed to cool to room temperature. Gentle probing with a small scribe helped to determine the state of hardness.

The Arcoflex mold was gently separated from the Araldite by stretching it away with the fingers. When the mold was completely free from the Araldite, it was slid carefully off the tube and the rough edge was trimmed off the tube with a sharp razor blade. The hollow that remained was then filled with a few drops of the Araldite mixture, leaving a professional appearance.

►**Socket Molding Technique**—Having manufactured the tube bases, it was necessary to make a socket to match.

Special small pins, with a turret-type soldering connection on one end and spring contacts on the other, were made up. These were silver-plated and rhodium-flashed.

A mold was constructed from Teflon block and aligning pins were mounted in one part to support and align the other. Lead wires of No. 20 plastic-covered wire were soldered to the pins before they were set in the mold and two small pieces of Teflon tubing were set over the contact ends to keep the pins free from the surrounding Araldite. The entire mold was greased with a thin film of Dow Corning No. 7



It's a question that's been asked over and over again, and usually we've answered at once . . . yes, Ampli-Film *can*. Sometimes, however, we couldn't answer until we made tests. Then invariably we found that Ampli-Film *could* perform under the specified conditions. We learned, too, that Ampli-Film has more applications than we ever imagined!

"can Ampli-FILM® do this?"

That's why we say

Ampli-FILM IS THE ALL-PURPOSE DIELECTRIC

Ampli-Film is insoluble, incompressible and inert. That is, it is not affected by acids or organic solvents . . . undergoes no distortion under high temperatures and pressures . . . can readily be bonded by adhesives . . . is free from pinholes and flaws . . . is easy to handle and fabricate.

Write for the Ampli-Film Handbook for further details on the Dielectric and how it is used in A-MP'S Capitron® Capacitors, Pulse Forming Networks, Power Packs and Pulse System Packages.

AIRCRAFT-MARINE PRODUCTS, INC.

chemicals and dielectrics division

155 Park Street, Elizabethtown, Pa.

A-MP Trademark

A-MP of Canada, Ltd., Toronto, Canada A-MP—Holland N.V. 's-Hertogenbosch, Holland

Aircraft-Marine Products (G.B.) Ltd., London, England Societe A-MP de France, Courbevoie, Seine, France



Shown with Cover off — approximately ⅓ Size

ALTITUDE POTENTIOMETER

THE TRANS-SONICS® Type 1067 Pressure Operated Potentiometer provides a linear voltage ratio versus altitude output. Input impedance is 10,000 ohms. Maximum voltages up to 100 volts can be obtained so this Altitude Potentiometer can be used without amplifiers in applications such as:

a) Varying servo loop gain as a function of altitude.
b) Modulating the subcarrier oscillator of telemetering systems.
c) Recording and indicating altitude remotely.

Accuracy and interchangeability including effects of nonlinearity, hysteresis, stiction, and friction are within a band ±0.01 VR of the nominal line. Voltage Ratio is 0.55 at −400 ft. and varies linearly with altitude to 1.0 at 50,000 ft. This *linear-with-altitude* relationship is obtained from the linear-with-pressure mechanism by shaping the electrical output with additional resistors across tapped sections of the potentiometer winding.

The Type 1067 Pressure Transmitter is an example of an instrument which TRANS-SONICS, INC. designed for a specific application and produces in quantity and on schedule. Similar instruments, but having a *linear-with-pressure* voltage ratio output, are offered for applications such as telemetering, recording, and experimental development. These units have potentiometer coils with multiple taps connected through a convenient, accessible terminal board to a connector.

Write for Multi-Tap Potentiometer Bulletin

"For Transducers See Trans-Sonics"

Trans-Sonics, Inc.

5 FOREST STREET • BEDFORD, MASSACHUSETTS

silicone grease. This permitted removing the base easily when the Araldite had set.

In using this mold, additional precautions must be taken to avoid the formation of air bubbles. While mixing the Araldite, the mold was preheated at 70 C for about one-half hour. The Araldite was then poured in slowly down one side of the mold to avoid air pockets.

After the unit was baked at 70 C for one-half hour, it was allowed to cool to room temperature. The mounting screws were removed from the mold, and the upper portion of the mold was lifted away. By applying downward pressure against a hard surface, the aligning pins exerted a similar pressure on the socket pins, causing the tube base to rise out of the mold. The aligning pins and the small Teflon sleeves were then removed and the remaining kerf (or flash) was removed with a sharp razor blade.

Because of the design of the mold, the pins are recessed into the socket. Thus, when the tube is plugged into its socket, there is no exposed metal and complete insulation as well as handsome appearance are achieved. Tubes having these bases have been used at frequencies up to 1,000 mc with no deterioration of operation.

Aluminum Hole-Filler

A PUTTY consisting of approximately 80-percent powdered aluminum and 20-percent plastic, known as Devcon F, can be used for filling undesired holes in aluminum and steel castings, as well as to build up worn sections.

Adherence to aluminum, steel, bronze, brass and cast iron is excellent. It will bond to a flat surface and can be machined to a feather edge. It is not necessary to undercut the metal or treat it in any special way. No volatile solvents or thinners are used, hence there is no shrinking or pulling away during the 2-hour hardening time in air.

The hardener furnished with the material is simply added and mixed with a screwdriver or a nail. The manufacturer is Chemical Development Corp., Danvers, Mass.



with all these measurements

AIL PRECISION TEST RECEIVER

offers complete versatility

How often have you put together a breadboard setup of a pre-amplifier, post-amplifier, attenuator, power supply, output indicator, bias control and the rest of the haywire needed to make the multitude of measurements which require an intermediate frequency receiver?

AIL's engineers did it often enough to force the design of a single package for their own use. As a result, the type 130 Receiver is an engineer's design for engineers' use.

The AIL Type 130 Precision Test Receiver is a versatile instrument combining a high-gain, low-noise-figure i-f receiver and a secondary standard of attenuation. It is designed to operate from the i-f output of a wide variety of standard microwave mixers. In combination with such mixers and a suitable local oscillator, the Receiver becomes a sensitive detector of microwave energy. It can be used wherever accurate measurements of the differences of r-f or i-f power levels are required.

The complete AIL Type 130 Precision Test Receiver is priced at $1,350.00. The standard model is available for 30MC use. Prices on models operating at other frequencies will be provided on request. F.O.B. Mineola, N. Y.

SEND FOR DESCRIPTIVE LITERATURE

AIRBORNE INSTRUMENTS LABORATORY
INC
160 OLD COUNTRY ROAD, MINEOLA, L. I., N. Y.

Want more information? Use post card on last page.

New Products

Edited by WILLIAM P. O'BRIEN

74 New Products and 70 Manufacturers' Bulletins Are Reviewed . . . Control, Testing and Measuring Equipment Described and Illustrated . . . Recent Tubes and Components Are Covered

TRACE CRO

presents multichannel data

SOUTHWESTERN INDUSTRIAL ELECTRONICS CO., 2831 Post Oak Rd., Houston, Texas. Model MO24 trace cro presents multichannel information on a 21-in. picture tube for direct viewing.



▶ **Method of Presentation**—Information is presented by intensity modulation of a 5,000-cps raster. The raster method results in frequency response useful to 500 cps on all 24 traces with only a single electron gun. Each trace may cross over other traces, and is limited in amplitude only by the size of the crt. A position control is provided for each trace. A special window control permits a portion of the sweep to be accelerated for careful examination.

▶ **Auxiliary Unit**—The event preselector puts 0.1 and 0.01-sec timing lines over the scope, and triggers the sweep after an adjustable delay period following the initial pulse. This feature is especially useful when the MO is used as a monitor for 24-channel magnetic tape recordings, such as those used in seismograph work.

▶ **Prices**—The oscilloscope, complete with power supply, is $6,000. The event preselector sells for $1,500.

DELAY LINES

are hermetically sealed

PCA ELECTRONICS INC., 2180 Colorado Ave., Santa Monica, Calif., has released a complete range of standard single-stick hermetically sealed delay lines. The units are in round, 0.4 in. o-d, brass tubing with capacitor end-seals. They are commonly mounted in a fuse-clip or with a cable-clamp.

▶ **Designs**—Three general designs are available in each impedance level and delay time. One design emphasizes maximum delay per cu in., with a fair rise time. The second combines moderate delay per cu in. with good rise time. The third emphasizes fast rise time, with a low delay per cu in.

All designs are miniaturized and are commonly used for delaying video pulses, pulse shaping, gating, storage of information in computers, time standards in count-down circuits, synchronization of waveforms, time-modulation, generation of waveforms, and high-impedance connecting cables.

Prices range from $10 each to $7.10 each, depending on quantity ordered.

DIGITAL UNIT

interval timer and counter

RANSOM RESEARCH, P. O. Box 382, San Pedro, Calif. The functions of several digital instruments have been combined into one portable instrument in the Digitac model 1500 digital interval timer and counter.

The instrument contains 10 plug-in decade counters arranged in two banks of five each. It will count up to 10 billion at a rate not exceeding 100,000 per sec. Timing capacity is 10 μsec to 100,000 sec and timing increments may be preset



NEW COLOR TV TUBE

Does the work of 1½ tubes

—combines phase splitting with other color circuit functions

Here's a Sylvania tube development that can make an immediate improvement in your color TV chassis tube complement and layout. The 6BJ8 has two diodes and a low mu triode with three separate cathodes.



Thus, with a single miniature package, you can achieve phase splitting plus horizontal oscillation, or any other low mu triode function. Prior to the development of the 6BJ8 the need for independent cathodes in phase splitting called for at least a double diode with separate cathodes and half a double triode to accomplish this same work.

In some circuits the diodes may be used for phase comparison. For applications where two diodes and a high mu triode are needed Sylvania offers the type 6BN8 which also has the three-cathode construction of the type 6BJ8. The versatility of these tubes can introduce improvements in new black and white TV designs as well as color.

Sylvania can supply all your color TV tube needs with these important types.

3A2.....**miniature half-wave rectifier**
3A3.....**T-9 half-wave rectifier**
5V3.....**full wave vacuum rectifier**
6BK4.....**sharp cutoff beam triode**
6CL5.....**T-12 Beam power amplifier**
6CL6.....**miniature pentode video amplifier**

Write for complete details

SYLVANIA®

SYLVANIA ELECTRIC PRODUCTS INC.
1740 Broadway, New York 19, N. Y.
In Canada: Sylvania Electric (Canada) Ltd.
University Tower Bldg., Montreal

LIGHTING • RADIO • ELECTRONICS • TELEVISION • ATOMIC ENERGY

Want more information? Use post card on last page.

at any value in 10 μsec steps within that range.

▶ **Uses**—Model 1500 may be used as a lab instrument to measure time, frequency or events; as a counting or measuring device in process control and other types of automation; as an integral part of a computer; and as a test instrument for maintenance of telephone carrier and other communications and electronic equipment.

Weight is 25 lb, and the unit sells for $795.

GAGE CONTROLS

employ no bridge circuits

VACUUM ELECTRONIC ENGINEERING CO., 86 Denton Ave., New Hyde Park, N. Y. Types RG-2 and RG-3 ionization gage controls measure pressures from 1 micron to 2×10^{-10} mm Hg. Performance is due mainly to an ion current amplifier, employing 100 percent negative feedback, similar to those used in electrometer amplifiers. Amplification is independent of variations in tube and component characteristics and as a result, periodic adjustment of circuit calibration is entirely unnecessary. Constant checking of



zero is also eliminated. The feedback insures linearity through the entire pressure range.

▶ **Prices**—Catalog RG2-R gage control (smallest reading 2×10^{-9} mm Hg) sells for $397; and the RG21-R (smallest reading 2×10^{-10} mm Hg), $447. These prices are for panel units suitable for mounting in standard racks. The same units in a cabinet are priced at $28 more. The RG3-R and RG-31-R circuits are similar to the RG2-R and RG21-R, respectively, but are provided with a two-station thermocouple gage control, with separate output meter. Prices for these two units are $502 and $552. Again, cabinets are $28 extra.

PULSE TRANSFORMERS

with ferrite cup cores



TECHNITROL ENGINEERING CO., 2751 N. Fourth St., Philadelphia 33, Pa. The new M series of pulse transformers measure only 0.44 in. in diameter by 0.56 in. long. They can be wound to cover a range of pulse widths from 0.05 μsec to 2.0 μsec. The transformers weigh only 4 grams and are completely encapsulated for protection.

Specially designed ferrite cup cores make it possible to wind transformers of this size covering a wide range of applications in transistor and tube circuits.

▶ **Prices**—For three winding and two winding types prices are $8.50 and $8 each, respectively, for quantities of 1 to 3; $7.50 and $7.15 each for lots of 4 to 10; $6.75 and $5.85 each for 11 to 50; and $6.25 and $5.45 each for 51 to 100.

CAMERA SWITCHER

for industrial tv systems

GENERAL PRECISION LABORATORY, INC., 63 Bedford Rd., Pleasantville, N. Y. Model PD-133 camera switching unit permits operation of four PD-150 tv cameras from a single camera control unit. Switching units may be cascaded to provide pushbutton selection of any number of cameras. Price of the PD-133 is $1,430.

▶ **Automatic Sequential Switching**—With the addition of a motor driven timer or a series of thermal activated relays, it is possible to provide automatic sequential switching of any number of GPL cameras thus providing completely automatic remote surveillance of an automated production line.



Preset control of gain, blanking, beam, target and focus for each camera, plus current regulation of electrical focus and camera heater circuits, makes reliable pushbutton or automatic sequential switching of a multiple camera system possible.

CAPACITORS

miniature and subminiature

CAPCON, INC., 25 Willett St., New York 2, N. Y., is now producing a complete line of miniature and subminiature capacitors of all types. They are ideal for applications

For ACCURATE HIGH SPEED SWITCHING..

Specify

ELECTRO TEC

miniature ultra-low torque Precision Selector Switch

- Withstands Shock and Vibration
- Offers High Accuracy Measurement
- Operates at High Speeds

This new Electro Tec Precision Selector Switch is ideal where miniature size, low friction torque, high accuracy, and low electrical noise at high speeds are requirements. Simplified circuits and long service life recommend it for a wide variety of uses including sampling, pulse generation for precision measurement, telemetering and strain gage applications, in aircraft, missiles, servos, computors, etc. Switch design incorporates many exclusive features that have gained industry-wide acclaim for Electro Tec precision slip rings, commutators and brush blocks.



CALL OR WRITE FOR ILLUSTRATED BROCHURE

8 or 10 position switches in standard size 10 synchro housings are available for immediate delivery; other circuit combinations supplied to specifications.



ACTUAL SIZE



Electro Tec Corp.

SO. HACKENSACK
NEW JERSEY
Tel.: HUbbard 7-4940



Corning Fixed Capacitors are alternate layers of conductor and dielectric sealed under heat and pressure in a glass case of same composition as the dielectric. Result is a monolithic structure. Shown actual size are four standard pigtail types.

CORNING FIXED GLASS CAPACITORS

. . . stable, rugged, miniaturized

Corning Fixed Capacitors assure excellent moisture resistance, high temperature operation, and extremely high reliability. Now in mass production, these capacitors are available at attractive prices.

Check these features of Corning Capacitors—

The Dielectric—A homogeneous, scientifically produced continuous ribbon of glass; no foreign inclusions, no cracks, no imperfections.

Construction—Only three simple elements: (1) The glass dielectric and case of identical composition; (2) active metal foil plates; (3) the pigtail wire leads—bright, clean and ready to solder. No potting materials, no impregnants, no mechanical slips, no plastic cases. Corning Fixed Capacitors are *fused* together into a solid, strong, monolithic block. To affect or change their excellent electrical characteristics, you would have to mechanically destroy the capacitor.

Electrical Characteristics—(A) Temperature coefficient is $+140 \pm 25$ ppm/°C. over the range of -55°C. to $+85$°C. Variation of TC at any given temperature between individual units is less than 15 ppm. The TC remains the same after repeated cycling. The capacitance drift is less than 0.1% and usually less than the error of measurement. This means reliable, predictable circuit control. (B) Dissipation factor is not more than 0.1% at 1 kilocycle.

Operating Temperature—Standard temperature range of -55°C. to $+85$°C. can be extended to 150°C. with derating. Units available to Military Specification MIL-C-11272A.

Miniaturization—The illustration above shows four standard pigtail types of Corning Fixed Capacitors actual full size. We can pack a lot of capacitance into a small space. The CY10, for example, measuring 5/16"x9/64"x3/64" is available up to 240 uuf at 300VDCW. The CY30 is available up to .01 uf at 300VDCW.

Tolerances—The standard tolerance for capacitance is ±10%. Units are also available in 5, 2 and 1% tolerance.

We would like to send you additional information, prices, and samples.

We invite discussion of variations you might need for custom applications, and we manufacture many special types of capacitors. Write, wire, or phone us.

Other Corning Capacitors

Medium Power, Transmitting
Subminiature Tab Lead
High Capacitance, Canned
Special Combinations

CORNING GLASS WORKS • CORNING, N. Y.

Electronic Components Department • 94-1 Crystal Street

Corning means research in Glass

where space is severely limited.

▶ **Available**—The tiniest capacitor most suitable for any given application can be supplied by the company. This includes the following types: paper, metallized paper, electrolytic, mica, ceramic, and all the film dielectric capacitors such as Mylar, Teflon and polystyrene.

The capacitors are available in all capacitances from 0.1 $\mu\mu$f to 500 μf, and in capacitance tolerances from 0.1 percent to 20 percent. Units are furnished in voltages from 3 v to 1,000 v. Operating temperature ranges are available as specified, from —65 C to +200 C, without derating.

Units can be supplied cased or uncased, flat or round. Leads can be positioned radially, axially, for plug-in or in any other required position.

Prices are determined by quantities ordered of a particular rating and tolerance required.



PARABOLIC ANTENNAS with multi-element grid

MARK PRODUCTS CO., 6412 W. Lincoln Ave., Morton Grove, Ill., announces a new series of parabolic antennas for the 890-960 mc and 450-470 mc regions. At 960 mc three models are available: P-942, P-972 and P-9120 are 42 in., 6 ft and 10 ft in diameter and produce gains of 15, 20 and 25 db respectively over a dipole. At 460 mc two units are available: P-472 and P-4120 are 6 ft and 10 ft in dia-

501: TIME-RATE INDICATOR
Frequency Measurements 0 cps to 10 mc.
Period Measurements 10μ sec to 28,000 hours.
Recorder Output; Timing Pulse Output; Heterodyne Outputs.

502: PREDETERMINED COUNTER
Input Sensitivity
AC: 120 millivolts rms.
DC: 3.5 volts.
Predetermined Pulse Output.
Pulse Train Output.
100 kc Oscillator Output.



503: DIGITAL MULTITESTER
DC Ranges: ±.01 to ±1000 v.
Relative Accuracy: ±0.15% of full scale.
AC Ranges: [illegible] to 1000 VRMS.
Relative Accuracy: ±1% of full scale.
Resistance Ranges: 10 ohms to 10 MEG.
Relative Accuracy: ±.2% of full scale.
Measurement Rate: 20 per second.

504: DIGITAL RECORDER
Decimal Digits per Line: Seven.
Printing Rate: Variable from approximately 4 to 60 per minute, or manual.
Input Requirements: Normally wired to accept code voltage outputs from LFE scalers in the following order:

Here are four late model precision instruments from LFE to help you solve your problems in research, production, test and development.

The Model 501 **Time-Rate Indicator,** a 10 megacycle digital frequency meter. Also measures time interval periods, ratio and totals at the turn of a switch. The Model 502 **Predetermined Counter** counts to a predetermined number of pulse and gives a control signal output. Useful for automatic packaging, control of machine tools, generation of precision delays and so forth. The Model 503 **Digital Multitester,** the challenging digital meter which measures ac and dc voltages and resistances to new accuracies. The Model 504 **Digital Recorder,** designed for use with Models 501 and 503 and LFE plug-in scalers, records readings continuously — up to 1 reading per second.

For more specifications and details about each of these four outstanding performers, write for our free informative bulletins and the name of the LFE Engineering Representative nearest you.

LABORATORY FOR ELECTRONICS, INC.
75 PITTS STREET • BOSTON 14, MASSACHUSETTS

FOR EXPORT SALES CONTACT ANDREW S. SZUCS, INC., 50 BROAD ST., NEW YORK 4, N.Y.

Want more information? Use post card on last page.

Sierra 166 Carrier Systems Impedance Meter

New Sierra Model 166 is specifically designed for measurements on high noise level power and telephone lines and circuits where conventional instruments are ineffective. Covering all frequencies from 30 kc to 300 kc, it can be used with signal sources ranging in output from 1/6 to 1600 voltamperes.

Model 166 is ideal for determining impedance vs. frequency characteristics, and its wide impedance range permits use (through series coupling capacitors) on "hot" lines. On low noise level laboratory circuits, the instrument measures impedance using a standard vacuum tube voltmeter as a detector. Under less ideal conditions, impedance may be measured conveniently by using a frequency selective voltmeter (such as Sierra Models 101B, 104 or 108) as the detector.

Brief specifications of new Model 166 are given here. Please write for complete data on Impedance Meter and Sierra Carrier Frequency Selective Voltmeters.

TENTATIVE SPECIFICATIONS — MODEL 166

Frequency Range:	30 kc to 300 kc
Inductive Reactance Range, X_L:	30 to 3000 ohms at 100 kc
At a given frequency, f_{kc}:	$X_L = \frac{(\text{X dial reading})\ f_{kc}}{100}$
Capacitive Reactance Range, X_C:	30 to 3000 ohms at 100 kc
At a given frequency, f_{kc}:	$X_C = \frac{100\ (\text{X dial reading})}{f_{kc}}$
Resistance Range, R:	0 to 1000 ohms
Accuracy:	±5% on impedance magnitude and phase angle
Maximum Signal Input:	1600 voltamperes, not exceeding 400 volts, or 4 amperes, whichever is larger.
Dimensions:	11⅛ inches wide, 8⅞ inches high and 8¼ inches deep, over all
Weight:	Approximately 8 lbs.

Specifications subject to change without notice.

Sierra Electronic Corporation
San Carlos 2, California, U. S. A.
Sales representative in major cities

sierra

Manufacturers of Carrier Frequency Voltmeters, Wave Analyzers, Line Fault Analyzers, Directional Couplers, Wideband RF Transformers, Custom Radio Transmitters, VHF-UHF Detectors, Variable Impedance Calibrated RF Loads, Reflection Coefficient Meters, Bi-Directional Power Monitors, Television Waveform Monitors, Color Television Picture Monitors, Impedance Meters. 3265

meter and produce gains of 15 and 20 db respectively over a dipole.

▶ **Construction**—The multielement grid construction affords many economies in production allowing for lower costs especially in the larger sizes as compared with spun or mesh type reflectors. The low weight and wind loading allow for great savings in tower and installation costs as well as the possibility of utilization of these parabolas on existing towers where wind loading caused by conventional spun parabolas would be prohibitive. Adjustable mounts are also available to allow for tilt in elevation where necessary.



SMALL TRANSISTOR
is *pnp* fused junction type

RAYTHEON MFG. CO., 55 Chapel St., Newton 58, Mass., announces a new *pnp* fused junction germanium transistor for push-pull class B audio output applications. The 2N138 is sold only in pairs matched for optimum output and minimum distortion.

In a typical class B application using a 4.25-v supply the average power output is approximately 50 mw with a power gain of 30 db. The small physical dimensions are identical to those of the 2N130 series of miniature transistors.

ALL-PURPOSE RELAY
with wide application

OHMITE MFG. CO., 3681 Howard St., Skokie, Ill., has announced the Amrecon model DOS relay. Specially designed to meet the rigorous standards for aircraft relays, model DOS meets industrial needs for a compact, lightweight relay capable of handling power loads usually

DO YOU HAVE A PROBLEM IN

ULTRASONICS?

Let us assist you in its solution. A fully equipped experimental laboratory and elaborate test facilities, staffed by experts, are at your service. Pilot models can be supplied assembled to specifications.

Send your requirements to

FREED

TRANSFORMER CO., INC.

1718 Weirfield Street
Brooklyn (Ridgewood) 27, New York

Ultrasonic output transformers combining high quality large power capacity (up to 2 KVA), and small sizes are available.

Ultrasonic amplifiers and oscillator-amplifier combinations can be ordered in kits from stock.

Send for complete Transformer and Laboratory Test Instrument Catalogs.

FREED TRANSFORMER CO., INC.
1722 Weirfield Street
Brooklyn (Ridgewood) 27, N.Y.



A copy of this quick-reading, 8-page booklet is yours for the asking. It contains many facts on the benefits derived from your business paper and tips on how to read more profitably. Write for the "WHY and HOW booklet."

• • • • • • • • • • • • • • •

McGraw-Hill Publishing Company, Room 2710, 330 West 42nd St., New York 36, N. Y.

POWER AT *PRECISELY*

THE FREQUENCY YOU REQUIRE

Model 1435
2 KVA Unit

Any *CML* Electronic Generator is available with a total of up to four *precision* American Time Products tuning fork oscillators in the 50-6000 cps range.

The use of these precision oscillators gives a frequency accuracy and stability of *1* part in 50,000 *entirely independent* of line voltage or frequency.

CML Electronic Generators are available in single and three phase units in power output ratings from 50 VA to 80 KVA. Write for Catalogue "N".

COMMUNICATION MEASUREMENTS LABORATORY, INC.

350 LELAND AVE., PLAINFIELD, N. J.

"TORQUE WRENCH" MANUAL



SENT UPON REQUEST

Formulas
Applications
Engineering Data
Screw Torque Data
Adapter Problems
General Principles

PA STURTEVANT CO.
ADDISON QUALITY ILLINOIS

Manufacturers of over 85% of the torque wrenches used in industry

FOR PUBLIC ADDRESS, RADIO, and kindred fields, JONES 400 SERIES PLUGS & SOCKETS

of proven quality!

P-406-CCT



S-406-AB

Socket contacts phosphor bronze cadmium plated. Plug contacts hard brass cadmium plated. Insulation molded bakelite. Plugs and sockets polarized. 2, 4, 6, 8, 10, 12 contacts. Steel caps with baked black crackle enamel.

Catalog No. 20 gives full information on complete line of Jones Electrical Connecting Devices — Plugs, Sockets and Terminal strips. Write

Jones
HOWARD B. JONES DIVISION
CINCH MANUFACTURING CORPORATION
CHICAGO 24, ILLINOIS

FOR *the scientist or engineer who has more to offer . . .*

A limited number of positions of unusual responsibility

IBM, long a leader in the growing field of digital computers for business, science, and government, offers a limited number of long-range creative assignments to outstanding men with Master's or Doctor's Degrees in Electrical Engineering, Physics, Mathematics, Chemistry or Physical Chemistry.

- **Research in solid state materials**
  Investigation of electronic phenomena in solids
  Study of ferrite and semi-conductor characteristics
  Study of the role of surface effects in semi-conductor device characteristics
  Evaluation of sample semi-conductor or ferrite components
- **Development of new concepts, new approaches to internal handling of information in computer systems**
  Information Theory
  Research in Machine Organization
  Theory of Control of Digital Devices
  Switching Circuit Theory
  Digital Data Transmission
- **Circuit Design, Systems Design and Analysis**
  Electronic pulse circuits for accounting and data processing machines—arithmetic switching and logical circuitry—pulse amplifiers, shapers, gates, etc.—magnetic storage—transistor circuitry—input-output device controls.

If you have more to offer, IBM offers you

• Stimulation . . . Satisfaction
At IBM men find the kind of facilities, associates and climate which stimulate achievement.

• Professional Growth
In Company growth lies personal opportunity, and IBM has an enviable record of steady and consistent growth. Over the past quarter century, IBM's business has doubled every five years on the average.

Out of respect for the unusual man's talent and promise, IBM encourages qualified candidates to visit its Poughkeepsie, N. Y. laboratory—at their convenience, and IBM's expense. Write, outlining your qualifications, to: William M. Hoyt, International Business Machines, Room 401, 590 Madison Avenue, New York, N. Y.

IBM®

Producer of electronic data processing machines, electric typewriters, and electronic time equipment.

demanded of much larger and heavier relays.

▶ **Insulation**—The insulation is of high grade, molded phenolic material.

Contact rating is 15 amperes at 115 v a-c or 32 v d-c noninductive load. The relay is available from stock in a wide range of coil operating voltages for either a-c or d-c. Write for catalog R-26.

TIME DELAY UNIT
features controlled amounts

KAY ELECTRIC CO., 14 Maple Ave., Pine Brook, N. J., has announced the Auto-Vox, a variable time delay instrument designed to introduce controlled amounts of delay into an audio system. It provides one output as a reference and a second output with variable delay in two ranges. The unit permits two signals to be developed in two independent channels with separate or mixed output. Price is contingent on ranges specified.



SPEED CONTROLS
in 1 and 1½ h-p ratings

GENERAL RADIO CO., 275 Massachusetts Ave., Cambridge 39, Mass. A small, rugged, and inexpensive drum controller is used in place of magnetic contactors as the switch-

AdjusToroiD®



A LOW-COST ADJUSTABLE TOROID

- precise, instant adjustment
- inductance variation of 10%
- eliminates critical close tolerance capacitors
- high Q
- no external power supply
- truly hermetic sealing
- temperature coefficients same as fixed toroids
- no increase in case diameter
- developed by Burnell, creators of the Rotoroid®

Write for Adjusteroid Technical Brochure A-55

LET BURNELL ENGINEERS SHOW HOW USE OF ADJUSTOROIDS REDUCES EQUIPMENT COSTS

Many types of Adjustoroids and Rotoroids now available from stock.

Teletype: Yonkers, N. Y. 3633

BURNELL & CO., INC.

45 Warburton Avenue
Yonkers 2, New York
Pacific Division: 720 Mission St., S. Pasadena, Calif.

Copyright patent applied for

HOW 3-D MICRO-VISION HELPS FAIRCHILD

manufacture world's tiniest production-run potentiometer



In a case less than ½" in diameter, 35 sub-miniature parts are precision-assembled; hair-thin springs are welded into fine slots. This tiny unit, designed and developed by the Guided Missiles Division of Hughes Aircraft Company, is a sensing and controlling element for aircraft and missiles; critical tests must assure highest mechanical and electrical efficiency.

Fairchild Camera and Instrument Corporation attributes the efficient mass-production of this unit to the use of Bausch & Lomb Stereomicroscopes—in assembly, inspection, and quality control. "Operators have both hands free and use both eyes to obtain normal, three-dimensional vision magnified to the required power—with high efficiency and operator comfort."

Write for FREE Copy of this Exclusive 3-D Micro-Vision Data Book

- See actual stereo views!
- Know *how* and *where* to use Stereomicroscopes!
- Fit exact model to job needs with Selector-Chart!

WRITE TODAY for Data Book D-15. Bausch & Lomb Optical Co., 61401 St. Paul St., Rochester 2, N.Y.

BAUSCH & LOMB
SINCE B&L 1853

America's only complete optical source... from glass to finished product.

ing unit for forward, reverse and stop operations. The controller and the speed-adjusting Variac are separate from the main chassis which can therefore be mounted in any out of the way location.

▶ **Protection**—A dynamic braking resistor is included for use where quick stopping is required. Overload protection of the Klixon type with appropriate time-delay characteristics is incorporated in the Variac.

▶ **Prices**—Type 1704-B 1 h-p control is priced at $330 complete, and at $308 without the drum controller; type 1705-B 1½-h-p control is priced at $380 complete and at $358 less the controller.

D-C AMPLIFIER
uses new chopper circuitry

KAY LAB, Box 16, San Diego 12, Calif., has announced model 110 chopper stabilized broadband d-c amplifier.

▶ **Performance** — Longtime drift (40 hr) of ±2μv is assured by the use of radically new chopper circuitry. Equivalent input noise is less than 5μv peak to peak for 3-cycle bandwidth, less than 5μv rms for 750-cycle bandwidth, and less than 12μv rms for 50-kc bandwidth. Variable gains of 0, 20, 30, 50, 70, 200, 300, 700, 1,000 accurate to 1 percent are provided. Bandwidth is flat within 3 db from d-c to 30 kc.

A unique output circuit with 4 tubes arranged symmetrically with multiple feedback loops provides a damage-proof circuit which recovers rapidly from overloads. Output

of the amplifier is 25 v with a 1,000-ohm load. Linearity is better than 0.1 percent.

Modular plug-in construction is used so that 3 amplifiers can be housed in a standard 19-in. rack adapter. The amplifier is extremely useful for multiple strain gage testing and as a recorder amplifier.

Price, complete with cabinet or rack adapter, is $550.

MILLIAMMETERS
for industrial panel uses

HOYT ELECTRICAL INSTRUMENT WORKS, 42 Carleton St., Cambridge 42, Mass. Model 649 d-c milliammeter provides a 2½-in. scale. Antistatic treated, virtually dust tight and with standard mounting dimensions, it is designed to provide accuracy and legibility in modernized industrial panel installations.

Identical in appearance and mounting dimensions, the companion a-c meter, No. 650, has an accurate, air-damped jeweled repulsion movement. Both meters are available in quantity only.

VOLTAGE SOURCE
constant from —55 to 100 C

AVIEN, INC., 58-15 Northern Blvd., Woodside 77, N. Y., has announced

EAGLE
Timers and Counters
VITAL COMPONENTS IN MODERN AUTOMATION


MICROFLEX RESET TIMER
Micrometer dial for precision adjustments. 150+ operating arrangements.
CYCL-FLEX RESET TIMER
With vertical dial, holding contacts, progress pointer for panel mounting.
MULTIFLEX RESET TIMER
For sequence operation of several circuits — each adjustable.
FLEXOPULSE REPEAT CYCLE TIMER
On-OFF time independently adjustable on calibrated scale.
MULTIPULSE REPEAT CYCLE TIMER
Provides sequential or programmed operation of 2 to 12 circuits.
MICROFLEX RESET COUNTER
Trips switches open or closed after preset number of counts. Electric reset.

Represented above are but a few of the complete line of popular EAGLE Industrial Timers and Counters.

Models are available in a wide range of modifications to fit your particular application. Modern compact design and precise construction of these EAGLE components has won them an enviable coast-to-coast reputation for accuracy and long service-free life of operation. Write us about your needs.

MAIL COUPON TODAY!

EAGLE SIGNAL CORPORATION
Industrial Division, Dept. E-156
MOLINE, ILLINOIS

Please send free Automation Booklet "See What Timing Can Do For You."

NAME AND TITLE _____

COMPANY _____

ADDRESS _____

CITY _____ ZONE _____ STATE _____

For additional information on all items on this page, use post card on last page.

UNION

AC Miniature Relays

designed with all the features of our DC relays





Now, in proven production, Union AC relay with self-contained rectifier has retained all the best operating characteristics of the type M DC miniature relay. All parts are precision made—assembly is quality controlled. The relay is hermetically sealed and meets or exceeds all requirements of Mil-R-5757. Note these important features:

NYLON ENCLOSED SELENIUM RECTIFIER of our own manufacture assures highest reliability . . . permits operation in 115 volt, 60-400 cycle airborne circuits. Temperature range—55°C. to 85°C.

GOLD ALLOY OR PALLADIUM CONTACTS cleaned and polished by a special process, assure a degree of contact reliability unsurpassed in this field. Relay is especially fitted for dry-circuitry applications.

HIGH VIBRATION AND SHOCK RESISTANCE. Withstands vibration up to 1,000 cycles at 15 G's and shock in excess of 50 G's.

HIGH LIFE EXPECTANCY. Tested through 1,000,000 operations.

SMALL SIZE, LIGHTWEIGHT. Measures only ½" higher and weighs approximately 5 oz. All other construction features are the same as the DC relay.

TYPES AND MOUNTINGS. Available in either 6 PDT or 4 PDT models, plug-in or solder-lug connections and all the usual mountings.

For complete information or test samples, call our nearest sales representative listed below or write to our home office.

GENERAL APPARATUS SALES

UNION SWITCH & SIGNAL

DIVISION OF WESTINGHOUSE AIR BRAKE COMPANY

PITTSBURGH 18 PENNSYLVANIA

NEW YORK, IVanhoe 3-2424 (Hempstead) • BOSTON (Ashland) TRinity 2-4485
BALTIMORE, VAlley 5-3431 • ST. LOUIS, Jefferson 5-7300 • CHICAGO, LOngbeach 1-3042
LONDON, OHIO, London 1555 • LOS ANGELES, VAndyke 8731

a new high-stability voltage source that provides constant d-c output through ambient temperatures as low as —55 C and up to 100 C. Known as the k-volt standard, the unit is designed to replace the chemical cell and v-r tube as an absolute reference, constant output working supply or precision voltage regulator in airborne, lab, and other instrumentation requiring extreme stability over widely varying environmental and operating conditions.

▶ **Design**—The unit utilizes a voltage regulating network based upon special types of double anode silicon diodes selected for stability of conduction characteristics. Using neither tubes nor moving parts, it is unaffected by position, vibration or mechanical shock, and conforms to MIL-E-5272A. Uniformity of output is maintained through repeated on-off switching.

The unit, which measures 1½ in. high and 1¼ in. diameter, weighs less than 3 oz. It is available for operation from 26.5 v d-c, or 117 v a-c, with d-c output of 6 v or 1 v, at 1 ma or 10 ma. Power consumption is less than 1.8 w. Case is hermetically sealed and employs a 7-pin miniature plug-in base.



PRECISION CONNECTOR features 15 contacts

DeJur-Amsco Corp., 45-01 Northern Blvd., Long Island City, N. Y. The plug of the GS series has twelve 0.040-in. diameter pin contacts and three 0.090-in. diameter center polarizing contacts molded into a mineral filled mica phenolic body. Pin contacts are phosphor bronze and gold plated. Floating socket contacts are Beryllium cop-

per, gold plated 0.0002 in. thick. Soldering lugs are annealed to prevent breakage.

Technical information, specifications and diagrams are available free on request. Write for bulletin GS.

VIDEO SIGNAL SCOPE
10 test functions in 1 unit

TARC ELECTRONICS, INC., 48 Urban Ave., Westbury, N. Y., has developed Colorscope which combines the functions of seven bulky test units in one compact instrument. The new unit occupies a space of only 14 in. by 16 in. by 24 in., plus power supply, and can be set up for dolly carry or rack mounted.

▶ **Displays**—By means of a function switch, 10 displays are seen in sequence on the crt face: picture monitor, pulse cross monitor, two line horizontal time, two fields at vertical time, NTSC vectorscope presentation, external vertical signal at horizontal or vertical time, external horizontal and vertical amplifier, phase demodulator scope, and quadrature phase demodulator scope.

The unit is presently priced at less than $5,000.

POWER PACK
for transistor operation

ELECTRONIC MEASUREMENTS CO., Lewis St., Eatontown, N. J. Use of new circuit techniques in the 212-A transistor power pack results in a unit 3½ in. tall, weighing 14 lb, to provide 0 to 100 v d-c at 100 ma. Two approximately calibrated con-

UNION

Specially designed
SELENIUM RECTIFIERS
fitted to your application



Our Engineers Can Help You

The first metallic rectifier was developed by Union Switch & Signal engineers back in 1916. Since then, they have built up an extensive experience in rectifier applications that can be of tremendous value to you.

It's possible that you are working in rectifier problems that have already been solved in our research laboratories. The selenium rectifiers we show here are just a few of the many varieties that we are now producing.

Standard UNION selenium rectifier cells, pencil type, range in size from ⅛" to ½" diameter rated from 2.5 to 40.0 milliamperes per cell and stack type 1" x 1" to 5" x 6" rated from .180 to 10.0 amperes per cell in a single-phase full-wave bridge basis. Special combinations can be made to fit practically any current and voltage conversion requirements in various housings or shapes.

Why not tell us what you need, and our sales engineers will help you determine the best rectifier for your application.

GENERAL APPARATUS SALES
UNION SWITCH & SIGNAL
DIVISION OF WESTINGHOUSE AIR BRAKE COMPANY
PITTSBURGH 18 PENNSYLVANIA

NEW YORK, IVanhoe 3-2424 (Hempstead) • BOSTON (Ashland) TRinity 2-4485
BALTIMORE, VAlley 5-3431 • ST. LOUIS, JEfferson 5-7300 • CHICAGO, LOngbeach 1-3042
LONDON, OHIO, LOndon 1555 • LOS ANGELES, CLinton 6-2255



SHOWN: TYPE BXP, FOR PLUG-IN. PIN DIAMETER .040"; PIN LENGTH .238"; PIN SPACING .192".

PERFECTION IN PINT SIZE

Large or small—consistent quality is a *must* characteristic with Bliley ***BANTAM*** crystal units.

Tiny crystals, with polished surfaces parallel within a few millionths of an inch, get special tweezer handling as they go through Bliley production. The final assembly, hermetically sealed, is a precision package with performance equal to its larger counterparts.

The ***BANTAM*** is available for plug-in as well as solder-in applications. Type BXW for wire leads; type BXP for plug-in. Fundamental mode supplied 5-20 mc and overtone mode 15-125 mc; meets specifications for military types CR-55 and CR-56 as proposed for MIL-C-3098B.

Bliley CRYSTALS

BLILEY ELECTRIC COMPANY
UNION STATION BUILDING
ERIE, PA.



trols sweep 0 to 100 v and 0 to 10 v respectively, to permit precise adjustment from 0 to 100 v. A modulation unit is provided to permit measurement of transistor parameters by the small-signal method.

▶ **Features**—Remote control connector is provided whereby the unit may be controlled from a distance by inserting resistance across a two-terminal line. Voltage is controlled according to $E_o = KR$ where K is a constant and R is the inserted resistance. A typical application would be tube testing with automation.

Other features include 0.1-percent regulation, 0.15-percent stability, ½ mv ripple and polarity reversal with a switch.

NOISE GENERATOR is a well-filtered unit

R S Electronics Corp., 435 Postage Ave., Palo Alto, Calif., has produced a noise generator designed to measure i-f amplifier and other receiver noise figures by providing a known amount of random noise to the amplifier under test. It features diode current indication within 1.0 percent accuracy and BNC connectors for use with single or double-ended receiver inputs.

Plug-in precision resistors (±1 percent) permit selection of resistance while adjustable capacitors permit adjustment of capacitance, to simulate various types of mixers. The noise diode operates on rectified

filament power to eliminate line voltage ripple and harmonics.

▶**Shielding**—Extremely well filtered, the noise generator has double and triple shielding to eliminate danger of pickup. Under certain conditions the unit is useful up to 500 mc. Provisions include a remote control, so that the noise output may be automatically turned on and off by the attenuator switch in RS post amplifier.



POWER SUPPLY
for operating strain gages

PERKIN ENGINEERING CORP., 345 Kansas St., El Segundo, Calif., has developed a hermetically sealed strain gage power supply for operation of strain gages and telemetering equipment in aircraft systems.

▶**Specifications**—The d-c output is 5 v at 1 ampere; a-c input, 105 to 125 v, single phase, 380 to 420 cps; duty cycle, continuous; controls, potentiometer, externally mounted; dimensions 5 in. by 5 in. by 4 in.; and weight, 6½ lb.

Bulletin M562 is available on request describing and illustrating this unit in detail.

SIGNAL GENERATOR
a multipurpose unit

BYRON JACKSON DIVISION, Borg-Warner Corp., 492 E. Union, Pasadena, Calif., announces the AN/USM-16 standard signal generator. Over its range of 10 to 440 mc it can be tuned to within less than 1,000 cps of the desired frequency,

Where can you use VARFLO?

(the highly flexible Class B Sleeving and Tubing that licks Class A in performance—equals it in price)

• MORE FLEXIBLE — can be bent, even tied in knots, without cracking or crazing.
• MORE RESISTANT to water, alkalis, mild acids, common solvents, oils and greases.
• LONGER LASTING at high temperatures — withstands hundreds of hours at 300° F.
• INHERENTLY STRONGER — stands up under vibration, varnishing, baking. Good shelf life, too.
• MORE STABLE—retains dielectric value when pulled back during soldering.
• WIDER RANGE—available in 3 NEMA grades, 10 colors, coils, 36" lengths or shorter pieces.

Cuts inventory, too!

Superior to Class A insulation in performance—yet on a par with it in price—Varflo Sleeving and Tubing can be used economically for all Class A and Class B installations. This low-cost adaptability of Varflo enables many of our customers to achieve substantial savings in inventory. Available in NEMA Grades A-1 and B-1 tubing and Grade C-2 sleeving.

Perhaps Varflo can solve your insulating problems. Describe them in a letter—no cost or obligation for our recommendations.

FREE TEST SAMPLES Mail coupon for yours

Varflex CORPORATION *Makers of Electrical Insulating Tubing and Sleeving*

VARFLEX CORPORATION
506 W. Court St., Rome, N. Y.

Please send me free folder containing description and test samples of Varflo Sleeving and Tubing. I am particularly interested in insulation for .....

Name .....

Company .....

Street .....

City ..... Zone ..... State .....

BIG CAPACITY

Small Size

STABLE!

Fansteel

TANTALUM CAPACITORS

Fansteel Tantalum Capacitors offer practically unlimited life . . . either in use or on the shelf. They have a maximum d-c leakage of only 0.000008 ampere . . . and their stable characteristics are unchanged over a wide temperature range.

This stability results from the tantalum oxide film employed in these Fansteel Capacitors . . . the most stable dielectric, chemically and electrically, yet discovered.

Only a partial listing of Fansteel Tantalum Capacitors is shown at right. The 87 sizes and ratings Fansteel can supply are available from stock.

Send for bulletin 6.100

CATALOG NUMBER	CAPACITY MFD*	WORKING VOLTAGE D-C	MAXIMUM D-C LEAKAGE†
FP3086A1	30	6	1.0
FP2588A1	25	8	1.0
FP2081OA1	20	10	1.0
FP1581 5A1	15	15	1.5
FP1082 0A1	10	25	2.0
FP8630A1	8	30	2.0
FP5650A1	5	50	3.0
FP4860A1	4	60	3.0
FP3.5875A1	3.5	75	3.0
FP2810OA1	2	100	3.0
FP1.75125A1	1.75	125	3.0
FP14086A1	140	6	2.0
FP10081 0A1	100	10	2.0
FP7081 5A1	70	15	3.0
FP4083 0A1	40	30	4.0
FP2585 0A1	25	50	5.0
FP2086 0A1	20	60	5.0
FP1587 5A1	15	75	6.0
FP1181 00C1	11	100	7.0
FP9612 5C1	9	125	7.0
FP3258 6A1	323	6	3.0
FP2508 10A1	250	10	3.0
FP175 15A1	175	15	4.0

*—15% +20% at 120 cps, 25°C

†Microamperes, at 25°C

FANSTEEL METALLURGICAL CORPORATION

North Chicago, Illinois, U.S.A.

TANTALUM CAPACITORS . . . DEPENDABLE SINCE 1930

with reference to a two-stage temperature-controlled crystal calibrator, without charts or auxiliary equipment.

Stability is assured by automatic frequency and automatic level control.

▶ **Outputs**—Available outputs are c-w, a-m, f-m, pulse modulation (with or without video pulse of variable rate, width, and delay and a sync out pulse through separate connectors), or swept frequency with marker pip.

The instrument has an output of 0.1 μv to 0.224 v (—127 to 0 dbm) into a 50-ohm load with the selected output remaining constant over the full frequency range.

Price of the unit is $5,000.

SERVO AMPLIFIER
with instantaneous response

SERVO CORP. OF AMERICA, 20-20 Jericho Turnpike, New Hyde Park, L. I., N. Y. Type 1121-A18 reluctance servo amplifier accepts two a-c inputs and one d-c input in any combination. With instantaneous response (time lag is negligible compared to one cycle of supply frequency), it produces proportional and reversible power circuit output for most 115-v 400-cycle servo motors rated at 18 w or less.

▶ **Features**—Operating directly from the power line, total power consumption is low for small input signals and less than half plate dissipation is required at no load. Featuring built-in power supply and built-in preamplifier, the amplifier is compact—the factor of output vs weight is over 5 w per lb.

The unit has no tuned elements. Supply voltage variations will nat-

urally affect peak power output correspondingly, but with little effect on the amplifier's gain.

VOLTAGE REGULATORS
are ± 0.25 percent accurate

MAGNETIC RESEARCH CORP., 200 Center St., El Segundo, Calif. Stablvolt magnetic a-c line voltage regulators perform with ±0.25 percent regulation accuracy with load variations from 0.3 to 3 kva. Output voltage is stabilized within a band of 0.25 v rms for line voltage variations from 100 to 130 v and line frequency variations from 57 to 63 cps. Control of voltage output is continuously adjustable between 110 and 120 v rms.

▶ **Long Life**—Magnetic amplifiers replace tubes in the new regulators to provide a long-life a-c power source of extreme reliability. There are no fragile elements to burn out, no parts to wear out.

Price is $785.

PROTECTIVE COATING
for printed circuitry

PHOTOCIRCUITS CORP., Glen Cove, N. Y. A new, noncorrosive film protects and prolongs shelf life of etched circuit boards that are inventoried prior to assembly and dip soldering. The film is applied after etching the printed circuitry.

Trade-named "Photofinish No. 4," the coating is an inexpensive colorless special plastic film applied thin enough to be hardly perceivable. The film vaporizes upon contact with hot solder leaving no disagreeable residue or contamination

BIG OUTPUT
Small Size
DEPENDABLE!

Fansteel



HIGH-TEMP SELENIUM
RECTIFIERS

CATALOG NUMBER	CIRCUIT	INPUT A-C VOLTS	CONT. D-C OUTPUT AT 100°C	
			VOLTS	AMPS.
TADL38L	1-35-1-H	495	402	0.004(*)
TEUH315(*)	2-8-1-D	132	254	0.020(*)
TBU100L	1-100-1-H	2600	1090	0.080
TEB328L(*)	2-11-1-D	363	297	0.150
TEW066L	4-4-1-B	132	108	0.180
TEC070L	4-5-1-B	165	135	0.300
TEX084L	4-1-3-B	33	27.8	1.89
TED300(*)	2-13-1-C-N	214	-175	0.600
TBV060L	4-3-1-B	78	62.7	1.0
TBV060L	4-3-1-B	78	62.7	1.0(*)
TEEW334L(*)	2-7-1-D	231	295	2.3(*)
TEFW332L(*)	2-19-1-D	429	548	4.6(*)
TBG084L	2-1-1-C	13	10.4	5.2
TET050L	4-2-1-B	66	53.9	4.6
TEP314L(*)	2-7-2-D	231	189	14.0
TER070L	6-3-1-B	66	79.5	12.9(*)
TER030L	6-1-3-B	33	27.8	25.8
TBR000L	6-1-4-B	26	32.5	51.6(*)

(*) Capacitive Load. Ratings in brackets are for resistive or inductive loads.
(*) Hermetically Sealed.
(*) Two stacks required.
(*) Three stacks required.
(*) Resistive, inductive or capacitive load.

Continuous operation at 100°C requires *no derating whatever* in the output of Fansteel High-Temp Selenium Rectifiers. They were developed to deliver full rated power output up to this specified ambient temperature. And at higher temperatures, up to 150°C (302°F), only moderate derating is required.

All standard cell sizes and circuit arrangements are readily available. The table at left indicates only a partial list of over 100,000 types. And all Fansteel High Temperature Selenium Rectifiers are available with standard protective finishes that resist moisture, fungus or salt spray, the latter meeting MIL specifications.

Send for bulletin 6.401

FANSTEEL METALLURGICAL CORPORATION
North Chicago, Illinois, U.S.A.
DEPENDABLE RECTIFIERS SINCE 1924

TIME ... for "flight – vital" ground installations



HAYDON* 7008 SERIES ELAPSED TIME INDICATOR

Now available for 60 cycle operation

Now available for 60 cycle as well as 400 cycle operation, HAYDON 7008 Series Elapsed Time Indicators retain the same important features . . . high quality, extreme dependability, compactness and light weight.

Here is the ideal means of providing precise, fully reliable timing for the many types of vital, permanent or portable ground installation equipment that require an accurate record of running time for correct maintenance and assured functioning.

On the ground or in the air — wherever performance demands sky-high timing standards — count on HAYDON. Write today for Engineering Bulletin No. 5 describing the new 7008 Series Indicator for 60 cycle operation . . . and for catalogs describing the complete lines of HAYDON Timing Motors and Devices. Or contact the HAYDON Field Engineer located near you.

*Trademark Reg. U.S. Patent Office

HAYDON AT TORRINGTON
HEADQUARTERS FOR TIMING

A SUBSIDIARY OF GENERAL TIME CORP.

HAYDON Manufacturing Company, Inc.
2425 ELM STREET, TORRINGTON, CONNECTICUT

of the solder pot when dip soldering.

Photofinish No. 4 has excellent electrical characteristics. It is easy to handle both during and after application. The film will be applied by the company prior to shipment of printed circuit boards upon specification.



FIELD STRENGTH METER
for 19 to 125 mc range

TELECTRO INDUSTRIES CORP., 35-18 37th St., Long Island City 1, N. Y. Model 728 radio field strength meter makes field strength measurements in the range of 19 to 125 mc and will accurately measure intensities ranging from 2 μv to 2.5 million μv per meter. It can be used to measure the field intensities of both a-m and f-m transmitting stations.

Provisions for linear or logarithmic output indications for recording meter use are included. Readings in db above 1 μv per meter are made by the simple addition of three values. Measurement of noise intensities can be made by means of accessory probes.

Net price is $2,200.

SINE-WAVE GENERATOR
0.9 cps to 510 kc in 5 ranges

ALLEN B. DUMONT LABORATORIES, INC., 760 Bloomfield Ave., Clifton, N. J. A new sine-wave generator for magnetic amplifier, servomechanism and computer development, for laboratory testing or field maintenance, and for measurements of frequency response, bandwidth or distortion has been introduced.

▶ **Features**—Type 348 sine-wave generator features an extended l-f range, high output power, low distortion and a calibrated output control including a 4-step decade attenuator. Frequency accuracy is

±2 percent, with vernier tuning and a scale length of 14 in. on each range. Five decade tuning ranges and an additional band-spread h-f range are provided.

Price is $325.



TINY FERRITE CHOKES
have Q to 100

SUPEREX ELECTRONICS CORP., 4 Radford Place, Yonkers, N. Y. Illustrated are the new microminiature ferrite cored chokes. An idea as to the size of these components can be had by their comparison to a paper clip and the 2.5-mh ferrichoke. The Mini-Choke is available from stock, in values of: 500μh, 1 mh, 2.5 mh, and 5 mh.

A 4-page inductor catalog, covering specifications of Mini-Chokes, as well as other types of inductors, is available.

PRECISION POT
accurate voltage divider

NIPPON ELECTRIC CO. LTD., 1753, Shimonumabe, Tamagawamukai, Kawasaki City, Japan. Type A precision potentiometer is intended to subdivide any audio or d-c voltage with an accuracy which is better than 8 parts in 100,000. A built-in

TEFLON*

PARTS OR MATERIALS FOR UHF APPLICATION?

FOR MINIATURE AND SUB-MINIATURE COMPONENTS?

YOU CAN GET JUST WHAT YOU WANT

from JOHN CRANE



FOR: insulators of all types, sleeves or inserts, capacitor seals, feed through insulators, bushings, slot liners, coaxial spacers, layer insulation or any other parts or forms subject to high charge, extended frequency range, mechanical and thermal shock, extreme temperatures and climatic conditions.

You can order in any quantity and be sure of true Teflon performance, because "John Crane" gives you these *plus* factors: complete uniformity throughout, high density control, freedom from flaws and rigid adherence to your specifications.

"John Crane's" complete fabrication facilities assure you prompt delivery on *exactly* what you want. If you have an entirely new requirement, no standard design or procedure—"John Crane's" laboratory facilities, know how, research and engineering experience go to work on *your particular* need.

Now is a good time to put "John Crane" to test. Contact Crane Packing Company today.

*TEFLON *DuPont trademark*

Dielectric Strength: 480 v/mil.
Dielectric Constant (60 to 10^8 cycles): 2.0
Power Factor (60 to 10^8 cycles): < 0.0005
Volume Resistivity: 10^{15} ohm-cm
Surface Resistivity: 3.6×10^6 megohms
Surface Arc-Resistance: does not track
Temperature Range: −450° to +500°F.
Chemical Resistance: completely inert
Moisture Absorption: zero

Crane Packing Co.,
6402 Oakton St.,
Morton Grove, Ill.
(Chicago Suburb).

In Canada: Crane Packing Co., Ltd., Hamilton, Ont.

JOHN CRANE CRANE PACKING COMPANY 30 YEARS INDUSTRIAL PROGRESS

OFFICES IN ALL PRINCIPAL CITIES

WHITNEY BLAKE
CORD and CABLE

FOR POWER SUPPLY, COMMUNICATIONS AND ELECTRONIC APPLICATIONS
ADVANCED DESIGN, HIGHEST QUALITY

MICROPHONE CABLE



Super flexible with semi-conducting textile shield and long-wearing neoprene jacket. Cadmium copper conductors for long flex life, insulated with high dielectric strength rubber. Noisy circuits are eliminated. Other types also available.

SPEECH INPUT AND SOUND SYSTEM CABLES

Semi-rigid polyvinyl chloride Types. Solid or stranded conductors with bare or tinned copper shield. And, with cotton braid or Plastite® jacket. Also, Enamel Textile Types.

SIGNAL WIRES

Bare soft copper conductors insulated with high dielectric strength polyvinyl chloride insulation. Underwriters' Laboratories approved for fire and burglar alarm system internal wiring.

INTERCOMMUNICATIONS CABLES

TELECABLE® Multiconductor Paired Inside Wiring Cable

Semi-rigid polyvinyl chloride insulation, brown or ivory polyvinyl chloride jacket. Light weight, easy to install, unaffected by humidity.

PORTABLE CORDS

Underwriters' Laboratories approved — for power supply on electrical equipment. Neoprene jacketed DYNAPRENE® and rubber jacketed types.

CORD SETS AND CABLE ASSEMBLIES

Custom-built to customer's requirements. Using either standard cordage or cord designed to fit your particular application, Whitney Blake can furnish regular line cords or special purpose cords having attached or integrally molded rubber or Plastite fittings.

Well Built Wires Since 1899

© 1955
WHITNEY BLAKE COMPANY

New Haven 14, Connecticut

sinusoidal-voltage generator is incorporated.

The unit is designed to be used for model measurements of electron trajectories within a vacuum tube by an electrolytic trough.

► **Makeup**—The unit essentially consists of two parts: the a-f oscillator and the voltage divider. The a-f oscillator is a Wien-bridge resistance-capacitance oscillator of purely sinusoidal waveform operating at around 550 cps. The output voltage of the oscillator is around 5 v.

The voltage divider consists of 4 resistance elements. The first 3 have a total resistance of 200 ohms each and are capable of dividing the oscillator voltage in 100 divisions. The fourth element has a total resistance of 20,000 ohms and the same voltage can be divided into 1,000 divisions.



LOUDSPEAKER
an 8-in. industrial unit

ALTEC LANSING CORP., 800 Hollywood Blvd., Hollywood, Calif. Model 401A loudspeaker is an 8-in. industrial all-range type designed to meet the requirements of public address and various types of commercial sound systems.

It has a power capacity of 14 w, impedance of 8 ohms, with resonance 75 cps. The voice coil diameter is 1 in., and the depth 3¾ in. Price is $13.20.

DATA RECORDER
a 5-channel, 3-speed unit

TELECTRO INDUSTRIES CORP., 35-18 37th St., Long Island City 1, N. Y. Model TR-150-5 magnetic tape recorder-reproducer is designed specifically for recording and repro-

ducing data from telemetering channels. Data are recorded on and reproduced from a 2,400-ft magnetic tape moving at 15 ips, 30 ips or 60 ips.

► **Response**—The frequency response is 200 to 20 kc ± 3 db at 15 ips; 200 to 40 kc ±3 db at 30 ips; 100 to 80 kc ±3 db at 60 ips. Rewind time is less than 1 minute for a full reel of tape.

The model TR-150-5 is supplied as 5 separate units, each suitable for mounting in a standard relay rack. The separate units comprise a low and high-voltage power supply; filament and bias supply, recording amplifiers, playback amplifiers and tape-transport mechanism.

Price of the machine is $5,500; delivery, 120 days.

CRYSTAL UNIT
measures 4⅛ in. by 2 in.

BULOVA WATCH CO., INC., Valley Stream, L. I., N. Y., has added model GA-100 to a line of high-stability crystal units. It contains

PRECISION ATTENUATION to 3000 mc!

Protected under Stoddart Patents

six-position
TURRET ATTENUATOR
featuring **PULL-TURN-PUSH** *action*

FREQUENCY RANGE: dc to 3000 mc.
CHARACTERISTIC IMPEDANCE: 50 ohms.
CONNECTORS: Type "N" Coaxial female fittings each end.
AVAILABLE ATTENUATION: Any value from 1 db to 60 db.
VSWR: 1.2 max., dc to 3000 mc/s, values from 10 to 60 db. As value decreases below 10 db, VSWR increases to not over 1.5.
ACCURACY: ± 0.5 db.
POWER RATING: One watt sine wave power dissipation.

SINGLE "IN-THE-LINE" ATTENUATOR PADS and 50 ohm COAXIAL TERMINATIONS

This new group of pads and terminations features the popular Type C and Type N connectors, and permits any conceivable combination of the two styles. For example, the two connector types, either male or female, can be mounted on the same attenuator pad, with or without flanges, so that it may serve as an adapter as well as an attenuator. Frequency range, impedance, attenuation, VSWR, accuracy and power rating are as designated above. Send for free bulletin entitled "Measurement of RF Attenuation."

STODDART aircraft radio co., inc.
6644-A SANTA MONICA BLVD., HOLLYWOOD 38, CALIFORNIA · HOLLYWOOD 4-9294

This is the 4" model, type MCF-300. Ultimate pressure—5×10^{-7} mm Hg; speed for air—290 liters/second; throughput—800 micron-liters/second. Casing is stainless steel construction.

CVC fractionating oil diffusion pumps give you:

1. **low pressures** (10^{-2} to 10^{-7}mm Hg)
2. **high speeds** (65 to 19,000 liters/second)
3. **high throughputs** (100 to 15,000 micron-liters/second)
4. **high limiting forepressures** (up to 400 microns Hg)

If you want to exhaust electronic tubes to extremely low pressure, exhaust gases of low molecular weight, or large gas loads of any kind, there's an MCF pump to do the job.

There are *seven* of these fractionating oil-diffusion pumps, ranging in diameter from 2 inches to 32 inches. Here you have your choice of the widest range of size, speed, and throughput available.

The jet assembly of an MCF pump can be removed easily for cleaning. Jets are plated to prevent rust and reduce heat loss. Large diameter cooling coils insure top operating efficiency. Heaters are mounted externally to facilitate maintenance.

These are just a few of the reasons MCF pumps have become the standard diffusion pumps of the electronic industry, outselling by far all other types.

For further information, write for data sheet 6-55.

CVC

Headquarters for High Vacuum

Consolidated Vacuum Corporation Rochester 3, N.Y.

a subsidiary of CONSOLIDATED ENGINEERING CORPORATION, *Pasadena, California*

CVC sales now handled through Consolidated Engineering Corporation with offices located in: Albuquerque • Atlanta • Boston • Buffalo • Chicago • Dallas Detroit • New York • Palo Alto • Pasadena • Philadelphia • Seattle • Washington, D.C.

a 100-kc GT high precision quartz element in an evacuated glass bulb fitted with a standard octal base. The overall dimensions are 4½ in. by 2 in.

► **Other Features**—The unit exhibits a frequency shift of less than ½ cycle over a temperature range of 25 C to 70 C. Aging characteristics average less than one part in 10^8 per week. Readily attainable are Q's in the order of one million.

LONG-LIFE BATTERIES
for transistor applications

RADIO CORP. OF AMERICA, Harrison, N. J., has developed two new battery types, specifically designed for transistor applications. Both the VS300 and VS301 are being recommended as power supplies in new transistorized portable receivers. The VS300 is a 9-v unit designed for transistorized portables. The battery is approximately 2 in. long and 1 in. in diameter. The VS301 was designed for applications requiring long-life operation and low cost-per-hr playing time. Its dimensions are 8 by 1⅞ by 2⅛ in. Voltages of 3, 6 and 9 v may be obtained from a small 4-hole socket mounted flush with the battery case.

► **Assemblies**—Both battery assemblies consist of 15 separable 1.4-v alkaline-type dry cells enclosed in a plastic sleeve. The voltage required for any experimental transistor application is obtained by slicing off the number of cells needed.

FASTENERS
with spring-steel coil form

TINNERMAN PRODUCTS, INC., P. O. Box 6688, Cleveland 1, Ohio, is producing a new spring steel coil form fastener that accommodates

0.218-diameter electronic tubes. It overcomes the problem of holding close tolerances during high-speed mass production.

▶ **Assembly**—To assemble, coil screw is threaded into fastener where sheared prongs provide correct tensioning on screw. Coil tube is then inserted into fastener and retained by four small barbs on inside. Assembly is then snapped by hand into chassis where tab on leg of fastener fits into small hole in panel to prevent it from turning.

UHF AMPLIFIERS
are wide-band units

APPLIED RESEARCH INC., 163-07 Depot Road, Flushing, N. Y. Models UH-4(A) and UH-6(A) amplifiers feature a center frequency of 400 mc and a bandwidth of 50 mc. They incorporate the GL6299 vacuum tube in lumped constant, triple-tuned circuitry. All efforts have been made to maintain a low peak-to-valley ratio to preserve phase linearity in the passband.

▶ **Specifications**—Both models have an input and output impedance of 50 ohms. Power gain for the UH-4A is 35 db; for the UH-6A (illustrated), 50 db. Noise figure for each is $\leq$ 7 db, and peak-to-valley ratio, $\leq$ 2db.

COIL CEMENT
available in two viscosities

BARRETT VARNISH CO., 1532 S. 50th Court, Cicero 50, Ill., has introduced Gripo, a new cement especially recommended for use on electronic coils. It provides a firm bond to overcome fragile coil conditions and has excellent insulating properties as well.

▶ **How Applied**—Gripo may be applied by dipping, spraying or brushing, and since it is thermo-



The "QUALITY" name for PHENOLIC TUBING

To make your product better . . . and at lower costs . . . specify CLEVELITE!*

High performance factors, uniformity and inherent ability to hold close tolerances, make Clevelite outstanding for coil forms, collars, bushings, spacers and cores.

Wherever high dielectric strength, low moisture absorption, mechanical strength and low loss are of prime importance . . . the combined electrical and physical properties of Clevelite are essential.

Fast, dependable deliveries at all times!

Why pay more? For Good Quality call CLEVELAND!

* Reg. U. S. Pat. Off.

THE CLEVELAND CONTAINER COMPANY
6201 BARBERTON AVE. CLEVELAND 2, OHIO
PLANTS AND SALES OFFICES:
CHICAGO • DETROIT • MEMPHIS • PLYMOUTH, WIS. • OGDENSBURG, N.Y. • JAMESBURG, N.J. • LOS ANGELES
ABRASIVE DIVISION of CLEVELAND, OHIO
Cleveland Container Canada, Ltd., Prescott and Toronto, Ont.

Representatives:
NEW YORK AREA: R. T. MURRAY, 604 CENTRAL AVE., EAST ORANGE, N. J.
NEW ENGLAND: R. S. PETTIGREW & CO., 62 LA SALLE RD., WEST HARTFORD, CONN.
CHICAGO AREA: PLASTIC TUBING SALES, 5215 N. RAVENSWOOD AVE., CHICAGO
WEST COAST: IRV. M. COCHRANE CO., 408 S. ALVARADO ST., LOS ANGELES





Here is a ⅝" potentiometer that offers you the extreme precision found in larger sizes of Gamewell Potentiometers.

Body is of anodized aluminum and the shaft is made of stainless steel. Kohlrausch type winding provides excellent linearity and the unit meets MIL-E-5400 specifications as they apply.

The unit can be modified for special mounting, Multiple gangs, higher operating temperatures, and other special features upon request. Write for additional information about this miniature precision potentiometer.

CONDENSED TECHNICAL DATA:

Resistance	*30K ±5%
Min. Resistance	20 ohms
Linearity	*0.25
Electrical Angle	345°
Resolution	*0.09%(1100T)
Test Voltage	1000 RMS
Temperature	105°C
Watts	1
Size	⅝" OD 1⅛" long
Torque	0.2 oz.-in.

*Maximum Values

THE GAMEWELL COMPANY
NEWTON UPPER FALLS 64, MASS.

GAMEWELL®

PRECISION POTENTIOMETERS

Manufacturers of Precision Electrical Equipment Since 1855

setting, must be cured at high temperatures. Television coils should be dipped after assembly and baked at a temperature of 275 to 300 F for 30 to 45 minutes. Large coils will require higher temperatures and longer baking time.

Gripo is available in two viscosities. Gripo X is heavier bodied, corresponding to X on the Gardner scale, while Gripo C is lighter, corresponding to a reading of F. Price of the former is $3.70 per gallon in drums, and the latter, $3.50 per gallon in drums. There is an additional charge per gallon for smaller quantities.

The cement has a minimum dielectric strength of 2,500 v per mil d-c.

COMPACT RESISTORS
are wire-wound type

PRECISION RESISTOR CO., INC., 107 U. S. Highway No. 22, Hillside 5, N. J., has available a line of precision wire-wound resistors designed especially for subminiature and transistor requirements where physical size, weight and simplicity are of prime importance.

▶ **Varieties**—They are supplied in either inductive or noninductive windings in varying sizes from ¼ in. up to ¾ in. lengths in any resistance values desired, 0.10 ohm through 0.50 megohm, and in a choice of standard tolerances of ±1, 0.5, 0.26 and 0.1 percent including precision tolerances. All have temperature-coefficient of resistance of 20 ppm per deg C.

F-M WAVE TRAP
is precision tunable

BLONDER-TONGUE LABORATORIES, INC., 328 North Ave., Westfield,

N. J., has announced a precision tunable trap to eliminate f-m interference in master tv systems and individual tv sets. The weather-protected unit, called MWT-1, may be mounted on the antenna mast, at amplifier inputs or at tv set terminals.

▶**F-M Aid**—Any f-m channel from 88 to 108 mc may be attenuated more than 20 db. Two trimmer screws tune out the interfering frequency. Rejection ranges from 35 db at channel center to less than 3 db 1.5 mc on either side. The feed-through circuit insures excellent 75-ohm impedance match on all vhf tv channels. Standard uhf connectors are used.

Price is $23.



CERAMIC COIL FORMS
used with printed circuits

CAMBRIDGE THERMIONIC CORP., 445 Concord Ave., Cambridge, Mass., announces two new printed circuit coil forms, the SPC-11 and SPC-12, made of grade L-5 ceramic. One has a mounted height of $\frac{5}{8}$ in. and the other $\frac{13}{16}$ in. Both have an o-d of $\frac{1}{4}$ in. and have a $\frac{1}{2}$ in. threaded powdered iron core and silicone Fiberglas collar.

▶**Other Features**—The coil forms are available with 2 to 4 solder lugs and feature a design which allows the units to be dip soldered after mounting. They are available as a form alone or wound to the required specification of the user. They come complete with threaded slug and the terminal collar of silicone Fiberglas is securely fastened to the form.

▶**Prices**—In quantities of 1 to 49 they sell for 0.174 each; 50-249,

Which Cable For Your Job?

Depend on PHALO *for the Answer!*

This man is surrounded with perfectly good cables . . . maybe one of them will fit his special requirements. However, the chances are that he'll need a custom-made cable, one designed exactly for his task.

Here at Phalo we specialize in removing the fences that separate average cable performance from superior cable performance. Send us the "specs" that have been adding gray hairs to your head. We'll turn the stumbling block into a stepping stone to product or service success!

Ask For The Complete Phalo Catalog



PHALO
PLASTICS CORPORATION
The Custom Cable House
CORNER OF COMMERCIAL STREET
WORCESTER, MASS.
Insulated Wires, Cables – Cord Set Assemblies

Eccosorb CH
Microwave Absorber
for Darkrooms

Microwave Darkroom with
Emerson & Cuming Luneberg Lens under test

Eccosorb CH is a series of broadband absorbers reflecting less than 2% of the energy incident upon its surface. It is composed of enmeshed, rubberized fibers and made in sheets 2 feet by 2 feet in various thicknesses. Eccosorb CH is light weight and flexible. It is easily mounted and its natural, white surface color gives good light reflection.

Free Space Rooms are easily and economically built for indoor antenna measurements. Reflections are eliminated for all practical purposes. You can build your own microwave dark room or **we offer you a complete Free Space Room ready to use.** Emerson & Cuming engineers design and build special types for unusual conditions. Send us your specifications.

Another absorber, ECCOSORB HF comes in rods, sheets or molded shapes in several volume resistivities for waveguide terminations and similar uses. If you have a problem write for information on . . .

Plastics for Electronics

Emerson & Cuming, Inc.

869 WASHINGTON STREET, CANTON, MASS

PLASTIC FOAMS
LAMINATING AND IMPREGNATING RESINS
PLASTIC-FIBER GLASS LAMINATES
HIGH DIELECTRIC CONSTANT PLASTICS
METALIZED PLASTICS
ELECTRONIC EMBEDMENTS
CASTING RESINS
LOW LOSS ROD AND SHEET STOCK
MICROWAVE ABSORBERS

Sales Representatives

DAYTON
ROBERT G. SIFF & ASSOCIATES
11 W. Monument Bldg., Dayton 2, Ohio
Hemlock 1254

KANSAS CITY
ENGINEERING SERVICES COMPANY
4550 Main Street, Kansas City 11, Mo.
Jefferson 7765

NEW YORK
M. RAYMOND KALLMAN
P. O. Box 104, Roslyn, L. I., New York
Roslyn 3-6511

ST. LOUIS
ENGINEERING SERVICES COMPANY
6635 Delmar Blvd., St. Louis 5, Mo.
VO 3-3661

WASHINGTON, D. C.
TED BRITT
1500 Mass. Ave., Washington 5, D. C.
Columbia 5-2694

WEST COAST
McCarthy Associates
P. O. Box 36, Altadena, Calif
Sycamore 8-5790

0.154 each; 250-499 0.134 each; and 500-999, 0.119 each.

VACUUM GAGE
a 1 to 4-station unit

CONSOLIDATED ENGINEERING CORP., 300 N. Sierra Madre Villa, Pasadena 15, Calif., has announced the Autovac, a 1 to 4-station vacuum gage which gives continuous pressure readings from 100 mm. Hg to 1 micron Hg. It covers substantially all laboratory and industrial applications now using Pirani and similar gages.

▶ **Features**—A special range-selection circuit provides automatic switching from the millimeter range (100 to 0.1 mm Hg) to the micron range (100 to 1 micron Hg). Other features include (1) wide measuring range, (2) its ability to actuate an external relay circuit for various purposes, and (3) connection for 4 gage tubes.

The single station gage is priced at $275. Each additional station increases price by $25. Thus a 3-station gage is $325.



INSTANT SOLDER GUN
features tiny tip

HEXACON ELECTRIC CO., 130 W. Clay Ave., Roselle Park, N. J., announces an instant solder gun with ⅛-in. tip. The gun is soldering-hot in a few seconds, without the use of heavy

transformer or fragile thermostats.

Trigger control gives any degree of heat required without danger of overheating. The gun has more heat capacity than size indicates because the heating element is right in the $\frac{1}{8}$-in tip.

▶ **Applications**—It is recommended for printed circuits, subminiature assemblies, radio, telephone, tv, laboratories and the like.

Rated at 150 w and available for 120 v, it operates identically on d-c as well as a-c, any cycle. List price is $7.95.



KLYSTRON POWER SUPPLY
up to 75 ma beam current

BROWNING LABORATORIES, INC., 750 Main St., Winchester, Mass. Model TVN-11B universal klystron power supply provides up to 75 ma beam current at voltages from 225 to 500 v, with both beam and reflector voltages being continuously variable. Price is $425.

▶ **Also Featured**—It has both square wave and saw-tooth modulation, the square wave with minimum overshoot and the saw tooth with good linearity for driving an external instrument; reflector voltages from 25 to 875 v with less than 1-percent regulation and better than 2.5-mv ripple content on both beam and reflector voltages.

A large illuminated panel meter indicates beam voltages and currents, and accurately calibrated panel controls give rapid readings of reflector voltage and current.

CODING SYSTEMS
digitize analog data

WANG LABORATORIES, INC., 37 Hurley St., Cambridge 41, Mass., an-

mcCoy HAS GOOD NEWS



McCoy's "McMite" Saves Space . . . Fourteen fit readily into a strip of sockets only 3" long. Two-inch diameter switch assembly takes ten "McMites" without crowding.

Here's Aid For Manufacturers, Designers and Researchers

When frequency selection is part of your sub-miniature design, McCoy's "McMite" will control it accurately.

"McMite" is an hermetically sealed precision quartz crystal unit, packing regular-size stability, dependability and performance into sub-miniature size. Meets all military specifications for fundamental operation above 5 mc. and overtone operation above 15 mc. McCoy's "McMite" is made with wire leads (M-20) or .040" diameter pins (M-21), providing easy adaptability to all types of assemblies.

mcCoy "McMite" . . . Frequency Range 5 mc. to 125 mc.



Other McCoy crystal components are shown in our catalog. Write for your copy today.

mcCoy ELECTRONICS COMPANY

Phone 376 and 377 MT. HOLLY SPRINGS, PENNA.



To fit numerous applications, Bourns has 200 designs of miniaturized, high-performance sensing instruments on file. These designs are either standard types, or variations made to meet critical electrical and environmental specifications. The pressure potentiometer designs range from ½ to 10,000 p. s. i. Linear motion units provide travels of ⅛" to 30", and you can choose from a wide variety of resistance ranges.

The instrument you need may be among these Bourns designs — ready for production from parts in stock. Or one of the designs now on our boards may meet your specs. If not, we will gladly consider developing the instrument you require. Send us your specifications — your problem may already be solved.



BOURNS LABORATORIES

6135 Magnolia Avenue, Riverside, California
Technical Bulletins on Request, Dept. 12

nounce their angular position coding systems, a complete line of compact units for converting analog data which is in the form of a shaft position into digital form.

The systems are available in two types—a nonambiguous coded type which can be read out on demand, either on the fly or at static shaft positions, and the incremental coded type which registers the instantaneous position of the shaft and each incremental change.

▶ **Cost**—The price of the coder units type 3A (1,000 parts per 360 deg) is $395; type 13A (10,000 parts per 3,600 deg) is $745; and the price of the translation matrix which will accommodate static as well as on the fly readout (type 3AT) is $700. A translation matrix providing static readout only is $500.



CAPACITORS
of the electrolytic type

SPRAGUE ELECTRIC CO., 35 Marshall St., North Adams, Mass. Type 17D electrolytic capacitor is now applicable to other electronic equipment. Long life and faultless performance require this series to use specially high-purity materials and the utmost care in manufacture.

Turret-terminal and mounting lugs and a special vent construction are molded right into the cover of the capacitor as are the numbers which identify each terminal. The seal, made by crimping the aluminum can on to a gasket, has been long proven for dependability. The cans themselves are covered with a corrosion-resisting insulating coating.

▶ **Ratings**—Nineteen standard ratings covering a wide range of appli-

cations in single, dual and triple section units are available in the series. All are characterized by low maximum leakage current and remarkable life test capabilities.

Complete technical data are provided in engineering bulletin 340.

FREQUENCY METER
with built-in calibrator

VARO MFG. CO., INC., 2201 Walnut St., Garland, Texas. Model 6501 frequency meter features a built-in precision calibrator using the Varo temperature-compensated tuning fork. Output terminals permit using the 400-cps reference frequency in laboratory applications, or as a secondary frequency standard.

▶ **Versatility**—Model 6501 has two scales for extra versatility. These scales cover the range 395 to 405 cps, and 350 to 450 cps. The unit will measure signals of 2 to 200 v rms.

Overall accuracy is better than 0.1 percent, and the accuracy of the calibrator reference frequency is 0.05 percent or better. Dimensions are 5¾ in. wide, 7⅞ in. high and 4¼ in. deep. Price is $345.



POWER DIODES
miniature, highly efficient

CLEVITE TRANSISTOR PRODUCTS, a division of Clevite Corp., 241-257 Crescent St., Waltham 54, Mass., have announced germanium junc-

PROBLEM: Suitable Transformers

Illustrated here is a typical circuit requiring special miniaturized transformers for use in Servo and Audio Transistor Power Amplifiers. Available standard transformers were not suitable. Specifications required a minimum of Class B switching transients and low D.C. resistance to conserve battery power.



CLASS B TRANSISTOR POWER AMPLIFIER

SOLUTION: Through Special Techniques

Microtran engineers, specialists in the design and manufacture of miniaturized transformers, solved the problem by using Bifilar winding techniques and the most recently developed high permeability and grain-oriented core materials. Listed below are two sets of transformers produced to the above requirements.

Application	Transistor	Pri. Imp.	Load Imp.	Power Level	Freq. Range	Catalog Number
Audio Driver	2N98	25,000 Ω	1200 Ω C.T.	75mw.	200-6000~	MT7-FB
Audio Output	2N43	1000 Ω C.T.	3.2 Ω	250mw.	200-6000~	M2251
Servo Driver	2N57	560 Ω	400 Ω C.T.	150mw.	400~	8126
Servo Output	2N57's	560 Ω C.T.	250 Ω	2.5 watts	400~	8127

SEND US YOUR REQUIREMENTS

Microtran manufactures a wide variety of transformers for standard and special, military and industrial applications. Send us your requirements for prompt reply and quotation. Detailed catalog and specification design sheets available on request. Catalog items to MIL-T-27A immediately available from:

HAROLD H. POWELL CO.
2102 Market St.
Philadelphia, Pa.

RADIO PRODUCTS SALES, INC.
1501 So. Hill St.
Los Angeles, Cal.

MONTAGUE RADIO SUPPLY
760 Laurel St.
Beaumont, Texas

PEERLESS RADIO DISTRIBUTORS
93-32 Merrick Rd.
Jamaica, N. Y.

W. D. BRILL CO.
198 10th Street
Oakland 7, Cal.

WOLMAR DISTRIBUTORS
417 Columbia St.
Utica, N. Y.

MICROTRAN® division of crest laboratories, Inc.

84-13 Rockaway Beach Blvd., Rockaway Beach 93, New York NEptune 4-3328

How helpful to a busy engineer is that sooner-than-expected report: "We've found the trouble!", "We can ship Friday!" or "I'm flying the prints out tonight!". Phillips customers are used to that help —a unique combination of engineering skill* and personal attention. We call it the *Phillips Plan*. To enjoy that extra service, write us, or call your local man from Phillips.

***FOR EXAMPLE:**
Phillips Engineered Relays
are used by the aircraft industry in automatic fire control equipment, and in propellor synchronizers for multi-engine planes.



20493 TYPE 4 — Hermetically-sealed miniature relay. Three stud mounting, maximum 14 pins, solder terminals. O.D. 1⅝"H x 2⅛"L x 1⅞"W.

TYPE 338QA / TYPE 338AC — all-purpose power relay, five pole. O.D. 2⅛"L x 2"W x 2⅛"H.



20445 TYPE 27QA — Hermetically-sealed power relay, three pole. Four stud mounting. O.D. 2⅛"W x 2⅛"L x 3⅝"H.

MULTI-CONTACT, POWER, HERMETICALLY SEALED RELAYS • ACTUATORS

PHILLIPS

PHILLIPS CONTROL CORPORATION . . . JOLIET, ILLINOIS

SALES OFFICES: NEW YORK • PHILADELPHIA • BUFFALO • SAN FRANCISCO • DENVER
SANTA MONICA • ATLANTA • DETROIT • CLEVELAND • DALLAS • SEATTLE

tion power diodes types 1N91, 1N92 and 1N93. They are designed for use in high-level modulation and detection in communications and control, a-f switching applications and rectification in the power range up to 25 w.

▶ **Specifications**—The diodes feature peak inverse voltages up to 300 v; peak forward currents up to hundreds of ma; low full load voltage drops (approximately 0.5 v); operating frequency, 50 kc; and storage temperature, 85 C.



F-M/A-M RECEIVERS
cover 19 to 500 mc

MARCONI INSTRUMENTS, 44 New St., New York 4, N. Y., has available two new f-m/a-m Eddystone receivers for measurements in the range of 19 to 500 mc.

Model 770R (covering 19 to 165 mc) is a superhet with a 5.2-mc i-f. Narrow-band a-m and f-m operation is augmented by a wide-band f-m position for use with high-quality transmissions. Deviation ranges are 15 and 75 kc. Sensitivity is better than 5 μv for 50 mw output and 15-db signal-noise ratio. A maximum of 2½ w audio is available from the push-pull low-distortion output stage.

The 770U (covering 150 to 500 mc) is a double superhet with i-f frequencies of 50 and 5.2 mc designed for a-m and f-m operation. Sensitivity is better than 10 μv for 50 mw output and a signal to noise ratio of 15 db. The bandwidth is 15 kc and image rejection is 25 db down at 400 mc and 10 db down at 200 mc.

MAGNETIC AMPLIFIER
low-level, push-pull unit

POLYTECHNIC RESEARCH & DEVELOPMENT CO., INC., 202 Tillary St., Brooklyn 1, N. Y. Type R6A5M1 low-level push-pull d-c magnetic am-

plifier is designed to amplify the output of low level devices such as thermocouples, strain gages, thermistor bridges phototubes or crystal detectors so as to operate an insensitive relay or meter. The amplifier is self-contained and requires no external rectifier.

▶**Specifications**—The unit has a power gain of 60, a low drift of 1 μa and will give 5 mw output with a 300 mv input. Stability and linearity are excellent within the ambient temperature rating of —55 C to + 85 C.

Units can be cascaded for increased gain. The R6A5M1 is hermetically sealed and highly resistant to shock and vibrations.

CRT TEST SET
operates automatically

RESEARCH ELECTRONICS LABORATORIES, Roslyn, Pa. Model 808 Autotester (for manufacturers' use) is a crt test set with one meter to read and one button (on tube socket) to push. Two small meters are for calibration purposes only.

▶**How It Works**—The operator merely places socket on the tube under test. This automatically starts a timer (adjustable to your own specifications) for warmup



"CLIP-TYPE"
closed entry socket contact
now standard in

BENDIX SCINFLEX ELECTRICAL CONNECTORS

Cannot be overstressed—eliminates intermittent circuit problems resulting from socket contact malfunction.

The heart of any electrical connector is the socket contact. This is why the Bendix-Scinflex* socket contacts have always been machined from bar stock. Stampings, with their required thin sections, can be easily overstressed.

Even with the machined sockets, industry has been plagued with overstressed spring leaves due principally to the misuse of test probes and lax tolerances on pin contacts. Bendix engineers have now provided the only socket contact on the market today which completely eliminates all these problems.

The "Clip-Type" socket will not accept any oversize probe or pin nor can one be forced into it. Also, no amount of wrenching or twisting of an acceptable pin or probe can possibly distort the spring clip. This new socket is now standard in all Scinflex connectors including those using solderless, high-temperature and thermocouple contacts.

Our sales department will be glad to furnish complete information on request.

*TRADE-MARK

SCINTILLA DIVISION of Bendix
SIDNEY, NEW YORK
AVIATION CORPORATION

Export Sales: Bendix International Division, 205 E. 42nd St., New York 17, N. Y.
FACTORY BRANCH OFFICES: 117 E. Providencia Ave., Burbank, Calif. • Stephenson Bldg., 6560 Cass Ave., Detroit 2, Michigan • 512 West Ave., Jenkintown, Pa. • Brouwer Bldg., 176 W. Wisconsin Avenue, Milwaukee, Wisconsin • 8401 Cedar Springs Rd., Dallas 19, Texas • American Bldg., 4 S. Main Street, Dayton 2, Ohio • 1701 "K" Street, N. W., Washington 6, D. C. • Boeing Field, Seattle 8, Washington.

Three of the world's largest producers of electronic equipment have recently made CUBIC Calorimetric Wattmeters standard test equipment in their laboratories and plants. For very good reason. No other instrument designed for power measurement gives you direct power readings... with such precision, and yet so simple in its application.

The model shown is the MC-1B for power measurement from 2600 to 26,500 MC. Also available are the models MCX-1A (coaxial type) for power measurement from 100 to 3000 MC, and MCL-1A (L-Band waveguide type) for power measurement from 1120 to 2600 MC.

Whether checking field equipment, developing or making acceptance tests on new equipment or magnetrons in the lab, or in production, one of CUBIC'S Calorimetric Wattmeters will be an invaluable addition to your test equipment. Standard laboratories calibrate secondary power devise, especially bridge type bolometer instruments. Exact calibration is provided month to month.

Write for more information, and ask for our catalog of other test equipment and waveguide components. Or if you have a problem in development or engineering, CUBIC offers the services of its engineering staff and facilities in its solution.

CUBIC CORPORATION
ELECTRONIC EQUIPMENT RESEARCH...DEVELOPMENT
2481 CANON STREET, SAN DIEGO, 6, CALIFORNIA

check. If within time (usually 30 seconds) tube emission is not standard (usually 0.5 ma, also adjustable) all further tests are locked out, and an indictor lamp shows SLOW WARM-UP. But a good tube, as soon as it reaches specific emission, automatically changes over to the next position, the standard two neon lamp short and leakage test, which indicates leakages up to 100,000 ohms—and the tube can be bounced in this position. Then gas is read by pushing a button on the crt socket, which automatically regulates all conditions for authoritative gas ratio test. No resetting is necessary—merely pull the socket off and on to the next tube immediately.

Price of the model 808 Autotester is $240.

LAB-TYPE OSCILLATOR
covers from 18 cps to 1.1 mc

ALLEN B. DUMONT LABORATORIES, INC., 750 Bloomfield Ave., Clifton, N. J. Type 347 extended-range oscillator covers from 18 cycles to 1.1 mc in 5 overlapping ranges. It costs only $150. It weighs 6 lb and measures 6 in. deep, 6½ in. high and 4½ in. wide. Output voltage is 10 v open circuit and distortion is less than 0.2 percent over most of its useful range.

► **Applications**—The combined advantages of the type 347 make it an ideal instrument for testing of sound and high fidelity systems and for work in ultrasonics. The unit's ability to operate on power supplies of 50-400 cps permits it to be used in airborne applications such as

testing of intercom installations and other aircraft electrical systems.

For application where it is necessary to operate the type 347 with balanced output, a new matching transformer, type 2624, is available. This provides the maximum output of +8 dbm.

PRECISION WATTMETER
is a low-power unit

PHYSICS RESEARCH LABORATORIES, INC., 507 Hempstead Turnpike, West Hempstead, N. Y., announces the Goerz (Vienna) low-power precision wattmeter.

▶ **Ranges and Accuracy**—With current ranges of 10 ma and 50 ma and voltage ranges of 150, 300 and 450 v at a full-scale accuracy of 0.5 percent, this wattmeter is particularly well adapted to the measurement of power consumption in relay coils, voltage coils and the like.

TELEPHONE AMPLIFIER
uses magnetic induction

REMLER CO., San Francisco, Calif. A new 3-oz telephone amplifier powered by dime-sized batteries is now available for those who use telephones in noisy locations and for

ACE

SPECIALIZED SERVICE

. . . . . keeps your Ace enclosure on the job!

Put it up . . . take it down . . . air condition it . . . make it larger—or smaller! Whatever the future demands of your Ace shielded enclosure, *you'll be prepared.* Years from now you'll still benefit from the same sound advice and counsel offered by Ace engineers in the original design of your enclosure. Why? Because Ace—and only Ace—*stands behind the service of your enclosure, as well as the performance.*

Little wonder, then, that laboratories, hospitals, manufacturers of every description, and the military prefer Ace. *It's the one enclosure you can buy today for tomorrow's needs.* Whether you're interested in an entirely new enclosure or modification of your present installation, you'll find it pays to call on Ace.

Detailed information on the complete line of Ace enclosures—featuring highest attentuation, full interchangeability*, inside bolting* . . . and exceeding the performance requirements of MIL-E-4957A (ASG)—is given in Bulletin 10 available on letterhead request.

(*Patents Pending)

As an additional feature Ace can now supply shielded enclosures with microwave absorber to simulate free space—or can modify existing installations for microwave testing.

ACE ENGINEERING & MACHINE COMPANY

3644 North Lawrence Street • Philadelphia 40, Pennsylvania

JENNINGS VACUUM RELAYS

For Switching Antennas, Pulse Forming Networks, and Similar RF and DC Circuits



Jennings RADIO
VACUUM ELECTRONIC COMPONENTS

NOTE the copper disk in the coil housing between the armature and coil. This disk provides a vacuum seal without shorting out the magnetic circuit. The result is an efficient magnetic circuit that permits the use of a small, low wattage coil in a relay that will pass MIL-R-5757B vibration tests.

Other outstanding features common to all of these relays are:

- High voltage and current ratings because the series-break contacts are sealed in a high vacuum.
- Very low contact resistance (less than .01 ohms); a contaminating film cannot form on properly outgassed contacts sealed in a vacuum.
- An actuating coil that is easily removed.
- Simple flange mounting. If necessary, the high voltage terminal can be inserted into a pressurized or sealed container with the low voltage terminals accessible from the outside.

Continuous ratings are 10 and 12 KV, 10 to 15 amperes rms. Contact arrangements now available include NO, NC, SPDT, 2PDT, and 4PDT.



Send for catalog literature describing these and larger vacuum switches and relays with ratings up to 85 KV and several hundred amperes.

JENNINGS RADIO MANUFACTURING CORPORATION · 970 McLAUGHLIN AVE. P.O. BOX 1278 · SAN JOSE 8, CALIFORNIA

the hard of hearing. The phone aid clips over any style telephone receiver.

The pocket-size electronic device is a reproducing receiver and a 3-stage amplifier with transistors taking the place of tubes. It increases the acoustic output of telephones by 49 db.

► **Magnetic Induction**—The phone aid picks up speech from the telephone by magnetic induction which cuts out all room noise. An ingenious circuit shuts out disturbances created by electrical circuits and appliances.

No warmup is necessary. Volume is adjusted while in use and the unit automatically shuts off when removed from the telephone.

Price, including batteries, is $49.50.



ELECTRONIC SWITCH
for wide-band operation

TELETRONICS LABORATORY INC., 54 Kinkel St., Westbury, L. I., N. Y. Model ES-180A wide-band electronic switch provides d-c to 15 mc dual trace oscilloscope presentations on any conventional oscilloscope at switching rates up to 400 kc.

A movable horizontal index and provisions for introducing time markers make extremely rapid and accurate amplitude and time measurements possible. A control dial, calibrated in both volts and percent, allows absolute and relative amplitude measurements to within 2 percent accuracy.

► **Specifications** — The amplifier rise time is 0.023 μsec; input impedance, 1 megohm; and output impedance 93 ohms.

Unity gain, negative feedback

and regulated power supplies are provided for maximum linearity and stability. Price is $495.



COIL WINDER DRIVE
a compact bench-type unit

CROWN INDUSTRIAL PRODUCTS CO., 713 Amsterdam St., Woodstock, Ill. The series 50 coil winder drive handles everything from solenoid coils up to 5-hp winding field, mush, armature and similar types of coils. The gear arrangement is designed for smooth operation and constant torque with no backlash, giving the operator precise control.

Price is $198 without motor, $225 with ½-hp 120-v motor.



TINY CRYSTAL OVEN
for military communications

BULOVA WATCH CO., INC., Valley Stream, L. I., N. Y. Model AB-200 miniature precision crystal oven is designed primarily for use in military communications equipment. Fitted with an octal base, the unit features a patented heater design which eliminates the necessity for



headquarters for digital magnetic and perforated tape handlers

Model 902 Magnetic Tape Handler treats the tape gently while providing a start/stop time of 5-milliseconds. Fully reversible without stopping.

Model 903 Perforated Tape Reader provides a 5 millisecond start time and stops on the character at 300 characters per second and on the character following a stop code at 600 characters per second.

The Potter Digital Magnetic Head eliminates "digit drop-outs" due to oxide collection. Phosphor bronze head mount provides close tolerances insuring complete interchangeability of tape from one machine to another.





Whether your data processing requirements call for perforated or magnetic tape handling, Potter offers a complete line of high-speed equipment to meet your needs . . . for either intermittent or continuous playback with speeds of up to 60 inches per second and start/stop times of less than 5-milliseconds!

Servo-controlled tape drives permit fast starts and stops without tearing or spilling tapes. At 30 inches/second speed, less than ⅛" of tape is consumed in a start/stop cycle!

For complete specifications on Perforated Tape Readers, Magnetic Tape Handlers and Digital Magnetic Recording and Playback Heads, write TODAY:

Potter

POTTER INSTRUMENT CO., INC.
115 Cutter Mill Road
Great Neck, New York

Stupakoff

ALUMINA CERAMICS



These man-made "sapphires" provide

EXTRA strength . . .
EXTRA hardness . . .
EXTRA precision . . .

For mechanical, electrical and electronic applications, Stupakoff Alumina Ceramics provide highly valuable characteristics. Because they are exceptionally hard, parts made of this material serve well under conditions of abrasion and wear. Because of the material's high strength, it finds many applications where its resistance to pressure, shock and impact adds to the life and service of an assembly. Because Stupakoff has the equipment and skill to mass-produce alumina parts with dimensions held to close tolerances, Stupakoff precision ceramics assemble readily and function correctly.

Parts may be simple or complex, ground or machined, plain, metallized or assembled. Our research and engineering facilities are available to assist in the design of your parts.

Stupakoff

Write Dept. E.

Division of The CARBORUNDUM Company

LATROBE, PENNSYLVANIA

two thermostats. Long trouble-free service is claimed.

Operating temperature of the unit is preset to customer's requirements; the heater voltage, either 27 or 110 v.

D-C AMPLIFIER
has 160,000 maximum gain

KEITHLEY INSTRUMENTS, INC., 3868 Carnegie Ave., Cleveland 15, Ohio. Model 303 d-c indicating amplifier has an input impedance of over 1 million megohms, a maximum gain of 160,000, and a frequency response of d-c to 100 kc.

▶ **Other Features**—The unit has an accurate meter, with ranges of 2 to 2,000 mv full scale, a power amplifier for driving all common direct-writing recorders, a differential input, and a zero drift of less than 2 mv per hour on any range or gain setting.

Input terminals are mounted on a small plug-in panel which can be interchanged with plug-in multipliers that extend the voltage range to 800 v full scale, or a plug-in decade shunt that converts the instrument to a direct-reading micromicroammeter.

▶ **Uses**—The amplifier may be used to measure voltages as low as 200 μv, currents down to 10^{-15} amperes, and resistances up to 10^{14} ohms. It is suited for measuring transistor, piezoelectric crystal, and capacitor potentials, and currents in semiconductors, photocells and ion chambers.

HOT-COLD CABINET
primarily for aircraft use

ATMOSPHERE CONTROL CO., INC., 5315 Chester Ave., Philadelphia 43, Pa., has announced a hot and cold cabinet that is used primarily by aircraft component producers. It is



available in a choice of two models —stationary and movable—and can be used efficiently in any part of the laboratory in conjunction with breaking-strength and tensile-strength testing machines.

Range of temperature is from −100 to +600 F.

▶ **Control Specifications** — Either model can be equipped with various types of controls from vapor-pressure type to the electronic type, depending upon the degree of accuracy demanded, and same may be either the indicating or recording.

Air circulation is according to customer specifications.



FREQUENCY RELAY
a low-cost series

POTTER AND BRUMFIELD, INC., Princeton, Ind., announce a new

Stupakoff

KOVAR ALLOY
for glass sealing



Kovar is available as sheet, strip, foil, rod, tube, wire—or fabricated cups, eyelets, leads, other shapes.

STRONG . . . DURABLE . . .
Easy to use
Available

The ideal alloy for glass sealing, Kovar matches the expansivity of certain hard glasses over the entire working temperature range. It resists mercury attack, has ample mechanical strength and seals readily with simple oxidation procedure.

Kovar produces a permanent vacuum-tight seal, and is readily machined or fabricated to permit the use of small and intricate shapes. It is of controlled composition and processing to permit duplication of results. Usable in any thickness; no need to feather edge on tubular or intricate shapes, and is relatively inexpensive, eliminating restraints on sizes and capacity. Can be welded, soldered, and brazed to other metals.

Stupakoff

Write Dept. E

Division of The CARBORUNDUM Company

LATROBE, PENNSYLVANIA

For additional information on all items on this page, use post card on last page.

JET PROPULSION LABORATORY

OF THE

CALIFORNIA INSTITUTE OF TECHNOLOGY

Pasadena, California

jpl

has positions now open in several fields of

MISSILE GUIDANCE SYSTEM DEVELOPMENT

This is an opportunity to associate yourself with the nation's foremost guided missile research and development facility.

1) *System Analysis*

Engineers, Physicists or Mathematicians are wanted for rocket guidance system planning and analysis. The work requires a combination of imagination and a high level of analytical ability. Experience in the engineering type problems of guidance or related equipment is very desirable. This overall system work provides the opportunity to become familiar with a broad variety of interesting and challenging fields. Excellent digital and analogue computers are available for use in the studies.

2) *Inertial Guidance*

Engineers and Physicists are wanted for missile inertial guidance component development. Work involves design, development and evaluation of gyros, accelerometers, integrators, stable platform systems and associated apparatus. Particular emphasis is placed on the problem of achieving component performance under severe environmental conditions, and on development of advanced testing techniques.

3) *Layout and Packaging*

Engineers are wanted for layout design and proof testing of electronic and electro-mechanical packages with emphasis on meeting vibration, temperature, and system operation requirements.

4) *Switching Circuits*

Engineers are wanted to design low power switching, control, and power circuits, with emphasis on reliability and ease of operation.

The Jet Propulsion Laboratory is located in a suburban area of Pasadena, California. It offers these advantages:

Desirable academic associations
Emphasis placed on research and development
Excellent laboratory and model shop facilities
Attractive salaries
A stable yet progressive organization

Interviews are conducted by members of our engineering staff.

Airmail your summary of qualifications to:

CALTECH | **JET PROPULSION LABORATORY**

4800 Oak Grove Drive — Pasadena, California

low-cost series TR frequency relay.

► **Range**—It features a range of frequency from 40 to 170 cps with a 400-ohm coil as standard. Other frequency ranges are available for special applications.

A maximum of 10 standard relays may be installed in a control panel each operated by a signal to which it has been tuned. Each in turn will operate an auxiliary relay for closing or opening any circuit.



SMALL BLOWER
for space-conscious designs

RIPLEY CO., INC., Middletown, Conn. The L-R No. 1 subminiature self-contained motor blower is engineered for space-conscious designs.

Using a 1-in. diameter impeller, this unit will efficiently move 8 cfm at 1-in. static pressure when running at 20,000 rpm. Total weight of blower and motor unit is less than 2¾ oz. Designed to meet military specifications, it is available in ccw and c-w rotation. High efficiency and long life under the most rigorous conditions are assured.

P-W AMPLIFIER
for keying and recording

APPLIED SCIENCE CORP. OF PRINCETON, P.O. Box 44, Princeton, N. J., announces a new model DKA-1 p-w keyer-record amplifier unit used for p-w multi coding and direct recording of numerous data channels onto single track of an Ampex magnetic tape recorder. The unit combines a standard 900

sample-per-sec pulse width keyer and a record amplifier in a single unit which is interchangeable with the f-m or pwm/a-m record strips in the record electronics assembly of any of the Ampex 800 series airborne recorders.

For each track of p-w recording required the DKA-1 and any standard ASCOP p-w commutator producing timing signals and 900 data samples per sec in the 0 to +5-v range achieve the desired result with a minimum of equipment.

The unit meets all essential functional requirements of MIL-E-5400.

▶ **Measurements**—Model DKA-1 is 1.484 in. wide by 6.718 in. high by 6.522 in. deep. Weight is 1 lb 3 oz.



ACCELEROMETERS
for aircraft applications

CEDAR ENGINEERING, INC., 5806 W. 36th St., Minneapolis 16, Minn. A series of new accelerometers offer a wide selection of single and multi-axis devices that have been fully qualified for yaw damping, acceleration limiting, turning rate, and sim-

Kleiner's Pride: PERSONNEL, PLANT, AND PRODUCT

Seamless tubing parts cut, flared, flanged or bulged to exacting engineering specifications, require special handling all the way down the line for highest results. All our personnel take a special interest in every order received in this plant—to see that our product never falls short of the customers' standard.

We believe our highly skilled personnel are worthy of the finest tools and machines. As a result our plant is equipped with tools and machines specially designed by these skilled craftsmen.



Kleiner seamless tubing parts retain uniform wall thickness—are cut with square ends, and vary from no burr to a maximum of one thousandths of an inch. Our continuous quality control checks these and other factors to insure parts that meet our customers' every requirement.

We have produced more than 300 million parts from seamless tubing—all to close-tolerance engineering specifications, so we hope you will pardon our use of that overworked phrase, "KNOW HOW".

Cost per piece is lower due to high production—seamed components with their high tooling and die costs are eliminated—no secondary spot welding and deep draws needed.

USE KLEINER SEAMLESS TUBING PARTS
Send Your Prints For Quotation

KLEINER METAL SPECIALTIES INC.
P. O. BOX 185, DUNELLEN, NEW JERSEY

NEW!

smaller socket for
septar based tubes such
as the 5894, 6524, 6252



Considerably smaller than previously available types, this new 7-pin VHF septar socket permits compact design in mobile, aircraft, and other types of transmitting equipment. Bases on all three types are grade L4 steatite, glazed on top and sides—underside DC200 impregnated.

Available in three grades to meet all applications:

Standard—122-105-1
Industrial—122-105-100
Military—122-105-200

Contacts on the standard grade are cadmium plated, with brass clips and steel springs. Contacts on industrial and military grades consist of phosphor bronze clips with beryllium copper springs. Contact plating on industrial type, .0005 silver; military, .001 silver. Aluminum shell finish is etched on standard; Iridite No. 14 on industrial and military types.

Additional Features

- Molded recesses in base for each contact—prevents turning
- Contact cushion washers of fungus resistant glass base melamine
- Sockets molded with pin circle groove and recessed tube pin holes for easy tube insertion
- Aluminum shell submounts tube for optimum input and output shielding, ⅜" hole provides adequate ventilation.

Special Types Available

Wafer socket alone, without shield base. Sockets with special grid terminal for direct mounting of components.

Write today for prices or further information.

E. F. JOHNSON COMPANY

2334 Second Avenue Southwest • Waseca, Minnesota

ilar aircraft applications, as well as industrial automation. They measure accelerations from ½ g to 50 g.

► **Response Element**—A nonpendulous, turly linear response element eliminates crosstalk and provides a completely basic linear output. The response elements can be housed in a variety of frames to meet mounting conditions and are available with potentiometer pickoff, inductive pickoff, or switches with manual or automatic reset.

Potentiometer life for most models is in excess of 8 million cycles.

TINY COAX CABLES
are Teflon insulated

HITEMP WIRES, INC., 26 Windsor Ave., Mineola, N. Y., introduces a new line of miniature coaxial cables. These Teflon insulated cables are available in 3 standard types, 50, 70 and 93 ohms. Each type of cable can be obtained with an outer covering of Vinyl, Nylon, Kel-F, Teflon or a glass-fiber braid. Special low noise types are also available in any of the aforementioned types. Prices range from $125 to $382.50 per 1,000 ft, depending on the conductor, outer covering and type of cable.

► **Uses**—Because of their small diameter and light weight, these cables are excellent for aircraft and telemetering applications.

PULSE TRANSFORMERS
withstand severe conditions

TECHNITROL ENGINEERING CO., 2751 N. Fourth St., Philadelphia 33, Pa., announces availability of MIL grade and X grade pulse transformers in the same sizes as the



standard TE and TP types. They exceed MIL T-27A specifications for temperature cycling. MIL grade units safely withstand temperatures from — 70 C to + 105 C, and X grade units from — 70 C to + 150 C.

▶**Other Features**—The new encapsulating material renders these transformers nonflammable and impervious to humidity, salt spray and other severe conditions. A special phosphor bronze alloy now used for the pig tail leads enables the units to far surpass the bending and twisting requirements of military specifications.



PLUG-IN UNITS
in varied lengths, materials

STAMCO INSTRUMENT CORP., Larkin St., Springdale, Conn. Plug-in units made of heavy gage (0.060) aluminum are available in stock lengths from 1 in. to 12 in. in steps of ½ in. Standard diameter is 1⅛ in. o-d. Other materials may be substituted for aluminum according to requirements, including steel, stainless and others.

▶**Special Requirements** — Opening at both ends, the units are applicable to many special requirements including potting. The end caps are made to close tolerance making a friction closure strengthened by screws. Terminal-strip circuit mountings are included in the assembly in all lengths upon request.

Standard plugs are octal or mini-

NEW SENSITIVE, WIDE RANGE DC-VTVM

Measures 25 uV to 1 000,000,000 uV



Type MV - 27 C

IT FILLS A NEED .... where higher sensitivity and greater accuracy are required and justify its slightly higher cost.

MV-27C (NEW)
RANGE: 0 - 250 uV to 0 - 1 kV
ACCURACY: 2 % full scale
PRICE: $320.00 f.o.b. Schenectady

MV-17C (STANDARD)
RANGE: 0 - 1 mV to 0 - 1 kV
ACCURACY: 3 % full scale
PRICE: $295.00 f.o.b. Schenectady

Time Progresses - So Do We

MILLIVAC INSTRUMENT CORPORATION
P.O. BOX 997, SCHENECTADY, NEW YORK

92,000 hours from now!

It is difficult to realize that this historic "flying machine" is just 92,000 working hours old.

From that 1910 beginning to today's new multi-jet Navy XP6M SeaMaster, Martin has developed and produced a new aircraft design every 1500 hours of the working calendar.

On this backlog of experience—unmatched by any other aircraft company in the world—one of the youngest and most dynamic managements in the industry is engineering new methods that are thousands of hours ahead of the aircraft calendar.

You would do well to find out what's happening at Martin – and what the opportunities there in AERODYNAMICS, ELECTRONICS, STRUCTURES, PROPULSION and NUCLEAR POWER might do to speed up your own calendar of progress.

Contact J. M. Hollyday, Dept. E-1, The Martin Company, Baltimore 3, Maryland.

MARTIN
BALTIMORE

ature. Upon request, octal or miniature sockets may be mounted on top to accept tubes or facilitate stacking.

Complete descriptive literature is available. Information concerning diameters other than the standard 1¼ in. will be furnished upon request on company letterhead.



CRYSTAL FILTERS
produced by new technique

HYCON EASTERN, INC., 75 Cambridge Parkway, Cambridge 42, Mass. A new technique for the synthesis of quartz crystal filters resolves many of the problems heretofore associated with their design and production. Filters can be produced on short notice in large or small quantities to meet exact performance requirements.

▶ **Characteristics**—Quartz crystal filters can be realized to any frequency from 10 kc to 10 mc. Throughout this range the attenuation characteristic can be tailored to meet almost any desired specification within the bandwidth limits from 0.01 percent to 14 percent of center frequency.

For applications where absence of phase distortion is essential, crystal filters can be designed with a high degree of phase linearity. Stable band-pass delay lines may be produced in this manner.

For a given filter specification, information on the most economical values can be provided.

COMMUTATOR
drum type coded-switching

ELECTRO-MINIATURE CORP., 205 Lafayette St., New York, N. Y., has developed and is in production on a new drum-type coded-switching

commutator. The commutator in drum form gives dependable, trouble-free performance in the smallest possible space. All switching combinations are attainable.

▶ **Purpose of Drums**—These drums are particularly well suited to cascade operation. Solid, precision made, precious metal or alloy segments and Nylon or Kel-Fallow extensive ranges of operating conditions, insure long shelf life and give stable operation in service.

Simple registration techniques make possible highly accurate angular resolution as well as exceptionally small segments. Size and weight for airborne and military applications are minimal.

PULSE HEIGHT VTVM
for development engineers

TELEVISION ACCESSORIES CO., 1412 Great Northern Bldg., Chicago 4, Ill. The PV-812 pulse height vtvm measures repetitive pulse heights with an accuracy of better than 2 percent of full-scale deflection.

Readings are entirely independent of pulse width from 0.01 μsec upward.

▶ **Ranges**—The unit provides ranges of 0 to 10, 0 to 30, and 0 to 100 v; and the 5-in. meter is equipped with a knife-edge pointer and mirror scale.

OSCILLATORS
are voltage tuned

HUGGINS LABORATORIES, INC., 711 Hamilton Ave., Menlo Park, Calif., has available a series of backward-

HEILAND OSCILLOGRAPH CHARTS "NIGHTGLOW" ON LONELY MOUNTAIN PEAK

Dr. Franklin E. Roach, consulting physicist to the National Bureau of Standards, loads a record take-up drum into the Heiland oscillograph.

On wind-swept "Fritz Peak" in the Colorado Rockies, the broad capacity of the Heiland 712 oscillograph goes to work on every cloudless and moonless night, charting the airglow in the sky.

Charting these night-light phenomena formerly required 30 minutes, but a complete record of the skies is now taken every 3 minutes.

A 4-telescope Photometer—installed at the top of the 9,000 foot mountain—sends information on the amount and quality of light in the skies to the Heiland 712 Oscillograph located in the trailer laboratory below. Heiland galvanometers convert these data into clear, easily-readable oscillograms for later study.

The National Bureau of Standards "Airglow" Project is engaged in a study of the earth's upper atmosphere. It is expected that this research will reveal high-speed fluctuations in the airglow, which originates in that part of the upper atmosphere known as the ionosphere.

Heiland Series 700-C Recording Oscillographs provide record widths as great as 12 inches, accommodate up to 60 channels and have record speeds through 144 inches per second. Galvanometers with unequalled sensitivity ratings are available in frequencies up to 5000 cps.

• **Write for Bulletin 700 CFPK for details.**

Heiland® H HONEYWELL
A DIVISION OF MINNEAPOLIS-HONEYWELL
130 E. 5th Ave., Denver 3, Colo.

PRECISION
Continental Connectors

Solve space and weight problems with Continental subminiature electrical connectors

Continental Connectors are pace-setters in subminiaturization to meet increasing demands for rugged equipment of small size and weight. Where weight and space are at a premium, in aircraft and instrumentation applications, they provide excellent precision connection.

Series 1300, 5-Contact ACTUAL SIZE

Subminiature AN-Type Series 1300

Precision-machined aluminum shells meet military requirements for salt-spray test resistance. One-piece molded inserts prevent moisture traps and electrical breakdowns possible with conventional AN two-piece inserts. Floating contacts guarantee self-alignment of each contact and reduce engagement and disengagement to a minimum. Inserts are permanently swaged into shell to form a single cartridge unit. Current Rating: 7.5 amps. Contacts take #20 AWG wire. Two shell sizes are available: one for 3, 4, and 5 contacts; the second for 15, 19, 27, and 31 contacts.



Series SM-20, 7 Contacts (Shown with * Polarizing Screwlocks) ACTUAL SIZE

Subminiature Rectangular Series SM-20

Contacts are phosphor bronze, gold plated over silver for low contact resistance and soldering ease. Floating contacts assure positive alignment of each contact. .040 diameter contacts eliminate assembly difficulties encountered when soldering sub-standard wires. Polarizing screwlocks (See photo) and other contact arrangements are also available in this series. Rating: 5 amps. Contacts take #20 AWG wire.

Series G-20, 2 Contacts ACTUAL SIZE

Subminiature Rectangular Series G-20

Ideal for the small spaces. Molding has hole for convenient, space-saving side mounting. Precision-machined sockets of spring temper phosphor bronze and pin contacts of brass are gold-plated over silver for lowest contact resistance and easy assembly soldering. Connectors are available in 2, 3, and 4 contacts with a variety of pin arrangements, with or without hood and cable clamp.

* Pat. Pend.

Technical data on these connectors, and special designs requiring the use of subminiature, hermetic seal, pressurized, high voltage, or power connectors, are available on request. Write today for complete catalog.

Electronic Sales Division
DeJUR-Amsco Corporation,
45-01 Northern Boulevard, Long Island City 1, N. Y.

DeJUR



wave oscillators featuring electronic tuning across their respective frequency ranges. Tuning is accomplished by varying or sweeping a single voltage without any complementary mechanical adjustments. The frequency band may be traversed at μsec rates.

► **Applications**—This type of oscillator should find its greatest use as a swept signal source for microwave instrumentation and testing, as a swept local oscillator in superheterodyne receivers, and as a master oscillator in variable frequency transmitters.

► **Characteristics**—The four tubes span the frequency ranges of 2 to 4 kmc, 3.75 to 7 kmc, 7 to 14 kmc, and 12.4 to 18 kmc with power outputs of approximately 100 mw, 100 mw, 50 mw and 10 mw respectively. Tuning voltage in all cases is within the range of 300 to 3,300 v.



TRANSFORMERS
missile and computer types

PULSE ENGINEERING, 2431 Spring St., Redwood City, Calif. A complete range of designs in miniature wide-band transformers are available from this firm for application in pulse and computer circuitry. Type ES6 and ES7 performance ratings extend from 0.2 μsec to 20 μsec pulse width in blocking oscil-

lator and pulse coupling circuits. They are also provided as wide-band step-up step-down transformers for tape and computer circuits up to 10-to-1 turns ratio. High potential ratings of 2 kv d-c may be called out on ES6 designs.

▶ **Military Requirements**—All units are epoxy impregnated and will withstand environmental requirements of MIL-T-27A including shock, temperature cycling, humidity, salt spray and vibration.

L-V CAPACITOR
for transistor use

GLENCO CORP., 212 Durham Ave., Metuchen, N. J., is producing a new series of Ceramistor low-voltage capacitors, particularly well-suited for use in transistorized circuits for bypass and coupling applications.

▶ **Construction and Size**—Rated at 75 v maximum, this subminiature component features rectangular plate construction and the patented thin-sheet process of manufacture for obtaining maximum capacitance in minimum space. Sizes vary from $\frac{1}{8}$ to $\frac{1}{2}$ in. sq, with capacitance range from 0.001 μf to 0.1 μf. Ceramistor capacitors of other values and sizes can be built to specification.

TEST EQUIPMENT
inspects bars and tubing

MAGNETIC ANALYSIS CORP., 42-44 Twelfth St., Long Island City, N. Y., has developed new electronic testing equipment designed for the metal-producing and metal-working industries to inspect nonmagnetic

BALLANTINE

BATTERY OPERATED
ELECTRONIC VOLTMETER

VOLTAGE RANGE:
100 microvolts to 100 volts rms of a sine wave in 6 decade ranges.

INPUT IMPEDANCE:
2 megohms shunted by 8 mmfd on high ranges and 15 mmfd on low ranges.

FREQUENCY RANGE:
2 cps to 150,000 cps.

ACCURACY:
3%, except 5% below 5 cps and above 100,000 cps and for any point on meter scale.

MODEL 302B
Size: 6⅞"x 7½"x 12⅛"
Weight: 14 lbs.
Price complete with cover and batteries: $245.

- Available accessories increase the voltage range from 20 microvolts to 42,000 volts.
- Available precision shunt resistors permit the measurement of AC currents from 10 amperes down to one-tenth of a microampere.
- Features the well-known Ballantine logarithmic voltage and uniform DB scales.
- Battery life over 100 hours.
- Can also be used as a flat pre-amplifier with a maximum gain of 60 DB. Because of the complete absence of AC hum, the amplifier section will be found extremely useful for improving the sensitivity of oscilloscopes.

For further information on this Voltmeter and the Ballantine Model 300 Voltmeter, Wide-Band Voltmeters, True RMS Voltmeter, Peak to Peak Voltmeters and accessories such as Decade Amplifiers, Multipliers, Precision Shunt Resistors, and Precision Sensitive Inverter, write for catalog.

BALLANTINE LABORATORIES, INC.

100 FANNY ROAD, BOONTON, NEW JERSEY

PRESSURIZE ELECTRONIC EQUIPMENT

with Eastern UNITS

The extensive line of Eastern Pressurization Units for airborne electronic equipment accommodates a broad range of requirements, and meets appropriate government standards.

Units can be modified to meet your specific requirements. These modifications usually consist of: 1) Different compressors; 2) Motor change to meet your requirement; 3) Change in pressure switch settings; 4) Different mounting provisions. Eastern welcomes the opportunity to discuss and quote on your particular application problem.

MODEL E AP-100 TYPE 202

- Maintains a system pressure of 25 P.S.I.A. minimum.
- Motor is .03 H.P.—10,000 R.P.M., 208 V., 3 ph., 400 cy.
- Current draw is .7 amperes/phase maximum under normal operating conditions
- Unit operates continuously
- Weight is 4¾ lbs. maximum



MODEL E AP-150 TYPE 205

- Operating pressure switch maintains a system pressure of 17 P.S.I.A.
- Motor is 1/25 H.P. 7,500 R.P.M., 27 volts D.C. — T.E.S.B.
- Current draw is 2.0 amperes maximum under normal operating conditions
- Life is 500 operating hours
- Weight is 8 lbs. maximum



MODEL E AP-1500 TYPE 203

- Operating pressure switch maintains a system pressure of 30 P.S.I.A.
- Motor is 1/15 H.P. nominal 24-28 volts D.C., 5,000 R.P.M., continuous duty, shunt wound
- Current draw is 3.4 amperes maximum under normal operating conditions
- Life is 500 operating hours
- Weight is 12 lbs. maximum



MODEL E AP-2400 TYPE 201B

- Maintains system pressure of 31 P.S.I.A.
- Motor is 1/10 H.P., 24-28 volts D.C., 5,000 R.P.M. continuous duty
- Current draw is 5.5 amperes maximum
- Life is 500 operating hours
- Weight is 10-3/4 lbs. maximum



MODEL E AP-3600 TYPE 200

- Maintains system pressure of 31 P.S.I.A.
- Motor is 1/7 H.P., 10,000 R.P.M. { 208 V., 400 cy., 3 ph. / 24-28 V.D.C. } continuous operation
- Current draw is { 1.3 amp./phase / 7.1 on D.C. } amperes maximum under normal operating conditions
- Life is 1,000 operating hours
- Weight is 8-1/2 lb. maximum



Eastern INDUSTRIES, INC.
100 SKIFF STREET
HAMDEN 14, CONN.

COMPLETE AVIATION CATALOG #330-P ON REQUEST.

stainless steel bars and tubing—both seamless and welded.

▶**Warning System**—An audio-visual warning system indicates external mechanical defects in bars, such as cracks, seams and slivers. In seamless and welded tubing, it indicates mechanical defects both on inside and outside diameters, as well as imperfect welds. Differences in chemical composition and cross-sectional dimensions are likewise detected.

A meter and an oscilloscope are provided in addition to the audio-visual warning system to give more complete information. Testing speed is approximately 200 ft per minute.



BATCH COUNTER
operates indefinitely

SPENCER MFG. CO., 3253 N. Cicero Ave., Chicago 41, Ill. The batch counter has been developed for controlling the number of items in a batch to be counted or measured with control of quantity before or after an operation, as desired. The control function—ringing of a bell or stopping of a machine, can be

made on a conveyor or at a machine or press.

▶ **Performance**—This counter can be preset at any figure within the range of 5 digits (specials available). At each impulse a subtraction of one is made from the preset figure until the counter reaches zero. The counter then performs the control function. As further impulses are received, the counter adds one for each impulse until it reaches the original preset figure, then it again performs the control function and then starts the subtracting operation over again.

This counter requires no resetting at the end of each cycle and will continue to operate indefinitely until the preset figure is changed. Electrical control panel with release are built in. Size is 5 in. deep by 10 in. high by 12 in. wide.



DRIVE MOTOR
with adjustable speed range

SERVO-TEK PRODUCTS CO., INC., 1086 Goffle Road, Hawthorne, N. J. The 100 series of drive motors permits a precise adjustment of speed over a 100-to-1 speed range. Any given speed setting can be repeated and held to better than 0.5 percent of full-rated speed in spite of wide changes in line voltage, temperature or torque load. Both ¼ and ½-hp models are available, either of which can be adjusted for any speed between 36 and 3,600 rpm.

▶ **Encapsulation**—Of particular note is the use of a concrete-like epoxy resin to fully encapsulate all resistors, capacitors and the like, within easily removed plug-in assemblies. A screwdriver is the only

From DIALCO—New, Compact

OIL TIGHT INDICATOR LIGHTS

for heavy duty industrial applications

OIL TIGHT
DUST TIGHT
OMNIDIRECTIONAL

Exceptionally Rugged!

Perfect oil-tightness is effected by retained oil-proof gaskets and the gasketed glass lens assembly.

These units have many heavy-duty features: *One-piece solid brass bushing, solid brass lens holder, high impact phenolic insulation, rugged binding screw terminals.*

They install easily in a single 1" or 1 3/16" panel mounting hole. Other units available for 1 1/16" mounting hole. *A choice of 3 lens styles, 7 lens colors,* and other optional features provide adaptability. If you have an unusual problem, consult our engineering department.

DISCS with legends, behind flat lenses, deliver specific messages.

Illustrations are approx. actual size

DIALCO

OIL TIGHT INDICATOR LIGHTS

accommodate a wide range of Incandescent and Neon Glow Lamps. For neon, DIALCO offers an exclusive feature — *BUILT-IN RESISTORS* (U. S. Patent No. 2,421,321) for operation on 105-125 V, or 210-250 V. Simple external resistors are provided for all higher voltages. *EVERY ASSEMBLY IS AVAILABLE COMPLETE WITH LAMP.* For design purposes we will send:

SAMPLES ON REQUEST—AT ONCE—NO CHARGE

CATALOG "L-200" gives you complete specs on DIALCO'S Oil-Tight Indicator Lights. Also available—a file of Special Catalogs on DIALCO Pilot Lights covering every indication requirement.

FREE — Brochure on *"Selection and Application of Pilot Lights"*.

Foremost Manufacturer of Pilot Lights

DIALIGHT CORPORATION

58 STEWART AVENUE
BROOKLYN 37, N. Y.
HYACINTH 7-7600

DIALIGHT CORP., 58 Stewart Ave., Brooklyn 37, N. Y.

☐ Please send Cat. "L-200" on Oil-Tight Lights
☐ "Selection" Brochure. ☐ Pilot Light Catalogs.

Name _____

Company _____

Address _____

City _____ State _____

Where dependability, long life and uniform performance are all-important . . . select

Bendix Red Bank

HARD GLASS Miniature Beam Power Amplifier

Here's another advance in the Bendix Red Bank "Reliable" Vacuum Tube program. Featuring a hard glass bulb and stem with gold-plated pins . . . plus a conservative design center of cathode temperature . . . the Bendix Red Bank RETMA 6094 can operate at temperatures up to 300° C. compared to an average of only 175° C. for soft glass bulbs. Thus, this new tube ideally meets aircraft, military and industrial applications where freedom from early failure, long service life, and uniform performance are essential.

The Bendix 6094 uses pressed ceramic spacers, instead of mica, for element separation. In other tubes, deterioration of mica in contact with the hot cathode causes loss of emission which is greatly accelerated under shock and vibration. Ceramic eliminates this problem and greatly reduces damage caused by fatigue failure of parts.

For complete details on our special-purpose tubes, write today.

ELECTRICAL RATINGS*

Heater voltage (AC or DC)**	6.3 volts
Heater current	0.6 amps.
Plate voltage (maximum DC)	275 volts
Screen voltage (maximum DC)	275 volts
Peak plate voltage (max. instantaneous)	550 volts
Plate dissipation (absolute max.)	12.5 watts
Screen dissipation (absolute max.)	2.0 watts
Cathode current (max. instantaneous peak value)	100.0 ma
Heater-cathode voltage (max.)	±450 volts
Grid resistance (max.)	0.1 megohm
Grid voltage (max.)	+5.0 volts
(min.)	−200.0 volts
Cathode warm-up time	45 seconds

(Plate and heater voltage may be applied simultaneously.)

*To obtain greatest life expectancy from tube, avoid designs where the tube is subjected to all maximum ratings simultaneously.

**Voltage should not fluctuate more than ±5%.

MECHANICAL DATA

Base	9 pin miniature hard glass—gold plated tungsten pins
Bulb	Hard glass—T6½
Max. over-all length	2⅝"
Max. seated height	2¼"
Max. diameter	¾"
Mounting position	any
Max. altitude	80,000 feet
Max. bulb temperature	300°C.
Max. impact shock	500g
Max. vibrational acceleration	50g

(100-hour shock excited fatigue test, sample basis.)

Bendix Red Bank

Manufacturers of Special-Purpose Electron Tubes, Inverters, Dynamotors, Voltage Regulators, Fractional D.C. Motors and A.C. and D.C. Generators.

DIVISION OF Bendix AVIATION CORPORATION

EATONTOWN, N. J.

West Coast Sales and Service: 117 E. Providencia Ave., Burbank, Calif.
Export Sales: Bendix International Division, 205 E. 42nd St., New York 17, N. Y.
Canadian Distributor: Aviation Electric Ltd., P.O. Box 6102, Montreal, P.Q.

tool necessary to replace any part within a few minutes.

► **Uses**—The precise nature of speed adjustment on these drives permits their use with proportioning pumps or feeders and tachometer test stands, as well as with rewinders and machine-tool drives. These units utilize a d-c tachometer generator, which can be remotely mounted, and are particularly adaptable for various automation devices.



SHOCK MOUNT
protects electronic tubes

ROBINSON AVIATION, INC., Teterboro, N. J. Miniaturized mounting, as in model K271, is the best insurance against shattered tubes and waveform distortion during important operations, whether airborne, mobile or otherwise.

► **Design**—Integral in the mounting system is a metal sleeve, serving as a brace and support for the tube, which may be adjusted with a screw clamp. Met-L-Flex spring-enclosed cushions, fabricated of stainless steel (in projecting cups), attenuate shock and vibration between the sleeve and the outer support.

Performance is unimpaired from heat because of resistance extending to 375 F throughout the all-metal system. Cold to −130 F does not hamper its resilient action. Flexible electrical leads are securely connected at the base of the tube and do not interfere with the free action of the mounts.

These types of mountings utilize every available portion of space in small chassis and electronic sets. They are designed for any shape to

fit all varieties of circuit configurations.



SMALL GENERATOR
proximity impulse type

MINATRON CORP., 14 Cliveden Place, Belle Mead 14, N. J. Model 50A miniature proximity impulse generator provides a self-generated output voltage proportional in amplitude and frequency to the velocity of magnetic material moving in proximity to the sensitive end of the pickup.

The device, when used with commercially available electronic counters, provides an accurate means of measuring, counting or detecting movement, vibration, or speed of a shaft or other part.

▶ **Construction**—Stock units are encapsulated in a stainless steel housing, which is ⅜ in. diameter by 1¾ in. long. Construction is such as to withstand extreme conditions of shock, vibration and operating temperatures to 500F.

Literature

Broadband Cavity Wavemeters. DeMornay-Bonardi, 780 S. Arroyo Parkway, Pasadena, Calif., has announced a 4-page, illustrated folder on precision broadband cavity wavemeters. It describes the sealed construction which maintains a dielectric constant, and explains the extremely high accuracy of the units. Eleven sizes are listed, covering frequencies from 2.6 kmc to 90 kmc. Applications, specifications and ordering information are provided.

Dip Soldering of Printed Circuits. Hi-Grade Alloy Corp., 1236 S. Talman, Chicago, Ill. Bulletin No. 14 describes the application of

PHAOSTRON
NONE FINER

CUSTOM
PANEL
METERS

The appearance of your equipment will be enhanced by PHAOSTRON meters with their high style, die cast bezels and large easy-to-read scales.

You can depend upon 2% accuracy because these meters are calibrated to within 1% of full-scale deflection with controlled, certified standards.

Continuous accuracy is assured by the UNITIZED METER MOVEMENT ASSEMBLY which provides integral mechanical stability. The aged alnico magnet of the meter is protected from the effects of stray magnetic fields by the steel case.

These units are also equipped with insulated zero adjustments.

Nine Types in 77 Standard Ranges are available at your Parts Distributor. If you have a special requirement, write to the Product Development Department for a practical recommendation.

PHAOSTRON INSTRUMENT AND ELECTRONIC COMPANY
151 PASADENA AVE., SOUTH PASADENA, CALIF.

RESINITE EMBOSSED COIL FORMS

...can increase efficiency of your iron core insertion production by 20%



Special embossed construction eliminates torque control problems and stripping . . . prevents breakage or freezing of cores due to cross threading or improper starts.

Custom fabrication to your exact specification assures correct dimensions to within the most critical tolerances, plus uniformity throughout.

Threads are positioned in accordance with your requirement —full thread, each end, one end, center only.

We will furnish—without charge—a pilot production run of custom-made embossed forms to fit your particular application. We will also send a winding mandrel made to the specifications you supply.

Contact us now for full details about this special offer. Request technical bulletin, *Use of Threaded Tubes, Threaded Iron Cores VS. Torque Control.*

▼ ▼ ▼

RESINITE CORPORATION

Sales Representatives in:

New England: Framingham, Massachusetts, Trinity 3-7091
Metropolitan New York, New Jersey: Jersey City, New Jersey, Journal Square 4-3574
Upstate New York: Syracuse, New York, Syracuse 4-2141
Northern Ohio, Western Penn.: Cleveland, Ohio, Atlantic 1-1060
Indiana, Southern Ohio: Logansport, Indiana, Logansport 2555
California: Pasadena, California, Sycamore 8-3919
Canada: Montreal, Quebec, Canada, Walnut 0337

Division of.. PRECISION PAPER TUBE COMPANY

2035E W. CHARLESTON ST. • CHICAGO 47, ILLINOIS

several new products in the dip soldering of printed circuits.

HG No. 19 flux lacquer applied to the circuit immediately after etching protects it from oxidation and acts as an efficient flux during soldering. HG No. 27 rosin flux used hot serves the double purpose of fluxing and preheating ceramic patterns so as to prevent cracking during soldering.

Bulletin No. 14, in addition to describing the above products, provides a complete guide to the techniques of fluxing, choice of soldering equipment and methods of soldering.

Electro - Pneumatic Controllers. Leeds & Northrup Co., 4934 Stenton Ave., Philadelphia 44, Pa. A 4-page data sheet gives complete information about the new Speedomax H electro-pneumatic controllers, current-adjusting type. Included in the sheet is a full description, complete with line drawings and photographs, of the controller and its associated converter. Specifications and standard ranges for all models are conveniently tabulated along with equipment for the complete control system. Ordering instructions complete the sheet. Ask for data sheet ND46-33(106).

Beacon Telemetering System. Stavid Engineering, Inc., U. S. Highway 22, Plainfield, N. J., has prepared a technical brochure on the Beacon telemetering system developed for the U. S. Army Signal Corps. The system described uses ppm with time separations of 25 to 125 μsec employing 0.8-μsec pulses corresponding to telemetered data signal inputs of 0 to 5 v d-c. Complete information is included on the system's three groups of equipments: airborne equipment (transmitting), ground equipment (receiving) and test equipment (calibration).

Phase Measurement. Berkeley Division, Beckman Instruments, Inc., 2200 Wright Ave., Richmond 3, Calif. Data file 107 describes the company's digital method for fast, precise phase measurement. The procedure discussed reads directly in degrees, mils, or any other unit

of angular measure, and banishes interpolation. Accuracy is 0.1 deg.

Basically, the procedure simply measures the time interval between the zero crossover point of a reference signal and the zero point of the shifted signal. Comparing the time interval with one period of the signal frequency determines the phase-lag magnitude.

Closed Circuit TV Systems. Dage Television Div., Thompson Products, Inc., Michigan City, Ind. A 16-page booklet covers the company's complete closed circuit TV systems. It discusses models 60 and 101 cameras, the 600-B video monitor, an amplifier, audio-video mixer, remote control, remote pan and tilt, and lens turrets.

Illustrations and specifications are included.

Photographic Printing Process. LogEtronics Inc., 1177 New Hampshire Ave., N.W., Washington 7, D. C. A colorful, descriptive folder outlines some of the types of problems already being solved by a new photographic printing process with automatic dodging and automatic exposure control.

Much discussion has centered around this new principle which brings electronic automation to the photographic darkroom. The folder answers many of the questions being asked, and is available upon request.

Dynamic Accuracy Tester. General Electric Co., Schenectady 5, N. Y. Bulletin GEA-6345 describes DYNAT, a dynamic accuracy tester developed for ground testing complete aircraft armament systems under fully simulated flight conditions. The 4-page bulletin describes the operation of the tester, its capabilities, and its advantages in speeding delivery of future armament systems.

Synthetic Micas. Mycalex Corp. of America, Clifton Blvd., Clifton, N. J., has available literature describing its compression-molded Supramica 500 and precision-molded Supramica 555 Ceramoplastics. Type 555, made with synthetic mica, provides all of the desirable properties of Mycalex 410 glass-bonded mica, plus tempera-



THE NEW MODEL 3

AUTOGRAF

trade mark

The Model 3 AUTOGRAF X-Y Recorder incorporates the proven features of the Model 2 in a compact instrument, ideal for use with standard 8½" x 11" graph paper. Rugged, accurate, fast, and stable, the Model 3 provides facilities for curve drawing and curve following with full visibility of the recording while in operation.

- Ranges: 5 mv up to 500 volts, full scale.
- Independent, isolated inputs, free of ground.
- Speeds: Up to ½ second, full scale.
- Resolution 0.1%; accuracy and resolution 0.25%.
- 200,000 ohms/volt input resistance.
- Zero set and one full scale length zero offset, both axes.
- Liquid ink or ball point pens.

The addition of the Model 3 to the Moseley AUTOGRAF line gives you three X-Y recorders to choose from:

MODEL 1	MODEL 2	MODEL 3
Drum type	Flat-bed	Desk Type
8½" x 11" paper	11" x 16½" paper	8½" x 11" paper
X-Y Recorder-	X-Y Recorder-	X-Y Recorder-
Curve Follower	Curve Follower-	Curve Follower
	Point Plotter	

More than 1000 AUTOGRAFS are in use in laboratories, universities, and industrial plants throughout the U.S. and overseas.

F. L. MOSELEY CO.
409 N. Fair Oaks Ave., Pasadena, Calif.

Bulletins describing these instruments are available and we'll be glad to send them to you.

The most advanced developments in electronics are being made in the sphere of airborne radar and related ground control systems because of military emphasis.

Further applications of electromechanical techniques in these fields are creating new openings in the Systems Division of Hughes Research and Development Laboratories.

Engineers who have demonstrated ingenuity and inventive ability will find interest in areas of work that call for devising reliable, maintainable, manufacturable designs for precision equipment developed at Hughes Research and Development Laboratories.

The design of this equipment, manufactured at Hughes, involves mechanical, electromechanical, electronic, microwave and computing problems. Design also requires the use of such advanced techniques as subminiaturization, unitized "plug-in" construction, with emphasis on design for volume production. Knowledge of electronic components, materials, finishes and military specifications is useful.

SCIENTIFIC STAFF RELATIONS

HUGHES

RESEARCH AND DEVELOPMENT LABORATORIES

Culver City, Los Angeles County, California

ture endurance up to approximately 950 F. Supramica 500 offers temperature endurance up to 1,000 F.

Prices range according to thickness, from $6.84 to $26.88 for sheets 14 in. by 18 in.; from $1.08 to $4.02 for 18-in. rods. Quantity discounts are available.

Operational Amplifier. George A. Philbrick Researchers, Inc., 230 Congress St., Boston 10, Mass. Complete data on a new operational amplifier, model K2-X is described in a new technical bulletin. General characteristics, operational details, applications, internal circuitry and suggested methods of applying bias are presented.

Radio Interference Filters. Televiso Corp., 1415 Golf Road, Des Plaines, Ill. A 4-page folder illustrates and describes radio interference filters to specification MIL-I-6181. Included is information on the company's interference laboratory facilities and field testing operations.

Electronic Wire. Alpha Wire Corp., 430 Broadway, New York 13, N. Y., has announced publication of catalog 55 of electronic wire, which contains complete descriptions, specifications and illustrations of the company's in-stock line of 1,373 items. The catalog lists 487 new items, full Government and MIL specification data, and special engineering cross-reference charts for easy determination of individual wire needs.

Thermistor Data. Victory Engineering Corp., Union, N. J., has prepared a new edition of the VECO thermistor data book with information on the historical background, operating characteristics, typical applications and engineering data. A new section on varistors is now included, with graphs showing typical curves. Priced at $1, it may be obtained free if requested on company letterhead.

Electronic Generators and Test Equipment. Communication Measurements Laboratory, Inc., 350 Leland Ave., Plainfield, N. J. A 16-page booklet contains illustrated

information on 7 electronic generators, a group of 3 phase and master units, and such test equipment as a Rotobridge and its accessories, a stroboscope, megohm meter and vtvm. Specifications and prices for all are included.

Relays. AEMCO, Inc., Mankato, Minn., has released a 4-page bulletin covering a wide variety of relay types. Complete specifications are given for each relay. The bulletin contains valuable mounting information, type enclosures available, and basic size information. Each relay type is pictured and platings, insulation grades and finishes are described.

Laminations Catalog. Magnetics, Inc., Butler, Pa., has issued a greatly expanded magnetic laminations catalog, describing the company's standard lines of laminations, laminated cores and dies. Catalog ML201 includes 16 pages of lamination specification sheets, showing both the individual laminations to actual scale, as well as properties of square cross-section core stacks, and weights and counts for different materials.

Catalog sections are devoted to laminated core assemblies, mechanical and magnetic parameters and lamination tolerances.

Instrument Type Switches. Cinema Engineering Co., Aerovox Div., Burbank, Calif., has available an 8-page catalog describing instrument-type switches. Illustrations, a complete code system outline and complete specifications are included in the data. Production switch parts discussed are prefabricated to insure speedy production, but all switches are precision made custom-built.

Information is also available on other CES switches with special terminal boards, dust-covers, ball-bearings, stainless steel shafting, coin silver contacts, special detent positions and h-v construction.

Industrial TV Cameras. Taller & Cooper, Inc., 75 Front St., Brooklyn 1, N. Y. Descriptive literature deals with three new products recently placed on the market. Bulletin 508 covers industrial tv cameras,

TRANSFORMERS for your SPECIAL REQUIREMENTS

TWO NEW NWL SPECIAL UNITS



Resistance Welding Transformer with eight point tap-changing switch on primary winding. Used for a varying secondary current output. Unit shown is 3 KVA. Units are available from .5 to 50 KVA.



High Voltage Plate Transformer for use under oil with other equipment in same tank. Unit shown is 50 KV center tap grounded, 4 KVA and high impedance. Note plastic insulation shield between coils. This unit available from 100 VA to 100 KVA.

For any special transformer, you will get the highest quality, the fastest delivery, the most reasonable cost and the highest efficiency from Nothelfer Winding Laboratories. Their production is geared to the manufacture of special transformers, chokes and reactors.

Write for complete information, specifying your particular requirements.

NWL Nothelfer WINDING LABORATORIES, Inc.

P. O. Box 455, Dept. 101, Trenton, N. J.


LIKE'M
TALL
LIKE'M
SHORT
LIKE'M
SQUAT
LIKE'M
THIN
...INFRA'S GOT'M
ALL TYPES
Stop being low man! Specify Infra servo motors, generators or syncros and get to the top fast! Thousands of standard Infra types are immediately ready to go to work for you . . . for unique applications Infra's specialized engineering staff quickly creates exactly the right unit for your system, saving valuable engineering time. Infra extra-tough components meet all applicable government specifications.
Build better performance into your systems, use Infra components.
infra
Send for Infra's complete Catalog 101 —today!
INFRA ELECTRONIC CORPORATION
ROSELAND, NEW JERSEY
DESIGNERS AND MANUFACTURERS OF PRECISION ROTATING EQUIPMENT AND SYSTEMS

a private tv system for supervising plant and traffic operations. Bulletin 507 discusses an automatic camera with which it is possible to record picture and pertinent data simultaneously on the same frame. Bulletin 503 has to do with remote control systems for the automatic operation of municipal water supply systems.

Cabinet Racks. California Chassis Co., Lynwood, Calif., has issued a supplementary catalog sheet on its cabinet racks for electronic uses. Another item listed is the C.C.C. miniature cabinet. The new catalog sheet is a supplement to the annual Cal Chassis illustrated catalog for its chassis, brackets, panels, cabinets, bottom plates and other production items. Dealer's price sheet is included.

Regulated Power Supply. Deltron Inc., P.O. Box 192, Glenside, Pa. A single-page bulletin covers a new regulated power supply that features low cost wide voltage range, large current output, excellent regulation, low ripple, relay-controlled preset voltage and heavy duty filament supply. Complete specifications are given.

Two models are illustrated in the bulletin. Model 900 is priced at $340, and model 900R $330.

Sprayed Metals. Metallizing Engineering Co., Inc., 1101 Prospect Ave., Westbury, L. I., N. Y. Bulletin 120 illustrates and describes a wide range of applications of metallizing—sprayed metal—in the production of electrical and electronic equipment. Originally used to provide a soldering base on nonmetallic materials, the use of this metal-spraying process has spread to applications in shielding, the production of other types of electrically reflective surfaces and in the replacement of wired circuits.

The bulletin provides engineering data on bond strength, conductivity characteristics, permissible coating thicknesses, circuit tests, surface preparation and spraying methods.

Delay Lines. Epsco, Inc., 588 Commonwealth Ave., Boston 15, Mass. Bulletin DL55 covers new delay lines designed particularly for tele-

metering, digital or analog computers, pulse circuits, coders and decoders, navigation systems and stable time reference units.

▶**Standard Units**—It covers units with the following characteristics: Temperature coefficient of delay is less than 50 parts per million per deg C; operating temperature range of —55 C to +125 C; delay tolerance, 3 percent; attenuation in db, approximately 0.1 to 0.2 times delay-to-rise-time ratio.

The bulletin presents design data on the following elements: precision audio delay lines; custom designed units; standard series and special applications; design formulas; characteristic impedance; attenuation; delay time, rise time, delay-to-rise-time ratio; bandwidth; phase linearity; spurious signals; operating temperature range; and typical circuits.

Gear Boxes and Precision Gears. Southwestern Industries, 5880 Centinela Ave., Los Angeles 45, Calif. A 4-page brochure illustrates and describes a line of miniaturized gear boxes for electronic and instrument applications, servomechanisms, computers, small actuators and electronic components. Also included is information on the company's miniaturized, vibration-resistant pressure switches for aircraft and missile systems applications.

Servo Amplifiers. Servo Corp. of America, 20-20 Jericho Turnpike, New Hyde Park, L. I., N. Y. A 4-page brochure fully describes Servoflex amplifier models 1120, 1121, 1123 and 1124. Each of the models discussed features instantaneous response, built-in preamplifier, built-in power supply, compact assembly, standard tubes and stability.

Printed Wiring Boards. General Electric Co., Electronic Components Dept., W. Genesee St., Auburn, N. Y. A new 6-page, 3-color brochure with technical data and circuit design pointers for G-E Thru-Con printed wiring boards is now available. The brochure includes layout and design information, specifications on base and conductor materials, use characteristics, and

another filter problem solved . . .

NEW FILTER RATED FOR 67% HIGHER AMPERAGE, 75°F HIGHER TEMPERATURE, REQUIRES NO ADDITIONAL SPACE



PROBLEM: Hoover Electric Company, Los Angeles, California designed a hydraulic pump motor for aircraft which successfully met all of the following requirements: operation at altitudes as high as 60,000 feet, ambient temperatures as high as 250°F, and ability to withstand continued starting under one hp loads at two-second intervals. It had to be of minimum size and weight, explosion-proof, and radio interference-free in accordance with MIL-I-6181B. Although the pump motor met its performance requirements, the 45 amp, 175°F filter originally designed and built into the unit could not withstand the severe inrush conditions, subjecting it to up to five times nameplate rated current thirty times a minute.

APPROACH: Hoover Electric brought the problem of replacing the inadequate filter to the Sprague Electric Company Radio Noise Suppression Laboratories in Los Angeles. They required a 75 amp, 250°F filter electrically matched to the motor and able to fit the same space as the original 45 amp filter. This design parameter was necessary for the continued use of other standard Hoover parts in production to meet crash deliveries, and to permit mechanical and electrical interchangeability with parts used previously in the field.

SOLUTION: Sprague Engineers made radio interference measurements to MIL-I-6181B and custom designed a filter electrically matched to the Hoover pump motor. This new 75 amp, 250°F filter fits in exactly the same space as the old one, is completely interchangeable with it, and fully conforms to the military specification.

PRODUCTION SCHEDULES for this and many other custom designed and standard filters are regularly met by Sprague plants on both coasts. Write, wire, or phone Sprague Electric Company, 12870 Panama Street, Los Angeles 66, California (TExas 0-7531) or North Adams, Massachusetts (MOhawk 3-5311).

YOU CAN DEPEND ON **SPRAGUE**® WORLD'S LARGEST CAPACITOR MANUFACTURER

Sprague on request will provide you with complete application engineering service for optimum results in the use of radio noise filters.

REVERE

Revcothene*

INSULATED

WIRE



Because of its extreme toughness, high heat resistance, and chemical inertness, Revcothene insulated wire is widely recommended for hermetically sealed equipment . . . for devices operating with small gauge wire at high temperatures . . . and for conditions where corrosion is a problem.

Revcothene is silver-plated copper wire with an extruded coating of monochlorotrifluoroethylene. Even at 150° C. (302° F.) the insulation is inert . . . with no volatile lacquers or plasticizers to ruin contacts. Revcothene withstands abrasion and flexing, and resists such corrosives as ozone, acids, alkalis and petroleum products.

Available in eight standard sizes from 28 to 10 gauge . . . in 15 colors. Flexible strandings, copper or silver braid shielding, heavy wall insulation and jacketing can also be furnished. Multiple-conductor cables are also available.

Revcothene is only one of many insulated wire and thermocouple wire products made to exacting specifications by Revere Corporation of America. Technical design assistance gladly offered. Write today.

TYPICAL SPECIFICATIONS — 22-Gauge Revcothene Wire

Spark Test Voltage	7500
Insulation Resistance	1000 megohms/1000'
Operating Temperatures:	
Flexing Application	—40° C. to 135° C.
Non-Flexing Application	—65° C. to 150° C.
Flammability	Does not support combustion
Operating Voltage	1000 volts
Water Absorption	0.00
Effect of Acids & Alkalis	Generally unaffected
Cold Flow (Compressive Strength)	32,000 PSI
Abrasion Resistance (MIL-T-5438)	Passes 36"-400 grit aluminum oxide with 0.3 pound weight

*Revere's tradename for monochlorotrifluoroethylene

Revere CORPORATION OF AMERICA 2

WALLINGFORD, CONNECTICUT A subsidiary of Neptune Meter Company

other customer information. The Thru-Con boards described are made by an additive process which plates the copper through the component lead holes.

Pressure Transducers. Statham Laboratories, Inc., 12401 West Olympic Blvd., Los Angeles 64, Calif., has available bulletins on the P130 absolute pressure transducer, the P131 differential pressure transducer, the P132 gage pressure transducer and the Type A pressure adapters. Price of the units described in the order listed are $200.00, $175.00, $175.00 and $5.00.

Doppler Data Translator. Potter Instrument Co., Inc., 115 Cutter Mill Road, Great Neck, N. Y. The first in a series of data sheets illustrating custom designed equipment manufactured by the company is available. The first sheet covers the Doppler data translator and describes in some detail the device and its application. The DDT takes Doppler data such as that obtained from radar tracking of a guided missile, digitizes it into a binary code and stores this information onto a magnetic tape suitable for playback into a conventional computer from which velocity and acceleration figures can be determined. The data sheet serves to illustrate the type of custom-designed equipment which the company is presently engaged in manufacturing.

Single Sideband. Eitel-McCullough, Inc., San Bruno, Calif. Application bulletin No. 9, "Single Sideband", is now available. The 24-page bulletin gives single sideband ratings for Eimac tubes and discusses other technical topics in this increasingly popular field.

Germanium Rectifiers and Stacks. Federal Telephone and Radio Co., 100 Kingsland Rd., Clifton, N. J. Two catalog inserts are now available covering the new germanium product line.

The first is a 4-page folder—"Federal Germanium Diffused Junction Power Rectifiers"—describing the 1N91, 1N92, 1N93 and 1N368 series. These tiny rectifiers are over 95 percent efficient, with electrical ratings ranging from 75 to

150 ma d-c output.

The second is a 12-page booklet—"Federal Diffused Junction Power Stacks." It describes a series of over 100 germanium stacks employing the diffused junction rectifiers to obtain higher power. The stacks are approximately ½ smaller than existing types and are rated electrically up to 565 v and 6 amperes d-c in configurations of 1 to 12 fins.

Miniature Electromagnetic Clutches and Brakes. Dial Products Co., 7 Bergen Court, Bayonne, N. J. An 8-page catalog describes the company's line of electromagnetic clutches and brakes with o-d from 0.920 in. to 1.500 in. and torque values up to 200 in. oz. All dimensions and specifications are shown. Graphs on power-input, torque and heating relationship are included. Also given is a new design for slip and tension-control application. Prices for 4 models of dial clutch range from about $25 to $52; for 3 models of dial brake, from about $20 to $24. Discounts are available for quantities over 10.

TV and Broadcast Microphones. Electro-Voice, Inc., Buchanan, Mich., has issued a complete, colorful and illustrated catalog on professional microphones for tv and broadcast applications. The 32-page catalog No. 120 gives detailed application information, features and specifications on each Electro-Voice microphone used in telecasting and broadcasting. It shows how the microphones work and includes polar patterns, frequency response curves and wiring diagrams.

Information on the relation of the particular microphone to the overall station operation is included. Development and manufacture of the microphones are explained in a special section of the catalog. E-V accessories are also illustrated and described.

Interference Locator. Sprague Electric Co., North Adams, Mass. A 4-page brochure completely describes the model 400 interference locator which provides tuning from 500 kc to 220 mc in six bands, thus covering the standard broadcast, short wave, f-m broadcast and vhf-tv spectrums. Illustrations, per-



Stoddart RI-FI* meters cover the frequency range 14kc to 1000 mc

VLF
NM-10A, 14kc to 250kc
Commercial Equivalent of AN/URM-68. Very low frequencies.

HF
NM-20B, 150kc to 25mc
Commercial Equivalent of AN/PRM-1A. Self-contained batteries. A. C. supply optional. Includes standard broadcast band, radio range, WWV, and communications frequencies. Has BFO.

UHF
NM-50A, 375mc to 1000mc
Commercial Equivalent of AN/URM-17 Frequency range includes Citizen's band and UHF color TV band.

Stoddart NM-30A
20mc to 400mc
Commercial Equivalent of AN/URM-47

PRINTED CIRCUITRY . . . Modern printed circuits offer many advantages over conventional wiring: lighter weight, more compact units and freedom from many of the troubles normally encountered in conventionally-wired electronic equipment. Vibration becomes even less of a problem with printed circuits, adding to the many portable features already available with Stoddart equipment.

ADVANCED DESIGN . . . Specialized engineering and modern production techniques have produced one of the most advanced instruments for the accurate measurement, analysis and interpretation of radiated and conducted radio-frequency signals and interference ever manufactured. Designed to laboratory standards, rugged, and with matchless performance, the versatile NM-30A is an outstanding example of modern instrumentation. Its frequency range includes FM and TV bands.

SMALLER SIZE . . . A wider frequency range and higher standard of performance is incorporated into an equipment whose size is one-third that of any similar equipment ever manufactured.

SENSITIVITY . . . Sensitivity ranges from one to ten microvolts-per-meter, depending upon frequency and antenna in use.

APPLICATIONS . . . Field intensity surveys, antenna radiation pattern studies, interference location and measurement for checking radiation from virtually any mechanical or electrical device capable of generating or radiating radio-frequency signals or interference.

STODDART aircraft radio co., inc.
6644-A SANTA MONICA BLVD., HOLLYWOOD 38, CALIFORNIA HOLLYWOOD 4-9294

HIGH Reliability PLUS



The feedback of results from a new series of tests has enabled North engineers to produce a new high in relay reliability. These relays are especially suited for a wide range of airborne applications where a high degree of shock and vibration immunity is required, and where reliability must exceed the standard resulting from present day practices under MIL-R-5757B.

North's high reliability program subjects *each* relay to these tests. Comparison of Curves above shows the ratio by which system reliability is reduced in proportion to the number of components employed. Tests prove that the uniformly tight control of the high reliability program developed by North* greatly improves the value of this ratio as applied to North Relays.

Conformity with the pattern which these tests define is your best assurance of reliable system performance.

*Detailed explanation of these tests is available on request.



ACTUAL SIZE

IR 226 RELAY (with cover removed)

Hermetically Sealed—Sensitive Type—Temperature Range -65° to +125°C—Zero Bounce or Chatter at 50 Gs Shock and 500 Cycle Vibration Tests—2C (two make-break) Contacts — 100,000 Operations at Rated Load of 2.0 amps at 30v DC resistive — specifications not applicable to your requirements may be deleted.

Industrial Division

NORTH ELECTRIC COMPANY

566 South Market Street, Galion, Ohio

formance data and specifications are included. Net price of the unit described is $369. A page is devoted to accessory items, and their individual prices are also given.

Power Supply. Consolidated Engineering Corp., 300 N. Sierra Madre Villa, Pasadena, Calif. Bulletin 1562 deals with the type 3-120A power supply, a d-c to a-c converter which provides 115 v at 60 cycles, from 26-v d-c input. Price of the unit described is $335. Prices for replacement parts are as follows: The B-36231 meter, $8.25; the B-36232 meter, $8.25; the A-34072 Variac, $17.25; and the 16656-16 fuse, $0.20.

Deposited Carbon Resistors. Electroseal Products, Inc., 22 E. 40th St., New York 16, N. Y. Technical information bulletin 100 describes the company's line of deposited carbon resistors for use in electrical and avionic applications.

Printed in two colors and illustrated with h-f response and temperature coefficient curves, the bulletin gives resistance values and specification data on both type B (axial lead) and type A (radial lead) resistors. It includes such information as tolerance, noise, temperature coefficient, construction and wattages.

Coaxial Transmission Line. Prodelin Inc., 307 Bergen Ave., Kearny, N. J., has announced a 2-color, 8-page catalog bulletin describing coaxial transmission line used for conducting tv transmitter signals to the transmitting antenna. Rigid type lines with RETMA flange connectors are described in 1⅝ in., 3⅛ in. and 6⅛ in. sizes.

Bulletin 431 fully describes lines and accessories complete with photographs, outline drawings, efficiency graphs and charts showing attenuation, velocity, voltage breakdown, diameters, weights and bead spacing.

Pressure Resistors. Clark Electronic Laboratories, Box 165, Palm Springs, Calif. Bulletin 269 illustrates and describes the company's line of pressure resistors. It discusses Celab resistance material as a variable resistance means capable of such wide range that a quarter

of a thimblefull of the powder will be an excellent insulator at 1-lb pressure, but will be a good conductor at 12 to 20-lb pressure.

A sample pressure-adjustable device which can be taken apart (suitable for design engineers) is available in the 15-w size for $15. The powder is available in ½-oz size for $5.

High-Speed Potentiometer. The Bristol Co., Waterbury 20, Conn., has released bulletin P1270 describing the new high-speed recording Dynamaster potentiometer. This recorder has full-scale pen-travel across its 11-in. calibrated chart of only 0.4 sec, without overshot on long or short traverses.

The 2-color bulletin features a full-size reproduction of a sample chart which shows the dynamic characteristics of the new recording potentiometer.

Quartz Crystal Filters. Hycon Eastern, Inc., 75 Cambridge Parkway, Cambridge 42, Mass., has just released a new bulletin on quartz crystal filters. Complete data, including selectivity curves and specifications, are presented.

Lower Manufacturing Costs. Magnaflux Corp., 7300 W. Lawrence Ave., Chicago 31, Ill. A booklet, entitled "Lower Manufacturing Costs", discusses various uses for testing. It indicates how a nondestructve testing program can be instituted in the production departments, as a cost-reducing, money-saving tool. It outlines how inspection should be considered productive machinery. Ask for Form No. 148-2, an 8-page, well-illustrated booklet.

Scintillation Counter. Chatham Electronics, Division of Gera Corp., Livingston, N. J. Model SC-102 scintillation counter is illustrated and described in a single-sheet bulletin. The unit discussed offers extreme sensitivity for uranium and oil prospecting. Specifications are included.

Hermetically Embedded Circuitry. Alcor Electronics Corp., 180 Lafayette St., New York 13, N. Y. A 4-page folder covers the Encapsor, a plug-in electronic circuit hermeti-

FOR HIGH SPEED PULSES

the Electro-Pulse
MEGACYCLE PULSE GENERATOR

- 20 CPS to 2 Megacycles
- Variable Duration
- Variable Delay

WIDE RANGE... ...LOW IMPEDANCE



Model 3450A

A true pulse generator for the megacycle range, providing variable width and amplitude pulses at variable delay from sync. pulse—operates from internal or external triggers. Designed for wide application in High Speed Computer Development and Test...Transistor Pulse Circuit Design...as a General Purpose Trigger Generator.

• 20 CPS to 2 Megacycles Rep. Rate • Internally or Externally Triggered • .1 to 5 μs Delay from Sync. Pulse • .1 to 5 μs Pulse Width • 50 V Amplitude • .05 μs Rise Time • 100 Ohms Internal Impedance

Write for Complete Data: Our Bulletin 3450A/E



The Model 3450A Megacycle Pulse Generator is one of a series of Electro-Pulse test instruments. Others: Precision Pulse Generators, Analog and Digital Time Delay Generators, Pulse Oscillators, Pulse Code Generators and Magnetic Core Testing Equipment.

Model 2120A PRECISION PULSE GENERATOR

Representatives in Major Cities

EP Electro-Pulse, Inc.
11861 TEALE STREET, CULVER CITY, CALIFORNIA
Telephones: EXmont 8-6764 and TExas 0-8006

POLYPENCO® TEFLON* SHAPES



Get All These Important Advantages of Teflon—Plus Low-Cost Fabrication

No other material is proving so versatile in the electronics and electrical field as Teflon. It is now widely used for insulating bushings, terminal connectors, stand-off insulators and many other parts as its applications continue to expand.

TEFLON'S OUTSTANDING PROPERTIES

Dielectric Constant	2.0
Power Factor	0.0005
Dielectric Strength, volts/mil	400-500
Surface Resistivity (100% R.H.) megohms	3.6 x 10^{7}
Temperature Range	−110°F. to +500°F.
Water Absorption	nil
Chemical Resistance	excellent

FABRICATION FROM STANDARD SHAPES

POLYPENCO Teflon Shapes are available in rod, tubular bar, tape, slab and flexible tubing—in a wide range of sizes—for fast, easy machining to close tolerances on standard metalworking tools or automatic equipment.

POLYPENCO TEFLON MEANS QUALITY

In order after order, POLYPENCO Teflon comes to you with uniform, controlled density and maximum dimensional stability. Stock sizes available for immediate delivery from distribution locations throughout the country.

Take this first step toward a more efficient, economical solution to your design problems. Write today for latest technical data.

THE POLYMER CORPORATION of Penna. • Reading, Penna.
In Canada: Polypenco, Inc., 2052 St. Catherine W., Montreal, P. Q.

POLYPENCO® Nylon, Teflon*, Q-200.5 and K-51

*DU PONT TRADEMARK

cally embedded in the new thermosetting plastic, Alcorite. Included is a full description of Alcorite. The bulletin tells where and why to use Encapsors, discussing dependability, reduced engineering, simplified production, faster equipment checkout, easy maintenance and smaller inventory.

H-V Control Tube. CBS-Hytron, A Division of Columbia Broadcasting System, Inc., Danvers, Mass. Bulletin E-258 gives complete data on the CBS 6792, a multipurpose beam tetrode for voltage stabilization service from 3,000 to 25,000 v. The tube described can solve h-v control problems as a regulator, gating tube, variable resistor or amplifier. Internal structure of the tube discussed is unusual in that, to attain high efficiency and dependability, it embodies the principle of the electron-beam gun found normally in crt's.

Equipment Bulletins. Adler Communications Laboratories, One LeFevre Lane, New Rochelle, N. Y., has announced 5 new equipment bulletins enclosed in a file folder. All are illustrated with photographs and schematic diagrams, and they explain the features, uses, electrical and mechanical specifications, and equipment supplied in each case.

Bulletin VS-5 describes an electronic video switcher; bulletin VA-18, a video distirbution amplifier; bulletin VA-19, a video clamp amplifier; bulletin UST-150, a 150-w uhf tv transmitter; and bulletin VST-150, a 150-w vhf tv transmitter.

Electronic Relay. Automatic Switch Co., 391 Lakeside Ave., Orange, N. J. Bulletin 585 covers the company's new electronic relay. The relay described is capable of: (1) complete follow-through action—brushing of contacts even momentarily effects immediate operation of controlled device; (2) responding to controls from a highly sensitive, essentially a fine-wire contact; (3) no arc operation—only microamperes are drawn by the grid circuit; and (4) direct control of the load operating solenoid. The literature provides design and application information, circuit de-

scription and complete dimensional and pricing data.

Modulized Standard Circuits. Aerovox Corp., 1200 Jefferson Davis Highway, Arlington, Va. A 12-page illustrated bulletin covers modulized standard circuits for the design engineer.

Standard circuits described include a video limiter, low-level cathode follower, common cathode mixer or dual cathode follower, cascade intermediate video amplifier, triode video driver amplifier, prf multivibrator and d-c regulator for +300 volts.

Precision Selector Switch. Electro Tec Corp., South Hackensack, N. J., has available a 4-page folder describing a miniature ultra-low torque precision selector switch for high-speed operation. Included are illustrations, a parts list, general description, design features and specifications. The switch described is available in both 8 and 10 positions.

Oscillographic Recording Equipment. Sanborn Co., 195 Massachusetts Ave., Cambridge 39, Mass. All of the company's 150 series oscillographic recording systems, components and associated equipment are fully described in a new 16-page illustrated catalog. Basic systems, in 1, 2, 4, 6 and 8-channel models, as well as the 11 currently available plug-in preamplifiers, are described in detail. Performance data for these interchangeable front-ends, as well as frequency response characteristics of galvanometer with driver amplifier, are also provided.

Technical details are included on the model 150-1900 master oscillator power amplifier, and model 150-300/700 wide-band driver amplifier and power supply.

► **Prices**—Equipment users will also find complete price lists covering basic assemblies, complete systems, preamplifiers, amplifiers, recorders, cabinets, cases and accessories.

Analog Computer. Electronic Associates, Inc., Long Branch, N. J. A 16-page booklet illustrates and describes the type 16-31 R computer group, featuring 20 operational

News in Analog Computing...



A choice of Plotting Boards...

A Chicago business analyst reports engineers and industries must have versatility in equipment selection, if they are to carry out the expanded research programs planned for 1956.

Foreseeing this, Electronic Associates is making available the only complete line of plotting boards. Four different models of the famous Variplotter Plotting Board, designed to give a rapid, accurate, graphic recording of any information that can be reduced to electrical form.

Reading from left to right in the picture above, there is the vertical Variplotter, Model 205J, with two arms and four pens . . . the horizontal Variplotter Model 205 K, with one arm and one pen . . . the horizontal Variplotter Model 205L, with two arms and two pens . . . and the latest Variplotter, the Model 1100 A, with one arm and one pen, and featuring small, convenient size, outstanding performance, and low cost.

For detailed information on Variplotter plotting boards, Precision Analog Computing Equipment, or rental of time at the EAI Computation Center in Princeton, New Jersey, contact Dept. EL-1. Electronic Associates, Inc., Long Branch, New Jersey.

ELECTRONIC ASSOCIATES Incorporated — EAI SETS THE PACE (PRECISION ANALOG COMPUTING EQUIPMENT)

LONG BRANCH, NEW JERSEY

ELIMINATE REJECTS!
MINIMIZE BREAKAGE!
use Bird jewel assemblies
Why chance rejects and breakage that add to production costs when you can eliminate these time-wasting "headaches" with Bird complete jewel assemblies — ready to install in your equipment. Bird's many years of precision production mean jewel bearings of the highest quality. These jewels are set according to your specifications by skilled craftsmen, in less time, for less money, and eliminate special set-ups in your plant.
Why not bring us your jewel problems — you specify — Bird will supply assemblies that fit your product and schedule. Our engineering staff is at your service for all your jewel bearing problems.
For information on jewel assemblies write for Bulletin 14
Over 40 years of serving industry with Quality jewel bearings
Richard H. Bird & Co., Inc.
Sapphire and glass jewels · Precision glass grinding · Ferrite precision products · Sapphire styli
1 Spruce Street, Waltham 54, Mass.

Fast, Accurate, Reliable

The — SKL — Model 302 includes two independent filter sections, each having a continuously variable cut-off range of 20 cps to 200 KC. Providing a choice of filter types each section has 18 db per octave attenuation. When cascaded 36 db is obtained in the high and low pass setting and 18 db in the band pass position. With low noise level and 0 insertion loss this versatile filter can be used as an analyzer in industry and the research laboratory or to control sound in the communications laboratory, radio broadcasting, recording and moving picture industries.

SPECIFICATIONS

- CUT-OFF RANGE — 20 cps to 200 KC
- SECTIONS — 2—can be high, low and band pass
- ATTENUATIONS — 36 db/octave maximum
- INSERTION LOSS . 0 db
- NOISE LEVEL — 80 db below 1 volt
- FREQUENCY RESPONSE — 2 cps to 4 MC

SKL SPENCER-KENNEDY LABORATORIES, INC.
181 MASSACHUSETTS AVE., CAMBRIDGE 39, MASS.

amplifiers, 32 attenuators, 4 free diodes, 3 function switches, full system monitor, audible overload alarm, temperature-controlled oven, shielded patch plugs and coaxial patch cords. Section 2 of the booklet features a building block method simplifying expansion by the addition of standard component groups.

Rectangular Connector. DeJUR-Amsco Corp., 45-01 Northern Blvd., Long Island City 1, N. Y., has available a 2-page illustrated color bulletin with special features, electrical and mechanical ratings, mounting and clearance dimensions, and diagrams of the new 15-contact rectangular connector with aluminum hoods. Write for bulletin GS.

Time Delay Relay. Elastic Stop Nut Corp. of America, Elizabeth, N. J. A 4-page bulletin, SD-1, contains selection information for the Agastat time delay relay models. The correct Agastat model for a particular time delay or combination of time delays in an electrical circuit may be chosen from a selection chart there. The chart presents method of adjustment, operating voltage, type of operation, contact arrangement, type of contact, dimensions and weight for each Agastat model. Various Agastat mountings and enclosures are shown in 6 diagrams.

Switchboards With Basic Circuits. General Electric Co., Schenectady 5, N. Y. The company's building-block concept as applied to switchboards is described in a 4-color 40-page bulletin, GEA-4127B. The publication shows how 8 classifications of standard switchboards are constructed, operated and tested. A complete discussion of basic circuit specifications in duplex switchboards is included.

Data Processing Systems. Logistics Research, Inc., 141 S. Pacific Ave., Redondo Beach, Calif. The Alwac III data processing systems are described in an 8-page, illustrated brochure. The data processing system described consists of the ALWAC III electronic digital computer, a punched card converter, magnetic tape storage, automatic typewriter and punched paper tape. The computer can read or punch

cards at the rate of 8,000 alphanumeric characters per minute and read from or record on magnetic tape at the rate of 60,000 characters per minute. The system's memory drum has a capacity of more than 16,000 single-address instructions.

The brochure contains data on the magnetic drum memory, speed of operation, programming, input-output, controls and indicators, physical characteristics, reliability, and a summary of instructions.

H-V Generator. Lintronic Ltd., 32 Lockwood Terrace, West Hartford 7, Conn. A 4-page bulletin covers a portable power unit featuring a generator-mains-transformer combination. Included are two sets of curves, an illustration and instructions for operation.

A-C Potentiometer. Perkin-Elmer Corp., Norwalk, Conn. A 4-page illustrated folder covers the 400-cycle Vernistat a-c potentiometer with this combination of features: high linearity, high resolution and low output impedance. Design principle and specifications are given.

Precision Panel Instruments. DeJUR-Amsco Corp., 45-01 Northern Boulevard, Long Island City 1, N. Y., has available a 2-page illustrated bulletin with diagram describing all special features, general specifications and mounting dimensions of the two new v-u and db meters including photographic representations of both. Write for bulletin VU133. Ordering information is included.

Miniature Wideband Transformers. Pulse Engineering, 2431 Spring St., Redwood City, Calif., has available a bulletin on its miniature wideband transformers (missile and computer types). Types ES6 and ES7 performance ratings extend from 0.2 μsec to 20 μsec pulse width in blocking oscillator and pulse coupling circuits. They are also provided as wideband step-up step-down transformers for tape and computer circuits up to 10 to 1 turns ratio. High potential ratings of 2 kv d-c may be called out on ES6 designs.

All miniature transformers described are epoxy impregnated and

Engineered for

tomorrow's needs...today...

NORDEN-KETAY OFFERS YOU DIRECT ANALOG-TO-DIGITAL CONVERSION WITHOUT TRANSFORMATION

Combining accuracy with compact design, Norden-Ketay's ADC-1A family of Analog-To-Digital Converters provides you with *unambiguous natural binary output*. All digits are available nearly simultaneously...allowing a high reading rate and may be read while the shaft is in motion. Both the binary number and its complement are available, simultaneously.

RAPID READOUT—up to 10^6 per second.
PARALLEL READOUT—greatly simplifies external circuitry.
COMPACT DESIGN—engineered for minimum size and weight.
INPUT—DC or pulse voltages.
LOW TORQUE—less than 0.2 inch ounces to turn input shaft.
LOW INERTIA—approximately 9 gram centimeters^2.
CLOCKWISE OR COUNTER CLOCKWISE OPERATION—either is possible by selection of appropriate output leads.
AVAILABLE IN ANY CAPACITY TO 19 DIGITS—other capacities available on special order.

For full details write for File #111.

NORDEN-KETAY CORPORATION
INSTRUMENT AND SYSTEMS DIVISION
Wiley Street, Milford, Connecticut

INDICATING PRECISION PRESSURE GAGES • REMOTE INDICATING DEVICES • ANALOG DIGITAL CONVERTERS • FORCE BALANCE PRESSURE TRANSDUCERS • ELECTROMECHANICAL CONTROL SYSTEMS • AIRBORNE RADAR • SHIPBOARD LINE CONTROL EQUIPMENT AIRCRAFT FUEL FLOW INSTRUMENTATION • ACCELEROMETERS

NEW

Sterling

LOW COST

SENSITIVE RELAY



1. Sensitivity—40 MW.
2. Coil resistances to 22,000 ohms.
3. High shock 25G operating.
4. Vibration—.15" excursion 5-55 cycles. 5G to 500 cycles.
5. Lightweight only 1¼ oz.

The unusual mechanical design provides 15% more coil winding space than similar conventional relays.

This results in higher contact pressure, resistance to vibration and reliability than heretofore possible in a relay of this size and cost.

An ideal relay for radiosonde, auto light dimmer, electronic toys, plus general low cost appliance applications.

Standard R5 relays available from stock through 500 Electronic Distributors throughout the United States, Hawaii and Canada.

Write Sterling Engineering or
Potter & Brumfield Mfg. Company, Princeton, Indiana

Another AMF Product
Sterling RELAYS

will withstand environmental requirements of MIL-T-27A including shock, temperature cycling, humidity, salt spray and vibration. Miniature units are normally supplied form-encapsulated but may be obtained hermetically sealed in a metal can.

▶ **Ordering**—Prices on the company's designs in 50 to 500 units are approximately as follows but will vary somewhat depending upon complete specifications: ES6 and ES7—$3.12 each; EF8, $6 each; H9 and H10, $11.80 each; H11, $18.50 each, and H12, $22 each. Ordering information is available.

Instruments. Radio City Products Co., Inc., Centre and Glendale Sts., Easton, Pa. An 8-page 8½ in. by 11 in. brochure includes the latest instruments that have been announced by the company and also includes some lower prices on several models. Ask for catalog No. 139.

Rectilinear Potentiometer. Markite Corp., 155 Waverly Place, New York 14, N. Y. Bulletin C54-1 covers the type 2064 dual-element rectilinear-motion potentiometer. Application advantages, typical performance, design features and prices are given.

Camera Tube Manufacturing. General Electric Co., Schenectady 5, N. Y. A 16-page booklet describes the company's camera tube manufacturing facilities. It illustrates how GE's power tube subdepartment has established extensive facilities with advanced equipment, and assembled engineering and technical skills for the manufacture of image orthicons, Vidicons and other pickup tubes for military and commercial applications. Ask for booklet ETD-1192.

Precision Voltage Divider. Leeds & Northrup Co., 4934 Stenton Ave., Philadelphia 44, Pa., has available complete information about a precision voltage divider, which provides a ratio as small as 1 to 100,000 and is correct within ±1 part of 0.001 percent of the total.

Data sheet E-51(4) describes how the divider is being used (1) for calibrating analog computing

elements such as potentiometers, slidewire components or other elements involving linear, nonlinear, trigonometric, or exponential d-c voltage functions; (2) for testing d-c output of power packs; and (3) as a calibrated potentiometer. Included in the sheet are photographs and a line drawing of the voltage divider and its circuit. A listing of specifications, accessories and special voltage dividers completes the sheet.

AN-Type Connector. DeJUR-Amsco Corp., 45-01 Northern Blvd., Long Island City 1, N. Y. A 4-page illustrated bulletin with diagrams, describes features, specifications and mounting dimensions of AN-type series 1300 miniature connectors. Write for bulletin AN.

High-Temperature Selenium Rectifiers. Sarkes Tarzian Inc., 415 N. College Ave., Bloomington, Ind. A 4-page folder, Form HT1, illustrates and describes high-temperature selenium rectifiers that are practical not only on application considerations but are adaptable to mass production techniques. The company's research departments have developed a compatible barrier layer and counter electrode that when combined with selenium produce a rectifier capable of operating at all temperatures of 150 C. Characteristics charts and tables are included in the folder.

Relays. Magnecraft Electric Co., 3352 W. Grand Ave., Chicago 51, Ill. Engineering catalog No. 55 is a 12-page booklet containing illustrated descriptions of the company's Class 11, Class 33 and Class 22 reliable relays for exacting requirements. Coil data as well as information on contacts and mounting are included.

Radio Interference Measurement. Stoddart Aircraft Radio Co., Inc., 6644 Santa Monica Blvd., Hollywood 38, Calif. A new 37-page bulletin describes the application of radio interference-field intensity measuring equipment in accordance with MIL-I-6181B. Specific instructions and practical examples are cited, including a

NEW! 1/2-inch wire-wound

ACTUAL SIZE

UP TO 100 K

PRECISION POTENTIOMETERS

Now You Can specify a Waters pot for your miniaturized designs that require 50K and 100K potentiometers. In the reliability-proved construction of the AP-½, these new, higher values give you:

- *Resistances — 10 ohms to 100 kilohms*
- *Ganging — up to four units*
- *Three mounting styles — plain-bushing, split-bushing, or servo*
- *Three terminal styles — radial, axial, or wire-lead*
- *Automation models — for printed circuits*
- *Encapsulated designs available*

General specifications: Centerless-ground, stainless-steel shaft can be sealed with O-ring; gold-plated, fork-type terminals; 2% standard linearity for 50K and 100K — 5% for lower values; temperature range —55 to +105C, to 125C on order; 2 watts at 80C; anodized aluminum body ½″ diameter × ½″ long — ⅝″ long for 100K; corrosion-resistant-alloy bushing; all electrical connections spot-welded or soldered; can be furnished with stops or for continuous rotation.

Write for your copy of our new data sheet giving useful information on these compact, dependable potentiometers.

MFG. INC.

WATERS MANUFACTURING, inc.

Waltham 54, Massachusetts

APPLICATION ENGINEERING OFFICES IN PRINCIPAL CITIES

Serving Industry—
FOR OVER 54 YEARS
PRECIOUS METAL WIRES
Produced in Platinum, Gold, alloys and pure metals—small diameter . . . Platinum alloy resistance wires...Pure Iridium and Rhodium-Iridium alloy Thermo-couple Wire.
BASE METAL WIRES
Very small diameter — for filaments, thermocouples, resistance units.
Metallurgists & Specialists in Small Wire
COATED WIRES
Comprising an extensive range of electroplated grid wires . . . Enamel insulated wires for precision resistors and potentiometers.
Write for Latest List of Products
SINCE 1901
SIGMUND COHN CORP. 121 So. Columbus Avenue • Mount Vernon, N.Y.

perspective illustration of a typical equipment setup.

An appendix includes important data on bandwidth concepts in interference measuring equipment. It explains that despite the fact that selective circuits may display the same maximum response and the same selectivity, they can still exhibit different sensitivities to noise. This must be taken into consideration to prevent erroneous indications.

Electronic Equipment. Specialty Engineering & Electronics Co., 79 Clifton Place, Brooklyn 38, N. Y. Bulletin No. 60 covers the company's line of r-f signal generators, precision attenuators, vtvm's, radiation detection instruments, electronic communication equipments, electronic navigation aids and Radiac equipments. Illustrations, chief features and specifications are shown.

Ceramic Magnets. The Indiana Steel Products Co., Valparaiso, Ind. The characteristics, design and application of Indox I—a lightweight, low-cost, nonmetallic ceramic permanent magnet—are described in a 4-page catalog.

The lightweight and high coercive force of this magnet described make it especially suitable for indicating gages, magnetic couplings, magnetic filters, special instrumentation and miscellaneous holding applications.

Its high coercive force also makes it well adapted for generators, motors, tv focusing units, polarized relays, and in applications where the magnetic length is limited or magnetization prior to assembly is necessary.

Sensitive Relays. Electronics Division of Iron Fireman Mfg. Co., 2838 S. E. 9th Ave., Portland 2, Ore. A comprehensive catalog on high speed and sensitive relays is available. The 12-page catalog describes relays especially designed for precision aircraft electronic equipment conforming to highest standards of inspection with excellent military ratings in quality control.

Operational charts and instructions for their use are included. The

charts provide a means of predicting the behavior of special values of coil resistance and other operating characteristics. Dimensional and wiring diagrams are also shown in the catalog.

Hermetic Seal Plugs. Seals, Ltd., 1010 Mission St., South Pasadena, Calif. A 2-color, 4-page brochure introduces the type S line of glass insulated connectors. It presents design drawings and specifications covering 48 products, and also includes discussions of general use, available finishes and standard characteristics, copper brazing service, and special customer design services. For a copy, write on company letterhead.

AN Connector Chart. The Deutsch Co., 7000 Avalon Blvd., Los Angeles 3, Calif., has prepared a new wall chart to assist engineers to quickly specify AN connectors for a wide range of applications. Items shown for ready reference on the chart are: "How to Select the Right AN Connector" which includes number of contacts, contact size, voltage rating, creepage distance and spacing information; and "How to Specify the Complete Connector Assembly" covering special insert insulation materials and shell finishes.

Other features covered are the code of contact sizes, shell dimensions and an availability check list and shell data. The chart, measuring 22 in. by 27 in. and printed in 3 colors, is available at no charge. Additional data are available on hermetic and quick-disconnects as well as on AN connectors.

Magnetostriction Transducers. The International Nickel Co., Inc., 67 Wall St., New York 5, N. Y. A 38-page booklet covers the design of nickel magnetostriction transducers. It was prepared to guide the engineer toward a workable design in exploring new fields in the sonic and ultrasonic regions.

The booklet, consisting of an article by Boyd A. Wise of Battelle Memorial Institute, contains diagrams, charts and illustrations, as well as a 2-page bibliography. It is available to engineers requesting it on their letterhead.

SERVO MOTORS

from FORD INSTRUMENT for EXTREMELY LOW INERTIA AND HIGH FREQUENCY RESPONSE



- STANDARD SERVO MOTORS in nominal ratings of 10w, 5w, 2½w, 1½w and ½w
- SPECIALS to customer requirements.

Ford Instrument's high precision servos are available in high and low voltage models, in 60cy and 400cy designs, for a multitude of applications. With Ford's smooth iron, low-inertia rotors, they offer these advantages:

- Linear torque-voltage characteristics
- Linear torque-speed characteristics
- Withstand continuous stalling
- High torque efficiency

FREE—Fully illustrated data bulletin gives specifications and performance information. Address Dept. E.

FORD INSTRUMENT COMPANY
Division of Sperry Rand Corporation
31-10 Thomson Ave.
Long Island City 1, N. Y.

Ford Instrument's standard components



DC-AC CHOPPERS

0-500 cycles DEPENDABLE

All military specifications met. Liberal factors of safety to meet emergency conditions.
1. Production sampled daily and life tested to check 1,000 hour rating.
2. Every Chopper given not only one but two tests over the full range of military temperatures before shipment.
3. Only gold contacts used for superior operation in the vital 0-1½ volt d-c range.
4. Liberal safety factors to meet emergency conditions.
a. 0-500 cps.
b. Input voltage ±30%.



WRITE FOR THESE CATALOGS.
No. 371, 0-500 CPS.
No. 370, 60 CPS.

STEVENS ARNOLD INCORPORATED

22 ELKINS STREET
SOUTH BOSTON 27, MASS.

Plants and People

Edited by WILLIAM G. ARNOLD

Industry societies elect new officers, honor engineers for technical accomplishments. Manufacturers continue to expand plants and facilities for future growth. Engineers are promoted and move to new positions in the industry

IRE Elects Officers For 1956, Announces Awards

Arthur V. Loughren

Herre Rinia

Frank J. Bingley

ARTHUR V. LOUGHREN, vice-president in charge of research of the Hazeltine Corp., was elected president of the Institute of Radio Engineers for 1956. He succeeds John D. Ryder, dean of the school of engineering of Michigan State University, as head of the international society of 44,000 members.

Herre Rinia, director of research of the Philips Research Laboratories in Eindhoven, Holland, will succeed Franz Tank, professor at the Swiss Institute of Technology, Zurich, Switzerland, as IRE vice-president.

Elected as directors for the 1956-1958 term are E. W. Herold, director of the electronic research lab, RCA Laboratories, Princeton, N. J. and J. R. Whinnery, professor of electrical engineering, University of California, Berkeley, Calif.

Regional directors elected for 1956-1957 are: Region 1 (North Atlantic), C. R. Burrows, director of the school of engineering, Cornell University, Ithaca, N. Y.; Region 3 (Central Atlantic), J. G. Brainerd, director of the Moore school of electrical engineering, University of Pennsylvania, Philadelphia, Pa.; Region 5 (Central), J. J. Gershon, director of resident instruction, DeVry Technical Institute, Chicago, Ill.; Region 7 (Pacific), C. F. Wolcott, technical director of Gilfillan Brothers, Los Angeles, Calif.

IRE also announced two annual awards for 1956. Frank J. Bingley, executive engineer of the Philco Research Labs, has been named to receive the Vladimir K. Zworykin Television Prize Award for 1956. He will receive the award for his study of the relationship between the science of colorimetry and the NTSC color signal.

The Browder J. Thompson Memorial Prize for 1956 will be awarded to Jack E. Bridges, research engineer of the Zenith Radio Corp., for his paper, Detection of Television Signals in Thermal Noise.

Seventy-five radio engineers and scientists from the U. S. and other countries were named Fellows of the IRE. The complete roster is published in this issue of ELECTRONICS beginning on page 346.

RCA Expands For Hi-Fi, Promotes Three

A $2.7 MILLION addition to the RCA plant at Cambridge, Ohio, will be constructed for increased production of tape recorders and high fidelity instruments.

The addition will add more than 210,000 sq ft of floor space to the present 135,000 sq ft at the Cambridge plant—now used for the manufacture of fabricated parts for record players, radios and television receivers as well as the assembly of record changers and phonographs.

Approximately 1,400 persons are now employed at the plant under the direction of T. F. Whitten, plant manager.

Work on the new addition will get under way immediately and is expected to be completed in 1956.

RCA also announced the election

NOW

adjustable

POLYSTYRENE CAPACITORS

with Accuracy in the order of 0.1% or better and Long Time Stability in the order of 0.03%



Available from 0.1 M.F.D. to 8 M.F.D.

Check these outstanding features:

- I. R. - @ 25° C - 10^{12} OHMS
- Dielectric Absorption - .015%
- Dissipation Factor - .0002
- Temp. Coeff. (-20° to 140° F.) 100 P.P.M. per °C

Excellent for Computer Integration, Test Equipment or Secondary Standards.

Join these other leading firms in specifying Southern Electronics' precision polystyrene capacitors for your most exacting requirements: Reeves Instrument Corp., Electronic Associates, Inc., Convair, Berkeley Scientific, M.I.T., Calif. Inst. of Tech., and many others. Write for complete catalog -

SOUTHERN ELECTRONICS

POLYCON SEC MYCON

Corporation

239 West Orange Grove Ave., Burbank, Calif.

INSIST ON S.E.C. CAPACITORS FOR **PERFECT** HERMETIC SEAL TO INSURE EXTREMELY LOW LEAKAGE!

Now available from 0.1 M.F.D. to 10 M.F.D.

of Douglas H. Ewing as vice-president of RCA Laboratories, Charles P. Baxter as vice-president and general manager of RCA Victor television division and James M. Toney as vice-president and general manager of the radio and "Victrola" division.

Dr. Ewing joined RCA in 1945. He was assigned to the Victor division as manager of the teleran section and, subsequently, as manager of advanced development. In 1949 he took leave of absence to become director of development of the Air Navigation Development Board in Washington, D. C.

Rejoining RCA in 1951, Dr. Ewing was appointed director of research services of the RCA Laboratories division in Princeton, N. J. In 1953, he became director of the physical and chemical research laboratory. He was named administrative director of the Laboratories, in June, 1954.

Capodanno and Vassar Join CBS-Columbia

R. T. Capodanno

R. T. CAPODANNO has been named vice-president in charge of engineering for CBS-Columbia. William Vassar was appointed director of engineering.

Capodanno was formerly vice-president in charge of engineering for Emerson Radio and has been in the engineering and development phase of the electronic field since 1927. Prior to his Emerson experience he was connected with Philco Corp. for eleven years.

Vassar was with Emerson Radio as executive chief engineer.

RETMA Honors Clement Of Avco



LEWIS M. CLEMENT, technical advisor to the vice-president and general manager of the Crosley government products division of Avco Manufacturing Corp., left, was recently awarded the RETMA 1955 plaque at the IRE dinner in Syracuse, N. Y. The plaque was presented by Arthur V. Loughren, right, vice-president in charge of research for the Hazeltine Electronics Corp. of Little Neck, N. Y. Loughren was honored with the plaque in 1954. W. R. G. Baker, director of the RETMA engineering department, said Clement, a resident of Washington, D. C., was chosen for the honor because of "his effective initiation and conduct of important activities in the field of reliability of electronic equipment and for his long time contribution to the work of the RETMA engineering department."

Westinghouse Selects Research Heads

Two Westinghouse research scientists, Daniel Alpert and Aaron Wexler, have been named associate directors of the Westinghouse research laboratories.

Dr. Alpert joined Westinghouse in 1941 as a research fellow and in 1950 was named manager of the physics department of the research laboratories.

Since 1950 he has headed a group engaged in ultrahigh vacuum research.

Before joining Westinghouse, Dr. Wexler served as research associate at Johns Hopkins.

He came to the Westinghouse research laboratories in 1947 and established the low temperature laboratory. In 1952 he was named an advisory physicist at the laboratories and in 1953 was named manager of the magnetics and solid state physics department.

In the consumer products section of the company, Chris J. Witting, formerly president of the Westinghouse Broadcasting Co., has been appointed general manager of consumer products.

Westinghouse also announced the formation of a new department in Baltimore for the manufacture of a line of industrial electronics gear.

Robert C. Cheek, formerly assistant manager of the company's Baltimore electronics division, has been named manager of the industrial electronics department.

The department, which will em-



Inspector checks finished enameled wire to insure customers' requirements are met.

THIS MAN CAN HELP YOU

Eliminate cost of incoming magnet wire inspection!

This inspector acts as customers' agent in the Anaconda magnet wire mill.

Result: Anaconda Magnet Wire complies with such exactness to specifications that many customers have felt it possible to *eliminate incoming inspection*... at considerable savings in money, time and manpower.

More than this, customers say Anaconda quality control pays off in smoother winding room performance . . . and helps them produce a consistently high quality product at lowest cost.

Talk to the Man from Anaconda about a trial run of Anaconda wire to prove it to yourself. Call or write: Anaconda Wire & Cable Company, 25 Broadway, New York 4, New York.

ASK THE MAN FROM ANACONDA® FOR MAGNET WIRE

have you ever seen a graphic recorder with . . .

- **PORTABILITY** . . . weighs less than 15 pounds, measures 10" x 7⅛" x 8".
- **VERSATILITY** . . . can be used as recording millivoltmeter or —with appropriate transducers — to record measurement of physical quantities.
- **RECTILINEAR** trace representation.
- **FULL CHART** zero positioning.
- **HIGH INPUT** impedance and high allowable signal source impedance.
- **PANEL** damping control for optimum stability.
- **CHART DRIVE** extension for synchronization with other equipment.

THE VARIAN G-10 GRAPHIC RECORDER HAS ALL THESE FEATURES AND MORE . . . IS PRICED AT $295



WRITE TODAY FOR COMPLETE TECHNICAL DATA ON THIS REMARKABLE NEW INSTRUMENT AND ITS FULL ACCESSORY LINE.

Special Products Division
VARIAN associates
PALO ALTO 1 CALIFORNIA

Representatives in all principal cities
MICROWAVE TUBES — INSTRUMENTS
Want more information? Use post card on last page.

ploy about 115 persons, will be responsible for the engineering, manufacture and sale of induction heating equipment, power line carrier equipment and a variety of other industrial electronic devices.

Cheek joined Westinghouse in 1939. From 1942 until 1951, he was a consultant on power systems problems and subsequently acted as a specialist in carrier and microwave applications. In 1951, he was transferred to Baltimore as assistant sales manager for the electronics division. He was appointed assistant division engineering manager in 1953.

Airborne Instruments Appoints Dunning

ORVILLE M. DUNNING has been appointed director of the engineering and production division of Airborne Instruments.

He was formerly vice-president in charge of engineering for Hazeltine Electronics Corp. of Little Neck, New York.

Dunning brings to his new position over thirty years of experience in management, production and engineering. His work at Airborne will be to direct all of the activities of the division.

Van Norman Acquires Insuline And Transitron

INSULINE CORPORATION OF AMERICA of Manchester, New Hampshire, manufacturer of electronic parts and equipment, has become a subsidiary of the Van Norman Co. of

Dependable • Precision Wire Forming and Stamping Specialists

Precision Parts to meet your Production and Engineering needs. From .002" dia. to .125" dia. Radio tube parts—Stampings—Drawings. Modern facilities, high-production equipment.

Send sketch or print for quotation.

PIX
MANUFACTURING CO., Inc.
81-A Hudson Street
Newark 3, New Jersey

Want more information? Use post card on last page.

Springfield, Mass., a machine tool firm. Van Norman also acquired Transitron of New York, N. Y.

No change in officers or personnel will be made at Insuline. Samuel J. Spector continues as president and chief executive officer; Bernard L. Cahn, vice-president for sales; Myles Spector, vice-president for manufacturing; William J. Schoenberger, assistant to the president and Augusta S. Spector, secretary.

Transitron, which will be operated as a wholly-owned subsidiary of Van Norman, currently operates two plants in New York City. However, present plans call for moving to Manchester, New Hampshire, where plant space of approximately 100,000 sq ft will be available. Entire engineering staff of Transitron is being retained and will move with the operation to Manchester. Insuline Corporation of America is located there.

Management of Transitron will consist of Samuel Lackoff, president and Samuel J. Spector, vice-president, who will act as directors with J. Y. Scott, president of Van Norman. Herbert I. Segal, chairman of the executive committee of Van Norman will also hold this position with Transitron. R. W. Porter is treasurer of Van Norman and also of the new subsidiary.

GE Sets Up New Sections, Selects Engineers

IN the General Electric light military electronic equipment department, William J. Kuehl was named manager of the communication and navigation subsection; Russell I. Mason was named manager of the airborne early warning systems and sonar subsection and Donald E. Uren was named manager of the special project subsection.

Establishment of the new subsections resulted from growth of the weapons system concept in some of the department's product lines, according to GE.

Robert R. Johnson has joined the communications and computer subsection of GE's Electronics Laboratory.

He previously was on the staff of Hughes Aircraft Co. at Culver City, Calif., where he spent four years as

AT LAST!
A SUBMINIATURE
THERMAL TIME DELAY RELAY*
for
GUIDED MISSILES and PRINTED CIRCUITS

The only Relay under 1" in height that offers the following:

- Time delays from 1 second to 10 minutes.
- Heater Voltages to 230 volts. Interchangeable on A.C. or D.C. of any frequency.
- Contact rating up to 6 amps.
- Hermetically sealed.
- Fully compensated for ambient temperatures of from −65°C to +125°C.
- Will withstand vibration of from 5 to 500 CPS at acceleration of 10 G.
- Shock up to 50 G.
- Rapid reoperating time.
- Available in 7 and 9 pin.
- Price of sample $9.25 net each.

*PATENT PENDING

FALCON ELECTRONICS CORP.
308 WILLIAM STREET, HARRISON, N. J.

space saver
RECORDER
at lower cost



NEW
miniature
RECORDING
POTENTIOMETER

The Westronic Model 2705 miniature potentiometer solves your recording needs and control panel space problems. Here are some of the features.

- ★ One second pen travel
- ★ Weighs approximately 25 lbs.
- ★ Guaranteed performance
- ★ Thermocouple or MV. calibrations
- ★ Lower cost
- ★ Panel space 9⅝" x 8½"
- ★ 5" Strip chart record
- ★ Continuous standardization
- ★ Null balance system
- ★ Accuracy better than 0.5%

Write for descriptive literature

westronics, INC.
3605 McCART STREET ★ FORT WORTH, TEXAS

Want more information? Use post card on last page.

VENTED-EXHAUST IS NOW AVAILABLE



on The Welch (Model 1402)

TWO-STAGE DUO-SEAL VACUUM PUMP

at no increase in price . . .

★ Vented Exhaust Permits Pumping of Most Condensable Vapors

★ Eliminates Use of Traps or Oil Separators in Systems Containing Water or Other Condensables

★ Reduces Number of Oil Changes Required

Illustration shows the 1402B Duo-Seal Pump equipped with Vented Exhaust.

At	PUMPING SPEED Vented Exhaust Closed	Vented Exhaust Open
1000 microns	110 L/M	100 L/M
100 microns	100 L/M	92 L/M
10 microns	92 L/M	68 L/M
1 micron	76 L/M	28 L/M

GUARANTEED VACUUM — with vent closed 0.1 micron. When the vent is open, only slightly higher ultimate pressures result — usually in the range of 1 micron.
FREE AIR CAPACITY — 140 liters/minute (5 cubic feet)

1402VEB. DUO-SEAL VACUUM PUMP, Motor Driven, For 115 Volts, 60 Cycles, A.C. Each, $295.00
1402VE. DUO-SEAL VACUUM PUMP. Unmounted, With pulley, but without motor, belt, or base Each, $225.00
For attached Belt Guard, add $15.00 to above prices.

1402VED. DUO-SEAL VACUUM PUMP, Motor Driven. For 115 Volts, DC. Each, $349.50
1402VEC. DUO-SEAL VACUUM PUMP. Motor Driven, For 250 Volts, 60 Cycles, A.C. Each, $295.00
For attached Belt Guard, add $15.00 to above prices.

VENTED EXHAUST IS AVAILABLE ON ALL TWO-STAGE DUO-SEAL® PUMPS

Write for our Complete Catalog listing Duo-Seal® Pumps and Vacuum Accessories

W. M. WELCH SCIENTIFIC COMPANY
DIVISION OF W. M. WELCH MANUFACTURING COMPANY
ESTABLISHED 1880

151 Sedgwick St., Dept. H, Chicago 10, Illinois, U. S. A.

PLASTICON

THE PLASTIC FILM CAPACITOR OF MYLAR MEETS MIL—C25A

Characteristics	Type MACM	Type MSCM
Temperature Range	−55°C to 85°C*	−55°C to 125°C
Insulation Resistance @ 25°C	100,000 Meg./mfd.	100,000 Meg./mfd.
Except that need not exceed	125,000 Megohms	125,000 Megohms
Insulation Resistance at High Ambient Temp	5,000 Meg./mfd.	400 Meg./mfd.
Except that need not exceed	10,000 Megohms	1,000 Megohms
Capitance Change 25°C to −55°C	6%	10%
Life Test — Percentage of Rated Voltage at High Ambient Temperatures	140	140
Power Factor — 1000 c.p.s.	0.5%	0.5%

All Case Sizes, Leads, Mounting Brackets and Tolerances to Meet MIL — C25A
SPECIAL UNITS DESIGNED UPON REQUEST

* Rated to 125°C with Derating

MYLAR — DU PONT'S NEW POLYESTER FILM.

CONDENSER PRODUCTS
Division of the New Haven Clock and Watch Co.
140 Hamilton Street, New Haven 4, Connecticut

a research physicist working on design of digital airborne computers, business data systems and machine tool automation projects.

GE also announced that William Jan van der Grinten has joined the company as a physicist in the semiconductor and solid state sub-section of the Electronics Laboratory.

Dr. van der Grinten has been with GE since 1940. He was with the Kaiser Wilhelm Gesellschaft, a research foundation, in Berlin, Germany from 1935 to 1940 and was a research associate at the GE Research Laboratory in Schenectady from 1940 to 1943.

From 1943 to 1945, Dr. van der Grinten was an assistant professor in the physics department of the University of Rochester. He returned to GE at Schenectady in 1945 and remained there until his present appointment.

Also in the Electronics Lab, W. Crawford Dunlap, Jr., has been named a consultant in the semiconductor field.

Dr. Dunlap has been engaged in the field of semiconductors since 1945.

During World War II, he was an assistant physicist in the western regional research laboratory of the U. S. Department of Agriculture. He joined the physics staff at GE's Research Laboratory as a research associate in 1945. He was appointed to the Laboratories Department of the Electronics Division in 1954.

Keller Appointed Panellit Research Head

ERNEST A. KELLER has been appointed director of research of Panellit of Skokie, Ill. The firm

designs, engineers and builds control and data handling systems. Dr. Keller will lead an expanded research program which includes development projects in data handling, automation and computer technology.

A native of Switzerland, Dr. Keller came to the United States in 1950 as a technical executive to evaluate markets for Oerlikon Machine Tool Works, Zurich. Later he joined Daystrom Electric Corp. as physicist in charge of tape recorder development and high-fidelity sound equipment.

Until coming to the U. S. he served as research director with Oerlikon, devoting himself to applied research in the fields of ballistics, electronic and mechanical test equipment, magnetic recording, telephone switching circuits and automatic production techniques.

Sylvania Builds More Plants, Names Engineers

SYLVANIA ELECTRIC will construct a multimillion dollar plant in Altoona, Pa. for the production of receiving tubes.

The new 110,000 sq ft single-story plant will ultimately replace an existing smaller plant and leased warehouse space in Altoona. It will be built on a 15-acre site which has already been acquired by the company. In the plant 100,000 sq ft will be for manufacturing. The remainder will contain offices and a cafeteria.

Employment is expected to remain at its current level of approximately 800 for the foreseeable future, since the new project will be a consolidation of existing production and warehousing facilities.

Sylvania also announced plans to build a new 76,000 sq ft warehouse and sales office in Atlanta, Ga.

Construction is already under way and completion is scheduled for March, 1956.

A single story building, the new warehouse will include 8,000 sq ft of office space. Located on six and a half acres, the building will have a storage capacity of approximately twice that of the present Atlanta warehouse facility.

In the firm's new Waltham Labs Richard M. Osgood has been ap-

MODERN DESIGN DOES MAKE *the BIG DIFFERENCE!*

...FOR MODERN DESIGN IN TRIMMERS SPECIFY THE

TTC® RFT METLFILM

★ Manufacturer of the world's finest potentiometers
★ Pioneer of precision wire-wound potentiometers
★ Foremost in the development of new designs
★ Unequalled for prompt delivery—production, prototype

TIC, leader in the development of new designs for industrial and military applications, incorporated the most wanted features of a trimmer potentiometer into the modern design of the diminutive RFT. Advanced design extends from its compact, rugged case to the revolutionary metallic film resistance element. The simplicity of RFT design also makes possible production and delivery at a rate unequalled in the industry.

Size, accuracy, and stability — essential characteristics of trimmer potentiometer combined in the low-cost RFT. Applicable as adjustable resistors or voltage dividers, the RFT provides infinite resolution . . . wide temperature range (−55°C to +125°C) . . . true miniature size (7 can be stacked in a square inch) . . . and wide resistance range (50 ohms to 25K).

Mechanical features include a housing of red Alumilite base and stainless steel cover for environmental protection . . . stainless steel 25-turn lead screw for precise, stable adjustment . . . precious metal contacts . . . and light weight (0.38 oz.).

Precision construction . . . environmental stability . . . and compact, modern design provide versatility for wide application of the RFT for:

- Balancing adjustments
- Critical biasing
- Trimming circuit voltages, currents, or resistances
- Padding
- Fixed gain adjustments
- Critical threshold voltage adjustments
- Varible parameter compensation

Complete specifications for the RFT Metlfilm Potentiometer available on request.

TECHNOLOGY INSTRUMENT CORP.

533 Main Street, Acton, Mass. COlonial 3-7711
West Coast Mail Address Box 3941, No. Hollywood, Calif. POplar 5-8620

Want more information? Use post card on last page.

STANDARD TELETYPEWRITERS AND RECTIFIERS

A wide range of standard teletypewriters and accessories are available for early delivery from current production. These machines are assembled from parts produced by a leading American manufacturer and are standard and interchangeable in every way. They can be supplied in either commercial or military packing, with instruction books. All units carry a 12-months' guarantee. We stock spare parts.

The following types of teletypewriters are available:

- Model 15 Page Printer.
- Model 19 Page Printer.
- Model 14 Tape Printer.
- Model 14 Typing Reperforator
- Model 14 Transmitter-Distributor.
- Type TG-7A or TG-7B Teletypewriter (U.S. Signal Corps version of Model 15)
- Type TG-26 Teletypewriter (U.S. Signal Corps Typing Reperforator Transmitter-Distributor Set).
- Type TT-7 Teletypewriter (U.S. Signal Corps version of Model 19)

Teletypewriters can be supplied in the following optional arrangements:

- Send and receive or receive only.
- 50 or 60 cycle synchronous or governed, or d-c governed motors.
- Holding or pulling-magnet selectors.
- Line relay and relay bracket optional.
- Tables optional.
- Rectifiers optional.
- Any standard keyboard and type-pallet arrangement.
- Any standard arrangement of functions.

Rectifiers: Input 115v 50-60 cycles A.C. Output 115 volts D.C.

Regulated		Non-Regulated	
Type	D-C Amps.	Type	D-C Amps.
REC-13	0.6	F11360	0.2
F3901	0.8	REC-4	0.25
RA43	4.5	RA-87	0.4
		F8387	0.6
		K55988	0.8

RADIO ENGINEERING PRODUCTS
1080 UNIVERSITY STREET, MONTREAL 3, CANADA
Telephone: UNiversity 6-6887 Cable Address: Radenpro, Montreal
MANUFACTURERS OF CARRIER-TELEGRAPH, CARRIER-TELEPHONE AND BROAD-BAND RADIO SYSTEMS

ALLIED world's largest supplier of
ELECTRON TUBES FOR INDUSTRY

ALL BRANDS IN STOCK
AMPEREX
G.E.
EIMAC
R.C.A.
RAYTHEON
SYLVANIA
TAYLOR
TUNGSOL
VICTOREEN
WESTINGHOUSE
and others

ALL TYPES IN STOCK
Power Tubes
Rectifiers
Phototubes
Radiation
Sub-Miniature
Oscillograph
Ignitrons
Thyratrons
Image Orthicon
Klystron
All Special Purpose Tubes

IMMEDIATE DELIVERY FROM STOCK
saves you time, effort and money

ALLIED regularly stocks for *quick shipment* the world's largest inventory of special-purpose electron tubes. We specialize in supplying the tube needs of industry, broadcast stations, laboratories, schools and government. Save time, effort and money on your electron tube orders —phone, wire or write us for expert, immediate shipment.

Refer to your ALLIED Catalog for all electronic supplies. Copies of our latest 324-page 1956 edition are available FREE on request.

ALLIED RADIO
100 N. Western Ave.
Dept. 11-A-6, Chicago 80, Ill.

EVERYTHING IN ELECTRONICS FROM ONE DEPENDABLE SOURCE

pointed manager of equipment fabrication.

He will direct the manufacture of prototype equipment developed by the avionics and guided missiles research staff.

Before joining Sylvania, Osgood was chief of the electronic systems division of the Air Materiel Command, U. S. Air Force. He was responsible for coordination of the design, production, and installation of a semiautomatic air defense system for the continental United States and the Distance Early Warning radar line at the northern edge of North America. Also, Heinz K. Henisch has been appointed a visiting scientist at the physics laboratory of Sylvania.

On leave of absence from the University of Reading, England, Dr. Henisch is serving in the Sylvania post for one year, working on semiconductor and electroluminescence research. At Reading, Dr. Henisch heads a group currently engaged in advanced research on transistor physics, in collaboration with Dr. P. C. Banbury. Engaged in this field since 1945, Dr. Henisch has been on the teaching staff of the University for eight years.

Beckman Builds New Plant, Promotes Managers

CONSTRUCTION has started on the new $250,000 plant in Richmond, Calif. of the Berkeley division of Beckman Instruments.

The new 55,000 sq ft building,

Donald C. Duncan

HYCOR
TELEMETERING
FILTERS



Hycor band-pass and low-pass telemetering filters are produced in exact accordance with accepted military standards. In addition to designs which conform to Applied Physics Laboratory specifications, miniature units are available.

Hycor Telemetering filters are potted for complete protection against vibration and humidity. The finest components are used to minimize aging effects on characteristics.

Send for **Bulletin TF** *which describes standard types available.*

Hycor engineers will be pleased to quote on your most exacting specifications.

Representatives in Principal Cities

HYCOR
Company, Inc.
Subsidiary of International Resistance Company
11423 Vanowen Street
North Hollywood 1, Calif.

Want more information? Use post card on last page.

situated on a 4½-acre site adjacent to the present Berkeley division facility, will approximately double plant capacity. The new building will be used to house the systems engineering department, substantially increase the research and development facilities and add to the overall manufacturing capacity.

Beckman also announced that Donald C. Duncan has been appointed general manager of the Berkeley division.

Thomas Allinson was named manager of the division. He will report to Duncan who will continue to serve as general manager of the firm's Helipot and Arga divisions in South Pasadena, Calif.

Duncan was an industrial control test engineer for GE in 1940, and from 1941 to 1945 served with the Navy's Bureau of Ships in Washington, D. C. as an electrical engineer.

Allinson joined Berkeley in 1951 as plant manager. In 1954 he was named marketing manager directing advertising and sales promotion, market research and sales activities.

Before joining Beckman he was plant manager for the Marchant Calculating Machine Co., in Emeryville, Calif.

Varian Dedicates Canadian Plant

VARIAN ASSOCIATES of Palo Alto dedicated a new $400,000 manufacturing and research plant in Georgetown, Ontario. It has 10,000 sq ft of space. The new plant will be operated by Varian Associates of Canada Limited, a wholly owned subsidiary of the California firm. It will produce microwave vacuum tubes and related devices for the Canadian government and commercial customers. It will also provide a second manufacturing source under several of the parent company's United States defense contracts.

The new plant's manager, C. W. Carnahan, was appointed vice-president and general manager. He was previously engaged in engineering management in the Varian Associates Palo Alto headquarters. Before that, he served five years as

NOW . . .
a DC Reference Voltage
That's Constant
from −55° to +100°C

K-Volt Standard
Tubeless Constant Voltage Source
For Measurement & Control Circuits

Designed to replace the chemical cell and VR tube in airborne, laboratory and other critical instrumentation, the K-Volt Standard provides constant voltage through extremes of operating conditions . . . including ambient temperatures as low as −55° and up to 100°C. Operating from AC or DC supply, it employs no tubes or moving parts, is unaffected by position, vibration or mechanical shock. Negligible temperature coefficient, dependable regulation characteristics and rugged design make it applicable as an absolute reference, a constant output working supply, or a precision voltage regulator wherever specifications demand highest stability. Other important features are:

- Small size: 1½" by 1⅛" dia.
- Power drain less than 1.8 watts
- Life: more than 10,000 hrs.
- Vibration: conforms to MIL-E-5272A
- Miniature 7-pin base
- Weight: less than 3 oz.
- Hermetically sealed
- Random drift less than 0.1% over 1000 hrs.

Models to Meet Wide Range of Application Requirements: The K-Volt Standard is available for operation from 26.5 volts DC, or 117 volts AC, 60 or 400 cycles; DC output 6 volts or 1 volt, at 1 ma or 10 ma.

For complete specifications and performance data send for bulletin No. F128

*TRADE MARK
AVIEN
Precision Instruments and Control Systems
58-15 Northern Blvd., Woodside 77, N. Y.

Want more information? Use post card on last page.

AMERICAN TELEVISION & RADIO CO. ST. PAUL, MINN.

introduces the new ATR TV

Full Door Console Receiving Sets

UNSURPASSED IN BEAUTY

UNEQUALLED IN PERFORMANCE

UNMATCHED IN QUALITY CONSTRUCTION

exclusive profitable dealer franchises now available

Designed with the Serviceman in mind ... easy to get at

WRITE TODAY FOR COLORFUL BROCHURE SHOWING THE NEW LINE OF ATR TV SETS

ALSO MANUFACTURERS OF DC-AC INVERTERS, "A" BATTERY ELIMINATORS, AUTO RADIO VIBRATORS

ATR AMERICAN TELEVISION & RADIO CO. *Quality Products Since 1931* SAINT PAUL 1, MINNESOTA - U.S.A.

manager of electronics research at Sandia Corp., Albuquerque, New Mexico.

B. A. Breckenridge, assistant treasurer, was appointed assistant secretary and business manager. Before joining Varian Associates of Canada, he was with Fleet Manufacturing of Fort Erie, Ontario.

Associated Missile Promotes Two

Earl R. Skaggs

EARL R. SKAGGS, vice-president and former director of product engineering, has been named to the newly created post of assistant general manager of Associated Missile Products Corp. of Pomona, Calif. Joseph Tampico, vice-president and former director of research and development, has been made the firm's director of engineering.

Modification of the AMF subsidiary's 55,000 sq ft plant has been completed. A personnel group of over 200 is anticipated by the end of 1955.

Mallory Opens Plant, Plans Another

A NEW manufacturing plant for the production of electrolytic capacitors has been opened in Huntsville, Alabama, by P. R. Mallory, (Huntsville), an affiliate of P. R. Mallory & Co. of Indianapolis.

The company chose Huntsville as its location because of the availability of power, an excellent water supply and ample labor.

Located on a twenty-one acre site, and completely equipped, the



BARE PLUTONIUM SPHERE

"JEZEBEL"

NEWEST OF THE CRITICAL ASSEMBLIES AT LOS ALAMOS

—where scientists and engineers, working with some of the Western World's finest equipment and facilities probe the unknown and seek answers to tomorrow's problems.

The Laboratory's program for pioneering in nuclear and thermonuclear power and nuclear propulsion, ranks in importance with the Laboratory's continuing and ever expanding achievements in atomic weapons research and development.

To top level scientists and engineers, capable of meeting the challenge of independent and original research, application and development work, the Laboratory—with its air of freedom ... the exciting presence of new ideas ... the stimulation of important things happening—offers unexcelled opportunity.

Los Alamos itself, nestling among the pines on the lower eastern slope of the towering Jemez Mountains, is a delightful small city—an ideal community and climate in which to live and raise a family.

For more detailed information, direct your inquiry and background resume to

DEPARTMENT
OF
SCIENTIFIC PERSONNEL
Division 403

los alamos scientific laboratory
OF THE UNIVERSITY OF CALIFORNIA
LOS ALAMOS, NEW MEXICO

plant represents an investment of $2 million.

Paul R. Hufnagel is vice-president and general manager of the Huntsville corporation.

In another move, Mallory with Schwarzkopf Development Corp. formed Mallory-Schwarzkopf Metals. The jointly-owned new company will produce and fabricate refractory metals principally for the electronic, chemical and aircraft industries.

Dr. Paul Schwarzkopf has been named chairman of the board and P. R. Mallory, president. Richard L. Hopkins is executive vice-president.

A new plant is planned for Huntsville, Alabama, with initial operations scheduled for late 1956.

Litton To Build New Plant

LITTON INDUSTRIES' power tube division in San Carlos, Calif. will build a 40,000 sq ft plant adjacent to its present facilities. It is to be completed by early 1956 on a recently purchased 11-acre site.

The present plant at San Carlos has 60,000 sq ft of space.

The firm will have a total plant area of 350,000 sq ft at its seven locations when the new plant is completed.

Lenkurt Elects Vice-President

WILLIAM H. HEFLIN has been elected vice-president and general manager of Lenkurt Electric Co. of Canada.

The Vancouver company, an affiliate of Lenkurt Electric Co. in San Carlos, Calif., produces carrier telephone and telegraph systems and other electronic equipment.

Heflin has been with Lenkurt in San Carlos for seven years during which time he has held various positions in sales, engineering and production. He had been manager of the procurement division since 1953. Before that he was factory manager of the special equipment division.

Division managers for Lenkurt of Canada are J. S. Agnew, account-

FANS
MOTORS
BLOWERS

YEARS-AHEAD ENGINEERING
Stainless Steel Thru-Bolts.
Die-Cast Aluminum Housings.
Riveted Stator.
Positive Bearing Alignment.
Uniform Air Gap.
Ball Bearings.
Shock, Vibration Resistant.
Humidity, Fungus Resistant.
Omni-Position Mounting.
Temperature Lubricated.

AIR-MARINE MOTORS

Blowers—Variable frequency, axial fan, axial vane, and centrifugal.

A15BF-15 50-800 cycles, single winding.

A15AB-2 50-60 cycles and 400 cycle, single winding.

A15CF-10 50-60 and 320-1000 cycles, dual winding.

Write for specific information and brochure . . . and use the Air Marine Motors advisory services without obligation.

Constantly developing to meet your exacting needs . . .

air-marine motors, inc.
369 Bayview Avenue • Amityville, N. Y.
West Coast Factory: 2055 Pontius Avenue • Los Angeles 25, Calif.

Want more information? Use post card on last page.

FOR TRANSISTOR CIRCUIT DESIGNERS!

The New MA Automatic Universal
TRANSISTOR CURVE TRACER

- Displays Output or Transfer Curve in Grounded Base or Grounded Emitter Connection Dynamically Displays Entire Family of Curves Simultaneously on Oscilloscope
- Internally Generated Calibration Axes Displayed at All Times in Any One Quadrant

Designed for comparing, matching and selecting—detecting anomalies—studying effects of temperature, age, normal usage and overloading—and for detecting failures and causes. Instrument tests NPN, PNP, Junction and Point Contact Transistors and features flexibility to accommodate new types. Plots entire family of curves simultaneously on a standard laboratory DC oscilloscope.



TRANSISTOR CURVES. Output (V_c vs. $I_c|_{I_e}$): Transfer (V_e vs. $I_c|_{I_e}$)
VERTICAL CALIBRATOR: 0-1, 10, 100 volts
HORIZONTAL CALIBRATOR: 0-1, 10, 100 volts
QUADRANTS: I, II, III, IV
LOAD RESISTANCE: 100-10,000 ohms
ACCESSORIES FURNISHED: Transistor receptacle

For illustrated literature containing complete specifications, call or write:

MAGNETIC AMPLIFIERS • INC
AFFILIATE OF GENERAL CERAMICS CORPORATION
632 TINTON AVE., NEW YORK 55, N. Y.
Telephone: CYpress 2-6610

Designers & Manufacturers of Servomechanisms, Magnetic Amplifiers & Industrial Controls

VACUUM TUBE RETAINERS

These retainers are used to secure Vacuum Tubes and to resist side motion of Vacuum Tubes used in radio equipment which is subject to shock and vibrations. These retainers meet the requirement of all JAN specifications. The insulated portion is made of a melamine base Fibre Glass Phenol which provides 300 volts insulation to ground and withstands a temperature of 350 F. The insulated plate can readily be fastened or released by hand.

Available for envelope types T7, T8, MT8, T9, T12, ST12, T12ZDI, ST14, S14, ST16, T5½, T6½, MT-IC, ST19, T14, ST128CT-9.

Manufacturers of Electronic Components

JAMES IPPOLITO & CO., INC.
1624 Stillwell Ave., Bronx 61, N. Y.

ing; C. W. Hunter, sales engineering; C. E. Whaley, applications engineering; M. O. Swailes, production and H. R. Herron, quality control.

Raytheon Rents Plant Space

RAYTHEON leased 65,000 sq ft of space in the former Assabet Mills of Maynard, Mass.

The space will be used for the development and engineering activities of the radar-system group attached to the missile and radar division.

Raytheon will open a new, multimillion dollar engineering laboratory in nearby Wayland. The Wayland plant has approximately 225,000 sq ft of floor space and will employ approximately 1,000 engineering personnel.

Eimac Names Production Heads

FRANCIS MIGGE has been named to the newly-created post of manager of manufacturing for Eitel-McCullough.

Robert Herdman will assume the duties of production manager, the position formerly held by Migge.

As manager of manufacturing, Migge will direct all phases of Eimac manufacturing activity at both the San Bruno and Salt Lake City plants.

He joined the firm in 1940 and served as head of various pro-



Francis Migge

One RELAY switches both *reliably*

Switches heavy loads up to 10 amperes with special heavy current contacts



Switches low voltage, low current signal loads with bifurcated (twin) contacts

Other variations obtainable in the versatile Magnecraft Class 22 Relay include—

Available for AC or DC operation

Resistance to shock, vibration and temperature change to meet military specifications.

Bifurcated, normal, heavy current and extra heavy current contacts up to 10 amperes.

Contact arrangements up to 12 arms per stack, (24 arms per relay)

Operating speed 3 to 5 milliseconds minimum; slow operate up to .1 second; slow release up to .15 sec.

Plug-in, open, hermetically sealed or dustproof enclosed.

Tell us what you need or send for Catalog.



MAGNECRAFT ELECTRIC CO

3350B W. Grand Ave. Chicago 51, Ill

Want more information? Use post card on last page.

duction departments until his appointment as assistant production manager in 1950. He was named production manager in 1951.

Herdman, who moves up from his position as assistant production manager, also joined the firm in 1940. He became assistant production manager in 1951.

Corning Glass Expands Parts Plant

CORNING GLASS plans to enlarge its facilities for manufacturing glass electronic components in Bradford, Pa.

The plant expansion will include the eventual installation of automatic resistor and capacitor production equipment. The expansion was required to meet increasing demand, especially from radio and television set manufacturers, according to the company.

The firm's low-power resistor line has been purchased by 13 television set manufacturers.

Additional space has been obtained that will nearly double the present Corning plant area in Bradford. While necessary alterations to the newly-acquired area are now being carried out, the expansion, which will include eventual consolidation of all the company's major electronic manufacturing operations, will be carried out gradually during 1956 to avoid disruption of delivery schedules.

Hupp Acquires Pioneer Electric

THE HUPP CORP. of Detroit, Mich. has acquired the business and assets of the Pioneer Electric and Research Corp. of Chicago, an electronics firm engaged in both manufacturing and research operations.

Hupp will issue approximately 16,000 shares of its common stock in payment for the business and assets of Pioneer. This stock is to be distributed to the Pioneer stockholders.

Pioneer Electric and Research has developed and is now manufacturing electronic remote control equipment. This equipment, which is primarily being used in teletype-

AINSLIE REFLECTORS

(Photo courtesy of the New England Bell Telephone Co.)

THE REFLECTION OF PRODUCT ACCEPTANCE

AINSLIE-built Reflectors were specified for the installation atop the New England Bell Telephone Company building, Boston, and have proven their dependability and accurate performance under severe service conditions for several years.

AINSLIE REFLECTORS

GIVE RELIABLE PERFORMANCE

Complete coordination of design, manufacture and performance gives permanent reliability to AINSLIE Reflectors. We deliver from stock Mesh Reflectors from 4' diameter to 18'; Spun Reflectors from 4' to 10'; larger sizes and Radar Reflectors made on special order to your specifications.

[We will gladly work with you in the development of any unusual antenna requirements]

Designed and Manufactured for:

- MICRO-WAVE RELAY • AIRCRAFT
- MISSILES • RADIO ASTRONOMY
- RADAR



Send for our NEW illustrated brochure. Quotations on request without obligation.

Ainslie CORPORATION

312 QUINCY AVENUE, QUINCY, MASS.

Want more information? Use post card on last page.

Pre-assembled partitions... made to exact specifications... for manufacturers of Radio, Electrical and Electronic components and allied products.

Partitions for Protective Packaging



WRITE, PHONE or WIRE for QUOTATIONS on YOUR REQUIREMENTS

peter partition corp.

Manufacturers of Cardboard Partitions

19-21 HEYWARD ST. BROOKLYN 11, N. Y.

Telephone: TRiangle 5-4033

Use "Unusable" Spaces with this

SUBMINIATURE

RECEIVER and POWER SUPPLY

Our Model 128 subminiature power supply (left) is designed to provide B + and filament voltages to various equipments. Being extremely compact (1" x 3" x 9") it may be mounted in inaccessible or normally unusable spaces. Lightweight (only 36 oz.), it has been ideal for critically balanced airborne devices. Consider it for your applications. The model 127 VHF receiver, as shown at right, incorporates modular design for flexibility of installation as one unit or separated for better space utilization. Wideband characteristics and module size (1" x 3" x 9") permit application in all fields of instrumentation and communication—airborne or otherwise. This receiver features crystal frequency control plus excellent sensitivity, quieting and noise rejection. Send the coupon below today for our Data Sheets 100 and 101 which give detailed specifications on this versatile equipment.



Land-Air Inc.

Instrument and Electronic Division

Oakland Int'l. Airport Oakland 14, Calif.

Subsidiary of California — Eastern Aviation, Inc.

Send me Data on your Subminiature Equipment:

Name .....

Address .....

City ..... State .....

writer communication facilities, also permits central control of remotely located teletypewriters on a common circuit.

Sperry Selects Four Engineering Heads

W. L. BARROW has been named vice-president for research and development, and George A. Richroath has been named vice-president for manufacturing of Sperry Gyroscope Co.

Dr. Barrow, vice-president and chief engineer since 1952, joined Sperry in 1943. He directed a number of projects in fire control and armament engineering with the company during the war, and for 14 years has served in various advisory capacities to the armed forces. Before joining Sperry he was an associate professor at M.I.T.

Richroath, formerly vice-president and works manager, will develop long range manufacturing goals in his new post. Upon joining Sperry in 1941, he supervised production preparations at the 2-million sq ft plant then being built at Lake Success, Long Island. During World War II and subsequently he managed various production phases at the plant.

The firm also announced that L. L. Wheeler has been named chief engineer, and Samuel Agabian has been named works manager.

Dr. Wheeler, since joining Sperry in 1942, has spent a decade in

W. L. Barrow

George A. Richroath

weapon system engineering with emphasis upon armament and bombing equipment. In 1951, he became assistant chief engineer.

Agabian, former assistant works manager, is a graduate of the U. S. Naval Academy. Since joining Sperry in 1940, he has held a number of research, development, engineering and production assignments. Prior to his appointment as assistant works manager in 1953, he was director of surface armament engineering.

Thomas Industries Acquires White

The White Corp. of Milwaukee, Wis., has been acquired by Thomas Industries of Louisville, Ky. White is engaged in electronics research and development, mostly on contracts from the U. S. Government. Thomas Industries is engaged in several fields including residential lighting fixtures and power saws.

All outstanding stock of the White Corp., headed by H. Louis White, president, was acquired in exchange for 10,000 shares of Thomas Industries class A common stock. White becomes a wholly-owned subsidiary of Thomas Industries.

Daven Moves To New Plant

THE DAVEN CO., manufacturers of attenuators, precision wire wound resistors, rotary switches and electronic test equipment, opened a new

THE NEW WAY TO
MARK EQUIPMENT....
with
GRAVOflex
the first chip-proof, flexible engraving stock
on the versatile
Engravograph



Send for booklets:
Engravograph Booklet 1M-29
Gravoflex Booklet G-29

So simple to engrave Gravoflex. Lettering stands out permanently on contrasting background. No paint needed. 10,000 Engravographs used for engraving on metals and plastics. Only Engravograph has these patented features:

- Adjustable for 15 ratios.
- Self-centering holding vise.
- Automatic depth regulator.
- Adjustable copy holders.

NEW HERMES ENGRAVING MACHINE CORP.
13-19 UNIVERSITY PLACE, NEW YORK 3, N. Y.

shear it
SAFETY VALVE
bend it
form it
punch it

THE NEW FREQUENCY CONVERTER
by AVION
A 400-CYCLE POWER SUPPLY
BENCH SIZE

- PLUGS INTO 60-CYCLE LINE
- DELIVERS 100 VOLT-AMPERES
- OUTPUT FREQUENCY ADJUSTABLE
  380-420 cps—Panel Control
  200-1700 cps—External Control
- OUTPUT VOLTAGE ADJUSTABLE
  90-130 volts—Panel Control

Frequency Regulation: Better than ± 1 cps
Voltage Regulation: Better than ± 1%
Harmonic Distortion: Total better than 3%
} Independent of power factor and 10% line variation

The small size (17" long x 9" high x 13" deep), power output (100 V-A), and low cost afford the convenience of using one converter for each bench set-up. Four hundred cycle power handling capacity need be paid for only as required.

Send for complete data on this new Avion product

OTHER AVION PRODUCTS
Electronic Choppers • Voltage Regulators & References • Altitude & Air Speed Control Units
Magnetic Memory Systems • Miniature Plug-In Amplifier Units • Multron
Power Supplies • Replaceable Subminiature Amplifier Assemblies • Signal Generators

AVION DIVISION
acf INDUSTRIES INCORPORATED
299 State Highway #17, Paramus, N. J.

Want more information? Use post card on last page.

AEROJET-GENERAL chose Missouri for its plant for some of the same reasons why you'll want to consider Missouri:

1. The Missouri plan is *different*—Missouri prepares the community for your plant, then *tailor-makes* the plant to fit your plans!
2. Excellent rail, water and highway network, radiating to all America.
3. Abundant water supply and power; 1500 miles of Missouri and Mississippi rivers.
4. Large supply of skilled and semi-skilled labor.
5. Fine living conditions and nearby recreational areas.
6. Temperate Midwestern climate.

Let MISSOURI "tailor-make" a plant for you!

Right now 181 industrial buildings are available—17 Missouri cities are ready and able to build—more than 100 cities and towns willing to cooperate in locating your tailor-made plant.

Get Missouri's Winter Industrial Plant Location Survey and complete detailed information about the Missouri cities ready to "tailor-make" a plant for you. Write us now, or

PHONE COLLECT
JEFFERSON CITY 6-7185
Lisle Jeffrey, Industrial Director
Dept. A692, Missouri Division of Resources & Development
Jefferson City, Missouri

MISSOURI IS VIRTUALLY DEBT-FREE
Only $2.52 per capita! The average of all 48 states is $50.02 bonded debt per person.

Want more information? Use post card on last page.

plant in Livingston, New Jersey. The building occupies over 65,000 sq ft of space.

Bendix Pacific Expands Plant

A LARGE addition to the engineering building of the Pacific division of Bendix in North Hollywood, Calif., is nearing complection. The new building will centralize and consolidate all engineering activities formerly housed at three separated locations in the San Fernando Valley. It will provide more space for increased engineering activity in the fields of radar, missile guidance, instrumentation, sonar and aircraft hydraulics.

The new addition will increase floor space from 23,000 sq ft to over 100,000 and will house both engineering and development activities. Total floor space devoted to engineering, development and test is equivalent to 50 percent of total manufacturing space.

Emerson Selects Engineering Head

MAURICE L. LEVY, technical assistant to the vice-president in charge of manufacturing at Emerson Radio, has been advanced to the post of director of the commercial engineering division. W. A. Auerbacher continues as director of the government project engineering division.

Levy joined Emerson in 1943 as chief engineer, special products, resigning in 1949 to become engineering consultant to various electronics organizations. In May, 1953, he rejoined Emerson and was named technical assistant to the vice-president in charge of manufacturing.

Consolidated Changes Name, Appoints Jones

CONSOLIDATED Engineering Corp. changed its name to Consolidated Electrodynamics Corp.

The change was made because the previous name did not adequately describe the broad scope of business in which the company is

ELECTRONIC AND RADIO ENGINEERING

Just Published—Fourth Edition

Completely revised edition of Terman's RADIO ENGINEERING. Basic guidance covers all phases of electronic and radio engineering, including vacuum tubes, transistors, electronic circuits, and radio systems. Provides essential data on circuit theory, electronic devices, antennas, wave propagation, transmitters, receivers, television, radar, and radio navigation aids. Includes new material on pulse techniques, microwave tubes, semi conductors and transistors, FM, color television, and others. Organized for quick reference. **By Frederick E. Terman, Dean, School of Engrg., Stanford Univ. 1078 pp., 688 illus., $12.50**

FUNDAMENTALS OF TELEVISION ENGINEERING

Just Published!

Up-to-date, theoretical treatment of the entire field of television. Analytical in approach, it covers in detail system concepts as well as circuits and techniques. Treats monochrome and color systems concurrently. Emphasis is on the television system itself, requirements to be met in achieving quality, and the analysis and design of the many component parts which make up the system. **By G. M. Glasford, Assoc. Prof. of Elec. Engrg., Syracuse Univ. 642 pp., 565 illus., $12.50**

LINEAR FEEDBACK ANALYSIS

Just Published!

Presents a systematic treatment for negative feedback circuit research and applications. Focuses on problem of stability of the feedback loop. Discusses causes of instability, using three methods of approach. Contemporary network analysis methods, feedback concepts, and tube amplifying stage characteristics are fully described. Application of the Laplace transform, with examples, is outlined. Includes material not presented in book form before, such as analyses of single- and multi-stage amplifiers. **By J. G. Thomason, Radar Research Estab., Malvern, England. 355 pp., 236 illus., $8.50**

CONTROL OF NUCLEAR REACTORS AND POWER PLANTS

Just Published!

Provides a servo-engineering approach to the physics problem of safely controlling nuclear reactors. Describes responses of reactors in engineering terminology and treats reactors as control elements in larger systems. Several systems are presented for research reactors and for power producing types. Gives special attention to operating control problems during startup, power level operation, and shutdown. Shows how simulators are designed, whereby control devices may be checked in laboratory without using reactor. **By M. A. Schultz, Atomic Power Div., Westinghouse Elec. Corp. 313 pp., 232 illus., $7.50**

10 DAY FREE EXAMINATION

McGraw-Hill Book Co., Att: H. W. Buhrow
Industrial and Business Book Dept.
327 W. 41st. St., N.Y.C. 36

Send me book(s) checked below for 10 days' examination on approval. In 10 days I will remit for book(s) I keep, plus few cents for delivery cost, and return unwanted book(s) postpaid. (We pay delivery costs if you remit with this coupon—same return privilege.)

- ☐ Terman—**Electronic and Radio Engineering**—$12.50
- ☐ Glasford—**Fundamentals of Television Engineering**—$12.50
- ☐ Thomason—**Linear Feedback Analysis**—$8.50
- ☐ Schultz—**Control of Nuclear Reactors and Power Plants**—$7.50

(Print)
Name .....
Address .....
City ..... Zone.... State.....
Company .....
Position .....

For price and terms outside U.S., write McGraw-Hill Int'l., NYC L-1

Want more information? Use post card on last page.

Another example of the superiority of...

Custom molded — Projection horn

MOLDED FIBERGLASS

THE PROBLEM: to produce, economically, a projection horn of superior tone quality . . . capable of projecting sound over a wide area, with extreme clarity . . . suitable for either indoor or outdoor use.

THE SOLUTION: fiberglass-reinforced plastic, custom molded in one operation by Molded Fiberglass Co.

THE RESULT: an exceptionally fine projection horn with excellent tone qualities . . . strong as metal . . . completely weatherproof (can be used indoors or out) . . . produced economically.

THE MORAL: in nearly every industry there is a product that can be made *better* with Molded Fiberglass. Write for literature.

molded Fiberglass company

4417 Benefit Avenue, Ashtabula, Ohio

WORLD'S LARGEST MANUFACTURER OF CUSTOM MOLDED FIBERGLASS PRODUCTS

Want more information? Use post card on last page.

engaged.

Also, Consolidated had been unable to qualify for intrastate business in certain key states under its previous name, which forced creation of a special subsidiary, CEC Instruments, to operate in such states. This unit is now being dissolved.

Consolidated Vacuum Corp., the Rochester, New York, high-vacuum subsidiary of Consolidated, has also been dissolved and its activities combined with those of the parent firm. It will be known as the Consolidated Vacuum division.

Consolidated also announced that Howard C. Jones has been appointed director of manufacturing of its vacuum division.

In his new position, Jones will direct all manufacturing phases of high-vacuum equipment. He will also direct traffic, purchasing, quality control, and plant engineering operations.

Jones joined the North East Electric Co. in 1921 as an equipment engineer. He became plant engineer, chief engineer, and works manager for the firm's successor, Delco appliance division, General Motors Corp. He was works manager there for eight years.

Navy Dedicates Atomic Lab.

THE NEW $8,500,000 main building of the U. S. Naval Radiological Defense Laboratory was dedicated in San Francisco.

The laboratory is devoted to the

Electronic equipment in new Navy Lab includes 40-channel gamma-ray analyzer

FULL LINE MINIATURE COMPONENTS

SIZE 11 FRAME

SIZE 11 400 ~ Motor Tachometers

(Drag cup type tachometer)

Tachometer input: 115 v
Tachometer output: 500 mv/1000 rpm.
Linearity: ±1%
Phase shift: 10° max.
Maximum total null voltage: 19 mv.
Motor input: 115 v fixed phase
115/57.5 v control phase
Stall torque: 0.63 oz in.
No load speed: 5900 rpm.

Separate motors or tachometers available with the same or different operating characteristics.

SIZE 11 400 ~ Induction Generators

Excitation: 115 v 400 ~
Voltage output: 1.25 v/1000 rpm.
Linearity ±1% up to 6000 rpm.
Maximum total null voltage: 60 mv
Phase shift: under 5°
Moment of inertia: 1.1 gm cm²

Damping generators with other characteristics available.

SIZE 11 400 ~ Resolvers

High or low impedance models
Network or winding compensated
Electrical equivalent to Mark 4 Mod. 0
Functional error: under 0.1%
Interaxis error: under ±5 min.
Input voltage: up to 60 v at 400 ~
Other frequencies available

SIZES 15, 18 and 23 Frames also available | SERVO MOTORS, GEARED SERVO MOTORS, MOTOR TACHOMETERS, BRUSHLESS INDUCTION POTENTIOMETERS, MINIATURE SYNCHRONOUS MOTORS; low and high temperature models.

American Electronic Mfg., Inc.

INSTRUMENT DIVISION OF AMERICAN ELECTRONICS INC.

9503 W. JEFFERSON BLVD., CULVER CITY, CALIF.

Engineering Representatives in all Principal Industrial Areas

Want more information? Use post card on last page.

where does
COTO-COIL
SQUEEZE into this picture?

In many of today's high speed elevators Coto-Coils control the sensitive circuits which make absolute smoothness and safety possible.

If you have a coil problem in production or design, let Coto-Coil provide the right coil for the job in the volume you need.

Send details of your problem to

COTO-COIL CO., Inc.

63 Pavilion Ave., Providence 5, R. I.
New York Office:
10 East 43rd Street
New York 17, New York

PRECISION
Coto Coils
WOUND

INDUSTRIAL
"Automaton"
PRINTED CIRCUIT SOCKET
First socket designed expressly for AUTOMATION . . .



Easy Insertion • Bullet nose terminals provide for easy location and insertion.

Mechanical Lock-in • Notches in terminals provide for locking of sockets into chassis. Will not loosen with vibration or handling.

Perfect Solder Joint • Round terminals contact copper foil on entire circumference of chassis hole.

Rigid Terminals • Will not deform in shipping or handling.

Opening between socket and chassis provides for good heat dissipation. Available in 7 and 9 pins; also available with tube shield clip.

Samples and information on request.

INDUSTRIAL HARDWARE
Manufacturing Company, Inc.
109 PRINCE ST., NEW YORK 12, N.Y.

study of nuclear radiation effects. The studies center around the harmful effects of radiations resulting from nuclear reactions, and developing means of preventing or minimizing the hazards of those effects.

The new building is a six story structure of reinforced concrete. Specially designed for use as a research laboratory, it is windowless to provide protection from atomic detonations.

Frank Cook Acquires Hart

HART MACHINE & MANUFACTURING Co., a tool and die machine shop at Denver, has been acquired by the Frank R. Cook Co., incorporated in Denver last July. Cook specializes in the design and manufacture of aeronautical and electronic equipment for military and commercial use. Cook said Hart's operations would be expanded to include production of devices designed by Cook and others.

The Hart firm, which will be a division of Cook, will be managed by Walter N. Lundahl, until recently chief of the advanced flight control design section of the aeronautical division of Minneapolis-Honeywell Regulator Co. Frank M. Hart, who headed the Hart firm the past 20 years, is retiring from business.

Furnas Appointed To Defense Post

CLIFFORD C. FURNAS, chancellor of the University of Buffalo, was appointed by President Eisenhower to be assistant secretary of defense (research and development). He succeeds Donald A. Quarles who became Secretary of the Air Force. Dr. Furnas will be on leave of absence from the University of Buffalo.

From 1946 until 1955, when he became Chancellor, Dr. Furnas was director of the Cornell Aeronautical Laboratory, Buffalo, New York. He has been serving the Department of Defense research and development organization that he will now head in a consultant capacity and had

been associated with its predecessor organization, the Research and Development Board, in various capacities since February 1948.

Clevite Adds Firm, Names Engineers

CLEVITE CORP. has acquired full ownership of Transistor Products and has changed its name to Clevite Transistor Products.

Clevite purchased a majority interest in the company early in 1953, as part of its expansion into the field of electronics.

Dr. R. B. Holt, founder of Transistor Products and former director of Harvard University's nuclear research laboratory, will continue as president of the unit.

Clevite also announced that John H. Harris has been appointed as vice-president in charge of planning, and Wallace T. Gray as general works manager of Brush Electronics Co. in Cleveland.

Harris has been vice-president and general works manager for the Clevite firm since 1948.

Gray was formerly works manager for the Leece-Neville Co. Prior to joining Leece-Neville, he served as plant manager for RCA and as factory manager for the Thomas A. Edison instrument division.

In another move, Clevite combined the Brush Laboratories Co. and Clevite-Brush Development Co. into a single organization, the

John H. Harris

Just a minute—

Please don't get us wrong . . .

we like **quantity** *business, too*

Just the other day an engineer told us: "I'd have asked you to quote on this order if I'd only realized you handled quantity production. But, somehow, from your ads, I got the impression that you specialized in custom-built transformers in very small quantities only."

"Whoa!" we shouted. "Sure we specialize in custom-built transformers, but we can make 'em custom built or standard in whatever quantity you need. And we can do it quickly without sacrificing precious quality control."

Maybe the fact that we can handle large quantities will help you. Why not write and ask for more information.

CALEDONIA

ELECTRONICS AND TRANSFORMER CORPORATION

Dept. E-1, Caledonia, N. Y.

for service and lab. work

Heathkit

PRINTED CIRCUIT

OSCILLOSCOPE KIT

FOR COLOR TV!

① Check the outstanding engineering design of this modern *printed circuit* Scope. Designed for color TV work, ideal for critical Laboratory applications. Frequency response essentially flat from 5 cycles to 5 Mc down only 1½ db at 3.58 Mc (TV color burst sync frequency). Down only 5 db at 5 Mc. New sweep generator 20-500,000 cycles, *5 times* the range usually offered. Will sync wave form display up to 5 Mc and better. Printed circuit boards stabilize performance specifications and cut assembly time in half. Formerly available only in costly Lab type Scope. Features horizontal trace expansion for observation of pulse detail — retrace blanking amplifier — voltage regulated power supply — 3 step frequency compensated vertical input — low capacity nylon bushings on panel terminals — plus a host of other fine features. Combines peak performance and fine engineering features with low kit cost!

① MODEL O-10 $69.50* Shpg. Wt. 27 lbs.

② MODEL TS-4 $49.50* Shpg. Wt. 16 lbs.

Heathkit TV

SWEEP GENERATOR KIT

ELECTRONIC SWEEP SYSTEM

② A new Heathkit sweep generator covering all frequencies encountered in TV service work (color or monochrome). FM frequencies too! 4 Mc — 220 Mc on fundamentals, harmonics up to 880 Mc. Smoothly controllable all-electronic sweep system. Nothing mechanical to vibrate or wear out. Crystal controlled 4.5 Mc fixed marker and separate variable marker 19-60 Mc on fundamentals and 57-180 Mc on calibrated harmonics. Plug-in crystal included. Blanking and phasing controls — automatic constant amplitude output circuit — efficient attenuation — maximum RF output well over .1 volt — vastly improved linearity. Easily your best buy in sweep generators.

Heath COMPANY

A SUBSIDIARY OF DAYSTROM, INC.

BENTON HARBOR 14, MICH.

WRITE FOR FREE CATALOG ...COMPLETE INFORMATION

Want more information? Use post card on last page.

An Invitation
TO MANUFACTURERS OF ELECTRONIC EQUIPMENT

1. Friendly labor supply.
2. Unusual city, county, and state tax advantages.
3. Industrial sites plentiful.
4. Good banking facilities.
5. Full cooperation guaranteed.
6. Strategic location.

for SMALL or MEDIUM INDUSTRIES

Businessmen of Lakeland, Florida will cooperate fully and furnish complete information to manufacturers who will consider relocating or establishing a branch unit in this fast-growing central Florida city . . . . .

INDUSTRIAL DEVELOPMENT COMMITTEE OF 100
LAKELAND TERRACE HOTEL

LAKELAND, FLORIDA

HEAVY DUTY

Multiple Arm
RELAYS by SIGNAL

- Versatile — Rugged
- Cast Aluminum Base
- High Shock and Vibration Resistant
- Available AC — DC
- Contact Capacities Available 10; 35; 50 amp.
- Contact Combinations on Same Base
- Designed to Meet Many MIL Spec's.



A superior relay that has endured the test of time . . . Specified for many years by America's largest manufacturer of electrical controls and communications equipment.

For complete data, write for Bulletin No. 30-6

Engineering representatives in principal cities

Wheelock RELAYS
SIGNAL ENGINEERING & MFG. CO
LONG BRANCH N.J.

Clevite Research Center in Cleveland, Ohio. A. L. W. Williams is president of the center. Dr. C. B. Sawyer, former president of Brush Labs, is now a consultant to Clevite Corp. on special scientific projects.

Stromberg Selects Operations Analyst

WILSON P. COGSWELL, Captain, U. S. Navy, Ret., has been appointed staff assistant for operational analysis—military, in the engineering and research department of Stromberg-Carlson.

At the time of his retirement from the Navy, Captain Cogswell was serving as director of the Electronic Production Resources Agency. From 1952 to 1954 he was a staff member and consultant at the Lincoln Laboratories of MIT. For the past two years he has been serving Stromberg-Carlson as a part-time consultant.

Texas Instruments Names Maj. Gen. Born

MAJOR GENERAL Charles F. Born, USAF, has joined Texas Instruments as director of service engineering of the apparatus division.

Gen. Born was commander of the crew training air force at Randolph Air Force Base until his recent retirement.

As director of service engineering, he will be responsible for engineering liaison with the Department of Defense and with other defense equipment manufacturers. He will be in charge of the division's service engineering group. The company also announced that an Eastern region marketing office has been opened in New York City. A Los Angeles office was opened in June and a Chicago office in August.

Computer-Measurements Appoints Lovejoy

R. E. LOVEJOY has been appointed director of research for the counting and computing instrument division of Computer-Measurements Corp., North Hollywood, Calif.

He has held executive positions

with several industrial companies and governmental agencies. During World War II, he was employed by the Naval Research Laboratory in Washington.

Prior to joining Computer-Measurements, Lovejoy was employed as instrumentation engineer with AiResearch Manufacturing of Los Angeles.

Condenser Manufacturers Changes Control

THE controlling interest in Condenser Manufacturers of Nashville, Tenn., has been acquired by E. W. Carmack of Murfreesboro, Tenn., and J. W. Hart, president.

Howard W. Gates will remain with the company as chief engineer and vice-president.

The company manufactures miniature and subminiature electrolytics. It also manufactures regular type electrolytics for 150v and less.

Electronic Engineering Adds Space

TOTAL of 6,300 sq ft of space has been added to the fabrication facilities of the Electronic Engineering Company of California. As the result of the addition, the company's Los Angeles laboratory facility now encompasses 26,000 sq ft.

Fairchild Camera Expands In Nucleonics

FAIRCHILD CAMERA AND INSTRUMENT CORP. established a nuclear instrumentation department headed by Harold E. DeBolt.

Dr. DeBolt comes to Fairchild from the nuclear power division of the Navy's Bureau of Ships and the naval reactor branch of the reactor development division of the Atomic Energy Commission. Prior to that time he was associated with the Westinghouse atomic power division in Pittsburgh.

Products under consideration for development and manufacture include radiation monitoring equip-

Simplifying **HF** *Power Measurement*

***Model 67* TERMALINE**

DIRECT-READING R-F WATTMETER

30 mc to 500 mc
(to 1000 mc if specified)

50 ohms

Triple Range 0-25 watts
0-100 "
0-500 "

Type N Input Connector
(Adaptor for PL-259 supplied)



● Model 67 is a larger type Wattmeter than the well-known AN-ME-11/U (our Model 611) R-F Wattmeter. Specifically designed for fixed station transmitters to 500 watts output, it may be used nicely on low range for mobile gear. Provided with an aluminum cased, shock-mounted meter, Model 67 is as simple to use as a DC voltmeter. Now in general use throughout the industry, TERMALINE Wattmeters may be depended upon for fast, accurate and repeatable power readings

NON-RADIATING
... Accuracy — 5%

RUGGED CONSTRUCTION
... Size — 17" x 9" x 6"
Wght. — 30 pounds

BIRD ELECTRONIC CORP.
1800 EAST 38TH ST., CLEVELAND 14, OHIO
TERMALINE Coaxial Line Instruments

VAN GROOS COMPANY
Sherman Oaks, Cal.

RON MERRITT COMPANY
Seattle

JET PROPULSION LABORATORY
OF THE
CALIFORNIA INSTITUTE OF TECHNOLOGY
Pasadena, California

jpl

has positions now open in the fields of

GUIDED MISSILE INSTRUMENTATION AND TELEMETERING

The Laboratory has the responsibility for the design and development of complete guided-missile systems such as the Corporal. Much of its success is credited to its small but outstanding telemetering and instrumentation group, which was one of the first in the nation to design and employ transistor telemetering systems.

This is an opportunity to associate yourself with the nation's foremost guided-missile research and development facility. Applicants must have at least a B.S. in a related field from an accredited university with good academic standing and meet one of the following experience requirements:

1) Experience or training in transistor circuit design.
2) Experience in the development of missile telemetering systems.
3) Experience in instrumentation system design and data processing.

Airmail your summary of qualifications and references to:

CALTECH | **JET PROPULSION LABORATORY**
4800 Oak Grove Drive — Pasadena, California

★ ULTRA LOW capacitance & attenuation

TYPE	μμF/ft	IMPED.Ω	O.D.
C 1	7.3	150	.36"
C 11	6.3	173	.36"
C 2	6.3	171	.44"
C 22	5.5	184	.44"
C 3	5.4	197	.64"
C 33	4.8	220	.64"
C 4	4.6	229	1.03"
C 44	4.1	252	1.03"

WE ARE SPECIALLY ORGANIZED TO HANDLE DIRECT ORDERS OR ENQUIRIES FROM OVERSEAS
SPOT DELIVERIES FOR U.S.
BILLED IN DOLLARS—SETTLEMENT BY YOUR CHECK
CABLE OR AIRMAIL TODAY

NEW 'MX and SM' SUBMINIATURE CONNECTORS
Constant 50Ω 63Ω 70Ω impedances

TRANSRADIO LTD. 138A Cromwell Rd. London SW7 ENGLAND CABLES: TRANSRAD, LONDON

BURGESS DESIGN AND ENGINEERING SERVICES CAN SOLVE YOUR PROBLEM!
For more than forty years, Burgess has offered to Electronic Engineers design and engineering facilities to meet any dry battery need. Burgess welcomes the opportunity to assist in solving your problems. Burgess popularity is based on uniform performance and consistent high quality that have earned and hold the respect of Engineers everywhere. Your local distributor carries a complete stock of Burgess Industrial batteries.



FOR YOUR CONVENIENCE!
Burgess offers, at no charge, an engineering manual listing the complete line of Burgess Batteries, a handy check sheet for new battery specifications and the new Transistor catalog folder. Ask your distributor or write Burgess Battery Company for your free copies today.

BURGESS BATTERIES
BURGESS BATTERY COMPANY
FREEPORT, ILLINOIS

ment, control rod drive mechanisms for atomic reactors, neutron detectors and associated temperature, pressure and flow controls.

ElectroData Promotes Meyer

RAYMOND MEYER has been named supervisor of manufacturing for ElectroData Corp.

Meyer, who previously was administrative assistant to the vice-president, will have charge of production, purchasing, plant maintenance and production and materials control.

Prior to joining ElectroData last spring, he was general manager of quality control for Hoffman Radio Corp. Prior experience includes managerial and engineering positions with RCA and Permoflux Corp.

Librascope Re-Groups Engineering Division

LIBRASCOPE, Glendale, Calif., manufacturers of computers and control devices has reorganized its engineering divisional structure into five departments. Each department will conduct its own research and development in specific fields.

The five departments, each functioning under a director responsible to chief engineer, D. C. Webster, are: commercial; special devices; airborne equipment; shipboard equipment, and administration. In each of the first four departments, teams of engineers, designers and technicians will work as self-sufficient units under the immediate direction of a project manager.

Clegg Triples Plant Facilities

EXPANSION of physical facilities and production capacities to three times their former size is being completed by Clegg Laboratories, at Morristown, N. J.

The company specializes in custom built electronic and microwave equipment and in the production of electronic scanning and control devices.

President of the firm is Edward

T. Clegg. Secretary and chief engineer is George Antanelis. They have been associated since World War II in radar work and in the development and application of thyratron tubes. Anthony Gerson is treasurer and plant manager.

Gertsch Products Promotes Hood

ROBERT S. HOOD has been appointed vice-president in charge of manufacturing of Gertsch Products of Los Angeles.

Hood has been with Gertsch Products for the past six years. He started as mechanical engineer, then moved to the position of production manager and in his new position is vice-president in charge of production, maintenance, and plant operation.

Corey Elected NEMA President

J. W. COREY, president of The Reliance Electric & Engineering Co. of Cleveland, Ohio, manufacturers of motors and generators, was elected president of the National Electrical Manufacturers Association.

Corey, former vice-president of NEMA, and a member of the board of governors since 1951, succeeds Albert F. Metz, chairman of the board and chief executive officer of the Okonite Co. of Passaic, N. J.

Kelly & Radley Honored In Italy

MERVIN J. KELLY, president of Bell Telephone Laboratories and Sir Gordon Radley, director general of the British Post Office, were recently awarded the first Christopher Columbus International Communication Prize at ceremonies in Genoa, Italy.

Dr. Kelly and Sir Gordon Radley received the prize in recognition of "the planning, now being placed into practice, of the submarine telephone cable which will make it possible to establish 36 telephone circuits across the Atlantic between

Arrows point to Paliney #7 contacts used in this Fairchild Type 746 Precision Potentiometer.

NEY'S small parts play a BIG part in precision instruments

Reliability of many precision electrical instruments depends upon accurate transmission of electrical signals between moving parts. The Potentiometer Division of the Fairchild Camera and Instrument Corporation has selected Ney Paliney #7* for use as wipers and sliders in their precision potentiometers because Paliney #7 provides the important advantages of a long life with excellent linearity and the ability to hold noise at a minimum.

Ney manufactures many other precious metal alloys which, like Paliney #7, have ideal electrical characteristics, high resistance to tarnish, and are unaffected by most industrial atmospheres. Ney Precious Metal Alloys have been fabricated into slip rings, wipers, brushes, commutator segments, contacts, and intricate component parts and are used in high precision instruments throughout industry. Should you have a contact problem, a call to the Ney Engineering Department will result in study and recommendations which will improve the output of your electrical or electronic instruments.

THE J. M. NEY COMPANY • 179 ELM ST., HARTFORD 1, CONN.

Specialists in Precious Metal Metallurgy Since 1812

*Registered Trade Mark 9NY55B

When Instruments Must Be Accurate...

The Burlington Meter was chosen for this Bendix-Friez Laboratory Temperature Indicator because they found it met their requirements for an accurate, yet low cost, meter and enabled them to set a desirable price on their instrument. Other famous-name manufacturers have made their selection from the wide ranges, styles and sizes offered by Burlington. Or, let Burlington build a meter to your specifications.

MODEL 741 SQUARE SEMI-FLUSH

BURLINGTON INSTRUMENT CO.
127 N. Third St., Burlington, Iowa

Burlington
CUSTOM BUILT TO SPECIFICATION

WRITE FOR CATALOG N1

Genisco's New GOH Accelerometer
WITHSTANDS VIBRATIONAL ACCELERATIONS
of 15 G's up to 2000 cps



PHYSICAL DIMENSIONS

OVERALL HEIGHT	3 1/16"
OVERALL WIDTH	3 1/4"
OVERALL DEPTH	3 3/4"
WEIGHT	38 OUNCES

Hermetically sealed

This newest Genisco Accelerometer is a rugged, oil-damped, potentiometer-type instrument designed to operate in the most severe missile and aircraft vibrational environment. For example, in a recent production test the GOH performed satisfactorily after vibrational environment of 15 G's up to 2000 cps. As further proof of its ruggedness, the GOH will withstand 40-G shocks of 5 millisecond duration on the sensitive axis, and steady-state accelerations of 30 G's on the non-sensitive axes and 10 G's on the sensitive axis without damage.

HEATING ELEMENT AVAILABLE—A thermostat-controlled, internal heater may be installed in the GOH to keep operating characteristics constant between −50° F. and +160° F. However, thermostat operation is limited to 60,000 feet or less, 95% relative humidity at 160° F., and a vibrational environment of 10 G's up to 500 cps.

SPECIFICATIONS

Ranges: ±1 G to ±3 G's inclusive.
Natural Frequencies: 7 cps. to 12 cps.
Nominal Damping: 0.65 of critical at 75° F. Values between 0.4 to 1 set if desired.
Resistance: 14000 ohms (±5%); center tap at 0 G-point. Other resistances also supplied.
Potentiometer Voltage: Up to 60 volts.
Resolution: One part in 300 for standard potentiometer.
Noise Levels: Less than 10 mv at 0.1 ma brush current.
Linearity: Within 1% of full scale from best straight line through calibration points.

Complete technical data on the GOH and other Genisco Accelerometers and Pressure Transducers is available from Genisco, Incorporated, 2233 Federal Avenue, Los Angeles 64, California. Write for your copy today.

RELIABILITY FIRST

Genisco INCORPORATED

Want more information? Use post card on last page.

Scotland and Canada with extension to New York, intending furthermore to reward hereby the numerous scientists, research workers and engineers who have contributed in the planning, production and placing in operation of the intercontinental submarine telephone line."

In the section of the cable lying on the ocean's bed, there are, at intervals of 40 miles, electronic repeaters. In these repeaters there are some 300 thermionic, high vacuum amplifying tubes and more than 7,000 associated circuit components. The tubes and components have expected lives without failure of more than 20 years.

Dr. Kelly said that the time is not too far distant when cables with band widths sufficiently broad for television transmission will be possible.

The Christopher Columbus International Communication Prize was instituted recently in Italy, under the auspices of the City of Genoa, as a memorial to Christopher Columbus, a native of Genoa. The annual prize is intended to honor any outstanding discovery or research work completed in the previous four years to aid communications among men.

New Firm Formed In Los Angeles

A NEW electronics company, Fenske, Fedrick, Miller, Inc., has been established in Los Angeles. The firm is developing electronic testing equipment and analyzers. Don Fenske is president, Jack Fedrick is secretary and treasurer and Robert Miller is vice-president.

IRE Makes Fellow Awards For 1956

SEVENTY-FIVE fellow awards were made by IRE for 1956. The grade of Fellow is the highest membership grade offered by the Institute and is bestowed only by invitation on those who have made outstanding contributions to radio engineering or allied fields.

Presentation of the awards will be made by IRE Sections all over

MOLDED OPEN TYPE TRANSFORMERS
THE CLIPPER SERIES



Built to pass MIL-T-27 specifications, including Grade I humidity tests, and to operate continuously at 150°C (Class C).

Result: Savings up to 50% in space and weight without sacrifice in performance.

SAMPLES? SPECIALS? SHORT RUNS?

The Clipper is only one of the many types we make. We specialize in custom-built transformers to your specifications. Let our engineering staff help solve all your transformer problems.

Samples delivered in 1 to 3 weeks

Write for Literature

STERLING TRANSFORMER CORPORATION
297 North 7th St. Brooklyn 11, N. Y.
STagg 2-4200

Want more information? Use post card on last page.

FIVE STAR ELECTRICAL COMPONENTS

COILS
Wound to Your Specifications

★ ★ ★ ★ ★



SOLENOIDS
Light and Miniature Types

★ ★ ★ ★ ★

RELAYS
Power and Sensitive Types



Send for catalog sheets describing these items in detail. Prompt quotations will be furnished on receipt of your complete specifications and requirements.

THE FIVE STAR COMPANY
10 WEST MAIN STREET
PLANTSVILLE, CONN.

MARKEM® MACHINES

Solve "IN-PLANT" PRINTING PROBLEMS
- FASTER - NEATER - AT LOWER COST

COLOR BANDING WIRE LEAD COMPONENTS

The Markem 69A Machine semi-automatically applies up to six color bands to wire lead components such as resistors and condensers. Band width and color changes are easily made. Automatically feeds and ejects; bands about 50 objects per minute. The 69A will also mark cylindrical objects with complete label detail, in one or two colors.

Other Markem machines available for marking electrical parts and products of all sizes and shapes. Write for detailed information.



MARKEM MACHINE CO.
KEENE 5, NEW HAMPSHIRE

BE SAFE WITH

Q-max

A-27
LOW-LOSS LACQUER

- Q-MAX provides a practically loss-free insulating coating for VHF and UHF components of every variety. Q-MAX penetrates deeply to seal out moisture, imparts rigidity to coil windings and promotes stability of electrical circuits. It scarcely alters the "Q" of R-F windings.
- Q-MAX is easy to apply, dries quickly, adheres to practically all materials and has a wide temperature range.

WRITE FOR DETAILED ENGINEERING LITERATURE

Communication Products Company, Inc.
MARLBORO NEW JERSEY

THE BEST TEST FOR TV

TIC's TYPE 1105 VIDEO SWEEP GENERATOR

Price: $600. F.O.B. Carlstadt, N. J.

- High Output
- Flat Frequency Response
- Keyed Carrier Markers to Zero Amplitude
- 75-ohm Internal Impedance
- Sawtooth Sweep Signal

Expressly designed for testing Video equipment requiring a high level signal, the Tel-Instrument Type 1105 provides a 2.0 V. Max. p-p signal from a 75-ohm source into a 75-ohm load, with a sweep range from 50 KC to 10 MC. Features include: Ten selectable crystal controlled pulse-type markers supplied at either integral megacyle point, or as desired; flat output within ±0.2 db over entire range, attenuated over 60 db; and external markers.

TIC has a complete line of monochrome and color TV studio and production test equipment. Complete information sent at your request.

TIC Tel-Instrument ELECTRONICS CORP.
728 GARDEN STREET • CARLSTADT, NEW JERSEY

GET the FACTS

GRC tiny molded PLASTIC PARTS specializing in NYLON

SEND FOR YOUR COPY OF THE NEW GRIES PLASTICS BULLETIN

Find out how Gries' exclusive techniques make possible product designs using tiny components that might be production problems by ordinary means. How Gries uses special machines which mean extremely low tooling costs, high speed production for volume requirements. Bulletin is packed with examples, charts, engineers' check list.

Write today for new Bulletin and Samples.

Send prints and quotation.

- **Completely automatic injection molding.**
- **Continuous or individual insert molding.**
- **GRC molds ALL thermoplastics *nylon a specialty.***

Quick deliveries on quantities of 25,000 to millions

NO MINIMUM SIZE!

Maximum size: .03 oz.—1¼" long

GRIES World's Foremost Producer of Small Die Castings

GRIES REPRODUCER CORP.

151 Beechwood Ave., New Rochelle, N. Y. NEw Rochelle 3-8600

Acme Electric makes Encapsulated Transformers



- For applications where environmental conditions require transformers of exceptional resistance to climatic conditions, put your problems up to Acme Electric engineers. Our facilities include equipment for encapsulating transformers in plastic resin compounds.

We invite your inquiries.



ACME ELECTRIC CORPORATION

311 WATER ST. • CUBA, N. Y.

West Coast Engineering Laboratories:
1375 W. Jefferson Blvd., Los Angeles, California
In Canada: Acme Electric Corp. Ltd.
50 Northline Road, Toronto, Ontario

Acme Electric TRANSFORMERS

the world wherever the recipients reside. Recognition of the awards will be made by the president of the IRE at the anual banquet on March 21, 1956, at the Waldorf-Astoria Hotel in New York City during the 1956 IRE National Convention.

The recipients of the Fellow award, which takes effect January 1, 1956, are as follows:

H. E. M. Barlow, Pender professor of electrical engineering, University of London, London, England

Leslie C. Jesty, chief of television research group, Marconi's Wireless Telegraph Company, Essex, England

Rolf Moller, c/o Fernseh GMBH, Darmstadt, Germany

Lothar Rohde, co-partner, Rohde and Schwarz, Munchen, Germany

M. J. O. Strutt, professor, director, Swiss Federal Institute of Technology, Zurich, Switzerland

Samuel N. Alexander, chief, data processing systems div., National Bureau of Standards, Washington, D. C.

Nicholas G. Anton, president, director of research and engineering, Anton Electronics Labs., Brooklyn, N. Y.

William S. Bachman, director, engineering and development, Columbia Records, New York, N. Y.

George W. Bailey, executive secretary, Institute of Radio Engineers, New York, N. Y.

William J. Barkley, c/o Rust Industrial Co., New York, N. Y.

Loy E. Barton, research engineer, RCA Laboratories, Princeton, N. J.

Robert E. Beam, professor of electrical engineering, Northwestern University, Evanston, Ill.

James E. Beggs, research associate, General Electric Co., Schenectady, N. Y.

Willis H. Beltz, Capt., (USN, retired), Sheraton Park Hotel, Washington, D. C.

William R. Bennett, Bell Telephone Laboratories, Murray Hill, N. J.

Enoch M. Boone, professor of electrical engineering, Ohio State University, Columbus, Ohio

Wilson P. Boothroyd, chief development engineer, Philco Corp., Philadelphia, Pa.

Paul N. Bossart, section engineer, Union Switch and Signal Div., Westinghouse Air Brake Co., Pittsburgh, Pa.

Arthur B. Bronwell, president, Worcester Polytechnic Institute, Worcester, Mass.

Archibald S. Brown, special assistant to director of research, Stanford Research Institute, Stanford, Calif.

Horace T. Budenbom, Bell Telephone Laboratories, Whippany, N. J.

R. D. Cahoon, prairie regional engineer, Canadian Broadcasting Corp., Winnipeg, Canada

Herbert J. Carlin, research professor, Microwave Research Institute, Brooklyn, N. Y.

Alva B. Clark, (vice-president of Bell Telephone Laboratories, retired), Washington, D. C.

George F. Corcoran, professor and chairman, electrical engineering dept., University of Maryland, College Park, Md.

Thomas M. Davis, head, radio techniques branch, U. S. Naval Research Lab., Washington, D. C.

Edward N. Dingley, Jr., special assistant to the chief, office of research and development, National Security Agency, Washington, D. C.

Ora S. Duffendack, president and director of research, Philips Labs., Irvington-on-Hudson, N. J.

J. Presper Eckert, Jr., vice-president, Remington Rand, Philadelphia, Pa.

Harold E. Edgerton, professor, Massachusetts Institute of Technology, Cambridge, Mass.

George A. Espersen, section chief, microwave tube and electron optics sections, Philips Labs., Irvington-on-Hudson, N. Y.

Clifford E. Fay, Bell Telephone Laboratories, Murray Hill, N. J.

W. G. H. Finch (USN, retired), Newton, Conn.

A. Gardner Fox, research radio engineer, Bell Telephone Laboratories, Red Bank, N. J.

Alan M. Glover, manager, semiconductor operations dept., RCA Tube Div., Harrison, N. J.

Stanford Goldman, professor of electrical engineering, Syracuse University, Syracuse, N. Y.
Ladislas Goldstein, professor of electrical engineering, University of Illinois, Urbana, Ill.
J. V. N. Granger, assistant chairman, engineering dept. and head, radio systems lab., Stanford Research Institute, Stanford, Calif.
Nathan I. Hall, vice-president and director, guided missile research and development div., Hughes Aircraft Co., Culver City, Calif.
Donald B. Harris, associate director, applied electronics lab., Stanford University, Stanford, Calif.
Rudolf C. Hergenrother, department head, Raytheon Manufacturing Co., Waltham, Mass.
Jesse E. Hobson, director, Stanford Research Institute, Stanford, Calif.
John C. Jensen, research engineer, Lincoln, Neb.
Henry P. Kalmus, physicist, Diamond Ordnance Fuze Lab., Washington, D. C.
Maurice E. Kennedy, director and chief engineer, department of communications, Los Angeles County, Los Angeles, Calif.
Glenn Koehler, professor of electrical engineering, University of Wisconsin, Madison, Wis.
N. I. Korman, manager, systems engineering group, RCA, Moorestown, N. J.
Kurt Lehovec, supervisory engineer and head, transistor lab., Sprague Electric Co., North Adams, Mass.
Humboldt W. Leverenz, director, physical and chemical research lab., RCA Labs., Princeton, N. J.
Harry F. Mayer, manager, advance engineer, General Electric Co., Utica, N. Y.
George McElrath, director, technical operations, National Broadcasting Company, New York, N. Y.
Maynard D. McFarlane, research scientist, Robertshaw-Fulton Controls Co., Anaheim, Calif.
Julian Z. Miller, assistant vice-president, development and research, Western Union Telegraph Co., New York, N. Y.
Burton F. Miller, director, communications div., Ramo-Woolridge Corp., Los Angeles, Calif.
Russell C. Newhouse, military development engineer, Bell Telephone Laboratories, Whippany, N. J.
Wayne B. Nottingham, professor of physics, Massachusetts Institute of Technology; vice-president in charge of research, Electronics Corporation of America, Cambridge, Mass.
Chester H. Page, consultant to director, National Bureau of Standards, Washington, D. C.
Winslow Palmer, research engineer, Sperry, Gyroscope Co., Great Neck, L. I., N. Y.
Salvatore E. Petrillo, director of engineering, Signal Corps Engineering Labs., Fort Monmouth, N. J.
Waldemar J. Poch, engineering section manager, RCA, Camden, N. J.
Jacob Rabinow, president, Rabinow Engineering Co., Washington, D. C.
George Rappaport, chief engineer, counter-measures branch, Wright Field, Dayton, Ohio
Avery G. Richardson, division head, direction finders and receivers, Federal Telecommunications Lab., Nutley, N. J.
Carl E. Scholz, vice-president and chief engineer, American Cable and Radio Corp., New York, N. Y.
John L. Sheldon, manager, television research, Corning Glass Works, Corning, N. J.
A. Melvin Skellett, director of color television, Tung-Sol Electric, East Orange, N. J.
John J. Slattery, vice-president of engineering, Sterling Precision Instrument Co., Flushing, L. I., N. Y.
John B. Smyth, Smyth Research Associates, San Diego, Calif.
Harold A. Snow, senior project engineer, Federal Telecommunication Labs., Nutley, N. J.
Edwin E. Spitzer, manager, power tube engineer, RCA, Lancaster, Pa.
Chauncey G. Suits, vice-president and director of research, General Electric Co., Schenectady, N. Y.
Gordon K. Teal, assistant vice-president and director of research, Texas Instruments, Dallas, Tex.
William A. Tolson, senior research engineer, RCA Laboratories Div., Princeton, N. J.
Aldert van der Ziel, professor of electrical engineering, University of Minnesota, Minneapolis, Minn.
Robert L. Wallace, Jr., Bell Telephone Laboratories, Murray Hill, N. J.

Now . . . INSULATED DEPOSITED CARBON RESISTORS

After intensive study of the many special requirements arising in modern resistor applications, Welwyn has succeeded in developing a resistor-encapsulating process employing a new, insulating material. When thus applied, this material will withstand an applied potential of 8000 volts. Its insulating effectiveness is in excess of 100,000 megohms.

Welwyn insulated resistors can be placed contiguous to each other without the need for additional insulating material. In all other respects, these new insulated resistors offer the same performance and quality advantages generally associated with Welwyn Deposited Carbon resistors. Available in ⅛, ½, 1 and 2 watt ratings.

Manufactured in England and Canada

Welwyn
High Stability
DEPOSITED CARBON RESISTORS

For complete data and specifications write to Dept. KA-7

Welwyn International, Inc. 3355 Edgecliff Terrace, Cleveland 11, Ohio

important facts about
LM ELECTRONICS complex wave
vibration test systems...

LM ELECTRONICS offers a complete line of complex wave vibration test systems — 12 sizes with outputs up to 400,000 watts — specifically designed to meet the growing demand for operating flexibility. Built to exacting performance standards, LM's fully integrated test systems offer unsurpassed simplicity, accuracy and reliability over a wide range of test applications.

HIGH POWER electronic power supplies . . . 250 to 400,000 watt outputs . . . ample to drive shakers up to 12,500 force-pounds.

COMPLETE INSTRUMENTATION . . . full console control provides greater set-up and operating speeds . . . handles any desired combination of instrumentation.

ADVANCED DESIGN . . . LM electronic power supplies offer proven reliability for either intermittent or continuous test cycles . . . walk-in construction . . . complete protection for operating personnel.

WIDE RANGE of accessories and optional equipment to meet all complex and sine wave vibration testing requirements.

WRITE FOR TECHNICAL DATA and specifications on LM Vibration Test Systems and related electronic equipment . . . unmatched for performance and reliability.

LM ELECTRONICS INC.
5017 EXPOSITION BLVD., LOS ANGELES 16, CALIF.
REpublic 2-6618

Want more information? Use post card on last page.

NOW

increased operational versatility . . . greater accuracy in RF, VHF and UHF SPECTRUM ANALYSIS

with the IMPROVED
PANORAMIC PANALYZOR
MODEL **SB-8b**

Check these advanced engineering features:

NEW Continuously variable scanning rate from 1 thru 60 scans/sec with one control. Three selectable modes . . . free running, line synch or external synch.

NEW Three selectable types of amplitude displays . . . Square law exponential, Linear 20 db, Log 40 db.

NEW Flat face CRT, edge lit calibrated screen and camera mount bezel for photographic records—optional.

NEW Differential markers to show frequency dispersion available in the Type T-10,000.

The Panalyzor Model SB-8b is available in three types:

Type	Sweepwidth Range	Resolution Range
T-200	200 kc-0 kc	50 cps-4.5 c
T-1000	1 mc-0 mc	400 cps-10 kc
T-10,000	10 mc-0 mc	9 kc-100 kc

Write today for complete specifications and prices.

PANORAMIC
RADIO PRODUCTS, INC.

Made by the makers of Panadaptor, Panoramic Sonic Analyzer, and Panoramic Ultrasonic Analyzer

10 South Second Ave., Mount Vernon, N. Y.
MOunt Vernon 4-3970

Want more information? Use post card on last page.

New Books

Electronic and Radio Engineering

BY FREDERICK E. TERMAN. *McGraw-Hill Book Co., Inc., New York,* 1955, 1,078 *p,* $12.50.

EACH passing year adds to the multitude of electronic engineers who have cut their professional eyeteeth on Terman's "Radio Engineering." Now in his fourth edition, the author recognizes in the title that radio is only a part of the rapidly expanding field of electronics.

►**Content**—The book provides a thorough treatment of electronic fundamentals with a considerable portion devoted to ramifications of the electron-tube amplifier. The author has made a highly commendable effort to keep the book timely.

There is a fairly long chapter on microwave tubes that will give the student a good qualitative understanding of the traveling-wave tube and other devices for microwave frequencies. It is a convenience to have the admittance-spiral discussion of the klystron within such a general book. This avoids the necessity for an outside reading assignment.

Another fairly long chapter discusses the transistor. This discussion will provide a firm basis for work with semiconductor circuits. Undoubtedly, subsequent editions will devote even more space to this extremely useful device—especially from the application standpoint.

The material on television has been completely revised from previous editions and includes a thorough coverage of modern practice including color television.

The chapter on aids to navigation provides an introduction to radar which is so important in the military end of the electronics business. Appropriate emphasis is placed on newer radar features such as moving target indication.

In his coverage of radio propagation, the author has anticipated the current interest in propagation beyond the horizon through the mechanism of forward scatter.

►**Evaluation**—The book is excellent as a general text on the under-

BLACK LIGHT—NEW INSURANCE AGAINST INADEQUATE COVERAGE

Tropicalization rejects caused by inadequate coverage are being eliminated by an economical *invisible* system known as Blak-Ray. Manufacturers of electronics equipment and parts report substantial savings in production and inspection costs.

Complete information is contained in new Case History 115E, available free from the BLACK LIGHT CORPORATION OF AMERICA, Distributors for Ultra-Violet Products, Inc. *Denver:* 1334 Speer Blvd.; *Houston:* 4616 S. Main St.; *Los Angeles:* 5403 Santa Monica Blvd.; *Long Island City, N. Y.:* 33-00 Northern Blvd.; *San Francisco:* 925 Harrison St.; *Seattle:* 104 Prefontaine Pl.

Main Plant: San Gabriel, Calif.



here's the answer to a **better** product!

Meet Star VITROLAIN, a really versatile electrical porcelain. This basic material is a feldspathic type ceramic having superior dielectric and mechanical strength. Its pore volume and moisture absorption factors are extremely low (less than 0.25%). It is ideal for parts used in the presence of moisture and chemical vapors. Available in white and color glazes. Our 26-page catalog contains complete data. Write.

Star Porcelain Company
42 Muirhead Ave., Trenton 9, New Jersey

STAR
porcelain company

Want more information? Use post card on last page.

Scouting for Incapsulated Coils?

DANO MAKES THEM!

Dano, makers of a wide variety of coils, is fully equipped to meet the increasing demand for these special coils. Keeping pace with modern design, Dano offers incapsulated coils with tough, molded covers that spell extra electrical insulation with freedom from moisture.

Every Dano Coil is custom-made to your specific requirements. Call or write today, and Dano's quote will be on the way!

- *Incapsulated Coils* • *Form Wound*
- *Bakelite Bobbin* • *Cotton Interweave*
- *Paper Section* • *Acetate Bobbin*
- *Coils for High Temperature Applications*
- Also, Transformers Made To Order

The DANO Electric Co.
MAIN ST., WINSTED, CONN.

ACEPOT* ACETRIM

Sub-Miniature

precision wire-wound

Potentiometers and Trimmers

Acepot actual size

200 ⁓ to 100K
½" size
linearity .3%
extremely high resolution

10 ⁓ to 50k
½" size
linearity 3%
low price

Acetrim actual size

For applications where you must be sure . . . fill your potentiometer and trimmer needs with these space and weight saving, highly accurate and reliable units.

Expedited delivery on prototypes; prompt scheduling of production orders. Send for catalog sheets and application data sheets.

* Trademarks applied for

ACEPOT *(potentiometer)* 200 ⁓ to 100K std., ±2%, higher or lower on special order; linearity .3%; ½" size; weight: ¼ oz.; torque: .035 oz/in @ 20° C.; power: 2 watts for 60° C. rise; ambient temperature, —55° C. to 125° C.; standard, servo or flush mountings, single or up to 6 gang units; tapped units, self-contained locking device; sealed, moistureproofed, anti-fungus treated; meets MIL-E-5272A standards.

ACETRIM *(potentiometer trimmer)* 10 ⁓ to 50k standard, ±5%; linearity 3%; ½" size; weight: ¼ oz.; torque: low or high as required; power: 2 watts for 60° C. rise; available with panel anti-rotation pin, stops, and self-contained locking device; low price.

ACEPOT* ACETRIM **ACE ELECTRONICS ASSOCIATES**
125 Rogers Avenue • Somerville 44, Massachusetts

SINCE 1920 QUALITY WENCO PRODUCTS

SPADE BOLTS

Specialists in designing and manufacturing of all-purpose fasteners and wire forms. Tooled to produce over 1000 styles in any screw size, material, finish, quantity, to your specifications.

Serving Industry for Thirty-five Years
— *OTHER PRODUCTS* —

Simplex
WIRE STRIPPERS & CUTTERS

• TOOLS • DIES • STAMPINGS
Bulletins on complete line upon request

WENCO MANUFACTURING CO.
1133 W. Hubbard St., Chicago 22, Ill., U.S.A.



experience pays

Yes, experience does pay in many ways. Our clients know from experience they have a dependable, responsible source for preparation of better industrial and business literature.

Why not do the job right? It saves time, money and produces results. Let us give you a proposal on your next publication.

We'll do the whole job—from planning to printing—or just those parts that you need.

product literature
military manuals
company publications
training material

Call or write for more information.

TECHNICAL WRITING SERVICE
McGraw-Hill Book Co., Inc. • 330 West 42nd Street • N. Y. 36, N. Y.

YOU BUILD EICO KITS

IN ONE EVENING BUT THEY . . .

LAST A LIFETIME AND YOU SAVE 50%

New . . . 460K DC Wide Band 5" Scope
Kit $79.95
Wired $129.50

425K 5" Scope
Kit $64.95
Wired $79.95

470K 7" Push-Pull Scope
Kit $79.95
Wired $129.50

221K VTVM
Kit $25.95
Wired $39.95

New 324K RF Signal Gen.
Kit $34.95
Wired $59.95

565K Multimeter
Kit $24.95
Wired $29.95
20,000 ohms/volt

46 KITS AND INSTRUMENTS — THE INDUSTRY'S MOST COMPLETE LINE OF MATCHED TEST INSTRUMENTS

377K
Sine & Square Wave Audio Gen.
Kit $31.95
Wired $49.95

½-million EICO instruments are now in use the world over! That's the proof of EICO's leadership in value.

For latest precision engineering, finest components, smart professional appearance, lifetime performance and rock-bottom economy—see and compare the EICO line at your jobber before you buy any higher-priced equipment! You'll agree with over 100,000 others that only EICO Kits and Instruments give you the industry's greatest values at lowest cost.



1050K Battery Elim.
Kit $29.95
Wired $38.95

Write NOW for FREE latest Catalog E-1

625K Tube Tester
Kit $84.95
Wired $49.95

Prices 5% higher on West Coast

EICO®

©56

84 Withers Street, Brooklyn 11 N Y

Want more information? Use post card on last page.



One-shot multivibrator using junction transistors

graduate level. The author gets his material across with a minimum of high-powered mathematics such as transform analysis and partial differential equations.

The specialist will have to look elsewhere for the answers to his special problems. Nevertheless, the material is here for a basic understanding of electronic and radio engineering together with a comprehensive view of the current electron art.—J.M.C.

Analysis of Feedback Control Systems

By ROBERT A. BRUNS and ROBERT M. SAUNDERS.
McGraw-Hill Book Co., New York, 1955, 383 *p*, $7.50.

THE past two years have seen an increasing number of books published on the subject of feedback control systems. This text is different, however, in that it not only deals with the analysis of such systems but also includes a good, extensive treatment of the individual components of which the system is composed. Especial emphasis is placed upon deriving the transfer function for each component since this constitutes the essence of the frequency response method of analyzing system behavior to applied disturbances.

The book was written primarily for the benefit of the scientist and/or the practicing engineer who is new to the field of feedback control systems and who desires to gain a knowledge of the subject matter and an appreciation of its limitations. It is also intended as a text for a senior-level engineering course. The required preparation consists of a-c circuit theory and some familiarity with dynamics and differential equations.

Basically the book is divided into two parts. Part I, which covers 222

"connectors?

Certainly sir, I'll *personally* see they are sent you today."

"a small order?

Wood's service is geared to meet your requirements, regardless of the size of your order."

"you're in a rush?

That's easy, sir. Woods supplies the connectors you want, when you want them. We'll ship today."

woods distributes only the finest lines

Authorized Distributor

- Cannon Plugs
- U.S. Relays
- Gremar R.F. Connectors

WOODS AIRCRAFT SUPPLY

"The Right Connection for the Right Connectors"

309 West Elmwood Ave., Burbank, California
Telephones: VIctoria 9-3211
THornwall 2-8182

Want more information? Use post card on last page.



- OIL COOLED
- WATER COOLED
- AIR COOLED

NEW! High Power DUMMY LOADS

Waveguide and Coaxial

Coaxial Loads:
up to 10 KV Average Power.

Waveguide Loads:
X-Band Loads up to 1000 Watts Average Power.
S-Band Loads up to 4000 Watts Average Power.
L-Band Loads up to 6000 Watts Average Power.

WRITE FOR NEW CATALOG

Electro Impulse Laboratory
208 River St. • Red Bank, N. J.
Red Bank 6-0404



Miniature and Sub-Miniature

SLIP RING ASSEMBLIES
BRUSH BLOCK ASSEMBLIES
COMMUTATORS

and other
Electro-Mechanical Components

PRECISION MADE TO YOUR OWN SPECIFICATIONS

Precision molded products with exacting tolerances in precious and non-precious solid metals of all alloys. All types of Thermo-Plastic and Thermo-Setting materials.

Slip Ring Assemblies fabricated or one-piece precision molded to your specifications in Nylon, Kel-F, Mineral filled Mellamine, Phenolic, and other materials. Rings and leads spot welded or brazed together for positive electrical circuit.

Our Swiss methods and techniques are geared to meet exacting requirements. We invite your inquiries.

COLLECTRON CORPORATION

MUrray Hill 2-8473 • 216 East 45th Street • New York 17, N. Y.

ZOPHAR

---WAXES
---COMPOUNDS

Zophar Waxes, resins and compounds to impregnate, dip, seal, embed, or pot electronic and electrical equipment or components of all types; radio, television, etc. Cold flows from 100°F. to 285°F. Special waxes non-cracking at 76°F. plain or fungicidal. Let us help you with your engineering problems.

For immediate service contact:
L. E. Mayer, Sales Manager
A. Saunders, Technical Director
H. Saunders, Chemical Laboratory

Phone SOuth 8-0907

110 YEARS

ZOPHAR MILLS, INC.
112-130 26th Street,
Brooklyn 32, N. Y.

---

the leading contender in the sensitive relay class!



KURMAN'S
MIGHTY SERIES "T"

Compare it and you'll know why

KURMAN SERIES "T"	Maximum Coil Resistance 12,000 ohms	DPDT Standard Adjust. 35 milliwatts	Gram Pressure 20 min.
Leading Make A	8,000	40	15
Leading Make B	12,000	40	10

The latest addition to a line of miniature hermetically sealed sensitive relays, the new Kurman Series "T" is 1" x 1" x 1¾" high and weighs only 3½ ozs.—the mighty midget of the sensitive class. Radically different in design, you will find the Series "T" to be superior in performance — economically priced with excellent delivery service.

Why not specify the Series "T" for your next sensitive relay application and check its performance for yourself? Detailed specification sheet "E" available on request.

KURMAN ELECTRIC CO., INC.

Quality Relays Since 1928
35-18 37th Street, Long Island City 1, N. Y.

Need HERMETICALLY SEALED TRANSFORMERS?

TAKE ADVANTAGE OF CREST EXPERIENCE

The CREST TRANSFORMER engineering laboratories have a complete, custom designed line of hermetically sealed transformers in addition to their hundreds of modern transformers, line voltage controls and equivalent parts series for over 200 television sets.

WRITE FOR OUR COMPLETE CATALOG

Gentlemen: Please send me your Catalog No. 554
Name_____
Position_____
Firm_____
City_____ Zone____ State_____

CREST
TRANSFORMER CORP.
DEPT. E
1834-36 W. North Ave. Chicago 22, Illinois

PHAZOR PHASE METER
Pat. Pend.

MODEL 200 A

PRICE $349.50 F.O.B. NEW YORK

- HIGH ACCURACY
- MEASURES FROM 0 TO 360 DEGREES
- READINGS NOT AFFECTED BY NOISE AND HARMONICS
- PHASE SHIFTS OF THE ORDER OF .01° CAN BE MEASURED EMPLOYING SPECIAL CIRCUIT TECHNIQUES
- MEASURES IN-PHASE AND QUADRATURE COMPONENTS SEPARATELY

For further information contact your nearest representative or write for brochure

INDUSTRIAL TEST EQUIPMENT CO.
55 E. 11th ST. · NEW YORK 3 · GR. 3-4684

Manufacturers of:

PHASE METERS
•
NULL DETECTORS
•
IMPEDANCE COMPARATORS
•
POWER OSCILLATORS
•
VACUUM TUBE VOLTMETERS
•
FREQUENCY STANDARDS
•
AUTOMATIC HI-POT
•

Other Electronic Test Equipment

IMPREGNATING
SEALING
DIPPING
INSULATING
BLENDING

POTTING
HEAT CONDUCTING
MOISTURE PROOFING
FUNGUS PROOFING
ENCAPSULATING

WAXES BIWAX COMPOUNDS

Standard compounds available from stock.
Samples and specifications on request.
Modifications developed and produced to meet specific requirements.
Information relating to your problem will enable us to make recommendations. Write to

BIWAX CORPORATION 3445 HOWARD ST. SKOKIE ILLINOIS

M-DC-3A super-regulated voltage standard



M-DC-2A super-regulated voltage and current standard

Calibration Partners

The two units combined, provide voltages up to 509.99 volts dc in 0.01 volt steps, however, either unit can function independently. The M-DC-2A provides current outputs of from 0 to 109.99 ma dc in 0.01 ma steps and voltages from 0 to 109.99 volts dc in 0.01 volts steps. Overall accuracy of both units is within 0.05 pct. of selected voltage or current.

RADIATION Inc.
Electronics · Avionics · Instrumentation



Magnetic-amplifier motor control

pages, deals with components. Part II, which spans the remaining 150 pages, treats the subject of feedback system theory. The authors chose to present the material on components first since they felt this would make understanding system behavior easier.

In presenting the material of the book the authors frequently resort to the use of instructive, illustrative examples. Moreover, the text is considerably annotated with well-chosen references. Another worthwhile feature is the termination of each chapter with a summary section in which the salient points of the chapter are condensed. There is also an abundance of problems after each chapter.

This is a book which has a definite contribution to make to the literature on feedback control systems. It should be well received.—PROF. V. DELTORO, C. C. N. Y. *School of Technology, The City College, New York, N. Y.*

Transistors and Other Crystal Valves

BY T. R. SCOTT. *Essential Books, Inc., Fair Lawn, New Jersey*, 1955, 258 *p*, $7.20.

MANY books about transistors concentrate heavily on how to design the units into electronic circuits. This book emphasizes fundamental behavior of transistors and thereby indicates broadly their potentialities.

▶ **Content**—The book starts off with a brief discussion of early Bell Labs work with transistors and a chapter on imperfections in crystals from which the transistor derives its amplification properties.

There follows a fairly comprehensive coverage of the *p-n* junction. This topic provides a jumping off point for discussions of various

MOLYBDENUM

•

PURE and THORIATED TUNGSTEN

For ELECTRONIC APPLICATION

RIBBONS

STRIPS

FORMED PIECES

Your special metals rolled to thin sizes - close tolerances

H. CROSS CO.
15 BEEKMAN ST., N. Y. 38, N. Y.
WOrth 2-2044 and COrtlandt 7-0470

WIDE-RANGE FREQUENCY METER 85-1000 MEGACYCLES

TS-175A/U

Government Approved Calibration Accuracy: .005% Stability: .0025% Resettability: .0025%

IMMEDIATE DELIVERY

A VERSATILE PRECISION MEASURING INSTRUMENT *Recommended Applications:*

- Precise Measurements of Frequencies
- Production Testing
- Alignment of Transmitters and Receivers
- Laboratory Testing
- Portable Field Testing
- A Secondary Frequency Standard
- Signal Generator Calibration
- U.H.F. and V.H.F. Television Alignment

COLORTONE
ELECTRONICS, Incorporated
200 Front Road, Hicksville, L. I., N. Y. WI 4-2124

Export Rep: Andrew S. Szucs, Inc.
50 Broad St., N. Y. C.

junction transistors and diodes of U. S., British and European manufacture.

Material on high-frequency semiconductor devices covers the *pnip* trabsistor and the field-effect transistor.

►**Evaluation**—Of special merit is the appendix which discusses transistor action from the quantum mechanical viewpoint. This material serves to integrate the behavior of the transistor into the overall physical concept of matter and energy. There is also a useful appendix devoted to testing techniques.—J.M.C.

Thumbnail Reviews

Application of Transistors to Electronic Counting Equipment. By R. E. Kimes. Report to Signal Corps Supply Agency. Available from OTS, Washington, D. C., 71 p, $2.00 (paper). Design and development of a transistorized frequency meter. Circuit details are presented.

Coyne Technical Dictionary. Howard W. Sams & Co., Inc., Indianapolis, Indiana, 160 p, $2.00. Defines 4,000 expressions used in television, radio and electronics. A data section is included.

Repairing Record Changers. E. Eugene Ecklund. McGraw-Hill Book Co., Inc., New York, 1955, 278 p, $5.95. Treats mechanical operation of record changers; discusses pickups, amplifiers, also magnetic-tape recorders.

Physical Mathematics. Chester H. Page. D. Van Nostrand, Inc., New York, 1955, 329 p, $7.50. Nicely groups the mathematics required for a first-year graduate-level course in theoretical physics. Considers eigenfunctions, transform analyses, partial differential equations and other important topics.

Powder Metallurgy. Organization for Europeon Economic Cooperation, Washington, D. C., 1955, 309 p, $3.00 (paper). Contains material on the properties and preparation of powdered metal magnets and ferrites.

A Study of the Double Modulated F-M Radar. Mohamed Abd-El Wahab Ismail. Berlag Leemann, Zurich, Switzerland, 112 p, 10.40 Swiss francs. Highly mathematical discussion of the technique of double-modulated f-m radar. Advantages are given. Conventional f-m radar is also discussed.

An Introduction to Automatic Computers. Ned Chapin. Technology Center, Chicago, Ill., 245 p. $9.00 (binder). Discusses design and programming of automatic digital computers and gives data sheets for available units, that provide technical and operating data.

How to whip your relay problems!

Just call **ADVANCE...** *we're ready and willing to make the relays you need.*



CONTACTS, *for example*

Say the word and we'll up the sizes... switch from fine silver to tungsten, palladium, silver-cadmium oxide, gold contacts, or... you name it!

INSULATION

Laminated phenolic, silicone glass, ceramic steatite, linen-base bakelite, or... you name it!



ANYTHING SPECIAL...

ADVANCE will engineer, develop and produce the custom relays you need in minimum time. Call ADVANCE for action.

For **ELECTRONIC USES**

We build a vast variety of sensitive, reliable relays...create superior new designs quickly. You'll find our quality control is now the tightest in the industry.

Write—and let us solve your relay problems

ADVANCE ELECTRIC AND RELAY CO.
An Elgin National Watch Company Affiliate
2435-A NORTH NAOMI STREET
BURBANK, CALIFORNIA

WIND UNIFORM TOROIDS WITH THE BOESCH AUTOMATIC COIL WINDING MACHINE

By eliminating repeated manual functions the BOESCH Automatic Model TW-200-A provides the means of producing uniform coils without depending on the constant attention and skill of the operator.

Winds coils .218" I.D. to 5" O.D. #20 to #42 wire, with standard equipment. For this and other BOESCH machines, write for detailed information . . . *we can cut your labor costs.*



Model TW-200-A

Now — no licensing, no royalties required in the sale and use of BOESCH Machines

BOESCH
MANUFACTURING CO., INC.
DANBURY, CONN.

Want more information? Use post card on last page.

Backtalk

Automatization

DEAR SIRS:

ON the article "Automatics" which appeared in UNESCO's Monthly Bulletin of the International Advisory Committee on Documentation and Terminology in Pure and Applied Science, 1955. 08,14, commenting on editorials and letters published, I think it useful to bring to the notice of interested scientists the following:

In the English language there is the verb "automatize" which is accompanied by many derivatives and related words.

The verb "automatize" and the connected words are of Greek origin and in use from ancient times . . .

The word "automation" means self acting or presenting a reflex action. It derives from Greek words meaning to act, to move, to attempt, to desire, to hurry, to be eager. The resultant of all these ancient meanings of "maomai" with the prefix "autos" is the modern meaning of the combined word "automation" . . .

There is no need for scientists to invent a verb of Latin appearance or origin, as has been suggested, because Latin has nothing to do with those completely Greek words. It seems necessary to emphasize that words like automation, automacy, automate, and who knows what else, are altogether out of the rules governing the mother root: "automat—", either in English or in Greek and in consequence they are erroneous . . .

As a technical man, I could say that those words: "automation, automacy, automate etc." do not bring any new conception in the technical field, which might justify their introduction in the technical vocabulary. They are intended to have the same meaning as the correct ones but they are wrongly formed.

The Oxford English Dictionary, besides the correct terms, gives: Automate (a substantive and adjective, obsolete, from French "automate"), Automacy (name indicating the "automatic quality", probably from French "automatie"). So, we see their formation



Specimen of template, custom-made for General Electric

Write for

FREE SAMPLE

of Our

Custom-Made Templates

And Judge Their Quality for Yourself

Our durable, plastic, precision-made templates—made to *your* specifications, to fit *your* needs—cost little more than standard guides. Yet they save hours of draftsmen's time, and help standardize your drawings.

Just send us a sketch of your particular needs—symbols, component parts, etc. Specify quantity desired. We will send you FREE a sample template—together with a surprisingly low quotation.

Prompt Service Assured

FISHER & CROME
109 N. Camac St. • Phila. 7, Pa.

on the LINE

in the FIELD

KWIKHEAT
Controlled Heat Soldering Irons

are better ... faster for Printed Circuits!

Light weight, perfectly balanced, small size, controlled-heat Kwikheat Type 200 soldering irons are designed for close soldering.

Sealed, high temperature, built-in thermostat maintains pre-set heat (800° for production, 700° for stand-by). Kwikheat irons, weighing only 7½ oz., are economical — maintaining heat on only one-third of heater capacity. Three versatile plunger-type tips are easily changed in the field.

For better, faster work — at lower cost — switch to KWIKHEAT soldering irons.

KWIKHEAT Manufacturing Co.
3732 San Fernando Rd., Glendale 4, Calif.

Want more information? Use post card on last page.

SAVE MONEY!

Measure frequency and FM deviation on a multitude of channels with just two small LAMPKIN METERS

LAMPKIN 105-B MICROMETER FREQUENCY METER—Heterodyne-type, universal coverage, 0.1 to 500 MC. Accuracy 0.005%. Weight 13 lbs. Width 13". Price $220.00.



LAMPKIN 205-A FM MODULATION METER—Indicates FM voice deviation, ± 25 KC., all channels, 25 to 500 MC.; meets FCC mobile specs. Weight 13 lbs. Width 12¼". Price $240.00.

NEW booklet: *"HOW TO MAKE MONEY IN MOBILE-RADIO MAINTENANCE"* free on request. Write today!

LAMPKIN LABORATORIES, INC.
Instruments Division
BRADENTON, FLORIDA

Brew Delay Lines

Distributed Constant
Lumped Constant
Ultrasonic



Here are some reasons why you can be sure your requirements will be fully satisfied when you come to Brew for delay lines:

- custom built to your specifications
- wide experience in all type lines
- advanced packaging techniques
- special manufacturing and testing procedures
- modern facilities and skilled personnel
- exacting quality control
- continuous research and development program

Send us your specifications or send for Catalog 54 giving the complete Brew story.

BREW
Richard D. Brew and Company, Inc.
Concord, New Hampshire
design development manufacture

NO SHORT CIRCUITS when you use • EthoLoc* CABLE CLIPS



Made of ETHYL CELLULOSE . . .
A TOUGH, DURABLE PLASTIC

NOW . . .
For Extra Strength
"D" WASHERS TO FIT OUR CABLE CLIPS

Write for Sample and Full Information

WECKESSER CO.
ALSO MFRS OF ALL NYLON CABLE CLIPS
5267 N. AVONDALE AVE. • CHICAGO 30, ILL.
West Coast Representative:
5777 West Pico Blvd. • Los Angeles 19, Calif.

HIGH ENERGY, PRECISION ALNICO PERMANENT MAGNETS

When you need them—as you need them
Experimental or production quantities

Catalog upon request

PERMAG CORP., 210 TAAFFE PLACE, BROOKLYN 5, N. Y.

24 HOUR DELIVERY
Phone:
MAin 2-0114

WE CARRY IN STOCK
ALL SIZES,
ALL SHAPES,
ALL ALNICO GRADES

PERMAG

services include
- ENGINEERING
- PRECISION CUTTING
- PRECISION GRINDING
- MAGNETIZING

experience pays

let TWS* prepare
your industrial literature

*TECHNICAL WRITING SERVICE
McGraw-Hill Book Co.
330 W. 42nd St., N.Y.C.

send for information

IF IT'S NEW . . . IF IT'S NEWS . . . IT'S FROM ELCO



MAKING CONNECTIONS FROM COAST-TO-COAST

Every day, more and more quality manufacturers are joining the imposing list of those "Variconizing" their designs. For Elco's Varicons offer an almost infinite number of combinations. Here, for example, are but three combinations; and all are possible from only four basic parts: end sections, center section and contacts. Elco has furnished from 2 to 64 contact Varicons, for commercial and military usage, in polarized or keyed combinations. The Varicon has been termed the "engineer's dream" — you design, we align! Available in general purpose phenolic, low loss mica, general purpose phenolic color, and alkyd (if quantity sufficiently large). Contact material, tested and approved in general use, is phosphor bronze, silver plated. Varicons are available in single tier and double tiers, with brackets, handles, covers, recessed housings — and now, for printed circuitry. Write, phone, wire for complete information.

ELCO CORPORATION, M STREET BELOW ERIE, PHILA. 24, PA., CU 9-5500

PRECISION PHASEMETER

0.1° ABSOLUTE ACCURACY
•
0.01° incremental accuracy
•
30 to 20,000 cycles per second
•
0 to 360° phase range
•
10-megohm input impedance
(shunted by 25 μμf)

Output connection for strip-chart recorder.

Self-contained power supply for 105-125 volts, 50-60 cycles.

Adaptable to standard relay-rack mounting.

Price $3990 net F.O.B. Long Island City.

THE NEW MAXSON Model 901 Precision Phasemeter is a direct-reading electronic instrument adaptable to a wide variety of demanding measurement applications in computers, synchros, and amplifiers.

The instrument measures phase difference between two sinusoidal voltages; phase angles are read from a two-degree, step control with vernier indicator having a precision of 0.01°. Built-in sensing provides direct reading of proper quadrant. Accuracy is independent of even harmonics and of third harmonics up to 1%. Input-level range is from 0.5 to 10 volts rms.

Write or phone us for further information.

MAXSON INSTRUMENTS
A DIVISION OF THE W. L. MAXSON CORPORATION

47-37 Austell Place
Long Island City 1
New York
Tel: RAvenswood 9-1850

comes from French instead of from Greek.

In conclusion, the expressed useful idea that we need a verb from which the abstract noun could be easily recognized, I think, is fully satisfied with the use of the existing Greek root: "automat—", which gives so many, so precise and so easily recognizable derivatives.

DIONYSIUS J. BATAIMIS
Athens, Greece

Television Pioneer

DEAR SIRS:

TWENTY-FIVE years ago Manfred Baron von Ardenne succeeded for the first time at his laboratory in Berlin Lichterfelde to transmit electron pictures in half-tones. This was encouraging, giving hope of further development of electron picture transmissions.

I wish to call your attention to the fact that these experiments caused the conversion from the generally used mechanical television technique to the modern electronic television technique.

The historical date of this experiment was December 14, 1930.

HANS KOEPPEN
Berlin, Germany

Network Analyzer



Example of industry-education teamwork, this $430,000 network analyzer presented to Syracuse University by two power companies and GE will solve power-distribution problems while training network analysts. The 20-ton machine consists of 16 generator units, 200 line units, 150 capacitor units, 64 load units, 32 autotransformer units, 50 mutual transformer units, two operating consoles and a recording table. It uses 25 miles of hookup wire, 3,500 resistors, 2,500 switches, 800 transformers and reactors and 800 relays

PROFESSIONAL SERVICES

Consulting—Patents—Design—Development—Measurement

in

Radio, Audio, Industrial Electronic Appliances

AIRPAX PRODUCTS CO.

Development Division

Specialists in the
Design and Manufacture of
UNUSUAL TRANSFORMERS AND RELAYS

Middle River — Baltimore 20, Md.

CONSULT THESE SPECIALISTS:

Let them save your time by bringing their broad experience in their specialty to bear on your problems.

PICKARD & BURNS, INC.

Consulting Electronic Engineers

Analysis and Evaluation
of Radio Systems
Research, Development and Production
of Special Electronic Equipment

240 Highland Ave. — Needham 94, Mass.

ANALYSIS INSTRUMENT CO

Consultants on Magnetic Problems

Magnetic Materials Tested
Special Magnetic Devices Designed
Magnetizing & Testing Equipment Supplied

P. O. Box 7 — Pequannock, New Jersey

ELECTRONIC RESEARCH ASSOCIATES, INC.

"TRANSISTORIZE" YOUR PRODUCT!
Complete Service in consulting, research, development, and production on Transistor circuitry, products and instrumentation.

67 East Centre Street — Nutley, N. J.
NUtley 2-5410

ALBERT PREISMAN

Consulting Engineer

Television, Pulse Techniques, Video
Amplifiers, Phasing Networks
Industrial Appliances
Affiliated with
MANAGEMENT-TRAINING ASSOCIATES

3224 - 16th St., N. Y. — Washington 10, D. C.

H. O. BIXBY ASSOCIATES

Consultants to the Electronic Industry

SURVEYS — PROMOTIONS —LIAISON
PERSONNEL PLACEMENT — TECHNOLOGY

238 Main St. — Cambridge 42, Mass.
ELiot 4-9404

ERCO RADIO LABORATORIES, INC.

Radio Communications Equipment

Engineering - Design - Development - Production
Our 27th Year in Air to Ground
Communications and Radio Beacons

Garden City • Long Island • New York

SUNSTEIN ENGINEERING CO.

David H. Sunstein and Associates

Consulting Services for Research, Engineering and Production of Industrial, Consumer, and Government Products.

464 Conshohocken State Road
Bala-Cynwood (Phila.) Pa.
MOhawk 4-0452

THOMAS H. BRIGGS & ASSOCIATES

Electronics Consultants

Electron Tubes - Automation - Project Surveys
Tube Materials & Reliability - Servo-mechanisms
Engineering and production facilities.

Box 125 RD #2 Norristown, Penn. Tel. No. 8-7871

HANSON-GORRILL-BRIAN INC.

Product & Mfg. Development

ELECTRICAL - ELECTRONIC
HYDRAULIC - MECHANICAL

One Continental Hill — Glen Cove, N. Y.
Glen Cove 4-7300

THE TECHNICAL MATERIAL CORPORATION

Communications Consultants

Systems Engineering
General Offices and Laboratory

700 Fenimore Rd., Mamaroneck, N. Y.

CROSBY LABORATORIES, INC.

Murray G. Crosby & Staff

Radio - Electronics
Research Development & Manufacturing
Communication, FM & TV

Robbins Lane, Hicksville, N. Y.
WEIs 1-3101

THE KULJIAN CORPORATION

ELECTRONICS DIVISION

Consulting Electronic Engineers

Research, Development, Production of
Automatic Controls — Special Instrumentation

1200 No. Broad St., Philadelphia 21, Pa.
Stevenson 2-9000

TELECHROME, INC.

Electronic Design Specialists

COLOR TELEVISION EQUIPMENT

Flying Spot Scanners, Color Synthesizers, Keyers, Monitors, Oscilloscopes and Related Apparatus
J. R. Popkin-Clurman, Pres. & Ch. Engr.

80 Merrick Rd. — Amityville, L. I., N. Y.

DELAWARE PRODUCTS CO.

Analog Voltage to Digital Conversion
Digital Voltage Recording Systems

Design-Development-Manufacturing

300 Broadway — Camden 3, N. J.

Measurements Corporation

Research & Manufacturing Engineers

HARRY W. HOUCK — MARTIAL A. HONNELL
JOHN M. VAN BEUREN

Specialists in the Design and
Development of Electronic Test Instruments

Boonton, New Jersey

WALSH ENGINEERING CO.

Design and Prototypes
of Electronic Apparatus

in which Transformers and Magnetic Components are especially important factors in Performance, Size, Weight and/or Cost

34 DeHart Place — Elizabeth, N. J.
Elizabeth 2-7600

EDGERTON, GERMESHAUSEN & GRIER, INC.

Consulting Engineers

Stroboscopy — Transient Oscillography
Photoelectricity — Pulse Techniques — Timing
High-Speed and Electronic Flash Photography
Telemetering - Industrial Television Applications

160 Brookline Avenue — Boston 15, Mass.

MINOT INFORMATIC DEVICES

AUTOMATIC RECOGNITION OF
SHAPES, PATTERNS & INFORMATION
RESEARCH - INVENTION - CONSULTING
on detection and interpretation of
complicated forms, characterization of
materials, printed characters, etc.

Otis N. Minot, 22 Eliot Rd., Lexington 73, Mass.
Tel. VOlunteer 2-9465 or -3974

WHEELER LABORATORIES, INC.

Radio and Electronics
Consulting — Research — Development
R-F Circuits — Lines — Antennas
Microwave Components — Test Equipment
Harold A. Wheeler and Engineering Staff

Great Neck, N. Y. — HUnter 2-7876

Eldico of New York, Inc.

Pioneers of Television Interference Elimination from Transmitters, Induction Heaters, Diathermy and otR.

Donald J. S. Morten & Engineering Staff

72 E. Second St. — Mineola, L. I., N. Y.
Pioneer 6-5213

NIAGARA ELECTRON LABORATORIES

CONSULTATION - DESIGN - CONSTRUCTION
MFG. THE THERMOCAP RELAY

Specializing in solution of problems of electronic and electro-physical instrumentation for the research or analytical laboratory. Industrial plant problems also invited.

Andover, New York Cable Address: NITRONLAB

YARDNEY LABORATORIES

Research-Design-Development

Electro-Chemical Generators of Energy

40-46 Leonard Street — Worth 6-3100
New York 13, N. Y.

CONTACTS

$175 f.o.b.
SHORTED TURN
INDICATOR
FOR UNMOUNTED COILS
SENSITIVE, RUGGED, NON-SHOCKING
Kartron LEhigh 9-4606
Huntington Beach, Calif.

ETCHED CIRCUITS
24 HOUR SERVICE
On
SAMPLES, MODELS & PROTOTYPES
SILK SCREENS MADE TO ORDER
ROWE ENGRAVERS
492 E. 39 St. Paterson 4, N. J.

MICA
India • Brazil
BLOCKS • FILMS • SPLITTINGS
All Grades & Qualities — Warehouse Stocks New York — Prompt Forward Shipments
Phone: WOrth 4-4192 or write:
Associated Commodity Corporation
Woolworth Bldg., New York 7, N. Y.

MANUFACTURER'S REPRESENTATIVES

ART CERF & CO. Manufacturers' Representatives
LEADING ELECTRONIC LINES
Regular Coverage • 10 Men
6 States and District of Columbia
Phone: Mitchell 2-6734
744 Broad St.
NEWARK 2, N. J.

"OUR FOURTH YEAR"
The NEWHOPE CORPORATION
Lee Hecks, Associate
A Sales Organization for the
RADIO, TV and ELECTRONIC INDUSTRIES
Four salesmen concentrating in Metropolitan New York City and New Jersey—in a 50-mile radius
Telephone: LExington 2-7372
6 East 39th Street New York 16, New York

SAMUEL K. MACDONALD, INC.
manufacturers representatives over 25 years
1531 SPRUCE STREET, PHILA. 2, PA.
Territory:
Pennsylvania • New Jersey
Delaware • Maryland
Virginia • West Virginia
District of Columbia
Other Offices:
Pittsburgh
Baltimore
Washington, D.C.

ELECTRICAL NAVIGATION COMMUNICATION FIRE CONTROL RADAR INSTRUMENT SYSTEMS INSTRUMENTATION SYSTEM ANALYSIS SYSTEM INTEGRATION ANTENNAS

electrical design

With 16 years leadership in the vital field of missile research and development, Northrop Aircraft offers unusual opportunities for advancement in the categories listed below. Here you can apply your skill and ability on the pilotless Snark SM-62 A-bomb carrier; on Northrop's new long-range interceptor project; and on numerous other weapon system assignments. Where better could you be, and grow, than with a pioneer? There's an interesting position for you in one of the following groups:

Electrical Group, which is responsible for the design of such things as power generation and distribution systems, rectifiers and power converters, and auxiliary systems as applied to manned aircraft, guided missiles and ground support equipment.

Communications and Navigation Group, which is responsible for the design of C/N systems in manned aircraft and installation of guidance systems in missiles. Considerable research effort is devoted to air-borne antennas and the elimination of radio interference in C/N systems.

Fire Control Radar Group, which is responsible for the installation and application of the most advanced type of fire control systems in fighter-interceptor aircraft. The work covers the installation of the equipment and associated wiring; continuing liaison with equipment manufacturers; preparation of system analysis and reports; and follow-up of system performance in the field as aircraft become operational.

Instrument Group, which is responsible for the design of instrument systems for manned aircraft and the installation of flight test instrumentation for guided missiles. Typical systems for which the group is responsible include: Flight Instruments; Engine Instruments; Instrument Panel Design; Automatic Pilots and Augmenters; Fuel Flow and Quantity Systems; and Integrated Electronic Instrument Systems.

All four basic groups originate their basic design and layouts, prepare production design releases and originate all types of tests to support flight, design and production requirements.

There are now a number of openings available for engineers in each of these groups at all experience levels. Too, there are opportunities for draftsmen with either electrical or mechanical experience.

If you qualify for any of these challenging opportunities, we invite you to contact Manager of Engineering Industrial Relations, Northrop Aircraft, Inc., Hawthorne, California, or call ORegon 8-9111, Extension 1893.

5-A-47-A

NORTHROP AIRCRAFT, INC.

PIONEERS IN ALL WEATHER AND PILOTLESS FLIGHT

RATES . . . . . .

"Employment Opportunities"

Displayed—The advertising inch is $21.50 per inch for all advertising appearing on other than a contract basis. Contract rates quoted on request.

An advertising inch is measured ⅞" vertically on a column—3 columns—30 inches to a page.

Subject to Agency Commission.

Undisplayed—$2.10 per line, minimum 3 lines. To figure advance payment count 5 average words as a line.

Discount of 10% if full payment is made in advance for 4 consecutive insertions.

Not subject to Agency Commission.

Send NEW ADS to ELECTRONICS, 330 W. 42nd Street, New York 36, N. Y., for February Issue closing Jan.

REPLIES (Box No.): Address to office nearest you
NEW YORK: 330 W. 42nd St. (36)
CHICAGO: 520 N. Michigan Ave. (11)
SAN FRANCISCO: 68 Post St. (4)
LOS ANGELES: 1111 Wilshire Blvd. (17)

SELLING OPPORTUNITY WANTED

Manufacturer's Representative: Established representative with electronic engineering background now selling to electronic manufacturers in Middle Atlantic Area, desires to take an additional line. RA-8546, Electronics.

PART-TIME WORK WANTED

Seattle sales engineer seeks part-time work for supplier. Aircraft only. PTWW-8261, Electronics.

MANUFACTURERS REPRESENTATIVE

Engineer desires repeat and expendable electronic and electro-mechanical products for sale to Guided Missile and Aircraft Companies located in Southern California. Reply to:

LEE GRANT SNYDER COMPANY
Technical Sales & Contract Administrators
1418 N. Highland Ave. Hollywood 28, Calif.
Phone Hollywood 9-6278

DRAKE PERSONNEL

National Placement Center for
EXECUTIVE AND
TECHNICAL PERSONNEL

General and Plant Managers
Plant Superintendents—Foremen
Accounting—Staff Personnel
Engineers: Design—Production
Sales Managers—Engineers

Please outline briefly your experience or personnel needs to:

John Cope
220 S. State St., Chicago 4, Ill.
HArrison 7-8600

CHIEF ENGINEER
NORTHERN CALIFORNIA

You will report directly to the Vice-President of Engineering. 1000-man plant making highspeed, automatic, electronic and electro-mechanical equipment. Company will assume interview, relocation expenses and agency fee. Starting salary $12,000-$15,000. All replies in strictest confidence.

MONARCH PERSONNEL
28 E. Jackson Blvd., Chicago 4, Ill.

EXPANSION AT VICKERS INC.

PROVIDES EXCEPTIONAL OPPORTUNITIES FOR

Hydraulic, Mechanical & Electronic Engineers

HYDRAULICS INDUSTRY GROWTH POTENTIAL
Indicative of the continuing rapid rate of growth of the hydraulics industry is Vickers need for the new 150,000 sq ft research, engineering and administrative building shown above. No manufacturing will be done here.

DESIGN ENGINEERS
Experienced product designers and recent graduates with degrees in Mechanical, Aeronautical or Electrical Engineering.

RESEARCH AND DEVELOPMENT ENGINEERS
Experienced theoretical and laboratory engineers (mechanical and electronic) and physicists.

TECHNICAL SALES ENGINEERS
Experienced Mechanical or Electrical Engineers who have sales ability and are willing to relocate after training. Excellent opportunities also for recent graduates to train for hydraulics sales.

PRINCIPAL FIELDS OF APPLICATION FOR VICKERS HYDRAULICS

AIRBORNE
Missile controls, jet engine controls, constant speed drives, servo-mechanisms, valves and complete aircraft hydraulic systems.

AUTOMOTIVE
Power steering and other hydraulic systems and accessories for passenger cars and light trucks.

MOBILE EQUIPMENT
Agriculture, construction, earth moving and materials handling hydraulic units and complete systems.

INDUSTRIAL MACHINERY
Components and complete systems for automation, numerical control, machine tools, mining, textile, lumber, etc.

FEDERAL AND MARINE
Army ordnance, atomic energy, marine and naval vessel components and complete systems.

• • • •

These are really exceptional opportunities to grow with a rapidly expanding company. Mail resume of education, experience and personal qualifications to

Salaried Personnel Dept.
Section 1155
VICKERS INCORPORATED
DIVISION OF SPERRY RAND CORPORATION
1400 OAKMAN BLVD. • DETROIT 32, MICH.

VICKERS®
THE LEADING NAME IN
HYDRAULIC SYSTEMS

7378

ENGINEERS AND BUILDERS OF OIL HYDRAULIC EQUIPMENT SINCE 1921

Career Opportunity for
ORGAN SALES ENGINEERS

An excellent opportunity for qualified men exists with a leading, established electronic organ manufacturer. Ability to play the organ for demonstration purposes required, plus interest or aptitude in electronics or mechanics. Applicant should have pleasant appearance and winning personality. Sales experience helpful. Salary open, commensurate with ability and experience, plus possible commission basis. Must relocate near Allentown. A career opportunity with a progressive company. ALLEN ORGAN COMPANY, 29-39 Locust Street, Macungie, Pennsylvania.

W.C. WALKER,
Engineering Employment Manager
PACIFIC DIVISION,
Bendix Aviation Corporation
11608 Sherman Way,
North Hollywood, California

PLEASE SEND INFORMATION...

I am a graduate engineer with_____degree.

I am not a graduate engineer but have_____years experience.

NAME

ADDRESS

CITY

STATE

ZONE

Mail this coupon or write us today if you are interested in

ELECTRICAL AND MECHANICAL DESIGN OF RADAR, SONAR AND TELEMETERING

Bendix-Pacific

located in Southern California, specializes in sonar, airborne radar and telemetering (both airborne and industrial). We have excellent positions open at all levels in these fields. The work is directly associated with our long range projects and you are assured of permanent, well-paid work in the very heart of Southern California.

LET US SEND YOU COMPLETE INFORMATION. PLEASE FILL IN THE COUPON OR WRITE US NOW.

Bendix
PACIFIC DIVISION
Bendix Aviation Corporation
NORTH HOLLYWOOD, CALIF.

RAYTHEON Excellence in Electronics



Excellent for Engineers

SPECIFICATIONS ENGINEER

Three or more years of experience in electronic design or applications engineering. Familiarity with military specifications and technical writing experience desirable.

SYSTEM ENGINEERS

Responsible experienced engineers required for design and development of airborne electronic systems including navigational and fire control systems. Systems engineers also required for integration of missile system with aircraft fire control systems.

CIRCUIT DESIGN ENGINEERS

Positions available at all levels from recent graduates to engineers with relevant supervisory experience. Electronic circuit design experience required. Should be capable of independent design, and analysis for work in development of circuits for complex radar and missile systems.

SYSTEMS ANALYSIS ENGINEERS

For synthesis and analysis of complex missile guidance and radar systems. Degree in electrical engineering or physics and three or more years experience in servo, feedback control systems, and dynamics required. Familiarity with noise theory desirable.

ELECTRONIC PACKAGING ENGINEERS

For packaging of electronic units of radar and missile systems. EE or ME degree required and three or more years experience in design or packaging.

• MISSILE SYSTEMS DIVISION •

Continued expansion of Raytheon's Missile Systems Division has created long range opportunities for experienced engineers. This Division is engaged in all phases of missile development from study programs through design, development and flight testing to production. Prime contracts for missile systems involve overall responsibility for system design including airframe, guidance, motor and auxiliary equipment. This Division is located 20 miles from Boston, offering a choice of urban or country living, excellent recreational facilities and proximity to Boston's educational and entertainment advantages.

GENERAL INFORMATION

Salary and advancement commensurate with ability. Liberal vacation, sick leave, group life and health insurance and a worthwhile pension system. Tuition support plan for engineering courses. Relocation expenses paid. Write, giving details on experience to G. P. O'Neil. A mutually convenient time for interview will be arranged.

RAYTHEON

MISSILE SYSTEMS DIVISION - BEDFORD, MASS.

ENGINEERS · PHYSICISTS

HERE'S A 'Castle' TO DREAM IN

New 86,000 Sq. Ft. LABORATORY ADDITION

Ideas are born here at the Burroughs Research Center. So many, so fast, that it has been necessary to erect the new 86,000 Sq. Ft. Laboratory Addition pictured above to guarantee an uninterrupted continuity in the planned expansion of our activities for industry and government.



A MAN'S CASTLE . . . consists of even more than his home and family. Yes, it includes even the arena of his professional life — the place where he can best tap the wellsprings of his ingenuity and imagination.

Here at Burroughs new multi-million dollar research facilities we sense completely these sturdy motivations of the engineers of the 20th Century. For nearly 75 years Burroughs has pioneered in the development and design of advanced equipment to aid business, government, science and the military. But, never before have so many arresting challenges been cast before us as in the creation and development of ideas for new machinery to meet the needs of the electronic age.

We take pride in this leadership . . . won't you share it with us?

OUR MAJOR ACTIVITY is presently in the fields of Computers, Solid State Techniques, Data Processing and Transmission, Automation and Process Control, offering truly challenging opportunities for experienced men or recent graduates to work on —

- GUIDED MISSILES
- TRANSISTORS
- TELEMETERING
- ELECTRONIC PACKAGING
- HIGH SPEED MECHANISMS
- MAGNETIC AMPLIFIERS
- DIGITAL & ANALOG COMPUTERS
- PAPER HANDLING DEVICES

. . . And Allied Products

Burroughs CORPORATION

RESEARCH CENTER

PAOLI, PA., ON PHILADELPHIA'S MAIN LINE

ACT NOW!

Write or Telephone To

M. E. JENKINS

For A Personal Interview

SALARIES—At RCA, engineering salaries average measurably higher than those of other companies in the field. Intermediate engineers range from $5000 to $8500, senior engineers from $8500 to $15,000. Staff and supervisory salaries open.

INDIVIDUAL RECOGNITION—RCA organizes engineering activities into groups small enough to allow broadest scope for your individual accomplishment. The average group has just 11 engineers. Yet, in all activities, you are backed by the entire facilities and engineering resources of RCA.

LOCALITIES—At Camden or Moorestown, you enjoy the educational advantages of Greater Philadelphia, with moderate-cost living in pleasant suburban communities. Waltham offers at-home opportunity for New England engineers. Los Angeles, ideal West Coast location. Harrison lies next to Greater New York. Lancaster and Findlay have small-city advantages.

ADVANCEMENT—Regular, objective appraisal of your work speeds your promotion. Professional and financial progress is just as sure as your achievements make it.

PROFESSIONAL STATUS—RCA world leadership in electronics is based on the abilities of exceptional men on every organizational level. Many have widely known engineering and scientific reputations. You work in day-by-day association with these leaders.

BENEFITS—There's a complete program at RCA. A very liberal Tuition Refund Plan. Company-paid life, sickness and accident, hospital-surgical insurance for you and your family. Modern retirement plan. Relocation assistance, suggestion and patent awards.

1955 — OVER 600 EXPERIENCED ENGINEERS AND SCIENTISTS* CHOSE RCA SYSTEMS, DESIGN OR DEVELOPMENT CAREERS

1956 — NEW SYSTEMS, DESIGN AND DEVELOPMENT POSITIONS AT RCA OPEN HIGH-LEVEL OPPORTUNITY FOR YOU!

*Plus hundreds of field service, recent graduates and other engineers.

FIELDS OF ENGINEERING ACTIVITY	MANAGERS	TYPE OF DEGREE AND YEARS OF EXPERIENCE PREFERRED											
		Electrical Engineers			Mechanical Engineers			Physical Science			Chemistry Ceramics Glass Technology Metallurgy		
		1-2	2-3	4-15	1-2	2-3	4-15	1-2	2-3	4-15	1-2	2-3	4-15
SYSTEMS *(Integration of theory, equipments and environment to create and optimize major electronic concepts.)*													
AIRBORNE FIRE CONTROL				W M			M			W M			
DIGITAL DATA HANDLING DEVICES	M C			C			C			C			
MISSILE ELECTRONICS • RADAR	M			M X			M			M			
INERTIAL NAVIGATION	M			M			M			M			
COMMUNICATIONS				C I						C I			
DESIGN • DEVELOPMENT													
KINESCOPES (B & W and COLOR), OSCILLOSCOPES—Electron Optics—Instrumental Analysis—Solid States (Phosphors, High Temperature Phenomena, Photosensitive Materials and Glass to Metal Sealing)		L	L	L	L	L	L	L	L	L	L	L	L
RECEIVING TUBES—Tube Design—Test and Application Engineering—Chemical and Physical Development—Methods and Process Engineering—Advanced Development		H	H	H		H	H		H	H		H	H
SEMI-CONDUCTORS—Transistors—Semi-Conductor Devices—Materials		H	H	H	H	H	H	H	H	H	H	H	H
MICROWAVE TUBES—Tube Development and Manufacture (Traveling Wave—Backward Wave)	H		H	H		H	H		H	H		H	H
GAS, POWER AND PHOTO TUBES—Photosensitive Devices—Glass to Metal Sealing		L	L	L	L	L	L	L	L	L	L	L	L
AVIATION ELECTRONICS—Radar—Computers—Servo Mechanisms—Shock and Vibration—Circuitry—Remote Control—Heat Transfer—Sub-Miniaturization—Automatic Flight—Design for Automation—Transistorization	M C	M C X	M C X	M C X	M C	M C X	M C X	M C X	M C X	M C X			
COMPUTERS—Systems—Advanced Development—Circuitry—Assembly Design—Mechanisms—Programming		C	C X	M C X	C	C X	M C X	C	C	M C			
RADAR—Circuitry—Antenna Design—Servo Systems—Gear Trains—Intricate Mechanisms—Fire Control	M C	M C X	M C X	M C X	M C X	M C X	M C X	M C X	M C X	M C X			
COMMUNICATIONS — Microwave — Aviation — Specialized Military Systems		C	C	C		C	C		C	C			
RADIO SYSTEMS—HF-VHF—Microwave—Propagation Analysis—Telephone, Telegraph Terminal Equipment		I	I	I									
MISSILE ELECTRONICS—Systems Planning and Design—Radar—Fire Control—Shock Problems—Servo Mechanisms	M	M	M	M	M	M	M	M	M	M			
COMPONENTS—Transformers—Coils—TV Deflection Yokes (Color or Monochrome)—Resistors		C	Z C	Z C	C	Z C	Z C	C	C	C		Z	Z
MACHINE DESIGN Mechanical and Electrical—Automatic or Semi-Automatic Machines			L	L		L H	C L H		L	L			

Locations: C—Camden, N.J. H—Harrison N.J. I—International Div L—Lancaster, Pa. M—Moorestown, N.J. W—Waltham, Mass. X—Los Angeles, Calif. Z—Findlay, Ohio

Modern benefits program . . . Liberal relocation assistance.

Please send resume of education and experience, with location preferred, to:

Mr. John R. Weld, Employment Manager
Dept. A-15A, Radio Corporation of America
30 Rockefeller Plaza, New York 20, N. Y.

RADIO CORPORATION of AMERICA

Copyright 1955 Radio Corporation of America

SYLVANIA'S

CALIFORNIA RESEARCH LABORATORY

(San Francisco Bay Area—Near Palo Alto)

Needs experienced creative engineers for a long range research and development program in microwave electronic systems and components. Also needs experts in design and custom packaging of specialized electronic communications equipment.

We have specific openings for ENGINEERING SPECIALISTS and SENIOR ENGINEERS in:

SYSTEMS ANALYSIS For weapons systems planning, operational analysis and data handling problems.

MICROWAVE ANTENNAS For investigation of new concepts in polarization and pattern control, direction finding and multi-function radiators.

MICROWAVE CIRCUITS For advancements in synthesis of filters, broadband mixers, power dividers, etc., involving modern techniques of stripline, ridge guide and periodic structures.

TRANSMITTER DEVELOPMENT For research and development involving microwaves and pulse techniques.

FIELD ENGINEERING For advanced engineering field tests of prototype equipment.

COMMUNICATIONS SYSTEMS For design and development of complex communications systems.

Sylvania offers the finest facilities and equipment available. We also provide financial support for advanced education, as well as a liberal insurance, pension and medical program.

Our Laboratory is located 5 miles from Palo Alto in the San Francisco Bay area, close to excellent schools and universities, unexcelled living conditions, ideal climate and ample housing.

RELOCATION EXPENSES PAID

Please send complete resume to
JOHN C. RICHARDS
Electronic Defense Laboratory
Box 205
Mountain View, California

ELECTRONIC DEFENSE LABORATORY

All inquiries will be answered within two weeks.

SYLVANIA
SYLVANIA ELECTRIC PRODUCTS INC.

ENGINEERS
Honeywell

"First in Controls"

OFFERS EXCELLENT OPPORTUNITIES IN

RESEARCH

. . . including analysis of electronic controls and control systems, using control theory and analog tests. Variety of other applied research activities.

DEVELOPMENT

. . . of electronic and electromechanical devices for detection and control of all types of industrial process variables.

. . . development and design of complex industrial instrumentation systems, data reduction and data handling systems.

. . . development of pneumatic and mechanical devices for flow measurement and control and other small electromechanical controls and recording instruments.

APPLICATION

. . . personal contact with customers, determining exact needs for custom-built devices or systems, determine feasibility of manufacturing special products by estimating engineering time necessary, etc.

Excellent Opportunities FOR MEN WITH

1.—A degree in E.E., M.E. or Physics

2.—From 1 to 7 yrs' experience in instrumentation or similar fields

3.—Group or Project Leader Potential

Send a confidential resume of your qualifications for consideration in the area of your interest.

HONEYWELL
BROWN INSTRUMENTS
Wayne & Windrim Avenues
Philadelphia 44, Pa.

Bendix OFFERS
3 SENIOR ENGINEERING JOBS
WELL WORTH LOOKING INTO...

SYSTEMS PROJECT ENGINEER
6-10 years experience in missile or radar electronic system development. Ability to direct systems engineering at the project level.
Senior Engineer
TEST EQUIPMENT DESIGN
7-10 years experience in development and design of electronic test equipment for complete systems involving microwave and pulse techniques, adaptation of commercial instruments to special applications, preparation of proposals and the actual product design of electronic and electro-mechanical devices. Familiarity with problems of maintenance helpful. Supervisory experience and ability required.
Senior Engineer
MECHANICAL DESIGN
6-10 years experience in missile or aircraft electronic package design. Familiarity with vibration and other environmental problems essential.

Here are three especially attractive job opportunities for engineers who want to get on the ground floor in the important, interesting, and challenging phase of a new industry—guided missiles.

Qualified men are given real job responsibilities with Bendix and grow with the development of what is not only the nation's most important weapon system, but a project that will undoubtedly lead to new and important long-range commercial application.

At Bendix you will be associated with top missile authorities and have at your command unexcelled engineering and manufacturing facilities. Salaries for these top jobs and other opportunities are open for discussion. Write today to: Mr. W. L. Webb, General Manager, Missile Section, Bendix Products Division, Bendix Aviation Corporation, 401 North Bendix Drive, South Bend, Ind.

23 OTHER ENGINEERING POSITIONS!

Bendix also offers unusual job opportunities for assistant engineers, junior engineers, and technicians, as well as a score of other assignments. A 30-page book describing in detail every phase of our guided missile operation will be sent to you on request. If you are interested in guided missiles, this book is bound to interest you. Write for it today.

This is the Evendale Plant, "headquarters" of the Crosley Government Products Division, AVCO Manufacturing Corporation. Located in Evendale, a Northern suburb of Cincinnati, this plant has every facility for long range research and development programs.

ENGINEER REQUIREMENTS
(IN PERCENT)



Engineers...

Our continuing expansion program means that highly creative opportunities are now available to Electronic, Electrical, Aeronautical and Mechanical Engineers, Physicists and Mathematicians. Crosley offers you a chance to achieve individual recognition in a successful growing organization.

Crosley's Engineering Staff is engaged in the design and development of a selected diversity of defense equipments. There are openings at all levels of Research, Advanced Development and Product Engineering for individuals experienced with any of the following: Guided Missiles, Air Navigation, Radar Systems, Communications, Gyros, Magnetic Amplifiers, Servos, Computors, UHF, VHF, Printed Circuitry, Transistors, Circuit Design, Fire Control Systems, Infra-Red Radiation, Detection Nucleonics and Human Engineering.

Address your resume to:

Director of Engineering
Government Products, Dept. F

Crosley DIVISION
AVCO MANUFACTURING CORPORATION
2630 Glendale-Milford Road
EVENDALE, CINCINNATI 15, OHIO

to all electronic engineers

who are tired



of being fenced in

■ THE FIELD OF ELECTRONICS knows no horizon. But many electronic organizations create horizons of their own that tend to curb the efforts of the creative engineer.

There are no such artificial barriers here at Electronic Engineering Company of California. Instead, you will find that every member of our experienced staff of engineers is encouraged to think boldly and is freed from procedural red tape so that he can devote full time to creative engineering.

If you are a qualified electronic engineer who is tired of being hampered by procedural barriers, we of Electronic Engineering Company would like you to join us. The wide variety of electronic projects that form our increasing backlog will give you a chance to exercise your versatility in an atmosphere of enthusiastic cooperation.

you'll find no fences here!

Send a resume of your background to Bob Lander

Electronic Engineering Company
of California
180 SOUTH ALVARADO STREET
LOS ANGELES 57, CALIFORNIA

Engineering | **Design**

Research | **Development**

Scope Unlimited



Engineers seeking a creative future will find in the range of projects underway at Goodyear Aircraft a *versatility* unmatched in scope anywhere else in the aeronautics industry.

As a valued member of the nation's air team, Goodyear Aircraft is delivering vital components to virtually every manufacturer in the industry—electronic equipment, guidance for missiles, booster cases, radar structures, airframe members, cockpit canopies, reinforced structural plastic products for many industries—and is the prime contractor of airships.

Successes in these fields are propelled by the forceful creative thinking which has made Goodyear a great place to work. Whatever your field may be, you'll find opportunity at Goodyear Aircraft.

The scope is unlimited—the ceiling's unlimited. Why not write for an application form, or send a complete resumé to: C. G. Jones, Personnel Department, Goodyear Aircraft Corporation, Akron 15, Ohio. Plants in Akron and Litchfield Park, Arizona.

They're doing big things at

GOODYEAR AIRCRAFT

THE TEAM TO TEAM WITH in AERONAUTICS

HERE'S A CHANCE FOR A REAL CHANGE - - - -

Right Now there are some fine career positions open in the ever expanding electronics industry. Why not write us and weigh the advantages of working with a leader in the field —

Admiral Corporation

Your Opportunity may be listed below if you have background or interest in these fields:

RADAR — MILITARY AND COMMERCIAL

Gun laying, IFF and beacons, navigational aids, air traffic control, video processing and distribution systems.

TELEVISION — MILITARY AND COMMERCIAL

Mobile TV systems, cameras, complete systems including RF front ends, IF amplifiers and RF cavities in the UHF region.

Household TV section requires engineers at all levels who are capable of offering original ideas of values in highly competitive field, monochrome and color.

RADIO — MILITARY AND COMMERCIAL

Airborne and ground communication systems at HF, VHF and UHF level. Domestic and export receivers, HI FI and phonographs.

TRANSISTORS

Development group being augmented to explore all phases of transistor application.

PHYSICISTS

Research in, and analysis of, high level nuclear radiation effects on electronic components. This concerns original investigations at reactor levels.

TECHNICAL WRITERS

To organize, write and edit instruction books, operating and maintenance manuals for electronic equipment. Experience preferred, but will consider qualified trainees.

Admiral engineers know the satisfaction of creative work that gives them the opportunity to explore and expand new techniques in their field.

- *Let's discuss our mutual interests.*

Send complete resume to: **Mr. Walter A. Wecker, Personnel Division**

Admiral Corporation 3800 W. Cortland St. Chicago 47, Illinois

ELECTRONIC ENGINEERS

Research & Development Physicists—Engineers

(SENIORS)

Experienced in research and development of various radar systems including: beacons, missile guidance and counter measures. Advanced training in applied mathematics, noise theory and probability analysis desirable. EE degree or equivalent required.

TECHNICAL WRITERS

DESIGN ENGINEERS

Must have EE degree with 3-5 years experience in one of the following:

— Flight Simulators
— Analog Computers
— Radar & Sonar Trainers
— Radar Guidance & Fire Control Systems
— Redesign, Modification & Testing of Radar & Electronic Systems
— Electronic Installation & Maintenance

*COMMUNICATIONS EQUIPMENT DESIGNERS

— Microwave Components & Circuits
— Signal Generators
— Microwave Test Equipment
— Video Test Equipment

*COMPUTER DESIGNERS

— DC Analog Circuit Design
— Digital & Analog Systems Applications
— Instrumentation & Evaluation

*AERODYNAMICISTS

— Jet Engine Instrumentation
— Flight Instrument Evaluation
— Flight Simulator Systems

(*) Other challenging openings in the fields of: Human Engineering, Psychology, Mathematics, Missile Guidance Systems and Low-Frequency vibration studies.

Salary and advancement commensurate with ability; liberal vacation, sick leave, 9 paid holidays, group life, sickness, accident insurance plans, and a worthwhile pension system.

INTERVIEWS IN YOUR AREA BY APPOINTMENT

STAVID Engineering, Inc.

U.S. Highway 22,
Plainfield, N. J.
Watchung, P.O.
Plainfield 7-1600

An employment advertisement in this EMPLOYMENT OPPORTUNITIES section will help you find the engineers you need. It's an inexpensive, time saving method of selecting competent personnel for every engineering job in the electronic field.

EXPAND YOUR HORIZON!

ELECTRONIC ENGINEERS
ELECTRONIC PHYSICISTS

Bendix Radio has new, exceptional opportunities for advancement while working on:

RADAR
MISSILE GUIDANCE
AIRBORNE COMMUNICATIONS
MOBILE COMMUNICATIONS
AUTO RADIO

Expand the horizon of your future with Bendix Radio—a leader & pioneer in the electronics field, one that has the knowledge, strength and resources to stay out front during the competitive days ahead! Your part is EASY! Wire, phone, write . . . or send us a post card. Simply state your name, address and phone number, your education and experience. We'll carry the ball from there! All replies held in strictest confidence, and we guarantee speedy action!

Address: Mr. L. H. Nogle
Dept. J
Bendix Radio
Baltimore 4, Md.
Phone: VAlley 3-2200

Bendix Radio
DIVISION OF
BENDIX AVIATION
CORPORATION
Baltimore 4, Maryland



Raytheon's new Wayland Laboratory is devoted to the design and development of high quality electronic equipment. It is located in the heart of a delightful rural residential area, yet it is only 17 miles from the center of Boston with all the advantages of a metropolitan area.

Positions are available for

Engineers and Physicists

for the Systems Analysis and Design of Radar, Communications and Countermeasures equipment.

For further details, send your name and address to Mr. E. L. WILLIAMS at:

RAYTHEON MANUFACTURING COMPANY

Wayland Laboratory

Wayland, Massachusetts

* No resume required—we will send you a brief form which can be completed in just a few minutes.

Excellence RAYTHEON *in Electronics*

DEVELOPMENT ENGINEERS

PROJECT
SENIOR
INTERMEDIATE

- Antenna & Microwave Systems & Components
- Pulse & Radar Circuitry
- Telemetering Systems
- Communications
- Navigational Systems

TAKE A STEP TOWARD THE FUTURE WITH . . . . .

the progressive and well established Maryland Electronic Manufacturing Corporation.

We've grown to now number more than 300 employees . . . steady growth, too, with never a layoff. Because MEMCO is an engineering-managed organization we feel that we offer an exceptional atmosphere for personal growth, with real opportunity for your recognition and advancement.

Here's what you will find at MEMCO

—Modern, complete and self-sufficient engineering and production facilities in suburban College Park, Md. 6 miles from Washington, D. C.

—Attractive salaries and profit sharing plan.

—Aid and encouragement in the presentation of technical papers plus the educational opportunities at 4 nearby universities.

—Suburban living with fine schools and housing plus the cultural advantages of the nation's capitol.

—A real challenge for imaginative and energetic engineering talent.

For interview please write Mr. J. E. Richardson

MARYLAND ELECTRONIC

Manufacturing Corporation

5009 Calvert Road

College Park, Maryland



LOW TEMPERATURE



SPIN RESONANCE

ENGINEERS, PHYSICISTS, CHEMISTS

TRANSISTORS

SYSTEMS ENGINEERING



TELEVISION RECEIVER DESIGN

Zenith wants to talk to you about:

- **Solid State Physics**
- **Transistors**
- **Circuits for Color & Monochrome Television and Radio**
- **New Types of Vacuum Tubes**
- **Radio & TV Receiver Design**
- **Subscription TV (Phonevision)**
- **Ceramic Engineering (High Dielectric, Piezoelectric)**
- **Patents**
- **Industrial Engineering (Automation)**

Modern Air-Conditioned Laboratories
Attractive Profit Sharing and Insurance Plans
Outer Chicago Location with Opportunity for Suburban Living and Graduate Study
Non-Classified Work—Publication Encouraged

Since 1919 Zenith has manufactured radios for home use and is one of the country's oldest companies continuously in this field. It is today a leading manufacturer of quality television sets and hearing aids. Continuity of management, a record of pioneer technical developments and a reputation for quality products are important factors for you to consider. Zenith's consistent, steady growth and unusually low engineering turnover rate indicate a desirable combination of opportunity and stability.



ACOUSTICS

For an appointment, write to
G. E. GUSTAFSON
Vice President, Engineering
Zenith Radio Corporation
6001 Dickens Avenue, Chicago 39, Illinois

ZENITH®

RADIO CORPORATION



ENGINEERS

Your Future Lies with a GROWTH Firm in a GROWTH Industry

You can move up fastest and most securely with a firm that grows ...in an industry that grows.

Projected growth of the electronics industry is more than double for the next ten years. Past indications prove that your best chance for a career is with Sylvania...in the past eight years Sylvania has grown 33% faster than the electronics industry of which it is a part.

Join Sylvania now and grow with it.

WALTHAM Engineering

Majors in E.E., M.E., Math, Physics. Research & Development experience in—

- Countermeasures
- Systems Analysis
- Transistor Applications
- Noise Studies
- Antenna Res. & Dev.
- Systems Development
- Mechanical Design
- Miniaturization
- Digital Computer Circuits & Systems
- Circuit Designs
- Shock & Vibration
- Technical Writing
- Missile Analysis

BUFFALO Engineering

Majors in E.E., Math or Physics. Experience in Advanced Development and Product Design

- Information Theory
- Advanced Circuit Design
- VHF-UHF Systems Design & Evaluation
- Logical Circuit Design
- Mathematical Analysis for Numerical Computation
- Pulse Techniques
- Data Processing Devices
- Components & their Applications
- Magnetic Amplifier Techniques
- Servo Techniques & Applications
- Digital Computer Design
- Control Circuits & Devices

Missile Systems Laboratory

- Radar Research & Development
- Missile Guidance & Ground Equipment Analysis
- Systems Evaluation Operations Research

INTERVIEW & RELOCATION EXPENSES WILL BE PAID BY SYLVANIA

Sylvania provides financial support for advanced education as well as liberal insurance, pension and medical programs.

Please forward resume to: Professional Placement Supervisor

Thomas A. Tierney | 100 First Ave. | Waltham, Mass.

Randall A. Kenyon | 175 Great Arrow Ave. | Buffalo 7, N.Y.

Your inquiries will be answered within 2 weeks

SYLVANIA

SYLVANIA ELECTRIC PRODUCTS INC.

APPLIED INFORMATION THEORY SPECIALIST

For Practical Application of Concepts

An unusual opportunity to apply this relatively new specialty to the practical problems encountered in complex electronic systems. At the General Electric Advanced Electronic Center at Cornell University, you'll find a stimulating technical atmosphere.

To qualify, you should have a Ph.D. in EE or Physics, (although an M.S. or B.S. plus experience might be acceptable). You'll need a thorough understanding of the theories involved in random processes, modulation-demodulation, microwave and servo-mechanisms, plus practical experience.

Please address inquiries to:

Dr. Paul Doigan
Advanced Degree Personnel
GE Advanced Electronics Center

GENERAL ELECTRIC

at Cornell University
Ithaca, New York

Executives and Engineers deserving higher salary

now can *completely, confidentially* make arrangements for better positions through our unique Job Improvement Service. We have close contact with leading manufacturing and research firms in all sections of the country.

Here's what you do. Send us your name, title, company and *home address.* We will forward to your home brief forms which you fill out and return. We compare your experience and desires with our file of specific job openings. You make the decision. No obligation to you, no cost whatsoever. Our clients pay us to find you. Find out what you're really worth—today. Write, phone or wire.

DECISION INC.

Management and Recruitment Consultants
Oliver P. Bardes, President
441 First National Bank Building
Cincinnati 2, Ohio

ENGINEERS

Live and work in Florida

RADIATION, Inc. has many outstanding opportunities for qualified electronic, mechanical, nuclear and aeronautical engineers in the fields of electronics, avionics, and instrumentation. Here is your chance to join a dynamic, expanding organization which offers excellent working and living conditions, professional recognition, and extensive employee benefits.



RADIATION, Inc. is a research and development corporation with a leading part in many of today's outstanding advances in electronics . . .

- Aircraft Positioning Development
- Special Weapons Instrumentation
- Solid-State Circuit Development
- Analog-to-Digital Conversion
- Missile Checkout Equipment
- Special Radar Developments
- Aircraft Instrumentation
- Digital Data Recording
- Pulse Code Telemetry
- Low-Level Switching
- FM-FM Telemetry
- Aircraft Guidance

Address your inquiry to:

Ralph L. Bickford
Director of Personnel
Radiation, Inc.
Melbourne, Fla.

Work of the engineering department is accomplished by small flexible groups, each assigned to a specific phase of a project. These groups generally include engineers with both highly specialized and comprehensive backgrounds. Such a system provides freedom, professional growth and recognition for the individual, and encourages initiative. Unusual opportunities are here for the competent engineer to continue his professional career with maximum advantage. Openings presently exist ranging from junior engineer to section head. Salaries and assignments are equably based on experience and background. You are invited to submit your qualifications with the assurance of prompt and careful consideration.

ORLANDO

MELBOURNE

NOTE TO MRS. ENGINEER

Florida has much to offer you and the children: freedom from snow and cold and all the inconveniences that go with it . . . good schools and housing . . . year-round outdoor recreation including lake and ocean beaches, boating, fishing, and picnicking. In short, Florida is a wonderful place to live and you can enjoy it with the additional satisfaction of knowing your husband has a place to work where his ability is recognized and he has unlimited opportunity for growth and advancement. We would be happy to talk it over with you when your husband is interviewed.

RADIATION Inc. Melbourne, Fla. Orlando, Fla.

Electronics • Avionics • Instrumentation

CHALLENGING CAREERS AT RAYTHEON



Measuring the impedance match of a backward wave oscillator, newest member of the Raytheon microwave tube family. Tube shown is an efficient, high power oscillator, electronically tunable over wide frequency range, and insensitive to load conditions.

How to make performance pay

As a result of Raytheon's microwave tube development program, tubes *now in production* include klystrons with wave lengths approaching 0.1 cm and magnetrons with power levels of 5 megawatts. These achievements are typical of the long-range program that has made Raytheon the world's largest manufacturer of magnetrons and klystrons.

When you join Raytheon you work in an atmosphere of progress. Openings now for engineers, scientists in many areas including:

microwave tubes • special purpose tubes • guided missiles
transistors • diodes • receiving tubes • TV receivers • radar
metallurgy • ceramics • communications • cathode ray tubes
sonar • servomechanisms • solid state physics • field engineering

Join a team where performance pays off. Please address inquiries to L. B. Landall, Professional Personnel Section.

RAYTHEON

RAYTHEON MANUFACTURING COMPANY
190 Willow St., Waltham 54, Mass.
Plants also located in California and Illinois

ELECTRICAL AND MECHANICAL ENGINEERS

Motorola Research Laboratories, located in the healthful climate of Arizona's Valley of the Sun, has several openings for engineers experienced in the following:

Electronic circuit design and development for missile guidance, radar and VHF communications.

Mechanical design of missile-borne and vehicular electronic equipment.

Microwave antenna and wave guide design.

Transistor circuit development.

Engineers desired who have B.S. degrees or above and at least two years direct experience. Free health, life and accident insurance. Free hospitalization plan. Profit sharing. Paid holidays. Sick leave, vacations. Ideal working conditions. Plenty of housing, reasonably priced. Excellent schools. Exceptionally mild and dry winter climate.

WRITE:
J. A. Chambers, Manager
Motorola Research Laboratory
3102 North 56th Street
Phoenix, Arizona

ELECTRICAL AND ELECTRONIC ENGINEERS

We have several outstanding opportunities for recent graduates and experienced men in electrical engineering for interesting research and development programs in the following areas:

Computer Development
Radio and Radar
Electronic Instrumentation
Electric Machines, Components, Measurements
Magnetic Recording

These are permanent positions offering attractive salaries and excellent opportunities for tuition-free graduate study. Please write:

Personnel Manager
ARMOUR RESEARCH FOUNDATION
of Illinois Institute of Technology
10 West 35th St.
Chicago 16, Illinois

WHEN *Answering Advertisements*

PLEASE *do not send original letters, certificates or photographs. We cannot be responsible for their return. Please send photostat or carbon copies.* Electronics

ELECTRONIC ENG.
MECHANICAL ENG.

LARGE Company...
Stability &
Security

SMALL Division...
Recognition &
Responsibility

Bendix York offers both!

As a young, expanding Division of Bendix Aviation Corporation, Bendix York is adding key personnel RIGHT NOW! . . . It's your chance to get specific assignments at the peak of the art in electronics and microwave development and design. Good salaries, all employee benefits, ideal suburban living conditions. Openings for Principal, Senior and Junior Electronic Engineers, Mechanical Engineers, designers and draftsmen.

Address: Dept. H

Bendix
AVIATION CORPORATION
York
DIVISION

York, Penna. York 5521

THE UNIVERSITY of MICHIGAN
ENGINEERS and SCIENTISTS

Unusual opportunities for outstanding and experienced men are available at The University of Michigan's Willow Run Laboratories. Research Engineers and Physicists with advanced degrees and/or experience in the fields of:

DIGITAL COMPUTER • LOGICAL DESIGN • INFRARED • ACOUSTICS • DIGITAL COMPUTER PROGRAMMING ELECTROMAGNETIC THEORY • COMMUNICATIONS CIRCUIT DESIGN • COMPONENT DEVELOPMENT • RADAR • OPTICS ENGINEERING • SYSTEMS DESIGN

Salary commensurate with training and experience. Excellent working conditions. Liberal vacation policy along with other fringe benefits. Unusual opportunity to carry on University graduate studies while working full time. Moving expenses paid. U. S. Citizenship required.

Write, giving details of education and experience, to

A. J. Procassini
The University of Michigan
Willow Run Laboratories
Ypsilanti, Michigan

ENGINEERING OPPORTUNITIES *for you!*

CONVAIR-Pomona is engaged in development, engineering and production of electronic equipment and complex weapons systems. The Convair-Pomona engineering facility is one of the newest and best equipped laboratories in the country. The work in progress, backed by Convair's outstanding record of achievement, offers excellent opportunities for recent graduates and experienced engineers in the following fields:

ELECTRONICS
DYNAMICS
AERODYNAMICS
THERMODYNAMICS
OPERATIONS RESEARCH
HYDRAULICS
MECHANICAL DESIGN
LABORATORY TEST ENGINEERING

Generous travel allowance to engineers who are accepted.

*For further information on Convair and its fields of interest, write at once, enclosing a complete resume to:
Employment Department 3-G

*ENGINEERING BROCHURE TO QUALIFIED APPLICANTS

CONVAIR
A DIVISION OF GENERAL DYNAMICS CORPORATION
POMONA, CALIFORNIA

a place where

Creativity

is encouraged and prized



ARMOUR RESEARCH FOUNDATION is one of the nation's largest and most progressive research organizations.

The Foundation was created some twenty years ago to provide research and development services to industry and government. How well it has fulfilled this purpose is reflected in its remarkable growth.

One of the key factors in Armour Research Foundation's success has been engineering and scientific teamwork. Intensive collaboration, utilizing highly skilled and diversified talents, is focused upon a particular problem to reach a solution.

The Foundation has been able to gather together an outstanding staff because—in addition to encouraging and prizing creativity—it has a competitive pay scale, good insurance and pension plans, variety of work, excellent facilities, and opportunities for personal and professional advancement.

These also are the reasons why more and more scientists and engineers are looking to Armour Research Foundation as the place to build their careers. Write to the Personnel Manager if you are interested in openings as:

Aeronautical Engineers
Ceramists
Chemical Engineers
Chemists
Structural Engineers
Design Engineers
Electrical Engineers
Electronic Engineers
Mathematicians
Mechanical Engineers
Metallurgists
Physicists

ARF

ARMOUR RESEARCH FOUNDATION OF ILLINOIS INSTITUTE OF TECHNOLOGY

Room 3048 10 W. 35th Street Technology Center Chicago 16, Ill.

PROJECT ENGINEER

Design and development of mechanical or electro-mechanical mechanisms in the field of ammunition. Projectiles, fuses, training devices, weapons systems. M.E. or Physicist, 5-10 years experience. Advanced degree preferred. Enjoy advantages of Connecticut living.

Reply

Employment Manager

WINCHESTER - WESTERN DIVISION

OLIN MATHIESON CHEMICAL CORPORATION

P.O. Box 906
NEW HAVEN 4, CONN.

To EMPLOYERS who advertise for MEN:

WHEN there are many applicants for a single position it frequently happens that the only letters acknowledged are those of the most promising candidates. Others may not receive any indication that their letters have even been received by a prospective employer much less given consideration. These men often become discouraged, will not respond to future advertisements, and sometimes question their bona fide character.

Every advertisement printed in the Employment Opportunities Section is duly authorized.

It will help to keep our readers interested in this advertising if you will acknowledge every application received, even if you merely return the letters of unsuccessful applicants with, "Position filled, thank you" written or stamped on them.

We suggest this in a spirit of cooperation between employers and the men replying to Positions Vacant advertisements.

★

"Put yourself in the other fellow's place."

★

Classified Advertising Division

McGraw-Hill Publishing Co., Inc.

ENGINEER

MISSILE & WEAPONS CONTROL SYSTEMS STUDIES

Enjoy full use of your skill and imagination, and friendly, professional give and take with top men in the field of electromechanical precision equipment.

You will perform studies related to airborne weapons control and guidance systems with the object of determining requirements, feasibility, performance and specifications of computers and over-all systems.

A degree in physics, ME or EE—or the equivalent in experience—is required. Must be able to handle problems in such diversified fields as: digital computers, digital data transmission systems, logic counting and conversion circuits, high precision gyro and gimbal structures, dynamic behavior of missiles; alignment of inertial platforms for guidance systems, and flight evaluation of guidance systems and instrumentation. Send resume in confidence to:

Technical Personnel Dept. 2-900

ARMA

Division American Bosch Arma Corp.
Roosevelt Field, Garden City
Long Island, N. Y.

COMMUNICATIONS ENGINEERS and TECHNICIANS

EXCELLENT SALARIES
MINIMUM PREREQUISITES

ENGINEER — EE Graduates with 3 years experience
TECHNICIAN — 2 years technical school in communications and 3 years experience.

Require installation adjustment and maintenance experience with communication receivers and associated terminal equipment. Also, men with similar experience with high-powered transmitters, antennas, transmission lines.

Must be willing to travel in United States and Overseas.

Page Communication Engineers, Inc.
710 Fourteenth St., N.W., Washington 5, D.C.

ELECTRONICS

- Research—Design
- Basic Development

FIELD TEST ENGINEERS
ELECTRONIC ENGINEERS

Must be graduate engineers with 4-5 years' experience in radar circuits or allied fields.

This is an outstanding New York engineering firm offering long-range career opportunities, high rates, overtime and out-of-town per diem allowance.

Convenient local interviews will be arranged.

Please send your resume to:
Mr. Donald Pisciotta

DEVENCO, Incorporated
117 Liberty St—New York, N. Y.

Dear wife and kids:

Got here o.k. today. Couldn't wait to tell you what I think of Farnsworth and Fort Wayne. It's more than a place to work .. it's a way of life! Most of the folks here own their own homes. There are no row houses and that cottage in the country is real and only 10 minutes from everywhere.

Schools? There are 50 of them (full time .. no half day shifts!) 5 beautiful High schools and I can take grad work at Purdue here at Farnsworth's expense!

This is also a town of churches ... 132 in a town of 135,000 that boasts one of the lowest juvenile delinquency rates in the country.

There's also a full size, full season symphony orchestra ... World championship basketball and hockey in a new 3 million dollar coliseum that's out of this world. (Are you listening, Jackie?)

Tell Joe and his wife to start packing because there's plenty of room here for more engineers like him in R and D and systems engineering in missiles, radar, antennas, microwaves, test equipment, countermeasures, transistor applications and other phases. Tell him to write the Technical Employment Manager, Farnsworth Electronics Co. (a division of IT&T) at Fort Wayne, Ind. He'll be glad he did.

I can't wait until you and the kids get here ... I know you'll love it. And, like they say at Farnsworth, "Very, very few ever leave it."

Love Jack

What Opportunities in Electronics are on the Horizon at GENERAL ELECTRIC?

Huge antenna used with new radar height-finder needs a room all its own above the control center in the radome building erected in Arctic climates. Air pressure supports the rubberized glass fabric radome "balloon." Entrance to the radome is through an air lock chamber.

Advances in electronics are so rapid at General Electric that today's predictions appear tomorrow as equipment bearing the GE symbol.

The opportunities created by the scope and pace of the field are increased at General Electric by the facilities and range of professional advantages which GE engineers enjoy.

This means that GE electronics engineers have incentives, satisfactions and rewards that lead to accelerated personal development and advancement in the company.

ENGINEERS • PHYSICISTS

Positions available in the following fields:

Advanced Development, Design, Field Service and Technical Writing in connection with:

MILITARY RADIO & RADAR • MULTIFLEX MICROWAVE MOBILE COMMUNICATION • SEMICONDUCTORS • ELECTRONIC COMPONENTS • TELEVISION, TUBES & ANTENNAS

Bachelor's or advanced degree in Electrical or Mechanical Engineering, physics, and experience in electronics industry necessary.

Please send resume to:
Dept. 1-6-E — Technical Personnel

GENERAL ELECTRIC

ELECTRONICS PARK, SYRACUSE, N. Y.

FIELD ENGINEERING WITH RAYTHEON

CAN YOU QUALIFY?

Raytheon needs qualified men who are interested in an extraordinary electronics future. Field experience has enabled many of our former field engineers to become executives at Raytheon. A real opportunity exists now for men who are interested in the following programs:

MISSILES	Air-to-Air — Ground-to-Air
RADARS	Search — Fire Control — Bombing — Countermeasures
Other Equipment	Ship and Airborne Sonar — Multiplexers Microwave Relay Links — Communications.

Raytheon Manufacturing Company has designed and built complicated electronics equipment for the past 30 years. One of the equipments presently being manufactured is the world's most publicized radar—The DEW LINE RADAR.

We prefer men with college degrees. However, if you have an extensive electronics background we will be glad to consider your application.

Attractive salaries, benefits, and allowances. Domestic and overseas assignments.

RAYTHEON

Excellence in Electronics

RAYTHEON MANUFACTURING COMPANY
Government Service Department
100 River Street — Waltham 54, Massachusetts

ENGINEERS

The APPLIED PHYSICS LABORATORY of THE JOHNS HOPKINS UNIVERSITY offers an exceptional opportunity for professional advancement in a well-established Laboratory with a reputation for the encouragement of individual responsibility and self-direction.

Our program of

GUIDED MISSILE RESEARCH and DEVELOPMENT

provides such an opportunity for men qualified in

- Design and Analysis of Pulse Circuits
- Research and Development in Radar and Microwaves
- Electronic Packaging
- Development of Telemetering, Data Processing, and Special Switching Equipment
- Magnetic Amplifier Design & Analysis
- Development and Application of Printed Circuits
- Servomechanisms and Control-System Analysis

Please send your resume to
Professional Staff Appointments

APPLIED PHYSICS LABORATORY
THE JOHNS HOPKINS UNIVERSITY
8609 Georgia Avenue
Silver Spring, Maryland

ENGINEER, M.E.

ADVANCED DESIGN, RADAR ANTENNAS

A chance to use the latest techniques and methods in lightweight construction. You will direct new work in the field and can make original contributions in structural design and stress analysis involving advanced design.

Experience in radar antenna design plus additional study a "must." Training and experience should indicate ability to undertake leadership in study, application and use of latest techniques and methods.

Especially attractive working location in Berkshire mountains of Massachusetts plus advantages of proper atmosphere planned to assist creative thinking. Extensive company-paid benefit plans. Excellent salary commensurate with ability.

SEND REPLY TO:

P-8599, Electronics
330 W. 42 St., New York 36, N. Y.

RECEIVER ENGINEERS
TRANSISTOR CIRCUIT ENGINEERS
SUBMINIATURE EQUIPMENT ENGINEERS

Career Opportunities With Well Established Central Connecticut Firm

Challenging Projects
Top Salaries
Suburban Living

Replies Held in Strict Confidence
Wire or Phone Collect
Personnel Mgr. SHerwood 7-2741

THE ALLEN D. CARDWELL ELECTRONICS PRODUCTIONS CORPORATION
Plainville, Connecticut

JET PROPULSION LABORATORY
of the
CALIFORNIA INSTITUTE OF TECHNOLOGY
Pasadena, California

Excellent opportunities exist for professional growth in research atmosphere for Engineers and Physicists of all grades. Facilities and equipment are superior.

Airmail your summary of qualifications to:

CALTECH
JET PROPULSION LABORATORY
4800 Oak Grove Drive
Pasadena, California

TO THE FINE ENGINEERING MIND
SEEKING THE CHALLENGING PROJECTS IN



ELECTRONICS

ELECTRONICS ENGINEERS are urgently needed to fill top career openings at Convair in beautiful San Diego, California. Qualifications include experience in missile guidance systems, microwave techniques, digital computers, servomechanisms, test equipment design, circuit analysis, transistor and magnetic amplifier circuit design, and electronic reliability. Antenna engineers also needed for airborne antenna research and development projects.

CONVAIR offers you an imaginative, explorative, energetic engineering department... truly the "engineer's" engineering department to challenge your mind, your skills, your abilities in solving the complex problems of vital, new, long-range programs. You will find salaries, facilities, engineering policies, educational opportunities and personal advantages excellent.

Generous travel allowances to engineers who are accepted. Write at once enclosing full resume to:

H. T. BROOKS, ENGINEERING PERSONNEL, DEPT. 913

CONVAIR

A Division of General Dynamics Corporation
3302 PACIFIC HIGHWAY SAN DIEGO, CALIFORNIA

SMOG-FREE SAN DIEGO, lovely, sunny city on the coast of Southern California, offers you and your family a wonderful, new way of life... a way of life judged by most as the Nation's finest for climate, natural beauty and easy (indoor-outdoor) living. Housing is plentiful and reasonable.

ENGINEERS
DESIGNERS
TECHNICIANS

Investigate Opportunities at

ERCO DIVISION
OF ACF INDUSTRIES INC.

ERCO Engineers have built a record of continuous progress and growth for themselves and for the Company for a quarter of a century . . . growth in physical plant, personnel, number and diversity of products and services.

Today this growth continues and we are constantly on the alert for new men to add fresh impetus to that progress . . . paying top salaries to capable people.

Your work will be interesting and stimulating . . . it might include electronic flight simulators, machine tools, guided missiles, or a variety of specialized electronic devices.

You can choose a home from a number of fine nearby residential areas convenient to both shopping centers and plant . . . and you can further your education at the many nearby Universities . . . you can enjoy suburban living and be within easy reach of the cultural advantages of the Nation's Capital.

ERCO now needs Electronic Engineers (all levels with some overseas positions available). Aerodynamicists, Analog Computer Engineers, Mechanical Design Engineers, and supporting personnel. Send resume or request for additional information to:

ERCO DIVISION
OF ACF INDUSTRIES
RIVERDALE • MARYLAND

ENGINEER, ME or EE

GYROSCOPICS

Research facilities that enable you to test out your most revolutionary ideas and encouragement to publish original work available to the engineer experienced in precision gyroscopic equipment.

Assignments in the field of missile guidance systems will include both mechanical and electrical problems involving lubrication, temperature control, bearings, vibration and shock mounts, development work in components such as pickups, accelerometers, amplifiers and computers, plus project work on complete gyroscopic systems.

ME, EE or equivalent experience required. Send resume in confidence to:

Technical Personnel Dept. 2-500

ARMA
Div. American Bosch Arma Corp.
Roosevelt Field, Garden City
Long Island, N. Y.

ELECTRICAL ENGINEERS

To work on engineering problems in development of new Regulated AC and DC supplies, transistors, semi-conductor circuitry and magnetic amplifiers. BEE, or BS with physics or math major, plus some allied experience.

SORENSEN & COMPANY, INC.
375 Fairfield Avenue Stamford, Conn.

SENIOR ELECTRONICS ENGINEER

needed for new contracts section of rapidly expanding military engineering department

NATURE OF WORK

- System Analysis and Study
- Preparation of Technical Proposals
- Long Range Planning
- Evaluation of Engineering Problems at Early Stages

REQUIREMENTS

- High Degree of Technical Skill and Imagination
- Ability to Organize and Compose Complex Technical Documents
- Friendly and Personable — Must Deal Extensively with Stromberg-Carlson and Military Engineering Personnel

Stromberg-Carlson has recently become a Division of the General Dynamics Corporation and is located in the Finger Lakes region of upstate New York. Excellent educational, living, and recreational facilities are available in this area. Please send resume to

Charles W. Finnigan, Chief Electronics Engineer

STROMBERG-CARLSON COMPANY
A DIVISION OF GENERAL DYNAMICS CORPORATION
Rochester 3, New York

ELECTRONICS FIELD ENGINEER

We require a man with considerable experience in the installation and maintenance of electronic business machines, plus the potential for possible supervisory duties. EE degree or equivalent experience is required. This is a permanent position with a well established progressive company offering a good starting salary, periodic merit reviews and liberal employee benefits.

All replies confidential

Send resume to

Employment Manager
FARRINGTON MFG. CO.
INDUSTRIAL CENTER
NEEDHAM HGHTS., MASS.

ELECTRICAL ENGINEER

Opportunity for young engineer in research and development department of expanding transformer manufacturing company. Experience in transformer design helpful but not necessary. Contact:

Personnel Department
NEW YORK TRANSFORMER CO.
3rd Ave. Alpha, N. J.

ELECTRONIC ENGINEERS

What Should an EE Know About Atomics?



Quite a bit these days, with so many companies getting into the field. While many new firms are now starting to explore the field, Electric Boat Division of General Dynamics Corporation led the way with the building of the first nuclear powered submarines, Nautilus and Sea Wolf.

In addition to increasing its engineering force for work on new and greatly advanced nuclear submarines, Electric Boat is expanding Research and Development operations to include the development of additional practical uses for nuclear energy.

Right now Electric Boat has interesting positions for EE's versed in servo-mechanisms, circuitry, motors and generators, radar & sonar, or electro-mechanical systems.

Study for bachelor's or advanced degrees is encouraged at Electric Boat, with courses in mathematics, naval architecture, nuclear engineering and nuclear submarine systems offered within the plant, and tuition paid by the company for study in these or other fields at leading colleges and universities.

Men interested in these openings should write complete details of background and experience including initial salary requirements. Interviews will be arranged promptly for qualified applicants. Address Mr. Peter Carpenter.

Electric Boat Division
GENERAL DYNAMICS CORPORATION
GROTON — **CONNECTICUT**
near New London on the Connecticut shore

TECHNICAL REPRESENTATIVES

LEAR, INC. is expanding its top notch Field Service organization to keep pace with increasingly widespread military acceptance of LEAR flight control systems and flight reference systems.

Attractive salary, liberal expense arrangements. Assignments may require travel or residence at assigned stations. Company orientation prior to assignment.

Qualifications include:

1. E. E. Degree of equivalent.
2. Knowledge of servomechanisms, gyros, electronics.
3. Tech. Rep. experience.
4. Must Be U. S. Citizen

To Apply, send resume to:
Field Service Manager

LEAR, INC.
110 Ionia Ave., N. W.
Grand Rapids 2, Mich.

For a BETTER JOB in ENGINEERING The Swing's to AMF

CHIEF RF ENGINEER

To design or supervise the design of Radio Frequency components for radar, radio equipment, antennas, horns, mixers, directional couplers, rotating joints and radomes. Must know cost estimating of this equipment and be able to advise shops on the best fabrication methods. Should be capable of setting up RF section. Approximately 10 years experience in design of RF components and systems.

SYSTEMS SPECIALIST

For the analysis of electronic system performance and establishment of design parameters for electronic systems. Must be able to prepare or supervise the preparation of technical proposals and act in the capacity of technical advisor on engineering program. Approximately 10 years experience in general electronic design work.

MECHANICAL ENGINEERS

Product Design, Production liaison on electronic packaging and mechanisms. Involves gear trains, printed circuits and electronic layout work. Knowledge of military specifications. Minimum 6 years experience in electronic equipment design and manufacture.

ELECTRONIC ENGINEERS

Experienced in Product Design and Production. Production liaison requires wide knowledge of electronic circuits and packaging. System and Component Testing. Some experience in cost estimating and project administration. Familiarity with all types of military specifications.

And remember that AMF is well-known for its liberal benefits program.

Please send complete resume to:
Personnel Manager, Electronics Division

American Machine & Foundry Co.
1085 Commonwealth Ave — Boston, Mass.

ENGINEERS
New Opportunities with Republic Aviation

Antenna Engineer

To conduct pattern studies, design prototype antennas and supervise flight tests of new antenna installations. College graduate in Physics, Math or E.E.

Electronic Instrumentation Engineer

Three to five years aircraft instrumentation experience required. Knowledge of transducers, amplifiers and recording equipment used in experimental research testing of hi-speed jet aircraft is essential. Knowledge of servo loop theory as applied to aircraft systems coupled with ability to properly instrument, record and analyze is desirable. Graduates with E.E. degree preferred.

Mechanical Systems Analysis

Senior Mechanical Engineer to study mechanical-pneumatic-hydraulic systems including analysis of systems, development of system equations, programming of equations on an electronic analog computer, planning and coordination of necessary physical tests and analysis of results. Prime requisites are strong basic understanding of mechanics and thermodynamics and the maturity to see difficult job through to completion. This work is completely new, challenging, and rewarding.

Controls Systems Engineer —Autopilots

Staff position available for qualified Aeronautical or Electrical Engineer with heavy experience in the design and installation of automatic flight control systems. Servo-mechanism background is essential while flight test experience is desirable. Must be capable of evaluating automatic control systems and monitoring design by outside vendors.

REPUBLIC'S NEW 2-FOLD RETIREMENT PLAN

PART 1. A basic Retirement Income paid IN FULL by Republic. PART 2. Optional. Engineer makes small monthly payment; company MORE THAN MATCHES contribution. WHAT IT MEANS: Example: engineer starting Jan. 1, 1956 averaging $8,000 a year for 15 years, then retiring at 65, receives $225.80 per month, including Social Security, (HE WILL HAVE PAID IN ONLY $8.50 per month.) OTHER REPUBLIC BENEFITS: All-Expense Paid Relocation Plan for engineers living outside New York and Long Island. Company-paid Life, Health & Accident insurance. Grants covering 2/3 cost of collegiate and graduate study.

Please send complete resume, including details of your technical background, to:

ASST. CHIEF ENGINEER — *Administration*
MR. R. L. BORTNER

REPUBLIC AVIATION
FARMINGDALE, LONG ISLAND, NEW YORK

ELECTRICAL OR ELECTRONICS ENGINEER

0-5 years experience plus degree, creative ability in automatic controls work. We offer singular opportunity to acquire breadth and scope of electronics-electrical instrumentation experience in a Massachusetts chemical plant in midst of multi-million dollar expansion program. Please send resume and salary requirements to

P-8493, Electronics
330 W. 42 St., New York 36, N. Y.

ELECTRONICS ENGINEER
DESIGNING ENGINEER
AIRCRAFT SERVOS AND CONTROLS

Opportunity for experienced men with ability and initiative to assume responsibilities in development, design and application. Permanent positions not dependent upon gov't contract. Established manufacturer with excellent reputation. Attractive benefits and living conditions.

Replies confidential.

Personnel Department
THE BRISTOL COMPANY
WATERBURY, CONNECTICUT

ENGINEERS
PHYSICISTS

You are needed for development staff positions in our rapidly expanding electronic control division.

This is challenging work on a wide variety of small electro-mechanical control devices, servo-mechanisms, transducers, magnetic amplifiers, computers, transistors and electronic circuitry.

We are looking for outstanding young engineering graduates with 5 to 10 years' experience in one or more of the above fields.

Why not contact us for further information regarding the unusual opportunity we have for you? Please send resume to Mr. Charles Swartwout.

Swartwout Co.
18511 Euclid Ave.
Cleveland 12, O.

DESIGN ENGINEER
TRANSFORMERS

Unusual Opportunity in Western N. Y. State. Must have experience in the Design of Audio Power, Pulse & Toroidal Transformers for use in commercial & government applications. Please send resume to

P-8651, Electronics
330 W. 42 St., N. Y. 36, N. Y.

THE MARINE LABORATORY
of
UNIVERSITY OF MIAMI
is seeking
ELECTRONICS ENGINEERS

for design of Radar Components, supervision of Radar Maintenance, or, research in underwater sound.

DIRECTOR, The Marine Laboratory,
Coral Gables, Florida

ENGINEERS and DESIGNERS NEEDED

for: MISSILE GUIDANCE SYSTEMS · BOMBING NAVIGATIONAL COMPUTER SYSTEMS · NEW CIVIL AVIATION PRODUCTS · JET AND TURBO-PROP ENGINE CONTROLS · AIRBORNE FIRE CONTROLS



GM CAREER OPPORTUNITIES IN

- Systems Engineering and Analysis
- Experimental Engineering
- Development Engineering
- Project Coordination
- Design Engineering
- Product Engineering
- Product Evaluation
- Field Engineering

AND WE ALSO NEED:

DESIGNERS • CHECKERS • LAYOUT MEN

Positions Are Permanent — Excellent Advancement Opportunities

Every inquiry treated confidentially and given immediate attention and personal reply.

WRITE TODAY FOR EMPLOYMENT APPLICATION

Mr. John F. Heffinger
Supervisor of Salaried Personnel

AC SPARK PLUG DIVISION
THE ELECTRONICS DIVISION

GENERAL MOTORS CORPORATION

Milwaukee 2, Wisconsin

Sales Manager

$30,000

HIGH PRECISION MACHINERY AND CONTROLS

Nationally known manufacturer, a recognized leader in the field, offers an exceptional opportunity for an experienced sales manager capable of directing a well-trained sales organization . . . as well as assuming responsibility for advertising, sales promotion and all other phases of marketing.

Sales are direct to industrial users.

- **The right man should have successful sales management experience with such products as: ELECTRIC MOTORS—MACHINE TOOLS—CONTROLS — TURBINES — COMPRESSORS . . . (or similar equipment)**
- **Preferred age 38 to 50 years.**

Excellent bonus, insurance and retirement program in addition to salary stated above.

Your reply will be treated in complete confidence and should include age, present connection and home telephone number.

P-8548, Electronics
330 W. 42 St., New York 36, N. Y.

TRANSFORMERS • AUDIO AMPLIFIERS • LOUDSPEAKERS • TAPE RECORDERS • ELECTRONIC CARILLONS • INTERCOMMUNICATION SYSTEMS • MICROWAVE • AUTO RADIO •

AUDIO • ACOUSTICAL • MICROWAVE ENGINEERS

If you are a graduate EE, there may be an exceptional career opportunity for you with the Stromberg-Carlson Company.

Here's a highly respected firm—one of the fastest growing in the fabulous electronics industry, and a member of the headline-making General Dynamics family.

If you're experienced in research, design or development of communications and sound equipment, your next big step up may be into a well-salaried position with this fast-stepping pioneer. Positions are now available in:

- Transformers
- Audio Amplifiers
- Loudspeakers
- Electronic Carillons
- Tape Recorders
- Intercommunication Systems
- Microwave
- Auto Radio

Stromberg-Carlson, at Rochester, N. Y., is in the heart of the lovely Finger Lakes region. This medium-sized progressive city offers unusual recreational and educational facilities, and fine residential areas within a mile of the plant.

With its varied product line (divided almost equally between civilian and military) and its 61 years of prominence in the field of communications, Stromberg-Carlson offers you stability along with a chance to grow. For further details, write immediately to:

CHIEF ENGINEER, SPECIAL PRODUCTS DIVISION

STROMBERG-CARLSON COMPANY

A DIVISION OF GENERAL DYNAMICS CORPORATION

ROCHESTER 3, N. Y.

ELECTRONIC CARILLONS • INTERCOMMUNICATION SYSTEMS • MICROWAVE • AUTO RADIO • TRANSFORMERS • AUDIO AMPLIFIERS • LOUDSPEAKERS • TAPE RECORDERS •

permanent assignments in the field of

MILITARY WEAPONS SYSTEMS

Missiles Reliability Studies Fire Control
Radar Sonar Underwater Ordnance

REAL CAREER OPPORTUNITIES

You'll enjoy the advantages of a small company atmosphere in the Silver Spring Laboratory . . . along with the stability of being part of the rapidly growing Vitro Corporation of America with 5 diversified operations throughout the United States

- Suburban Location in residential community adjacent to Washington, D. C.
- Plentiful housing — modern apartments, houses to rent or buy
- Advanced courses available at 4 major universities
- Cultural advantages of the nation's capitol

Vitro has similar opportunities also available at West Orange, N. J. laboratory and Eglin Air Force Base, Florida.

Systems Engineers
Applied Physicists

Write to Personnel Manager

Vitro

VITRO LABORATORIES
962 WAYNE AVE., SILVER SPRING, MD.

Electronic Engineer-Physicist With Applications Experience

This engineer will have a reputation as an "idea" man, but be completely familiar with the sciences concerned. He will have, most likely, a master's degree or better in the electronic field. His bachelor's degree will have been in either the electrical engineering or physics disciplines. His experience will have included electro-mechanical mechanism design, and he will have extensive experience in instrumentation.

The position to be filled is a new one. A manufacturing firm of the highest order of national standing in the food, drug, chemical and allied fields, and possessing one of the finest and newest plants in those fields, is creating the position of Automation Engineer. The incumbent will have the opportunity of advancing their use of instrumentation and automation, both in production, quality control and research. The application of instrumentation will be limited only by feasibility. All means to achieve better control, greater production, better product, and readier application of product research results, as well as ways to better effect research, are to be explored, with those offering opportunity of success applied.

At least in the beginning this man will act as a "one-man" department, although reporting to the operating management. This in no way will reflect upon his starting salary, which is to be commensurate with his promise. This man will be a person, however, who has a price tag, at least, in the lower five figure range, and shows proof of his worth at that figure. He will be in his thirties, have shown progressive advancement in his field, with heaviest emphasis on demonstrated technical achievements, though not without a good record of relations to subordinates and management. He will be a man who is looking for a permanent position, but one which will have continuing challenges in creative projects, many of which could prove vital in the progress of his company. Hence, he must have reached an age where he has become confident in himself.

All communications will be kept confidential. Applicants, to be considered, will include the usual personal information, complete particulars on education (including transcripts, if available), and a detailed record of employment. At least one instance of creative application of electronic sciences must be cited in detail. (If patented, the patent number should be included.) Also, the project the applicant has greatest pride in (including reasons for this) should be briefly discussed.

The location of this position is a seaboard, mid-Atlantic state city. The plant involved produces products in excess of $50,000,000 sales annually.

P8554 Electronics
330 West 42nd Street, New York 36, N. Y.

PERSONNEL MANAGERS

LOOKING FOR ENGINEERS . . . TECHNICIANS?

Write for free copy of

"RESERVOIR OF ENGINEERS AND TECHNICAL MEN"

The engineers and technicians you want to reach are gathered in convenient, compact groups—as this 12-page booklet points out.

It keys the job titles these men hold to the McGraw-Hill publications they read for on-the-job information. It explains how you can make contact . . . channel, concentrate your employment advertising to just the men with the job qualifications you want.

Write for your free copy to

ELECTRONICS
Classified Advertising Division
330 W. 42nd St., N. Y. 36, N. Y.



COMMON BASE CHARACTERISTICS VS. EMITTER CURRENT

Choose your future at TI!

ENGINEERS / PHYSICISTS

TEXAS INSTRUMENTS offers exceptional career opportunities in its expanding research, development and design programs. These are permanent positions that offer excellent opportunities with a progressive, expanding company. If you have a B.S., M.S., or Ph.D. in Electrical or Mechanical Engineering or Physics you should investigate the interesting, challenging and rewarding research or development positions now open at TI.

At TI you will enjoy the long-range stability of a 25-year-old leader in the electronics industry and many employee benefits . . . profit sharing, insurance, retirement plans, etc.

For interview appointment phone or write our Personnel Director.

TWENTY-FIFTH YEAR OF PLANNED GROWTH

TEXAS INSTRUMENTS
INCORPORATED
6000 LEMMON AVENUE DALLAS 9, TEXAS

ENGINEER
M. E. or E. E.
DIGITAL COMPUTER DEVELOPMENT

Excellent opportunity to join an expanding, stable company, with an outstanding position in the precision electronic control industry.

Opening now available for an engineer able to assume responsibility for the development of complete systems for fire control and guidance, or major portions of such systems. Work will include research and development in the field of complex analog or digital computers.

A degree in electrical or mechanical engineering is required or the equivalent in experience. Send resume in confidence to:

Technical Personnel Dept. 2-599

ARMA
Division American Bosch Arma Corp.
Roosevelt Field, Garden City
Long Island, N. Y.

PROGRESSIVE L. I. FIRM
needs ELECTRONIC ENGINEERS
Opportunity for self-expression and growth. Must have 2-6 yrs. exp. in the design of IF, VHF and/or UHF broad band systems. Many personal benefits. Phone or write Mr. G. W. Fellendorf, Vice Pres.
Instruments for Industry, Inc.
Mineola, N. Y. Pioneer 2-5300

Immediate Openings at KOLLSMAN

SYSTEMS ENGINEERS . . . For development, testing and field service of airborne navigational systems. Some experience with servos utilising electronic and electro-mechanical components desirable.

ELECTRICAL ENGINEER . . . Experience in small electro-mechanical devices, motors, synchros and induction pick-offs.

DESIGNERS
Electronic, Electro-Mechanical, Mechanical

1. Electronic and electrical packaging. Knowledge of sub-miniaturized techniques. Work is associated with servos, amplifiers and components.

2. Mechanical or electro-mechanical packaging of precision flight instruments.

These are permanent positions with Kollsman, designers of America's finest aircraft instruments . . . a progressive, growing organization in which the atmosphere is friendly, the facilities of the best, and the employee benefit program liberal.

Please submit complete resumes, preliminary to confidential interview to Thomas A. DeLuca.

kollsman INSTRUMENT CORPORATION
80-08 45th AVENUE, ELMHURST, NEW YORK • SUBSIDIARY OF Standard COIL PRODUCTS CO. INC.

ENGINEERING POSITIONS AVAILABLE AT STROMBERG-CARLSON

Stromberg-Carlson, a Division of General Dynamics Corporation, is located in the Finger Lakes region of upstate New York. In addition to providing a wide variety of challenging engineering opportunities, excellent salaries are offered with the finest working conditions in a modern electronics laboratory. Unusual recreational and educational facilities are available in this medium-sized progressive city, and fine residential areas are located within a mile of the plant. Because of the variety of its product line, which is approximately equally divided between military and civilian, Stromberg-Carlson offers a degree of stability and an opportunity for advancement unequalled in the industry.

OPENINGS IN THE FIELD OF:

Communications
Infrared
Digital Techniques
Microwave Circuits
Mechanical Design Engineering
Countermeasures
Data Systems
Radar
Transistor Applications
Navigational Systems

For further information please write or call—

Mr. C. W. Finnigan, *Chief Electronics Engineer*

S-C

STROMBERG-CARLSON COMPANY

A DIVISION OF GENERAL DYNAMICS CORPORATION

Rochester 3, New York

UNUSUAL CREATIVE FREEDOM at Bendix AVIATION RESEARCH LABORATORIES DIV.

● The center of advanced development activities for the Bendix Aviation Corporation offering excellent opportunities in design, research and development.

SYSTEMS ENGINEERS

To coordinate and supervise a group of engineers and mathematicians in systems analysis and design.

MATHEMATICIANS

Evaluation of servo control and guidance systems and components of a system Analysis of systems and applications.

MACHINE DESIGNERS

Design of automatic machine tools, machine tool hydraulic servos, and digitally controlled tools.

CONTROLS ENGINEERS

Analyse and synthesize control system and design, develop and package such systems.

COMPUTER ENGINEERS

Development of special purpose digital and analog computers for process and business applications.

MICROWAVE SPECIALISTS

Research and development in advanced microwave techniques.

MECHANICAL ENGINEERS

Develop mechanical and hydraulic components for servo controls. Systems engineering and dynamic analysis of numerically controlled machine tools.

● Staff will participate in the initial exploration of new fields and the development of new commercial products.

All replies confidential—
send brief resume to:

DIRECTOR OF PERSONNEL
BENDIX AVIATION CORPORATION
RESEARCH LABORATORIES DIVISION
4855 Fourth Avenue • Detroit 1, Mich.

ENGINEER
EE

Have you a "feel" for equipment — and a touch of wanderlust?

Inquire
About

FIELD SERVICE

It's not enough to understand the theory, in *field service*. You must have a natural "feel" for complex equipment, a sort of practical second sight.

If you're this kind of practical engineer, with 1 to 3 years experience in electrical or electronic engineering—preferably with servo-mechanisms and radar—there is an opening that will appeal to you as a Field Supervisor.

You'll be the Company's technical representative at airframe plants or at Air Force bases (HERE or ABROAD)—on complicated electronic mechanical devices.

You'll assist in the solution of technical difficulties, provide engineering advice and assistance on service tests, aid in training and advising Air Force personnel in matters of use, support and maintenance of our electronic systems.

You'll get a good salary, expense allowance, and all notable employee benefits. And a chance for advancement to administrative and responsible positions within our extensive field engineering and product engineering organizations.

Please send resume to

P-8680, Electronics
330 W. 42 St., New York 36, N. Y.

REPRESENTATIVES WANTED
ALL TERRITORIES

Sales organizations or individuals geared to sell laboratory grade test equipments to electronic, aircraft, and industrial concerns.
Several equipments are described on page 654 of the Electronics Buyers Guide.

DUBROW DEVELOPMENT CO.
Burlington, New Jersey

PART TIME SALESMAN

Salesman handling electronic supplies to sell plastics to the electronic industry; including casting resins, coating compounds, foams, adhesives, rods and sheets. Give details on present line and territory.

SW-8665, Electronics
330 W. 42nd St., New York 36, N. Y.

REPRESENTATIVE WANTED

Manufacturer of paper condensers, cardboard and ceramic encased, requires salesman, exclusive territory.

Philadelphia and Chicago area.

RW-8686, Electronics
330 W. 42 St., New York 36, N. Y.

When Answering
BOX NUMBERS . . .

to expedite the handling of your correspondence and avoid confusion, please do not address a single reply to more than one individual box number. Be sure to address separate replies for each advertisement.

TECHNICAL OPERATIONS, INC.

INVITES INQUIRIES FROM ELECTRONIC ENGINEERS INTERESTED IN JOINING A MODERATE SIZED RESEARCH AND DEVELOPMENT ORGANIZATION OPERATED BY SCIENTISTS FOR SCIENTISTS.

IF YOU ARE INTERESTED IN A FUTURE LIMITED ONLY BY YOUR OWN ABILITY, PLEASE CONTACT

Robert Smyth
Technical Operations, Inc.

6 Schouler Court
Arlington 74, Mass.

CORNELL AERONAUTICAL LABORATORY, INC.
of Cornell University
is seeking
ELECTRONIC ENGINEERS

for positions in all levels of experience above Junior Engineer

Communications
Dynamic Control Systems
Aircraft Instrumentation
Radar
Computers
Electrical Measurements
Varied Electronic Circuits
Servo-Mechanisms
Missile Guidance
Microwave

If you have a B.S. degree and experience, imagination and potential, we invite you to communicate with our Employment Manager

Cornell Aeronautical Laboratory
BOX 235 BUFFALO 21, N. Y.

ENGINEERS
Electronic *Mechanical*

There's room to... GROW AT MELPAR

Currently we seek men with experience in one or more of the following:

- Network Theory
- Systems Evaluations
- Microwave Technique
- UHF, VHF, or SHF Receivers
- Analog Computers
- Magnetic Tape Handling
- Digital Computers
- Radar and Countermeasures
- Packaging Electronic Equipment
- Pulse Circuitry
- Microwave Filters
- Flight Simulators
- Servomechanisms
- Subminiaturization
- Electro-Mechanical Design
- Small Mechanisms
- Quality Control and Test Engineers

More and more these days you hear top engineers talk about the many growth opportunities at Melpar. With an increasing number of significant electronic projects, an enlarged staff and facilities, Melpar provides many opportunities for professional growth and advancement. Our new laboratory is an engineer's dream come true; a building conceived by and constructed for the ENGINEER – 265,000 sq. ft. of complete engineering facilities.

We are located in Fairfax County of northern Virginia where housing is reasonable and plentiful—whether you desire a private home or an apartment. Although we are in a truly suburban atmosphere, we are only 10 miles from the nation's capital with all its recreational and social advantages. Here you and your family can grow in an environment to match your professional growth.

Send resume to Technical Personnel Representative,

melpar, inc.
A subsidiary of the Westinghouse Air Brake Co.
3000 Arlington Blvd., Dept. E-25 Falls Church, Va.
11 Galen Street, Watertown, Mass. • 99 First St., Cambridge, Mass.

Excellence **RAYTHEON** in Electronics

SENIOR ANTENNA DESIGNER

Position with technical and managerial responsibility in the design of antennas for the UHF through the microwave region. A degree in Elect. Eng. or Physics is required with at least 2 years experience if PhD or 5 years if B.S.

For a brief resume form, send your name and address to Mr. E. L. Williams:

RAYTHEON MANUFACTURING COMPANY
WAYLAND LABORATORY WAYLAND, MASSACHUSETTS

For information on this new laboratory, see our ad on page 372 of this issue.

PRODUCTION ENGINEER
TRANSFORMERS

2 years minimum experience in design, fabrication and processing of precision, specialty inductive components. Prefer graduate E.E. or B.Sc. Physics.

CAPACITOR ENGINEERS

Engineering of Mica and Paper capacitors. Prefer graduate E.E. or B.Sc. Physics. Will consider 2 years college, plus minimum 2 years experience.

Mail complete resume to Employment Manager,
SANGAMO ELECTRIC COMPANY,
Capacitor Division, Marion, Illinois.

PROJECT ENGINEERS
Electro-Mechanical

Opportunities are available in controls engineering department of leading aircraft accessories manufacturer. These are responsible positions requiring men with 7-10 years experience in electro-mechanical engineering. The work is related to precision control of relatively large high speed turbine driven devices. Previous supervisory experience necessary. Openings exist in the following areas:

Design and Development of Control Systems
Development and Test of Control Components
Product Engineering of Control Components

These are permanent positions with excellent opportunities for advancement under excellent working conditions.

Submit complete resume, including past earnings and availability for interviews in first letter to:

Technical Employment
Thompson Products, Inc.
23555 Euclid Avenue Cleveland 17, Ohio

EMPLOYMENT PROBLEM?

When you are in need of specialized men for specialized jobs, contact them through an employment ad in a McGraw-Hill Publication.

Management, Engineering, Production, Maintenance, Selling . . . these represent broadly the principal functions in business and industry. And it is principally to the men and executives who fill key jobs in these important divisions that McGraw-Hill publications are directed.

McGraw-Hill Domestic Publications

AMERICAN MACHINIST
AVIATION WEEK
BUS TRANSPORTATION
BUSINESS WEEK
CHEMICAL ENGINEERING
CHEMICAL WEEK
COAL AGE
CONTROL ENGINEERING
CONSTRUCTION METHODS AND EQUIPMENT
ELECTRICAL CONSTRUCTION AND MAINTENANCE
ELECTRICAL MERCHANDISING
ELECTRICAL WHOLESALING
ELECTRICAL WORLD
ELECTRONICS
ENGINEERING AND MINING JOURNAL
ENGINEERING NEWS-RECORD
FACTORY MANAGEMENT AND MAINTENANCE
FLEET OWNER
FOOD ENGINEERING
NATIONAL PETROLEUM NEWS
NUCLEONICS
PETROLEUM PROCESSING
PETROLEUM WEEK
POWER
PRODUCT ENGINEERING
TEXTILE WORLD

THE MEN YOU NEED ARE THE MEN WHO READ THE

McGRAW-HILL PUBLICATIONS
330 West 42nd St.,
New York 36, N. Y.

opportunities in

OPERATIONS RESEARCH

Operations Research Office of The Johns Hopkins University offers exceptional opportunities for scientists who prefer the challenge of operational problems of unusual scope and diversity to routine design and development work.

Our current research program has openings for men qualified in electronics and physics who are particularly interested in:

- Mathematical Analysis
- Determining applications of known photographic, acoustic, infrared and radar techniques to military problems
- Military communications systems planning, analysis and evaluation
- Electronic Countermeasures Analysis

Please send your resume to
Research Personnel Officer

OPERATIONS RESEARCH OFFICE

THE JOHNS HOPKINS UNIVERSITY
7100 Connecticut Avenue
Chevy Chase, Md.

DO YOU NEED ENGINEERS

EXPERIENCED IN:

Research
Development
Design
Instrumentation
Servomechanisms
Missiles
Audio Systems
Control Systems
Radar
Computers
Transistors

Place an "ENGINEERS WANTED" advertisement in this EMPLOYMENT OPPORTUNITIES SECTION. It's an inexpensive, time saving method of selecting competent personnel for every engineering job in the electronic industry. The selective circulation of ELECTRONICS offers you an opportunity to choose the best qualified men available throughout the industry.

For Rates and Information Write:

Classified Advertising Division
McGRAW-HILL PUBLICATIONS
330 West 42nd St., N. Y. 36, N. Y.

ENGINEERS
Electrical • Mechanical
PHYSICISTS

1956 Can be *YOUR* Year!

Westinghouse

ELECTRONIC TUBE DIVISION IN ELMIRA, NEW YORK

. . . offers opportunities to start on a rewarding career of professional achievement and financial success . . . in a delightful vacation-land area, with every advantage for a pleasant life for you and your family.

Openings in:

TUBE DESIGN & DEVELOPMENT

MICROWAVE TUBES: Magnetrons, traveling wave tubes, klystrons, reference cavities, and other devices.

PICK-UP DEVICES: Image orthicon, vidicon, infra-red, X-ray image intensifier.

CATHODE RAY TUBES: Color and black-&-white.

OTHER TUBES: Including receiving and power tubes.

APPLICATION ENGINEERING
for each of the aforementioned fields.

TEST & MFG. EQUIPMENT DESIGN
Seasoning and test units, induction heaters, waveguide apparatus, high-frequency oscillation test units, automatic receiving test circuits.

MANUFACTURING ENGINEERING
Microwave, image orthicon, receiving or color TV tubes.

Interviews in your area, or travel expenses paid for Elmira interviews.

Send resume to: R. M. Jarrett
WESTINGHOUSE ELECTRIC CORP.
P. O. Box 284, Elmira, N. Y.

You can be SURE . . . if it's Westinghouse

ELECTRICAL ENGINEER

Opening for recent Electrical Engineer graduate in electrical-instrument department of a rapidly growing New England chemical-plastics company. To an energetic young man with creative ability who is interested in the rapidly growing instrumentation field in chemistry, we offer singular opportunity to acquire breadth and scope of electronics-electrical instrumentation experience. Our plant is located in pleasant New England community. Send resume and salary requirements to

P-8165, Electronics
330 W. 42 St., New York 36, N. Y.

ENGINEERS

PuzzleD ...about PANAR?

. . . . it's a startling new conception of radar, developed by Sander Associates, Inc.

. . . . it's only one of many "firsts" achieved by this company since its founding 4 short years ago.

. . . . it's typical of the way this organization—run BY engineers, FOR engineers—is shaping the future of electronics.

Problems off the beaten track are not new to Sanders associates, Inc. Unregimented thinking is characteristic of the organization, and the ability to assess a new conception with an open mind. This has lead to such important developments as tri-scan antenna, "tri-plate" microwave plumbing, and—of course—PANAR.

Inevitably, Sanders Associates, Inc. is expanding . . . looking for a number of engineers with inventive minds—men with at least 3 years experience in guidance systems, weapons systems, countermeasures, system concepts, basic circuitry, component development, microwave antenna or electro-mechanical transducers.

We would value the opportunity to discuss your future at Sanders with you. Drop a note to D. H. Johnson, outlining your experience. Interviews can be arranged either in Nashua or in your own area.

SANDERS ASSOCIATES INCORPORATED NASHUA, NEW HAMPSHIRE

(A pleasant community set in the beautiful New Hampshire hills, only an hour from Boston.)

semi-conductors

An excellent opportunity for accomplishment and progress in the semi-conductor field.

A top-flight man needed to take charge of the metal evaluation procedures and interpretations of a major new program for silicon production.

Experience or formal training and a record of successful accomplishment essential.

Reply in confidence to:

Chemical & Metallurgical Division
PROCESS DEVELOPMENT SECTION

GENERAL ELECTRIC

1 Plastics Avenue
Pittsfield, Massachusetts

WANT TO PLACE AN ADVERTISEMENT?

EMPLOYMENT ADVERTISEMENTS RECEIVED BY JANUARY 3, 1956, can appear in the FEBRUARY issue.

Advertisements should be sent to: Classified Advertising Division
Electronics, 330 West 42nd Street, New York 36, New York

FOR RATES OR INFORMATION

About Classified Advertising

Contact The McGraw-Hill Office Nearest You.

ATLANTA, 3
1321 Rhodes-Heverty Bldg.
WAlnut 5778
W. D. LANIER

BOSTON, 16
350 Park Square
HUbard 2-7160
P. McPHERSON

CHICAGO, 11
530 No. Michigan Ave.
MOhawk 4-5800
H. BOZARTH
W. HIGGENS

CLEVELAND, 15
1510 Hanna Bldg.
SUperior 1-7000
C. J. LOUGHLIN

DALLAS, 2
Adolphus Tower Bldg., Main & Akard Sts.
PRospect 5064
J. CASH

DETROIT, 26
856 Penobscot Bldg.
WOodward 2-1793
L. SEEGAR

LOS ANGELES, 17
1111 Wilshire Blvd.
MAdison 6-4323
C. W. DYSINGER

NEW YORK, 36
330 West 42 St.
LOngacre 4-3000
W. SULLIVAN
D. COSTER
R. LAWLESS

PHILADELPHIA, 3
17th & Sansom St.
RIttenhouse 6-0670
J. WILLIS
E. MINGLE

ST. LOUIS, 8
3615 Olive St.
JEfferson 5-4867
H. BOZARTH

SAN FRANCISCO, 4
68 Post St.
DOuglas 2-4600
R. C. ALCORN

Employment Opportunities

ADVERTISERS INDEX

Admiral Corp. 370
Allen Organ Co. 361
American Machine & Foundry Co. 383
Applied Science Corp. of Princeton. 394
Arma Division
American Bosch Arma Corp. ..379, 382, 387
Armour Research Foundation of
Illinois Institute of Technology. 376, 378
AVCO Mfg Corp.,
Crosley Division 368
Avion Division of ACF Industries Inc. 393

Bendix Aviation Corp.,
Pacific Division 362
Products Division Missile Section. 367
Radio Division 371
Research Laboratories 388
York Division 377
Bristol Co., The 384
Brown Instruments Div., Honeywell. 366
Burroughs Research Center. 363

Cardwell Electronics Prod. Corp., Allen D. ..381
Convair, A Div. of General Dynamics Corp.
Pomona, Calif. 377
San Diego, Calif. 381
Cornell Aeronautical Laboratory. 389

Decision Inc. 374
Devenco Inc. 379
Drake Personnel Inc. 361
Dubrow Development Co. 388

Electric Boat Div.,
General Dynamics Corp. 383
Electronic Engineering Co. of Calif. 368
ERCO Div., of ACF Industries 382

Farnsworth Electronics Co. 379
Farrington Mfg Co. 382

General Electric Co.,
Ithaca, N. Y. 374
Pittsfield, Mass. 392
Syracuse, N. Y. 380
General Motors Corp.,
AC Spark Plug Electronics Div. 385
General Precision Lab., Inc. 393
Goodyear Aircraft Corp. 369

Instruments for Industry Inc. 387

Jet Propulsion Lab.,
Calif Institute of Tech. 381
Johns Hopkins University. 380, 391

Kollsman Instrument Corp. 387

Lear Inc. 383

Maryland Electronic Mfg. Corp. 372
Melpar Inc. 389
Miami, University of The. 384
Michigan, University of. 377
Monarch Personnel 361
Motorola Inc. 376

New York Transformer Co. 382
Northrop Aircraft Inc. 360

Olin Mathieson Chemical Corp. 378

Page Communications Engineers Inc. 379

Radiation Inc. 375
Radio Corp. of America. 364, 365
Raytheon Mfg. Co.,
Bedford, Mass. 362
Newton, Mass. 394
Waltham, Mass. 376, 380
Wayland, Mass. 372, 390
Republic Aviation Corp. 384

Sanders Assoc., Inc. 392
Sangamo Electric Co. 390
Sorensen & Co., Inc. 382
Snyder Co., Lee Grant 361
Stavid Engineering Inc. 370
Stromberg-Carlson Co.,
Div. of General Dynamics. 382, 385, 388
Swartwout Co. 384
Sylvania Electric Products Inc.,
Buffalo, N. Y. 374
Mountain View, Calif. 366
Waltham, Mass. 374

Technical Operations Inc. 389
Texas Instrument Inc. 387
Thompson Products, Inc. 390

Vickers Inc., Div. of Sperry Rand Corp. 361
Vitro Corp. 386

Westinghouse Corp. 391

Zenith Radio Corp. 373

This index is published as a convenience to the readers. Care is taken to make it accurate but CLASSIFIED assumes no responsibility for errors or omissions.

ENGINEERS Say "YES" to a Life with Roots

IF YOU are ready to put down roots . . . to embark on a permanent career with deep professional and personal satisfaction . . . General Precision Laboratory may have an opening for you.

There is a variety of long-range projects underway at GPL, a subsidiary of the large and diversified General Precision Equipment Corporation. We look for engineers who can contribute advanced ideas, sometimes pursuing an independent line, sometimes collaborating with experts in several fields. GPL men can count on recognition following quickly upon accomplishment.

Not the least of the advantages of working at GPL is the location in New York's well-known Westchester County. It's a particularly fine place to put down roots, with its beautiful countryside, modern homes and fine schools.

If you are experienced on microwave antennas, digital computers, circuits (microwave & audio frequencies) or various electro-mechanical work, send details of your background to Mr. Hollis F. Ware. Expenses will be paid for qualified applicants who come for interview. We regret we can consider only U. S. citizens.

GENERAL PRECISION LABORATORY
Incorporated
A Subsidiary of General Precision Equipment Corporation
63 Bedford Road Pleasantville, N. Y.

GPL DOES RESEARCH & DEVELOPMENT WORK IN:
. . . Electronics . . . Television, Motion Pictures . . . Aircraft & Missile Control, Guidance . . . Radar, Microwave . . . Systems Engineering: (aeronautical, industrial) . . . Precision Mechanics, Optical Devices . . . Instruments, Servos, Controls: (electro-mechanical, magnetic, electronic)

ELECTRONIC DEVELOPMENT ENGINEERS

Challenging DESIGN & DEVELOPMENT POSITIONS for CREATIVE ENGINEERS

These positions are tailor-made for highly imaginative engineers who enjoy problems of more than ordinary difficulty; problems that require a maximum of individual electronic creativity. Men selected will be entrusted with the complete electronic or electro-mechanical design and development tasks (initial circuits, systems, components, or product design) entailed in carrying a prototype project from original conception to its completion.

REQUIREMENTS: Senior and intermediate engineers with degrees and 4 to 8 years' experience; Junior engineers with degrees and 1 to 3 years' experience, capable of growing with our long-range, electronic design and development program in the following fields:

(1) ANALOG COMPUTER
(2) RADAR BEACONS
(3) MAGNETIC AMPLIFIERS
(4) ELECTRO-OPTICS
(5) MISSILE SYSTEMS
(6) SERVOS
(7) FIRE CONTROL SYSTEMS

PROOF OF U. S. CITIZENSHIP REQUIRED

WE ARE LOCATED in a suburban area, at the Paramus exit of Garden State Pkway., convenient to the N. J. Turnpike and only 15 minutes from Manhattan. If you choose, you can live nearby, avoiding the discomforts, costs and time wasted in commuting. Enjoy living in a clean, friendly community, minutes from work!

Interviews will be arranged at convenient locations. Send resume to:

AVION DIVISION
OF ACF INDUSTRIES INCORPORATED
Route 17, Paramus, N. J. COlfax 1-4100
Only 15 minutes from George Washington Bridge

ASCOP announces opportunities for ENGINEERS at Princeton, N. J.

POTENTIOMETER ENGINEER

Experience in the electrical design and performance of potentiometers, qualified in setting up accurate noise measuring circuits at low levels, simulating attached circuitry of customers, carrying out life, performance and environmental evaluations. To work with the Company's rapidly expanding Switch Division. Supervisory abilities highly desirable. Knowledge of MIL specs desired but not mandatory.

SENIOR R. F. ENGINEER

Five years experience in electrical circuitry, specializing in VHF, UHF and microwave design engineering. Some background in high altitude propagation study desirable. Record of successful equipment design as well as experience in production designing and planning. Experience or knowledge of instrumentation and telemetry is desirable.

TRANSISTOR ENGINEER

Senior electronics engineer or physicist with five to ten years experience in electronic product design, preferably instrumentation, including a minimum of two to three years experience in transistor circuit work. Familiarity with MIL specs required. Will consider electronics engineer with three to five years in electronic design with some transistor work as assistant to senior transistor man.

SALES ENGINEER

Comprehension of the concepts and applications of data systems, preferably with several years experience in Pulse Width Telemetry use or four years of telemetering or instrumentation experience in missiles, aircraft, or similar field. Must be willing to travel up to 40% of the time, usually not in stretches longer than two (2) weeks at a time. Sales experience not necessary but desirable.

Please Send Resumes to:

Applied Science Corp. of Princeton
Princeton, New Jersey
Plainsboro 3-4141

ASCOP

JOIN THE ELECTRON TUBE BANDWAGON!

CONTINUING INCREASE IN THE DEMAND FOR RAYTHEON'S LINE OF RELIABLE TUBES HAS CREATED SEVERAL OUTSTANDING OPPORTUNITIES FOR FUTURE-MINDED ENGINEERS.

- **PROJECT ENGINEERS** to supervise important and interesting projects. 3–5 years experience in vacuum tube design, development, or production engineering required.
- **DEVELOPMENT ENGINEERS** to work on short and long range electron tube developmental projects. 1–2 years experience desired.
- **PRODUCTION ENGINEERS** to work on electron tube production problems. Minimum experience of 1 year.

- **EXCELLENT BENEFITS**
- **FULL TUITION REFUND PLAN FOR IMPROVEMENT OF FORMAL EDUCATION**
- **RECOGNITION OF ABILITY**

Please Send Complete Resume to

RAYTHEON

TECHNICAL PLACEMENT OFFICE
RAYTHEON MANUFACTURING CO.
SPECIAL TUBE DIVISION
55 Chapel St. Newton 58, Massachusetts

NEED ENGINEERS

Place an "Engineers Wanted" advertisement in this EMPLOYMENT OPPORTUNITIES section. *It's an inexpensive, time saving method of selecting competent personnel for every engineering job in the electronic industry.* The selective circulation of ELECTRONICS offers you an opportunity to choose the best qualified men available throughout the industry.

INDEX TO THE SEARCHLIGHT SECTION ADVERTISERS

Allied Electronics Sales 402
Alltronics 408
Amber Industrial Co. 409
Arrow Sales Inc. 409

Barry Electronics Corp. 407
Belvision Inc. 408
Blan 395

C & H Sales 399
Communication Devices Co. 402
Communications Equipment Co. 401
Compass Electronics Supply Div. of Compass Communications Corp. 408
Cramer Electronics Inc. 400

Delaware Equipment Co. 402

Electronicraft Inc. 406
Empire Electronics Co. 406
Engineering Associates 395

Fair Radio Sales 396
Fay-Bill Distributing Co. 398
Finnegan, H. 395
Fischer Auction Co. 396
Fischer Scientific Co. 395

Gould Green 408
Green, G. 395

Harjo Sales Co. 402
Hodgson Co., R. W. 395

Instrument Service Co. 402
Instrument Service Engineering Labs. 406

JSH Sales Co. 397

Lectronic Research Labs. 404
Legri S. Co., Inc. 404
Liberty Electronics Inc. 404

Magnetic Development Corp. 395
McNeal Electronic & Equipment Co. 400
Mogull Co., A. 406
Monmouth Radio Labs. 407
M. R. Co., The 408

Page Electronics 395, 396, 400, 402, 404, 406, 409
Photocon Sales 404
Radalab 405
Radio & Electronic Surplus 408
Radio-Research Instrument Co. 400

Red Arrow Electronic Sales Co. 395
Relay Sales 398
Ruxur Electronics Corp. 406

Sanett, Bob 395
Societe Industrielle Alfa, S. A. 408

"TAB" 410

Universal General Corp. 409
U. S. Crystals Inc. 396

V & H Radio & Electronics Supply 400

Western Engineers 403
Wilgreen Industries 398

This index is published as a convenience to the reader. Care is taken to make it accurate but Classified assumes no responsibility for errors or omissions.

CLASSIFIED SEARCHLIGHT SECTION ADVERTISING

BUSINESS OPPORTUNITIES — EQUIPMENT - USED or RESALE

UNDISPLAYED RATE

$2.10 a line, minimum 3 lines. To figure advance payment count 5 average words as a line.

PROPOSALS, $2.10 a line an insertion.

BOX NUMBERS count as one line additional in undisplayed ads.

DISCOUNT of 10% if full payment is made in advance for four consecutive insertions of undisplayed ads (not including proposals).

DISPLAYED RATE

The advertising rate is $18.50 per inch for all advertising appearing on other than a contract basis. Contract rates quoted on request.

AN ADVERTISING INCH is measured ⅞ inch vertically on one column, 3 columns—30 inches—to a page.

EQUIPMENT WANTED or FOR SALE ADVERTISEMENTS acceptable only in Displayed Style.

Send NEW ADVERTISEMENTS to N. Y. Office, 330 W. 42nd St., N. Y. 36, N. Y. for February issue closing January 3rd

The publisher cannot accept advertising in the Searchlight Section, which lists the names of the manufacturers of resistors, capacitors, rheostats, and potentiometers or other names designed to describe such products.

TOROID COIL WINDING LAB

Complete laboratory for sale including laboratory model sub-miniature toroid coil winding equipment (modified), formvar insulated wire, many ferrite and permalloy cores, new inductance bridge, etc.

MAGNETIC DEVELOPMENT CORP.
40 Bloomfield St. Lexington, Mass.

WANTED

300 RCA TYPE 1654 Rectifier Tubes.

Must be new, boxed, and fully guaranteed. Address quotation for full or partial quantity to:

Purchasing Agent
Fisher Scientific Company
711 Forbes Street
Pittsburgh 19, Pa.

WANTED

ELECTRONIC TUBES, all types. Also want all types airborne electronic equipment: ART-13; BC-788; I-152; ARC-1; ARN/7, etc. Top dollar paid!

BOB SANETT, W6REX
1524 S. Edris Dr.
Los Angeles 35, California

WILL BUY ALL

ART-13T47A Transmitters $200.00	BC-348 Rec'r Modified $35.00
ART-13 T47 Transmitters $150.00	BC-348 Rec'r Unmodified $50.00
BC-788C Altimeters $150.00	ARC-1 Radio Complete $250.00
ARC-3 Complete $185.00	
RS/ARN-7 Radio Compass $175.00	BC-312 Receiver $40.00
	BC-342 Receiver $80.00

Ship via Express C.O.D. Subject to Inspection to
H. FINNEGAN
49 Washington Ave. Little Ferry, N. J.

WANTED

ART—13: type ATC, T-47, T-47A—transmitters
BC—348—342—312—224—receivers
EE-8 field telephones
Complete units and all component parts regardless of condition. Any quantity large or small

RED ARROW ELECTRONIC SALES CO.
1217 Summit Ave Union City, N. J.
N.Y. Tel. Oxford 5-0984 N.J. Tel. Union 3-7916

If there is anything you want
that other readers can supply
OR . . . something you don't want—
that other readers can use—
Advertise it in the
SEARCHLIGHT SECTION

---

3 Cond. KOILED KORDS
22 inches long stretches to 9 feet
List price $3.00 Net $1.26

REVERSIBLE GEARED-MOTOR
Delco-PM-Permanent Magnet Alnico Field Motor



#5071895 ¼ SHAFT or 11/16 GEAR.... $17.50
#5069600 ..... $18.50
Two Type of Clamps to hold motor: $1.50 ea.

MERCURY SWITCHES
59¢ to $6.00

FILAMENT TRANSFORMER
6v—1½ amps
Weighs—1 lb. 97¢

HG We Buy MERCURY HG

G.E. Switchettes
All types—75¢ ea.
10 for $6.00
100 for $50

115 v. AC RELAY
$2.90

TELECHRON Motors

4 RPM on 50cy or 4⅘ RPM	3.6 RPM, 3.15 1 RPM .. 3.95
on 60 cy. $2.85	3 R.P. Hr 2.85
2 RPM .. $2.90	1 R.P.2Hr 2.80
3 RPM .. 3.90	1 R.P.12Hr3.25
4 RPM .. 2.90	60 RPM .. 4.85

Laboratory Special 1 of Each Motor $25.

please include postage

BLAN

EST. 1923

64P Day Street
New York 7, N. Y.

BLOWERS 115 Volts A.C. 60 cy.

REDMOND 5" 18 watts....$8.95
DELCO 60 cfm. 40 watts. #5062369 used in 584 RADAR $14.50

HAND WOUND 10 Sec. to 24 Min. TIMER SWITCH.. $1.25

6 Watt Most POWERFUL TELECHRON 1 RPM
110 v. 60 cy.....$6.50
10 for $50.00

3" Round Elapsed Time Meter
Square Case
$13.75
$14.50

MARKTIME 5 HOUR SWITCH
A 10 amp. timing device. Pointer moves back to zero after time elapses. Ideal for shutting off radios and TV sets when you go to bed. Limited supply at this SPECIAL PRICE .. $4.90
Also available in 15 min., or 30 min. or 1 hr. at.... $6.50

HAYDON TIMING MOTORS

110v 60 cycle 30 RPM		$2.60
110v 60 cycle 1 RPM		2.60
230v 60cy	1 RPM	1.00
	2 RPM	1.00

AN/APR-4 LABORATORY RECEIVERS

Complete with all five Tuning Units, covering the range 38 to 4,000 Mc; wideband discone and other antennas, wavetraps, mobile accessories, 100 page technical manual, etc. Versatile, accurate, compact—the aristocrat of lab receivers in this range. Write for data sheet and quotations.

We have a large variety of other hard-to-get equipment, including microwave, aircraft, communications, radar; and laboratory electronics of all kinds. Quality standards maintained.

NEW TS-13/AP X-BAND SIGNAL GENERATORS with manual $575.00; T-47A/ART-13 Transmitters, $450.00; H-P, Boonton, G-R, Measurements, many others in stock.

ENGINEERING ASSOCIATES
434 PATTERSON ROAD DAYTON 9, OHIO

WHAT ARE YOUR INDUSTRIAL TUBE NEEDS?

FOR THE *RIGHT*
ANSWERS CONSULT:

PAGE ELECTRONICS
136 LIBERTY STREET, NYC 6 NY
COrtlandt 7-4245

★ ***MANUFACTURERS***
Let us handle technical sales representation of your products

★ ***INVENTORS***
We will share the cost of protecting your invention if accepted for commercialization

We Specialize in Electronics, Nucleonics, Instrumentation, Servomechanisms & Cybernetics.

R. W. HODGSON CO.
Technical Sales Representation & Research & Development Engineering
8406 W. Washington Blvd. Los Angeles 16, Calif.
REpublic 2-2651

ELECTRONICS AUCTION

R & S ENTERPRISES RETIRES FOREVER!

TUES.-WED. JAN. 17-18 • 10 30 A.M. EACH DAY

7636 SANTA MONICA BLVD. LOS ANGELES—CALIFORNIA

TEST EQUIPMENT

19 Haseltine 1030 TS/13AP-UHF Signal Generators—
Synchroscopes—
Dumont #241-UPM-1
56 Frequency Meters
OAO 2

CRYSTALS 1000 COMPLETE SETS

For SCR-508 and 608. 100 Complete Sets for SCR-543

POWER SUPPLIES

25 Davis Hydrogen Testers—15 McElroy Tape Pullers.
22 Standard 639 Racks/W Amplifiers
Plug Sockets—Switches—
1500 Slide Rules—
Head Sets—Filters

GAS ENGINES WAVE GUIDE 1592 ANTENNAS

AN-24A—50 ft.—
66 MOUNTING BASES (FT-237G)

REMOTE CONTROL UNITS-CORD SETS-CAPACITORS-METERS.

60,000 TUBES

Transmitting
Receiver
Cathode Ray
and
Magnetron
Tubes

3 MILLION FT. WIRE

Telephone
Radio
Bell
Aviation
Hook up etc.

20,000 NEW

Audio OSC
Transformer UTC
and Super Ouncer
2-Z9638-1

13 COMPLETE NEW RADAR SETS

APS-3

200 REGAL 5 TUBE RADIOS (ac & dc)
150 SETS Complete
FLUXGATE COMPASS
25 Sets Complete
MAGNESYN COMPASS
12 LORAN Complete
EQUIPMENT (apn/4b) and (apn/9)
15 INVERTERS
mg 153 and mg 149
DYNAMOTORS
14 and 28 Volts
283 RECTIFIERS
and VARIAC s/9r
INDICATORS
VIDEOSCOPES-S 0 2 1
Bearing Deviation
APA-10-1-82a
SCR-545 RADAR VAN L/PS

538 COMPLETE TRANSMITTERS RECEIVERS

ARC—TBY—TCS
MN 26c—WE-27
SCR-522—RTA-1
Walky Talky
BC-459a—BC-357
BC-611—BC-733
SCR-658—APR-4

TELEPHONE & TELETYPE

150 Stromberg Carlson Telephone Sets with Dial. EE-8 Phone Sets.
CF-3-A Carriers Equipment.
FRA Frequency Shift Converter

HARDWARE—TOOLS—BUILDERS HDWE

4572 Privacy and Passage Locks. 1831 Dry Chrome & Brass Door Knobs. Pulls—Taps—Letter Metal Stamping Sets—Clamps—Greenlee Punch—Die and Clap Screw Sets—C Clamps

SALES CONDUCTED By
FISCHER AUCTION CO.
648 MARKET ST.—SAN DIEGO, CAL.
Tel—BE-92248

OPEN for INSPECTION
Daily 12 to 4 p.m.
Jan. 12 until Day of Sale

BLOWERS:



12/24 VDC—AC CAST ALUMINUM BLOWER (Pictured at left)—100 CFM: 3" Intake; 2" outlet. Shunt Motor 4"x3" 3000 RPM @ 24 VDC...$5.95

6 VDC SINGLE—100 CFM—No. 6100. Used....$4.95

6 VDC FLANGE—150 CFM—No. 6150.

24 VDC DUAL—20 CFM—Min—No. 2420.....$7.95

10 CFM BLOWER (Pictured—right) 27.5 VDC; 1/100 HP.; 7000 RPM; Oster Motor CBP-1A; L-R Mfg. Co. Bakelite Blower #2, overall size: 2-½" x 4-⅛". Price $5.95
Same as above, 12 VDC operation: Price $5.95

115 V. 400 CYCLE—10 CFM—Eastern Air Devices Motor J31A—7200 RPM. 1/100 HP. L-R #2 Blower Assy. Overall Size: 4-⅛" x 2-¼". No. 3110....$5.95



10 CFM BLOWER (Pictured at left)—28 VDC—6 A; 5000 RPM. Pioneer Motor SH-2345. Aluminum Blower Housing; Overall Size: 4-⅛" x 3-⅛". Price $5.95

115 V. 60 CYCLE BLOWERS:

115-VAC 60 cycle SINGLE TYPE—100 CFM: 2-¼" intake; 2" outlet. Complete size: 5" x 6" —No. 1C939 ..... **$8.95**

115 VAC 60 cycle DUAL TYPE—100 CFM; 4" intake; 2" Dia. Each side. Complete size: 8" x 6" —No. 1C880 ..... **$13.95**

115 VAC 60 cycle COMPACT TYPE—108 CFM; Motor built inside quirrel cage; 4-⅛" intake; 2⅝" x 3" Dia. Complete size: 4-⅛" W x 8-⅝" H x 8-⅛" D—No. 2C067 ..... **$14.95**

115 VAC 60 cycle FLANGE TYPE—140 CFM; 3-⅛" intake; 2-½" Dia. Complete size: 7-⅛" W x 7-¼" H x 6-⅝" D—No. 1C807 ..... **$13.95**

115 VAC 60 cycle FLANGE TWIN—275 CFM; 4-½" intake; 3-¼" x 3" Dia. Complete size: 11-⅝" W x 3-⅝" H x 8-1/16" D— No. 2C069 ..... **$21.95**

115 VAC 60 Cycle BLOWER—300 CFM; 4" intake; 5" x 5" outlet. Overall size: 8" x 7" x 6". Bodine Motor NBI-33. Removed from New Equipment. #BOD-200 ..... **$14.95**

115—VAC 60 Cycle BLOWER—100 CFM: 3-⅛" intake; 2" outlet; Rd. Flange with Flap Director. Overall size with bracket; 5" L x 3-⅛" W x 7" H. Removed from New Equipment. Diehl Motor FB-2106-6 No. FDBL-2106..... **$6.95**

Same as above, but with 12- Curved Director. No. CDBL-2106 ..... **$7.95**

Previously Adv. Items Still Available. Please Write!

TOWERS and ANTENNA EQUIPMENT

TRIANGLE TOWER

(Illustrated) Galvanized Steel Tower, 12½" Base, 30 Ft. High—in 10 Ft. Sections. Knocked down. Complete with Hardware, two 50 Ft., one 50 Ft. Guys; three 5 Ft. Anchors, and Base Plate. Each section weighs 45 lbs. Complete with Erection Manual. Shipping Weight: Approx. 350 lbs. F.O.B. Ky.—Price.....**$31.95**

MAST BASES—INSULATED

MP-22 BASE—Ins. spring action, direction of bracket can be raised or lowered easily $2.95
MP-S-33 BASE—Ins. type with heavy coil spring and 5" dia. Ins. Requires 2" hole for mounting. Weight: 9 lbs. $5.95
MP-37 BASE—Ins. type with heavy coil spring, 7" dia. Ins. Requires 1¾" hole for mounting. Weight: Approx. 10 lbs. ...$8.95

MAST SECTIONS FOR ABOVE BASES:

Tubular steel, copper coated, painted—in 3 ft. sections, screw-in type. MS-53 can be used to make any length with MS-52-51-50-49 for taper. Any section.....@ 50¢ Each. Larger Dia. Section MS-54 75¢ Ea.

DYNAMOTORS:

INPUT VOLTS:	OUTPUT: VOLTS:	MA.	STOCK No.	PRICES: USED:	NEW
12 VDC	625	225	DM-38	$8.95	$12.95
12 or 24	230	100	DA-12		8.95
12 or 24	540	450	DA-14		14.95
12 or 24	500	50	USA/0518		4.95
24	250	60	PE-86		8.95
14 VDC	330	150	BD-87	3.95	5.95
14	250	80	DM-25	6.95	8.95
14	1000	350	BD-77	14.95	29.95
28	1000	350	PE-73	8.95	
12 or 24	275	110	USA/0518		4.95
12	230	80	PE-133	4.95	6.95
14 VDC	375	150	BD-83	3.95	4.95
12 VDC	220	80	DM-34	2.95	4.95

FAIR RADIO SALES • 132 SOUTH MAIN ST LIMA, OHIO

ROCKETS? PENCILS? LIGHTHOUSES?

2C37	32.50
2C39A	12.00
2C46	7.50
6BA4	22.50
5794	7.50

Fully guaranteed by

PAGE ELECTRONICS

Crystals

BUY NOW AND SAVE UP TO 90%

4,000,000 GOVERNMENT SURPLUS CRYSTALS

NOVICE, FT-243
FT-171, FT-241,
FT-249, DC-34/35
SHIP BAND, MISC.

SAME DAY SERVICE!
• • • •
SATISFACTION GUARANTEED!
• • • •
OVER 5,000 FREQUENCIES!

SEND FOR FREE CATALOG

"The House of Crystals"

U. S. CRYSTALS, Inc.
407 S. UNION AVE. • LOS ANGELES 17, CAL.

SAVE ON TUBES BRAND NEW TUBES GUARANTEED TUBES

OA2 .75	2K22 14.50	5J26 125.00	FG235A 25.00	464A 2.25	809 2.25	5611 75.00
OA3 .90	2K25 12.00	5J29 5.00	QK349 150.00	RH507 25.00	811 2.70	5634 7.50
OB2 .75	2K26 45.00	5J30 5.00	WE249B 2.50	527 22.50	812 2.50	5636 4.00
OB2WA 3.00	2K28 28.00	5J33 5.00	WE249C 3.00	ML531 4.00	813 11.00	5637 5.50
OC3/VR105 .75	2K33A 65.00	5MP1 3.95	250TL 15.00	539 .50	814 1.75	5651 1.40
OD3/VR105 .70	2K34 99.50	5NP1 5.00	WF-251A 47.50	KU610 3.50	815 1.50	5654 1.50
ELC1B 1.50	2K39 100.00	5R4GY .90	WE252A 10.00	HY615 .50	826 .75	5656 7.00
1AD4 .85	2K41 100.00	5R4WGY 2.25	QK253 149.50	WL616 50.00	829 6.00	5657 125.00
1B23 2.75	2K43 125.00	C6J 6.50	WE254A 5.00	KU627 10.00	829B 8.50	5663 1.50
1B24 5.50	2K44 125.00	6AJ5-JAN 1.25	FG258A 90.00	KU628 10.00	830B .75	5667 125.00
1B24A 12.50	2K45 45.00	6AK5W 1.25	271A 10.00	648P1 7.50	832 3.75	5670 1.50
1B26 2.00	2K47 125.00	6AL5W .65	WE274B 1.00	WL652 20.00	834 5.00	CK5678 1.00
1B27 10.00	2K48 80.00	6AR6 1.25	WE282B 6.00	HK654 25.00	836 1.50	5686 2.00
1B35 4.50	2K54 9.00	6AS6 1.25	QK283A 100.00	681/686 25.00	838 .75	5687 3.00
1B36 4.00	2K56 50.00	6AS7G 2.50	QK284A 100.00	WE701A 1.85	842 2.00	5691 4.75
1B40 2.00	2V3G 1.30	6D21 150.00	287A 2.50	702A .50	845 5.00	5692 5.00
1B42 4.00	2X2A 1.00	6F4 2.25	WE287A 3.50	WE703A 1.25	849 22.50	5693 4.75
1B51 6.75	3AP1 2.95	6J4 1.95	WE300B 5.00	WE704A .75	851 10.00	5696 1.00
1B63A 22.00	3BP1 2.00	6K4 2.25	GB302 5.00	WE705A .75	852 4.00	5702 1.75
1N21 .75	3B24 1.00	6Q5G 3.90	304TH 8.00	706AY-GY 15.00	860 3.00	5702WA 6.00
1N21B 1.50	3B24W 5.00	6LGW68 3.25	304TL 12.50	707A 3.50	861 15.00	5703 1.10
1N23 .75	3B26 3.00	6SK7W 2.00	WE305A 3.00	707B 4.50	872A 1.35	5718 3.00
1N23B 1.50	3B28 5.00	6SL7WGT 1.50	307A/RK75 1.00	WE708A .75	874 .60	5719 2.50
1N23BM 3.50	3B29 5.50	6SN7W 2.00	WE308B 15.00	713A .50	878 .50	RK5721 175.00
1N25 4.00	3C22 60.00	6SU7GTY 2.25	WE312A 2.00	714A 12.50	884 1.00	5725 1.75
1N26 4.50	3C23 5.00	6X4W 1.00			GL889 50.00	5726 .65
1N28 5.00	3C24 2.50	6X5WGT 1.30			GL889A 65.00	5727 2.00
1N34A .50	3C27 1.00	7C22 50.00			889RA 85.00	5744 1.90
1N35 1.50	3C31 1.50	7C24 90.00			902A 3.00	5750 3.10
1N42 8.00	3C33 9.95	NE16 .35			902P1 3.00	5751 2.20
1N47 3.00	3C45 6.00	RK21 1.00			917 2.50	CK5787 4.95
1N63/K63 1.75	3DP11A 7.50	RK31 5.00			919 2.00	5814 1.00
1N69 .40	3D21A 4.00	HK24 3.00			927 1.00	5814A 2.00
1P21 22.50	3DP1SE 5.00	D42 40.00			931A 2.50	5819 25.00
1P22 6.50	3E29 8.50	HK54 2.00			935 4.00	5825 7.95
1P28 7.50	3FP7A 3.50	QK59 30.00			954 .35	5829 1.00
1P36 2.50	3GP1 1.95	QK60 25.00			955 .35	5837 70.00
1W5 1.00	3J30 35.00	RK60/1641 1.35			956 .35	5844 3.00
2AP1 5.00	3J31 45.00	RK61 2.95			957 .35	5851 4.00
2C26A .50	3K30 125.00	QK61 25.00			958A .35	5896 6.50
2C33 .75	4B23 6.00	QK62 25.00			959 1.50	5899 7.00
2C35 2.50	4C27 3.50	HY65 1.50			991 .35	5901 6.50
2C39 7.00	4C28 25.00	RK65/5D23 10.00			CK1005 .35	5905 8.95
2C39A 8.00	4C35 13.50	RKR72 .50			CK1006 2.75	5908 7.95
2C40 10.00	4E27 8.75	RKR73 .50			CK1007 .75	5910 .45
2C42 10.00	4J22 35.00	ML-100 50.00			1603 3.00	5933 4.00
2C43 7.00	4J28 35.00	100TH 6.50			1620 3.25	5933/807W 4.00
2C44 .50	4J29 35.00	FG105 11.00			1623 2.25	5998 15.00
2C46 6.00	4J31 65.00	F123A 2.95			1624 1.00	6005 1.75
2C51 3.00	4J34 50.00	F128A 15.00			1625 .30	CK6050 2.00
2C52 3.50	4J42 25.00	FG154 15.00			1626 .25	6147 3.00
2C53 10.00	4J50 99.50	VT158 9.75			1636 .90	6177 49.50
2D21 .60	4J52 50.00	FG166 15.00			1641 1.35	8005 4.95
2D21W 1.35	4X150A 22.50	FG172 20.00			1642 .50	8012 1.00
2E26 3.25	4X500A 55.00	HF-200 10.00			1945 65.00	8025A 2.00
2E27 .75	5BP2A 5.00	WL200 75.00			2050 1.00	9001 .85
2E31 1.00	5CP1A 9.50	CE-203 3.75			2051 .65	9002 .65
2J31 14.50	5C22 29.50	203A 5.00			ZB3200 75.00	9004 .85
2J32 12.50	5C30/C5B 1.50	204A 25.00			5517A 1.75	9005 1.50
2J33 14.50	5CP7A 10.00	207 50.00			5551 25.00	9006 .25
2J34 14.50	5D22 7.50	211/VT4C .50			5553/655 90.00	9903/5894 20.00
2J36 15.00	5JP2 7.00	211E 15.00			5557/FG17 2.95	
2J42 60.00	5JP4 7.00	217A 1.50			5559/FG57 10.00	
2J48 35.00	5JP5 7.00	217C 2.00			5561 29.50	
2J49 40.00	5JP11A 9.50	WL218 19.00			5586 125.00	
2J50 35.00	5J23 20.00	RX233A .75			5591/403B 2.75	
2J51 150.00						
2J55 35.00						
2J56 50.00						
2J61 15.00						
2J62A 50.00						

SPECIAL!

5" DUAL GUN TUBE

Long persistency face, P7 screen. Value at $200.00. This tube has been rejected for military use.

Tested Before Shipped & Fully Guaranteed. Only **$17.95**

VACUUM CAPACITORS

6 mmfd. 30 KV 9.00
50 mmfd. 32 KV 9.00
75 mmfd. 20 KV 12.50

Also Other Values!

WE316A .50	715B 4.00						
327A 3.50	715C 12.00						
WE336A 5.00	717A .50						
WE338A 5.00	720AY-EY 50.00						
WE349A 6.00	721A .75						
WE350A 2.75	721B 7.25						
350B 2.75	722A 2.50						
354C 5.00	723A/B 8.50						
356B Q	WE724A .85						
357B 50.00	WE724B .85						
WE359A 2.00	726A 7.00						
368AS 2.00	726B 30.00						
371B .50	726C 20.00						
WE388A 1.20	730A 7.50						
WE393A 4.50	750TL 42.50						
WE394A 3.00	800 1.50						
WE396A 2.00	801A .50						
403B/5591 2.75	802 2.75						
GL414 99.50	803 1.40						
417A 3.50	804 9.75						
434A 3.00	805 4.00						
446A .50	806 7.50						
446B 2.00	807 1.20						
450TL 35.00	807W 4.00						
WL456 59.50	808 1.25						

THIS IS ONLY A PARTIAL INVENTORY. CHECK WITH US FOR YOUR REQUIREMENTS

Thousands of other types in stock. Send us your requirements. RECEIVING TUBES! We Carry a complete line in stock. Standard brands only.

jsh SALES CO.

ELECTRONICS
Dept. E-Y
1100 Venice Blvd
Los Angeles 15
California

All Prices F.O.B. Los Angeles, subject to change without notice. Minimum order $5.00. Check with us for items not listed.

FAY-BILL DISTRIBUTING CO.

Partial Listing Only — LARGEST SURPLUS DEALER IN THE COUNTRY—STANDARD BRANDS—TRANSMITTING AND RECEIVING

Type	Price
AR-158	9.95
CKP-220	.94
CK-508AX	.99
CK-521AX	.99
CRP-72	.79
DG-1290	2.00
EF-50	.39
F-1148	.39
FG-1	.39
FM1GA	39.50
F121A	5.00
F128A	19.50
FG-105	14.44
FG-166	16.98
HF-100	.69
HF-150	10.98
HF-200	10.98
HF-300	10.98
HK-24	3.99
HK-54	1.49
HY-114B	.69
HY-615	.29
KU-610	4.99
QK-59	39.50
QK-61	63.60
QK-62	69.00
QK-185	110.00
RK-34	.89
RK-38	5.85
RK-59	1.85
RK-60	2.45
RK-65	9.95
RX-21A	5.99
UH-65	1.95
10E/VT-25A	.39
VR-78	.89
VR-105	.89
VR-150	.89
VT-62	.89
100/VT-67	.39
VT-127A	2.00
VT-158	19.98
VU-111	.89
0A2	.44
0A3	1.10
0B2	.45
1B72	1.49
1B24	5.99
1B26	1.19
1B35	2.98
1B52/832A	.99
1N23	.49
1N34	.49
1N37	1.49
1P28	3.69
1P29	3.69
2AP1	1.98
2BP1	1.49
2BP2	1.49
2C22	1.49
2C27	3.98
2C26	.99
2C26A	.49
2C30	4.00
2C51/RX233	.99
2C39A	8.40
2C39A Boxed	12.40
2C40	8.99
2C43	10.40
2C43 (base 9)	14.40
2C46	3.98
2C48	1.49
2C51	3.98
2C53	11.75
2D21	1.49
2D21W	1.85
2E22	1.49
2E26	1.19
2G-22	1.19
2J-21	7.98
2J-31	3.79
2J-32	3.59
2J-33	16.98
2J-34	16.98
2J-35	16.98
2J-36	16.98
2J-38	16.98
2J-39	17.98
2J-40	34.98
2J-41	34.98
2J-42	69.98
2J-43	34.98
2K-22	18.99
2K-23	19.95
2K-25	18.99
2K-28	28.99
2K-33A	79.50
2K-39	164.98
2K-45	84.98
2K45	49.50
2K49	52.50
2K52	59.50
2K54	19.50
3A/879	.59
3A1	.59
3BP1	1.49
3BP2	1.49
3B22	1.49
3B24	2.49
3B24W	4.99
3B25	1.98
3B27	6.98
3B28	1.49
3C21	.94
3C22	64.95
3C23	6.98
3C24	6.98
3C27	1.49
3C28	4.99
3C33	1.49
3C35	15.98
3C45	7.98
3E29	9.98
3EP1	9.98
3GP1	2.89
3HP1	2.98
3J21	75.00
4A-11	.49
4AP-10	3.98
4B22	6.98
4B26/EL6C	3.98
4B28/CR225	3.98
4-125A	18.98
4B30	3.98
4C27	6.98
4C28	23.50
4C35	14.99
4D22	9.98
4D32	19.98
4E27	9.98
4J22	34.98
4J32	34.98
4J34	34.98
4J35	34.98
4/26	59.50
4J27	69.98
4/28	59.50
4J25	59.98
4J30	49.98
4J31	49.98
4J33	69.98
4J36	69.98
4AP1	4.99
4BP1	4.99
4BP1A	4.99
5BP4	2.99
5CP1	2.99
5CP1A	10.98
5CP7	6.98
5CP11A	6.98
5J	6.49
5C22	28.99
5D21	7.99
5BP1A	6.99
5EP1	2.98
5HP1	2.98
5HP1	6.98
5JP1	14.50
5JP1	7.49
5RP2	38.50
5J29	9.00
5J30	18.65
5J33	5.90
5LP1	11.49
5NP1	6.98
5RP4GV	3.98
5R4WGY	2.22
6-J	1.98
6AU6WA	1.10
6C4WA/6350	1.39
6C21	10.98
6J4WA	3.98
7C22	49.50
7C25	89.50
7BP1	6.98
7BP7	6.98
9LP1	5.98
10Y-	.31
12K7	1.66
15E	1.66
15H	.39
18C	.39
24W	1.98
25TG	4.44
51A	2.99
89Y	.10
100TH	6.98
100YL	8.98
203	4.99
204A	19.98
205B	1.98
207	49.50
211	5.98
218A	1.49
218B	2.98
217C	6.98
221A	2.98
242B	2.98
242C	7.98
245B	2.98
245C	4.98
250B	4.98
254TH	39.98
254YL	21.98
394A	4.39
417A	6.99
434A	3.99
446A	1.49
446B	2.29
WL-460A	9.99
WL-464A	4.77
GL-471A	2.35
527	22.50
WL-530	19.95
WL-531	4.99
WL-532	.99
GL-550	.99
700A/B/E/D	5.99
701A	4.99
702A	1.98
703A	1.98
704A	1.98
705A	.96
706B	10.98
706C	10.98
707A	1.99
707B	4.59
708A	2.45
709A	1.45
713A	1.98
714AY	27.50
715A	2.49
715B	6.98
715C	14.98
717A	.89
718AY/BY/ GY/EY	21.98
719A	33.75
720AY/CY/ EY/DY	29.75
721A	1.95
721B	8.10
723A/B	1.99
724A/B	3.29
725A	6.98
726A	14.50
726B	25.50
796C	26.50
738A	8.98
800	.89
802A	.89
803	2.89
804	2.99
805	4.25
806	10.98
808	2.98
809	1.45
810	1.49
811	1.39
813	2.98
814	2.59
815	2.98
828	5.75
829B	10.49
830B	1.99
832A	8.49
833A	17.49
835	2.98
836	1.98
838	1.99
841	.26
843	.49
845	7.48
851	32.50
852	12.48
860	1.98
861	14.98
864	.69
865	1.19
866A	1.19
869B	15.99
872A	1.26
874	.74
878	.96
879	1.29
884	.99
885	1.49
9-3	.69
9002A	3.98
915	2.18
927	1.65
931A	2.99
954	.36
955	.49
956	.59
957	.59
958	1.59
959	1.98
991	.33
1066	84.50
1603	.49
1614	1.99
1618	1.98
1619	1.98
1620	1.39
1625	.29
1626	.21
1629	.22
1638	.69
1639	.49
1640	.69
1641	2.49
1642	.29
1644	.69
1655P1	1.98
1851	1.39
1852	.69
2050	1.10
2050W	3.49
2051	.69
2A1	.69
2B1	.69
2G5GT	.69
2LC1	.94
2LD5	.94
2M	.94
2T1	.69
3A1	.79
3H1	.69
3N1	.69
3R1	.69
3S4	.69
3S5	.69
3U4	.69
3U5	.69
3X2A	.69
3V1	.69
3A1	.69
3B1	.39
3D6	.73
3V4	.73
3Y4	.83
4A6	.69
4B6	.69
4E1	.69
4Y1	.69
4Y4	.69
4Y6	.69
5Z4	1.19
5W4	.89
6AC7	.89
6AC7W	1.12
6AB7	.89
6AF4	1.29
6AG5	.44
6AG7	1.89
6AH6	.89
6AL5	.59
6AN5	.74
6AN8	.89
6AN4	.59
6AT6	.89
6AU6	.89
6B4G	.99
6BA7	.89
6BE6	.89
6BG6G	1.98
6BK5	.89
6BK7A	1.21
6BL7	1.10
6BM6	55.98
6BN6	1.24
6BQ6	1.15
6BQ7A	1.15
6BX7	1.24
6CD6	1.72
6CM6	.69
6CS6	.69
6CY5	.49
6CB6	.49
6DE6	.49
6DK6	.49
6EA8	2.75
6EB8	.79
6EM5	.79
6ER5	.79
6F4	.79
6F6G	.99
6F8G	1.25
6FG6	.99
6FQ7	.79
6G6G	.99
6GH8A	.89
6GM6	.79
6GT/G	.69
6GU7	.69
6GV6	.69
6GV8	.89
6GW6	.69
6HA5	.89
6HG8	.89
6HS6	.89
6J4	.89
6J5GT	.69
6J6	.89
6J7	.89
6J7G	.89
6J8G	.89
6K4	.79
6K7	.79
6K8G	1.49
6L6G	.99
6L6GC	1.49
6L6M	1.49
6L7G	.99
6L7	.99
6M7	1.10
6N7GT	.74
6N8	.69
6P5GT	.69
6P9	.74
6P28	.89
6Q7	.69
6R7	.79
6S4	.79
6S7	.79
6SA7	.79
6SC7	.69
6SF5	.69
6SG7	.69
6SH7	.69
6SJ7	.69
6SK7	.69
6SL7	.89
6SN7	.89
6SQ7	.89
6T8	.89
6U8	.89
6V6G	.69
6V6GT	.69
6W4	.69
6X4	.49
6X5	.69
6Y6	1.44
6Z4	.59
6ZY5	.89
7A4	.79
7A5	.89
7A6	.89
7A7	.79
7A8	.89
7B6	.89
7C4	.89
7C5	.89
7F7	.89
7G7	.89
7H7	.89
7N7	.89
7Q7	.89
7S7	.69
7V4	.69
7Z4	.69
12A6	.49
12AT6	.49
12AU7	.79
12AT7	.79
12AV7	.94
12AX4	.83
12AX7	.79
12AY7	1.33
12BA6	.64
12BA7	.64
12C8	.69
12SC7	.89
12SQ7	.89
12SN7	.89
12SF7	.89
12SG7	.89
12H6	.65
12SH7	.69
12SJ7	.69
12K8	.69
12SK7	.69
12SN7	.89
12SL7	.89
12Z3	.69
12AV6	.69
12BD6	.69
12BE6	.79
12BH7	.89
12AW7	.99
12AT7	.99
12AU7	.99
15E	.64
15GP8	.89
16A5	1.98
17Z3	.89
19T8	.89
19AU4GT	1.98
20P4	1.98
20P5	1.98
20P7	1.98
21A6	1.98
24A	.69
25A6	.69
25AV6	.69
25BQ6	.69
25L6	.69
25Z5	.69
25Z6	.69
25Z6WA	.69
27	.49
28D7	1.21
35A5	.89
35B5	.89
35C5	.89
35L6	.89
35W4	.49
35Z3	.89
35Z4GT	.69
35Z5	.89
50A5	.89
50B5	.89
50C5	.89
50L6	.89
50X6	.89
50Y6	.89
70L7	.89
75	.89
76	.69
77	.69
78	.69
80	.69
81W	.99
5651	1.38
5654	1.38
5656	1.38
5670	1.38
5686	1.40
5687	1.40
5702	1.49
5703/WA	1.49
5705	1.19
5725	1.39
5744	.99
5751	2.18
5763	1.39
5814	1.27
5879	1.38
5933	1.49
5963	.98
5965	1.98
6005/WA	1.98
6006/JR	19.98
6005	4.98
6021	1.94
6022A	1.94
6028	2.50
6025	1.79

We Buy Your Surplus Tubes.
Send Us Your List For Highest Quotation
LARGEST BUYERS IN THE COUNTRY

All based and fully guaranteed. Special quantity discount—10% on 100 or more of same type. Minimum order $10.00. Thousands of other types in stock . . . Send us your requirements F.O.B. New York 25% deposit with order or if paid in advance save C.O.D. charges. Rated firms net 10 days. Prices subject to change without notice. For fast service ask for Sy.

FAY-BILL DISTRIBUTING CO. DEPT. E1
418 Broome St., N. Y. 13, N. Y.
Telephone CAnal 6-8404

RELAYS
world's largest stock



★ Immediate Delivery
★ Hundreds of Types
★ All Standard Makes
★ New-Inspected-Guaranteed

Multiple Contact
Standard Telephone Type Relay
CODE 4 TWIN CONTACTS
11-Form A 1-Form B 1-Form C 1-Form D
Heavy duty armature bearing. Available in all standard coil resistances from 12 ohms to 12,000 ohms. Single or quantity prices on request. In stock.

24 HOUR DELIVERY OF THESE TYPES

Standard Telephone Relays
Short Telephone Relays
Midget Relays
Timers
Aircraft Contactors
Rotary Relays
Western Electric Type "E" Relays
Keying Relays
Hermetically Sealed Relays
Voltage Regulators and Cutouts
Differential and Polarized Relays
Special Relays
BK Series
Antenna and Ceramic Relays
Motor and Control Relays
Relay Assemblies
Latching and Interlocking Relays
Mechanical Action Relays
Ratchet and Stepping Relays
Time Delay Relays

Write for New Relay Sales Catalog C-6

Relay Sales
P. O. Box 186-AA, West Chicago, Ill. Phone West Chicago 1100

Your Inquiries to Advertisers Will Have Special Value...

—for you—the advertiser —and the publisher, if you mention this publication. Advertisers value highly this evidence of the publication you read. Satisfied advertisers enable the publisher to secure more advertisers and —more advertisers mean more information on more products or better service—more value—to YOU.

ELECTRONIC

WAR TERMINATION INVENTORIES

WRITE OR WIRE FOR INFORMATION ON OUR COMPLETE LINE OF SURPLUS ELECTRONIC COMPONENTS. ALL PRICES NET F.O.B. PASADENA, CALIFORNIA

C&H SALES CO.
2176-E East Colorado St.
Pasadena 8, California
RYan 1-7393

INVERTERS

10042-1-A Bendix
DC Input 14 volts; output: 115 volts; 400 cycles. 1-phase; 50 watt **$35.00**

12116-2-A Bendix
Output: 115 VAC; 400 cyc; single phase; 45 amp. Input: 24 VDC, 5 amps. **$35.00**

12117 Bendix
Output: 26 volts; 400 cycles, 6 volt amperes, 1 phase. Input: 24 VDC; 1 amp. **$15.00**

12121 Bendix
Input: 24 volt D.C. 18 amp. 12000 r.p.m. Output: 115 volts, 400 cycle, 3-phase, 250 volt amp, 7 pf. **$49.50**

12123 Bendix
Output: 115 V; 3-phase; 400 cycle; amps .5 Input: 24 VDC; 12 amp. **$49.50**

12126-2-A Bendix
Output: 26 volts; 3 phase; 400 cycle; 10 VA; .6 PF. Input: 27.5 volts DC: 1.25 amps. **$24.50**

12130-3-B Bendix
Output: 125.5 VAC; 1.5 amps. 400 cycles single phase, 141 VA. Input: 20-30 VDC. 18-12 amps. Voltage and frequency regulated. **$49.50**

12133 Bendix
Input: 26/29 volt D.C., 28 amps Output: 115 volt, 3 phase, 400 cycle, 250 volt amp., .8 pf. **$59.00**

12143-2-A Bendix
Output: 115 volts: 400 cycles; 250 VA; single phase pf. 9-1. DC Input: 26-29 VDC; 25-22 amp; voltage & frequency regulated **$49.50**

778 Bendix
Output: 115 volt, 400 cycle; 190 VA; single phase and 26 volt, 400 cycle, 60 VA, single phase. Input: 24 VDC. **$37.50**

10285 Leland
Output: 115 volts AC; 750 VA, 3 phase, 400 cycle, .90 pf and 26 volts. 50 VA, single phase, 400 cycle, .40 pf. Input: 27.5 VDC, 60 amps. cont. duty, 6000 rpm. Voltage and frequency regulated. **$59.50**

10339 Leland
Output: 115 volts; 190 VA; single phase; 400 cycle; .90 pf. and 26 volts; 60 VA; 400 cycle, .40 pf, Input: 27.5 volts DC, 18 amps cont. duty, voltage and freq. regulated. **$49.50**

10486 Leland
Output: 115 VAC; 400 cycles; 3-phase; 175 VA; .80 pf. Input: 27.5 DC; 12.5 amps; cont. duty. **$70.00**

10563 Leland
Output: 115 VAC; 400 cycle; 3-phase; 115 VA; 75 pf. Input: 28.5 VDC; 12 amps. **$35.00**

PE109 Leland
Output: 115 VAC, 400 cyc; single phase; 1.53 amp; 8000 rpm. Input: 13.5 VDC; 29 amp. **$50.00**

PE218 Leland
Output: 115 VAC; single phase pf 90; 380/500 cycle; 1500 VA. Input: 25-28 VDC; 92 amps; 8000 rpm; Exc. Volts 27.5 BRAND NEW. **$30.00**

MG149F Holtzer-Cabot
Output: 26 VAC @ 250 VA; 115 V. @ 500 VA; single phase; 400 cycle; input: 24 VDC @ 36 amps. **$40.00**

MG153 Holtzer-Cabot
Input: 24 VDC; 52 amps. Output: 115 volts—400 cycles, 3-phase, 750 VA. Voltage and frequency regulated. **$95.00**

DMF2506M Continental Electric
24-30 volts input; 5.5-45 amps; cont. duty. Output: 115 volts; .44 amps; 400 cyc; 1 phase; pf 1.0; 50 watts. **$39.50**

DUAL OUTPUT MOTOR GENERATOR

mfgd. Holtzer-Cabot MG209
Input: 115V 60 cy. single phase ½ h.p. 3500 r.p.m. Outputs: 24VDC 120 watt and 115 VAC 233 cy. 3 phase 80 VA. Dimensions 21" long, 12" high; weight approx. 120 lbs. ..... **$65.00 ea.**

SELSYNS-SYNCHROS

1CT Cont. Trans. 90/55V 60 cy.	$37.50
1DG Diff. Gen. 90/90V 60 cy.	37.50
1F Syn. Mtr. 115/90V 60 cy.	37.50
1G Gen. 115V 60 cy.	37.50
1SF Syn. Mtr. 115/90V 400 cy.	$12.50
2J1F1 Gen. 115/57.5V 400 cy.	7.50
2J1F3 Gen. 115/57 5V 400 cy.	10.00
2J1FA1 Gen. 115/57.5V 400 cy.	7.50
2J1G1 Cont. Trans. 57.5/57.5V 400 cy.	5.00
2J1H1 Diff. Gen. 57 5V 400 cy.	7.50
2J5D1 Cont. Trans. 105/55V 60 cy.	17.50
2J5F1 Cont. Trans. 105/55V 60 cy.	17.50
2J5H1 Gen. 115/105V 60 cy.	17.50
2J15M1 Gen. 115/57.5V 400 cy.	17.50
5CT Cont. Trans. 90/55V 60 cy.	34.50
5D Diff. Mtr. 90/90V 60 cy.	34.50
5DG Diff. Gen. 90/90V 60 cy.	34.50
5F Syn. Mtr. 115/90VAC 60 cy.	34.50
5G Syn. Gen. 115/90VAC 60 cy.	34.50
5HCT Cont. Trans. 90/55V 60 cy.	42.50
5SDG Diff. Gen. 90/90V 400 cy.	12.50
6DG Diff. Gen. 90/90V 60 cy.	25.00
6G Syn. Gen. 115/90VAC 60 cy.	34.50
7G Syn. Gen. 115/90VAC 60 cy.	42.50
R110-2A Kearfott Cont. Mtr. 115V 400 cy.	17.50
R200-1-A Kearfott Cont. Trans. 26/11.8V 400 cy.	15.00
R210-1A Kearfott Trans. 26/11 8V 400 cy.	15.00
R235-1A Kearfott Resolver 26/11 8V 400 cy.	22.50
C56701 Type 11-4 Rep. 115V 60 cy.	20.00
C69405-2 Type I-1 Transm. 115V 60 cy.	20.00
C69406 Syn. Transm. 115V 60 cy.	20.00
C69406-1 Type II-2 Rep. 115V 60 cy.	20.00
C76166 Volt. Rec. 115V 60 cy.	10.00
C78248 Syn. Transm. 115V 60 cy.	12.50
C78249 Syn. Diff. 115V 60 cy.	5.00
C78863 Repeater 115V 60 cy.	7.50
C79331 Transm. Type 1-4 115V 60 cy.	20.00
851 Bendix Autosyn Mtr. 32V 60 cy.	7.50
403 Kollsman Autosyn Mtr. 32V 60 cy.	7.50
CK5 Bendix Mtr. 2 phase 26V 400 cy.	17.50
FPE-25-11 Diehl Servo Mtr. 75/115V 60 cy.	22.50
FPE-43-1 Resolver 400 cy.	25.00
FJE-43-9 Resolver 115V 400 cy.	25.00
999-0411 Kollsman 26V 400 cy.	15.00
1377-0410 Kollsman 26V 400 cy.	10.00
15158-0410 Kollsman 26V 400 cy.	20.00
10047-2-A Bendix 26V 400 cy.	12.50
2900 Transicoil 115V 400 cy.	15.00

ESTERLINE-ANGUS RECORDER

Model AW 0-1 MA

DC Milliameter permanent magnet moving coil type. Spring clock duel speed drive (hour and minute). Instructions including connection diagrams and instrument data sheet with each instrument.
Portable case **$200.00**

RATE GYRO TYPE T-2004-3C-A MFG. KEARFOTT CO.

Gyro motor excitation 115V, 400 cy. 3 ph. Take off output: 26 VAC 400 cy. single phase. Rating 20°/sec. Approximate Diameter 3¼", Height 2⅜". Weight 1¾ lbs. Hermetically sealed. Equipped with 28 VDC heater. Operates efficiently in range of —54°C to +71°C. Sensitivity .2250 volts/degree at 10K load. This is the famous Gyro used in many military units. Government cost over $1700.00. New condition.
Limited quantity @ ..... **$150.00 ea.**

CENTRALAB ROTARY POWER SWITCHES



Steatite—750 watts at 115 VAC
Has positive, non-stall 20° indexing, double wiping solid silver contacts. (Mounting bushing ⅜"-32 thd)

a) 1 deck, 12 positions, 3 pole	$2.50
b) 5 deck, 12, positions, 3 pole	7.50
c) 6 deck, 12 positions, 3 pole	8.50

SMALL DC MOTORS



(approx. size overall 3¾" x 1¼" dia.)

5069600 Delco PM 27.5 VDC 250 rpm	$12.50
5069230 Delco PM 27.5 VDC 145 rpm	15.00
5068750 Delco 27.5 VDC 160 rpm w/brake	6.50
5068571 Delco PM 27.5 VDC 10,000 rpm (1x1x2")	5.00
5069625 Delco 27.5 VDC 120 rpm w/governor	15.00
MM A-11 Globe PM 24 VDC	7.50
5BA10AJ18 GE 24 VDC 110 rpm	10.00
5BA10AJ37 GE 27 VDC 250 rpm reversible	10.00
5BA10AJ52 27 VDC 145 rpm reversible	12.50
806069 Oster series reversible 1/50 h.p. 10,000 rpm 27.5 VDC 1⅛" x 3½"	5.00
C-28P-1A 27 VDC 1/100 h.p. 7,000 rpm	3.00
7100-8 PM Hansen 24 VDC 160 rpm	7.50
5SFD-6-1 Diehl PM 27.5 VDC 10,000 rpm	4.00
6-volt PM Mtr. mfgd. by Hansen 5,000 rpm 1¼" in dia. 2" long overall	4.00

ELECTRONIC TUBES —
All types – one dependable source !

- ALL V. H. TUBES are new, first quality and unconditionally guaranteed.
- ALL V. & H. TUBES advertised are in stock.
- All V. & H. TUBES are standard brands—R.C.A., Sylvania, G.E., Raytheon, Federal, etc.
- ALL TUBES—HATO, JAN, commercial, special purpose, transmitting and receiving from one source—V. & H. RADIO AND ELECTRONICS!

0A2	1N73	2J55	4J42	6SJ7Y	250TH,TL	574AX	875	5643	5962
0A3/	1N76	2J56	4J50	6SK7W	252A	575A	876	5644	5963
VR75	1N78	2J61A	4J51	6SL7W	253A	592	879	5645	5921
0A4/	1N79	2J62	4J52	6SN7	254A	615	884	5646	5922
0A5	1N91	2K22	4J59	6SN7W	259A	KU627	884	5647	5923
0B2	1N92	2K23	4PM60A	GT	264B	631-P	885	5651	5945
0B2WA	1N93	2K24	4X-150A	6SQ7	274A	666-P1	887/RA	5654/WA	5946
0B3/	1N126	2K26	4X-150G	GTY	QK284	HK654	891	5654	5962
VR90	1N127	2K28	4X250B	6X4W	299A	700B	892	5657	5963
0B4	1N128	2K29	4X-500A,	6X5GT	PM100	705A	892R	5658	5965
0C3/	1N158	2K30	F	7BP7, A	304B	704A	891A	5659	5977
VR105	1N198	2K33A	C1B	7CP1	304B, L	705A	895	5661	5980
0D3/	1P21	EL1B	7UP7	T4, TL	705A	892P1	5647	5982
VR150	1P24	2K41	4AP1	7YP7	GGJ305	5SERIES	898	5647	5993
0D3W	1P30	2K42	4BP1	8D21	CEJ06	707A, B	923	5670	5995
0Z4	1P31	2K43	4BP4	9LP1	307A	709EA	930	5672	6072
1A3	1P32	2K44	4C22	9LP7	310A	715A	930	5677	6002
1A7G	1P36	2K45	4CP1	10E/13	311CT	713A	931A	5686	6005
1B3/GA4B	1P39	2K46	4CP2A	10KP22	311A	713A, AY	CW-931A	5686	6005
1B3/GA4C	1P30	2K47	4CP7	10KP7	316A	713A, B, C	944	5686	6021
/5867	1P40	2K48	5D21	10KP17	ML-322	717A	955	5687	6028
1A6G4	1P42	2K49	5FP7A	11	T927A	715A	956	5687/WA	6044
1B-1	1Z2	2K54	5FP14A	12AT7	C-316	729	957	5691	6045
1B3/	2AC/15	2K55	5GP1	WA	317A	5SERIES	958A	5692	6050
1C31	2AC/15	2K56	5HP4	12AU7	317CA	707A, B	959	5693	6072
1B22	2AJ1	2X2A	5J21	WA	348A	CK-772A	991	5696	6073
1B23	2AP1	2AP1	5J26	15E	350A, B	CK-722	1001	5702	6074
1B24	2BP31		5J29	FG17	354C, F	715A/B	CK1005	5702/WA	6076
1B24A	2B22	2B4	5J30	RX21	368A	724B	CK1009	5703	6080W
1B27	2B23	2B24	5J31	HK24	171A, B	724A, B, C	YR1031K	5703/WA	6082
1B32	2B24	2B24W	5JP1	24G	ML-331	VC-1258	DG-1295	5704	6083
1B35A	2C22	WA	5LP1	RK20A	386A	725	DG-1296	5710	6085
1B36	2C34	2B25	5NP1	RK25	393A	5SERIES	CK-1301	5719	6090
1B37A	2C35	2B26	5RP4GY	25	394A	700TL	1003	5721	6097
1B38	2C36	2B28	5R4WGY	25Z6W	397A	800	1031	5722	6100
1B40	2C37	2B29	5RP11A	GT	401A	801A	1613	5726	6101
1B42	2C39, A	2B30	5TP1	26Z5W	403A, B	802	1614	5727	6102
1B44	2C40	2C21	GTA	28DTW	404A	803	1616	5727	6111
1B46	2C42	2C31	5ZP16	31Z	407A	804	1620	5732	6112
1B47	2C43	2C33	6AP7W	RK-34	408A	805	1621	5744	6136
1B50	2C44	2D6	6AP4A	35T, TG	409A	806	1622	5746	6140
1B51	2C45	2D21A	6AQ7Y	RK-39	412A	807, W	1624	5748	6141
1B52	2C50	2D22	6AH4	T-40	416	808	1625	5749	6142
1B53	2C51	2D24	6AH6	TZ-40	416A, B	809	1626	5751	6147
1B54	2C52	2DP1, S2	6AJ5	RX-47	417A/5842	810	1628	5763	6148
1B56	2C53	2E29	6AJ5D	RK-49	418A	811, A	1629	5764	6150
1B58	2D21	2EP1	6AK1W	V-50	419A	812, A	1631	5766	6158
1B59	2D21W	2FP7A	6AL5W	52HAP7	420A	811	1632	5768	6159
1B60	2E22	2GP1A	6AN5, WA	RK-55	422A	813	1635	5768/WA	6160
1B61A	2E24	2J31	6AN8	HY-65	422A	816	1638	5784	6201
1B68	2E26A	2K21	6AQ5W	HY-60	422A	826	1641	5787	6206
1B100	2E36	2K23	6AS6	RK-72	422A	826	1642	5792	6245
1C	2E36	2K25	6AS6W	RK-73	428A	826	1644	5793	6246
1C21	2E37	2L54	6AS7G	RK-75	429A	828	1654	5798	6247
1D	2E38	2P28	6BA6W	75TL, TL	430A	829	1655	5799	6267
1K	2E39	3A/4	6BA7	BR-50	438A	830B	1656A	5798	6268
1N21,	2E40	4-65A	6BE6W	CV-52	446A, B	832A	1907	5800	6295
A&C	2F21	4-65A	6BF5	C-1004	ZP445	833A	1908	5814	6336
1N22	2H21	4-250A	6BF7, W	HF100	450TH, TL	834	2050	5813	6002
1N23, A, B, C,R	2J21	4-400A	6BL6	100TH,	451A	836	2051	5814A	6003
		4-1,000A	6BM6	TL	464A	837	4220		6004
1N25	2J22	4B22	6C	101D	464B	838	4338	5819	6013, A
1N26	2J24	4B23	6C4W	FG105	471A	841	4340	5820	6014, A
1N27	2J25	4B24	6C21	WX21A	471A	841	4348	5823	6014A
1N33	2J26	4B26	6D4	VT127, A	805AX	845	4349	5825	6015
1N34	2J27	4B30	6F4	151N	807AX	845W	4350	5826	6016
1N34, A	2J28	4B31	6F5GT	F-124A	808	850	4351	5829	6020
1N35	2J30	4B32	6J5	FG154	810	851	4527	5841	6025A
1N38A	2J31	4B33	6J7	QK135	811X	852	4528	5842	6001
	2J32	4B34	6J4	151	812AX	853	4546	5843	6002
1N41	2J33	4B36	6J4WA	QK202	826AX	857B	4548	5844	6003
1N42	2J34	4C22	6J5GT	201A	827	860	4549	5847	6004
1N43	2J35	4C24	6J5WGT	203A	828	861	4550	5847	6005
1N44	2J38	4C28	6L5WGA,	207	832AX	862A	4551	5851	6006
1N47	2J41	4C35	GB	211D	N-311	864	5636	5854	AX5903
1N52	2J45	4C36	6Q5GM	212D	813	865	5635	5855	1N21A
1N55	2J46	4D21	6SA7W	217C	813AX	866A	5637	5879	D96475
1N56A	2J49	4D22	GT	218	813AX	868	5638	5880	D164496
1N57	2J50	4D27	6SA7Y	220B, C	813AX-A	872A	5639	5881	D171441
1N58	2J51, B	4J31	6SB7Y	NX231A	815	872A	5640	5894	1N3038
1N59	2J52	4J32	6SC7GTY	231A	813AX	874	5641	5895	6421640
1N70	2J53	4J33	6SG7Y	240A, B, C	77AX	874	5642	5899	G1

PRICES AND CATALOGUES ON REQUEST.

SEND US YOUR INQUIRIES TODAY

REMEMBER: WE ALSO BUY ALL TYPES OF ELECTRONIC TUBES

V & H RADIO AND ELECTRONICS SUPPLY

2029 2047 W. VENICE BLVD. LOS ANGELES 6, CALIF. REpublic 0215

WEATHER EYE RADAR

10 cm. 3,000 mcs. 4-20-50-100 mile range. 360° azimuth. 80° elevation sweep. 7" PPI. Beacon position ref. scope. Lightweight, Western Electric Mfg. Brand new. Complete. $2,400.

S BAND

GUIDED MISSILE BEACON FILTER CAVITY F-28/APN-19 2700-2900mc. 1.5-db max. loss at ctr. freq. over band, 3db at 15 mc band ends. JAN spec. Ideal as standard reference cavity. Brand new. Guaranteed, $37.50.
AN/APN-60 Crystal Mounting, $19.50.
COAXIAL CRYSTAL MOUNT. Type N fittings, tuneable silver plated. Holds any IN21 type Xtal. $15.00.
PULSE XFMR .3mu Sec. 1000 cy. 13.5 kv, 9.5A: 3kv 64A; 200V, 6"x2"x5" o.a. $14.50.
FEEDBACK DIPOLE ⅞" coax, 11¾" o.a. $14.50
60MC. IF STRIP uses (6) 6AK5, $9.50

X BAND

CUTLER FEED DIPOLE, 1"x½" slvr pl. $4.75.
E PLANE BENDS UG39/40 std Radius, pl. $4.75.
MITRED BEND. Vy Short Radius. E plane, $10.00.
TRANSITION, 1"x½" to 1¼"x⅝" Lgth 2¼", $6.50.
TWIST 90 DEGREE, UG39 to UG40, Silverd plated, $6.50.
CRYSTAL MOUNT. Hold any IN23 type xtal, 1" x ½" guide and coax output. UG40 flg. input, $15.00.
AS 24/APS 6 ROTARY JOINT SET $75.00.
DIRECTIONAL COUPLER "Airtron" 20 db. pressurized cross guide type. Aluminum, $18.50.
DUPLEXER, latest type incl. ATR switch tube mount, directional coupler, etc. 1"x½" guide, $27.50.
LINE STRETCHER, VSWR matching device for XMSN Lines, $34.50.

K BAND

DIRECTIONAL COUPLER bi-dir. UG-115/U flanges, $52.50.
KLYSTRON OUTPUT COUPLING for 2K50. RG 66/U guide, $6.50.
H BEND 90 deg. CG346/U, $12.50.
E BEND 90 deg. CG345/U. Cplg. UG-117 to UG-116. RG66 guide, $12.50.
ADAPTERS 1¼" lg UG116 to UG116, UG117 to UG117 ea. $5.00

TEST EQUIPMENT

MIT type TS155 Signal Gen. 2C40 lighthouse cavity 2700-2900mc, wg below cutoff atten., thermistor bridge, 115vac reg. pwr. supply, $325.00.
OAP WAVE METER, freq. meter 100-200mc band, $85.00.
10CM THERMISTOR BRIDGE — Power meter, direct reading, complete. Western Electric. $85.00.
ECHO BOX, TS-207/UP 2700-2900mc. $64.50.
ECHO BOX, OBU-3, Precision w/detector and meter, $325.00.
TTX 10RM 3 CM FM TEST SET. Sig. Gen., Freq. meter, calib. attenuator, Thermistor Bridge. 115v. 60 cy ac. $175.00.

RADIO-RESEARCH INSTRUMENT Co.
550 - 5 Ave., N. Y. 19, N. Y. Tel: JU 6-4691
PAUL J. PLISHNER

LOW-VOLTAGE TRANSFORMERS

New Release of Government Surplus Material

Model #8-9527. KENYON TRANSFORMER CO. — 2.3 KVA. Input 110/220 volts 50/60 Cy. Output 11 Volts C-T (5.5-0-5.5) At 200 Amperes! Continuous Duty. Case Size 8½ x 10½ x 13".

Price BRAND NEW ONLY ..... **$23.95 Ea.**
#8-9527-WE. — WESTINGHOUSE—Same Specs. But Single 115 V Input & Lighter Ft. NEW $22.95

DOZENS OF USES FOR INDUSTRIALS, TESTING LABS, EXPERIMENTAL UNITS & SCHOOLS
★ Heavy-Duty Soldering ★ Dip-Soldering ★ Plating ★ Battery-Chargers ★ Spot-Welding ★ Welding ★ Magnetizers ★ Heat-Treating ★ Electromagnets ★ Testing — Tubes, Coils, Breakers, & Relays.

Terms: Prices FOB St. Louis. Cash With Orders. Well Rated Concerns (D&B) Net 10 Days Cash.

McNEAL ELECTRIC & EQUIPMENT CO.
4736 Olive St., Dept. E-12, St. Louis 8, Mo.

PULSE TRANSFORMER PT-3
TUBE BASE PLUG-IN TYPE



Similar characteristics to UX 7350. Precision-made. Two 100-turn and two 50-turn coils wound on high quality hypersil cores. Built into octal bakelite tube bases. Completely impregnated and sealed—humidity-resistant. Diagram on end disc of each unit provides versatility of application.





THESE PT-3 TRANSFORMERS may be used

- In Blocking Oscillator, Multivibrator and Scope Circuits.
- For interstage coupling, impedance matching and isolation.
- Wherever accurate timing and triggering are essential.
- In circuit applications requiring the generation of low power and low voltage pulses.
- In circuits utilizing repetition rates from 0 to well over 1 MC and pulse widths from .03 microsecond.

CHARACTERISTICS
Impedance, ohms 120
Rise time, microseconds .03
Drop in 1 microsecond 20%
2 microseconds 40%
5 microseconds 65%
10 microseconds 75%



LOW INTRODUCTORY PRICE { Only $5.95 ea. / 2 for $11.00

Cramer Electronics, Inc.

811 Boylston St., Boston 16, Mass. CO 7-4700

Write for Bulletin of late items.

THYRATRONS?

C1A	4.50
C1K	6.00
FG105	12.00
5557/FG17	4.50
5720/FG33	7.50

Always stocked at

PAGE ELECTRONICS

COMMUNICATIONS EQUIPMENT CO.

MOVING TO LARGER DISPLAY QUARTERS

ON OR BEFORE JAN 1, 1956

To Serve You Better

343 CANAL ST - N. Y. C. - OPP CHURCH ST.

CHAS ROSEN • Phones — DI-9-4124 and CA-6-4882

HI-POWER SERVO TRANSFORMERS

INPUT TRANS: Amertran #31136. Response: 10 cy.—100 cy. Primary—500/125 ohms. Secondary 6800/1700 ohms. Level 43VU. $27.50
Output Trans: Amertran #31138. Response: 10 cy.—100 cy. at 58 V.U. Level. Primary: 3600/900 ohms. Secondary: 30/40/50/60 ohms $38.45
Set of input and output $57.50

PULSE TRANSFORMERS

4P37: Primary, 50 Ohms 750V, .001 Duty. Sec. 15KV, 1000 Ohms Impedance. Bifilar 12.6V/2.5A $32.50
RAYTHEON WX 4298E: Primary 4KV., 1.0 USEC. SEC. 16KV-16 AMP DUTY RATIO: 001 400 CYCLE FIL. TRANS. "BUILT-IN" $42.50
WECO: D-163247 For Modulator of SCR 720 ... $22.50

GE #K-2449A
Primary: 9.32 KV, 50 ohms Imp.
Secondary: 28 KV, 450 ohms.
Pulse length: 1.05/5 usec @ 635/120 PPS. PK Power Out: 1,740 KW
Bifilar: 1.5 amps (as shown) $62.50
GE #K-2748-A, 0.5 usec @ 2000 Pps. Pk. Pwr. out is 32 KW impedance 40:100 ohm output. Pri. volts 2.3 KV Pk Sec. volts 11.5 KV Pk. Bifilar rated at 1.3 Amp. Fitted with magnetron well $24.50
K-2745 Primary: 2.1/2.8 KV, 50 ohms Z. Secondary: 14/12.6 KV 1025 ohms Z. Pulse length: 0.25/1.0 usec @ 800/800 PPS. Pk. Power 200/150 KW. Bifilar: 1.3 Amp. Has "built-in" magnetron well $32.50
K-2461-A. PRimary: 3.1/3.6 KV—50 ohms (line). Secondary 14/11.5 KV—1000 ohms Z. Pulse Length: 1 usec @ 800 PPS. Pk. Power Out: 200/130 KW. Bifilar 1.3 Amp. Fitted with magnetron well $29.50
K35145—Pulse inverdion: PRI: 5 KV PK. Pulse Negative. Sec: Pos. Pulse, 4 KV; 1 usec. and .001 DUTY RATIO $6.50
54J318-1—3 wdgs. Ratio: 1:1:1, 1.10 uh. /wdg., 2.5 ohms DCR $3.50
UTAH X-151T-1: Dual Transformer. 3 Wdgs. per section 1:1 Ratio per sec 13 MH inductance $0 ohms DCR $5.00
UTAH X-150T-1: Two sections. 3 Wdgs. per section, 1:1:1 Ratio. 3 MH. 6 ohms DCR per Wdg. ... $5.00
68G711: Ratio: 4:1 ri: 200V, Sec. 53V, 1.0 usec Pulse @ 2000 PPS. 0.016 KVA $4.50
TR1049 Ratio 21 Pri. 220 MH, 50 Ohms, sec. 0.75 H. DCR 100 Ohms $6.75
K-904895-501: Ratio 1:1, Pri. Imp. 40 Ohm. Sec. Imp. 40 Ohms. Passes pulse 0.6 usec with 0.05 usec rise $8.95
RAYTHEON, UX-7350, UX-7307 ..... $5. ea.

PULSE NETWORKS

H-616 10KV, 2.2 usec., 375 PPS, 50 ohms imp. .$27.50
H-615 10KV, 0.85 usec., 750 PPS, 50 ohms imp. .$27.50
K58865 CHARGING CHOKE: 115-150 H @ .02A. 32 40H @ .08A. 21 KV Test $37.50
G.E. 9E25-1-350-50 PRT, "E" CKT, 1 Microsec. Pulse @ 350 PPS. 50 Ohms Impedance $69.50
KS9623 CHARGING CHOKE: 16H @ 75 MA, 380 Ohms DCR, 9000 Vac Test $14.95
H-605: 25 KV, "E" CKT, 1.5 usec. 400 PPS, 50 Ohms Impedance, 5 sections $62.50

PULSE MODULATORS

MIT. MOD. 3 HARD TUBE PULSER: Output Pulse Power 144 KW (12 KV at 12 Amp.) Duty Ratio: .001 max. Pulse duration: 5, 1.0, 2.0 microsec. Input voltage: 115 v. 400 to 2400 cps. Uses: 1-71B, 4-89-B, 3-'72's, 1-'73. New ..... Less Cover—$135
Airborne RF head, model A1A, delivers 50 Kw peak output at 3000 mc. at .001 duty. Complete with pulser unit and all tubes $185.00

DELAY NETWORKS

D-168184: 0.5 usec. up to 2000 PPS, 1800 Ohms. $4.00
D-170499: 0.25/.5/.75usec. 8 KV., 50 Ohms $8.50
D-165997 Delay 1.25 usec ..... $ 5.50
RCA #25565G-502: 1.7 usec. 1400 ohm impedance $2.00
D-162314, Delay of 0.5 usec. 72 ohms with 4 MC. Bandwidth $4.75
4-172578, 416 ohms Imp., 0.22 usec. Delay $4.75
D-150979: Oscillating network. Oscillates at 81,955 kc. When normal current of 10ma. is interrupted. Has built-in temperature control for stability. Assembled in shielded can 4" L x 4" Diam. $4.35

POWER TRANSFORMERS

COMBINATION—115V/60~INPUT

CT-131	150-C-150V/65MA, 6.3V/2.5A,6.3V/0.6A	$1.79
CT-127	900V/25MA PK, 5V/2A, 2V/7.5A	2.79
CT-086	350-0-350V/120MA, 5VCT/3A, 2.5VCT/ 12.5A, 2.5VCT/3.5A	4.39
CT-965	78V/0.6A, 6.3V/2A	3.95
CT-004	350-0-350V/90MA, 5VCT/1A, 2.5VCT/ 12.5A	4.60
CT-002	350-0350V/50MA, 5VCT/2A, 2.5VCT/ 7.5A	3.65
CT-479	7000V/.018V, 2.5V/5A/17,000 V. Test	22.50
CT-013	450-0450V @ 200MA, 10V/1.5A, 2.5, 3.5A, 5V/3A	4.35
CT-401	350VCT .025A 5V 1A	2.75
CT-931	685VCT .080A 5V 1A, 6.3V 4A	4.25

PLATE—115V/60~INPUT

PT- 07	400VCT/4.0 AMPS For RA61	17.50
PT 034	125V/45MA (For Preamp)	1.15
PT 133	3140/1570V. 2.36KVA	85.00
PT 801	22,000V/.234 MA., 5.35 KVA	115.00
PT 521	7500V/.06A. Half Wave	59.50
PT 913	2500V/12 MA H'SLD	4.95
PT-38-2	37.5/40V AT 750 MA	2.15

FILAMENT—115V/60~INPUT

FT-157	4V/16A, 2.5V/2.75A	2.95
FT-101	6V/.25A	.79
FT-924	5.25A/21A, 2x7.75V/6.5A	14.95
FT-824	2x26V/2.5A, 16V/1A, 1.2V/7A, 6.4V/10A 6.4V/2A	8.95
FT-463	6.3VCT/1A, 5VCT/3A, 5VCT/1A	5.49
FT-55-2	7.2V/21.5A, 6.5V/6.85A, 5V/6A, 5V/1A	8.95
FT-38A	6.3V/2.5A, 2x2.5V/7A 5KV Test	2.79
FT-650	2.5V/10A-3KV TEST LO-CAP	7.50
FT-825	2.5VCT/10A, 10KV TEST	6.95

FILTER CHOKES

Stock	Description	Price
CH-914	12HY/250 MA 2500 V. Test	$3.75
CH-CEC	3127-0-600H/.05-400 MA, 10 KV Test	$14.95
CH-313	2.5H/700 MA, 2.5 KV Test 18 Ohms	5.75
CG-044	8.5H/350 MA, 3.5 KV Test 50 Ohms	6.35
CH-291	6-1H/12 A, DCR: 0.3 Ohms	12.50
CH-291	6-1H/12 A, DCR: 0.3 Ohms	12.50
CH-322	.35H/350 MA—10 Ohms DCR	2.75
CH-341	Dual 7H/75 MA, 11H/60 MA	4.69
CH-69-1	Dual 120H/17 MA	2.35
CH-775	1.78H/130 MA/75 ohms	2.25
CH-344	1.5H/145MA/1200V Test	2.35
CH-366	20H/300 MA.	6.95
CH-999	15HY/15 MA—400 ohms DCR	1.95
CH-845	0.5HY/250 MA, 22.5 ohms, 3600 V.T.	1.29
CH-178	2x0.5H/380 MA, 25 ohms	2.79
CH-533	13.5H, 1.8 AMP DC. 13.5 KVINS.	29.95

400 CYCLE TRANSFORMERS

(All Primaries 115V, 400 Cycles)

KS13101	6.3V/15A, 6.3V/0.9A, 6.3V/0.4A, 6.3V/0.3A	$3.85
KS13104	1450VCT/0.281A, 1050VCT/0.217A.	7.50
KS9615	6.3V/4A, 1V/1A	1.57
KS9318	6.3V/4A, P/O R-55/ARQ-9	1.35
KS9608	1231/.35MA, 1148VCT/.07A	5.79
352-7187	6.3V/2.5A	1.45
M-7472426	1450V/1.0MA, 2.5/.75A, 6.4V/3.9A, 5V/2A, 6.5V/.3A, P/O ID-39/ APG-13	4.95
352-7039	640 VCT @ 380MA, 6.3V/.9A, 6.3V-6A 5V/6A	5.49
702724	8800 /5680 @ 12MA	8.95
KS9584	5000V/290MA, 5V/10A	22.50
KS9607	734VCT/.177A, 1710VCT/.177A	6.79
352-7273	700VCT/350MA, 6.3V/0.9A, 6.3V/ 25A, 6.3V/.08A, 5V/CA	6.95
352-7070	2x2.5V/2.5A (2KV TEST), 6.3V/ 2.25A, 1200/100/750V, @ .005A	7.45
352-7196	1140/1.25MA, 2.5V/1.75A, 2.5V/ 1.75A—5KV TEST	3.95
352-7176	320VCT/50MA, 4.5V/3A, 6.3V/CT 2A, 2x6.3VCT/6A	4.75
RA6486-1	2.5/1.75A, 6.3V/2A—5KV Test.	2.39
901697	11V5A	2.49
901695-501	2.77V @ 4.25A—10KV Test	3.45
901698-501	900V/75MA, 100V/.04A	4.29
Ux8855C	900VCT/.067A, 5V/1A	3.79
RA6405-1	880VCT/65MA, 5VCT/3A	3.69
T-48852	700VCT/886MA, 5V/3A, 6V/1.75A	4.25
352-7058	2500V/6MA, 300VCT/135MA	5.95
KS9336	110V/50MA TAPPED 625V 2.5V/5A	3.95
M-7474319	6.3V/2.7A, 6.3V/.66A, 6.3VCT/21A	4.25
KS9954	27V/4.1A, 63V/2.9A, 1.25V/.02A	2.59
52C080	650VCT/50MA, 6.3VCT/2A, 5VCT/ 2A	3.75
32112	400VCT/35MA,6.4V/2.5A,6.4V/.15A	3.85
68G611	1158-0-1158V 2MA	2.75
68G194	5VCT/.800MA RVA	1.75
302411A	6.3V/9.1A, 6.3VCT/6.5A, 2.5V/3.5A, 2.5/3.5A	4.85
KS9445	592VCT/118MA, 6.3V/8.1A, 5V/2A	5.19
KS9535	6.4/7.5A, 6.4V/3.8A, 6.4/2.5A	4.79
78G36G1	600VCT/36MA	2.65
M-7474318	2100V/.027A	4.95

VHF TEST SET

The signal generator is designed to serve as an aid in aligning 152-162 megacycle FM receivers. It consists primarily of a temperature controlled crystal oscillator, the plate circuit of which is tuned to the 48th harmonic of the crystal frequency. The generator provides an extremely stable output which can be varied continuously from zero to well over a hundred microvolts. Provision has been made for two-frequency output provided that is utilized.



a dual crystal

New, Less Crystal $32.50

DYNAMOTORS

TYPE	INPUT VOLTS	INPUT AMPS	OUTPUT VOLTS	OUTPUT AMPS	Prl
BDAR13	14		375	.150	$6.50
35X-059	35	3.8	485	.095	4.35
POSX-15	14	2.8	220	.08	8.95
DM13A	28	7	540	.250	3.95
23350	27	1.75	285	.075	3.95
B-19	12	9.4	275	.150	6.95
			500	.050	
DA-3A*	28	10	300	.260	3.96
			150	.010	
			14.5	5.	
PE73CM	28	19	1000	.150	10.50
BD 69†	14	2.8	220	.80	8.95
DAG-33A	18	3.2	450	.06	2.50
BDAR 93	28	3.25	375	.150	6.95

‡Less filter *Replacement for PE 94S
PE 94-, Brand New 5.95

INVERTERS

800-1B Input 24 vdc, 62 A. Output: 115 V. 800 cy. 7A, 1 phase. Used, excellent $10.75
PE-218H: Input: 25/30 vdc, 92 amp. Output 115V 300/500 cy 1500 Volt-ampere. NEW $32.50
PE206: Input: 28 vdc, 30 amps. Output: 80 V 800 cy, 500 volt-amp. Dim. 13 x 8½ x 10½. New. $22.50
AN3187-1. Input: 13.75 V; 18.4A. Output: 115 V/400~, 3ϕ, 0.95 PF. New $59
PU 7/AP. Input: 28 vdc/160 A. Output 115 VAC, 400~, 1ϕ, 500 VA., 21.6 Amp. Volt, and Freq. Reg. Used, Exce. $75

X BAND — 1" x ½" WAVEGUIDE

AT-68/UP 3 Cm Horn with type N. feed for receiver measurements, etc. New (as shown) $7.45
ROTARY JOINT (AIR-6) Sperry PT #658275, 180 deg. rotation, choke-to-choke. Has "Built-in" Di-Coupler, 20 DB., with "N" Takeoff $22.50
PARABOLOID DISH, 18" Diam. Spun Aluminum, 9" Focus. For AN/AIR-6 ..... $4.95
3 CM. DIPOLE and Feed Assembly. (May be used with above dish.) 8 inches long $5.00
FLEXIBLE SECTION 9 in. long Cover-to-Cover. $5.50
3CM. DIPOLE FEED, 15" L. for AIR-15 10¼" Focus $15.50
MITRED ELBOW. Cast aluminum, 1¼" x ¾" W.G. W.E. Flanges, "E" Plane $3.50
3 CM. ANTENNA ASSEMBLY: Uses 17" paraboloid dish, operating from 24 vdc motor. Beam pattern: 5 deg. in both Azimuth and elevation. Sector Scan: over 180 deg. at 35 scans per minute. Elevation Scan: over 2 deg. Tilt: Over 24 deg. $35.00
Cross-Guide Directional Coupler. UG-40 output flange. Main Guide is 6" Long, with 20 Deg. "E" Plane bend at one end, and is fitted with Std. UG 39/UG 40 flanges. Coupling figure: 20 db Nominal $22.50
RG52/U Waveguide in 6" lengths, fitted with UG 39 flanges to UG40. Silver plated. ..... per length $5.00
Rotating-Joints supplied either with or without dark mountings. With UG40 flanges ..... each $17.50
Bulkhead Feed-thru Assembly $15.00
Pressure Gage Section with 15 lb. gauge $10.00
Directional Coupler, UG-40/U Take off 20db $17.50
MAGNET AND STABILIZER CAVITY For 2J61 Magnetron $24.50
90 degree elbows. "E" plane 2½" radius $8.50
ADAPTER, waveguide to type "N", UG 51-U, p/o TS 12, TS-13, Etc. $7.50
ADAPTER, UG-165/U round cover to special HTL Flange for TS-45, etc. ..... $2.50 ea.

JAN WAVEGUIDE FLANGES

UG 39/U	$1.10	UG 51/U	$1.65
UG 40/U	$1.25	UG 52/U	$3.40
UG 40A/U	$1.65	UG 52A/U	$3.40

MAIL ORDERS PROMPTLY FILLED. ALL PRICES F.O.B. NEW YORK CITY. M.O. OR CHECK. ONLY SHIPPING SENT C.O.D. RATED CONCERNS SEND P. O. PARCELS IN EXCESS OF 20 POUNDS WILL BE SHIPPED VIA CHEAPEST TRUCK OR RAILEX.

343 Canal St., New York 13, N.Y. Dept. E-1 Chas. Rosen Phone: CAnal 6-4882



BRAND NEW

T-350XM

RADIOTELEPHONE
RADIOTELEGRAPH

TRANSMITTER

COMPLETE

- 2,000—20,000 KCS
- 350 Watts—A1 Output
- 250 Watts—A3 Output
- Built in Master Oscillator
- 5 Crystal Positions.
- Multi Range Impedance Antenna Tuning Network
- Manual or High Speed Keying
- Uses 2—813 P.A. and 2—805 Modulators Hi-Level Class B.
- Speech Amplifier, Remote, Mfg. by RCA
- Technical Manuals(2) with Each Transmitter.
- Size 59" X 16" X 24"
- Wt—690 Lbs. Net
- Power Input: 210/250 Volts Single Phase 50/60 Cycles
- Brand New—Complete—Unused

This modern precision built point-to-point transmitter is now available for delivery singly or in quantity to interested users at an attractive price. This transmitter is similar in characteristics to the RCA Model ET-4336.

The T-350XM was manufactured by Technical Radio Corporation, San Francisco, California, for the U. S. Signal Corps. All are new, unused and export cased. Each transmitter carries our guarantee. Spare parts available. Quotations on request.

COMMUNICATION DEVICES CO., INC

TWX—NY1—223
Cable—Communidev, N. Y.
Tel. ADirondack 4-6174

2331 TWELFTH AVENUE
NEW YORK 27, N. Y.

NEED METERS?

STANDARD or SPECIALS

ANY QUANTITY — NEW — SURPLUS

FOR ELECTRONIC — MILITARY
AIRCRAFT — HAMS

ALL MAKES — MODELS
RANGES — SIZES

METERS REPAIRED
RESCALED
RECALIBRATED

WRITE - PHONE - WIRE

INSTRUMENT SERVICE

455 B. 67th St.
Arverne, New York
CAA No. 4264 Ltd. NE 4-8594

XMITTING POWER TUBES?

3C22	60.00
4C36	30.00
4X500A	75.00
6D21	100.00
804	9.00

Peak values from

PAGE ELECTRONICS

RELAYS

3600—6 PDT—Struthers Dunn, type 220XFX100, 26.5 VDC, hermetically sealed.

$2.95 ea.—10 for $25.00—100 for $200.00

SELENIUM RECTIFIERS

Sarkes Tarzian miniature rectifier, ½ wave, bridge embedded selenium, 52VAC input, 21 VDC output at 5 milliamps, axial wire leads.

$1.00 ea.—10 for $8.50—100 for $70.00

DELAWARE EQUIPMENT COMPANY
124 N. 3rd St. Phila. 6, Penna.
Lo-3-4930

ALLIED ELECTRONICS SALES

POPULAR RUGGEDIZED and SUBMINIATURE TUBES AT SUBSTANTIAL SAVINGS
ALL TUBES ARE NEW and FULLY GUARANTEED

5635	4.00	5718	2.95	5819	37.50	6005/6AQ5W	1.75
5636	4.00	5721	150.00	5829	1.80	6021	4.95
5640	9.00	5722	5.95	5840	5.00	6073	1.65
5641	6.00	5725	1.85	5879	1.25	6082	3.25
5647	7.50	5726	.75	5881	2.50	6097	1.25
5654	1.35	5744	.90	5899	5.25	6098	5.00
5663	1.25	5751	2.20	5899A	5.25	6111	6.75
5687	2.75	5755/420A	8.50	5902	7.90	6130/3C45	9.95
5696	1.00	5783	3.50	5933/807W	3.50	*WRITE FOR NEW PRICE LIST*	
5702	1.40	5814A	1.95	5964	.75		

74 CORTLANDT ST., N. Y. 7, N. Y. **BARCLAY 7-5839** **Dept E.**

F.O.B. N.Y.C. Rated (D&B) Firms Open Account. Attractive Discounts To Quantity Buyers.

RCA TV CAMERA

NEW Surplus
for Labs! Export! Industrials! Medicine! Closed Circuit TV!

Ideal for labs, industry, prisons, TV technicians, swim pools, medics—"mechanical eye" for closed circuit TV. 1848 Iconoscope, 6-stage video amplifier and clipper. THE REAL THING! Send for new, free, complete technical data. SOLD AT FRACTION OF REAL VALUE!

Write today! Note our new address!

Harjo Sales Co.

Office-Warehouse: Dept. E-1, 503 N. Victory Blvd., BURBANK, CALIFORNIA

SPECIAL PURPOSE TUBES

OA2	$ .70	2K54	7.50	EL-C6A	6.00	RK-65	7.00	EL-302.5	5.00	800	1.50	1616	.50
OA3	.90	2K55	5.00	EL-C6J	6.50	FG-67	9.00	CE-303	2.25	801A	.50	1619	.30
OA5	4.00	2P21 (image orthicon)	35.00	EL-C6L	3.75	RK-69	2.00	WE-304B	7.50	802	2.25	1620	3.25
OB2	.65	2V3G	1.50	EL-6C	8.00	RK-72	.50	304TH	8.50	GL-803	2.00	1622	1.50
OB3	.75	2X2	.35	6AC7W	.75	RK-73	.50	304TL	15.00	803	1.40	1623	2.00
OC3	.70	2X2A	.85	6AJ5	1.15	HY-75	3.00	WE-305A	3.00	804	9.00	1624	.95
OD3	.70	3A4	.50	6AJ6	2.00	RK-75	.85	CE-306	7.50	805	4.50	1625	.30
EL-C1B	2.00	3A5	.50	WE-6AK5	1.35	VR-75	.90	307A	.85	806	5.00	1630	.40
EL-1C	1.50	3AP1	2.00	6AK5W	1.35	75TL	5.50	CE-309	2.75	807	1.20	1631	1.40
XFG1	2.00	3B21	5.00	6AL5W	.65	VR-78	.50	WE-310A	3.50	807W	3.00	1635	1.50
1AF4	2.50	3B22	1.50	6AN5	2.75	FG-81A	5.00	WE-311A	5.00	808	1.00	1636	1.00
1AG5	2.00	3B23	3.50	6AR6	1.25	VR-90	.75	WE-313C	2.25	809	2.25	1641	1.35
1B22	1.35	3B24	1.00	6AS6	1.25	CV-92	5.00	316A	.50	810	10.00	1642	.50
1B23	3.00	3B24W	5.00	6AS6W	1.50	FG-95	17.50	WE-323A	7.50	811	2.75	1649	1.00
1B24	5.00	3B25	3.00	6AS7G	2.35	VT-98BR	12.50	323B	4.50	811A	3.50	1654	3.50
1B27	10.00	3B26	2.25	6BM6	20.00	HF-100	7.50	WE-328A	3.50	812	2.25	1656	6.50
1B32	1.00	3B27	3.00	6C21	17.50	100R	5.00	WE-331A	7.50	RCA-813	12.50	1661	6.00
1B35	4.50	3B28	5.50	6G4	2.00	100TH	6.50	WE-337A	10.00	814	1.75	1846	50.00
1B36	3.75	3B28	5.50	6J4	2.00	WE-102D	2.50	WE-339A	10.00	815	1.45	1851	1.75
1B38	25.00	3BP1	2.50	6J6W	1.25	FG-105	12.00	WE-347A	3.00	816	1.25	1904	9.00
1B40	2.35	EL-3C	5.00	6L6WGB	3.35	VR-105	.70	WE-349A	7.50	822	10.00	1960	.50
1B42	4.50	EL-3CJ	8.50	6SC7GTY	2.00	VU-111S	1.00	WE-350A	3.00	826	.75	1984	10.00
1B47	7.50	3C23	3.50	6SN7WGT	1.50	HY-114B	.75	350B	2.25	828	7.50	2000T	175.00
1B59	10.00	3C24	2.50	6SU7GTY	2.00	WE-121A	3.50	WE-352A	15.00	829	6.00	2050	.95
1C21	2.00	3C31	2.00	7BP7	5.00	WE-122A	1.50	F-353A	2.00	829B	8.50	2051	.65
1P23	2.00	3C33	9.50	7CP1	12.50	F-123A	3.50	WE-353A	3.50	830B	.75	2172	10.00
1P24	.50	3C37	10.00	7EP4	10.00	WE-123A	5.00	WE-354A	14.00	832	3.75	2183	5.00
1P28	8.75	3C45	6.00	9GP7	5.00	WE-124A	3.75	WE-355A	15.00	832A	5.00	ZB-3200	75.00
1P29	1.50	3D21A	5.00	9LP7	3.50	VT-127A	2.50	WE-356B	7.50	833A	30.00	R-4100	5.75
1P30	1.50	3D22	9.75	9MP7	7.50	F-128A	15.00	WE-368A	2.00	834	4.75	R-4330	8.50
1P32	1.00	3DP1	3.75	10Y	.25	HF-130	.90	WE-368AS	2.50	835	5.00	5528	3.75
1P34	1.75	3DP1A	7.50	CE-11V	2.25	VR-150	.70	371A	1.00	836	1.50	5550	25.00
1P36	2.50	3E29	8.50	12A6	.50	FG-154	15.00	371B	1.50	837	.95	5551	35.00
1Z2	1.85	3EP1	2.00	12DP7A	25.00	HK-154	5.00	WE-388A	1.50	GL-838	2.00	5553	100.00
CE-2C	1.50	3FP7	2.00	12GP7	17.50	FG-166	15.00	WE-393A	5.00	838	.75	5556	6.75
VG-2	7.50	3FP7A	3.50	12J5WGT	1.50	FG-172	15.00	394A	1.85	842	2.00	5557	2.75
2A4G	1.15	3GP1	2.00	12K8Y	.50	QK-181	20.00	WE-394A	3.00	843	.35	5560	17.50
2AP1	4.00	3HP7	3.00	12L8GT	.75	FG-190	7.50	WE-396A	3.00	845	5.00	5610	1.00
2AP1A	5.00	3J21	50.00	LM-15	50.00	HF-200	10.00	WE-404A	10.00	845W	8.50	5638	8.50
2AS15	3.75	3J31	35.00	NE-16	.30	CE-201	2.75	410R	100.00	849	18.50	5637	5.00
2B21	.90	3K27	150.00	FG-17	2.75	CE-203	3.50	WE-417A	10.00	851	10.00	5644	7.50
2B26	1.25	3KP1	6.00	RK-19	.85	203A	2.50	WL-417A	2.85	852	5.00	5645	6.50
2C21	.50	3RP1	7.25	RK-20A	7.50	203Z	5.00	WE-418A	12.50	860	3.00	5650	85.00
2C22	.35	3X2500A3	125.00	1Z-20	1.75	204A	25.00	WE-421A	7.50	861	15.00	5651	1.35
2C24	.75	4.400A	40.00	CE-21C	2.00	WE-205B	.75	GL-434A	10.00	865	.35	5654	1.35
2C25	.35	4AP10	3.75	RK-21	.85	207	.50	446A	.50	866A	1.00	5656	6.50
2C26A	.50	4B22	6.50	RK-22	3.50	211	.50	446B	1.85	866-JR	1.25	5670	1.50
2C33	.75	4B23	6.50	CE-23C	1.40	WE-211C	10.00	451	5.00	868	2.00	5687	2.50
2C34	.35	4B24	5.00	PJ-23	2.00	WE-211D	8.00	WL-460	8150	869B	30.00	5691	4.50
2C38	10.00	4B25	8.00	RK-23	2.50	WE-212E	25.00	464A	2.25	GL-872A	2.50	5696	1.00
2C39	5.00	4B26	3.00	HK-24	2.85	217A	1.50	WL-468	12.50	CE-872A	1.50	5703	1.00
2C39A	10.00	4B27	2.25	HK-24G	2.00	217C	3.00	RH-507	20.00	872A	1.35	5720	15.00
2C40	10.00	4B28	3.00	CE-25A/B	1.50	WL-218	18.50	CK-510AX	.50	874	.50	5725	1.50
2C42	10.00	4B30	.75	RK-25	2.25	CE-220	.50	527	15.00	876	.75	5726	.65
2C43	7.50	4B32	10.00	25E6WG	4.00	CE-221	8.00	WL-530	25.00	878	.50	5727	1.40
2C44	.35	4C22	7.50	25T	2.85	221A	2.00	WL-531	7.50	879	.35	5728	9.00
2C46	6.00	4C25	3.00	25TG	2.50	CE-222	1.50	WL-532A	1.00	884	1.00	5740	44.00
WE-2C51	3.00	4C27	5.00	CE-28D	2.50	CE-224	5.00	GL-546	2.00	885	1.00	5763	1.00
2C53	10.00	4C35	15.00	RK-28	2.50	CE-225	3.00	559	.50	908P1	2.00	5801	2.50
2D21	.65	4F27	8.00	28D7	.75	CE-226	3.00	GL-575A	10.00	905	2.00	5819	25.00
2D21W	1.40	4J34	35.00	28D7W	1.50	WE-231D	2.00	WL-579B	10.00	913	20.00	5820	400.00
2E22	2.00	4J50	50.00	CE-29	1.25	RX-233A	.75	631-P1	5.75	917	2.25	5827	2.50
2E24	1.95	4X100A	18.50	CE30C	1.25	CE-235A	5.00	WL-632A	17.50	918	1.85	5829	1.50
2E25	1.85	EL-5B	1.00	Twin 30	7.50	WE-242A	5.00	WL-655/658	100.00	919	2.00	5842	10.00
2E26	3.25	EL-5BHD	6.50	HY-30Z	2.65	WE-242C	8.00	WL-670A	8.00	920	2.00	5847	10.00
2E29	1.00	EL-5B2.5	6.50	CE-31V	2.00	WE-249B	2.50	WL-681/686	25.00	921	1.00	5932	4.00
2E36	1.25	5AP1	3.00	FG-32	6.00	WE-249C	2.50	WE-701A	2.00	922	1.20	5933	3.00
2E41	2.00	5B21	2.00	FG-33	15.00	250R	4.75	702A	.50	923	1.40	5948	350.00
2J21A	2.75	5BP1	2.50	RK-33	.50	250TH	18.50	702B	1.00	924	1.35	5963	1.25
2J26	4.75	5BP1A	7.50	VX-33A	2.50	250TL	15.00	703A	1.50	925	2.00	5981/5650	85.00
2J27	4.75	5BP2A	5.00	RK-34	.35	WE-251A	47.50	WE-704A	.70	926	2.50	5998	7.50
2J29	15.00	5BP4	2.00	35T	4.50	WE-252A	9.50	705A	.75	927	1.00	6031	4.75
2J30	15.00	5C21	7.50	35TG	3.00	WE-253A	3.50	707A	3.00	928	2.50	6097	.65
2J31	14.00	5C22	25.00	RK-38	6.50	WE-254A	4.75	707B	4.50	929	1.25	6187	1.50
2J32	14.00	5C30	1.00	RK-39	1.50	HK-257B	8.50	WE-708A	.75	930	1.25	6188	2.00
2J33	14.00	5CP1	2.00	T-40	2.35	WE-257A	3.50	WE-709A	1.00	931A	3.00	R-6210	15.00
2J34	14.00	5CP1A	8.50	TZ-40	3.50	FG-258A	100.00	713A	.35	SN-948	7.50	UX-6653	.75
2J36	15.00	5CP7	8.50	VX-41	2.50	WE-261A	10.00	715A	2.00	954	.30	8001	8.50
2J37	5.00	5D21	5.50	CE-42C	1.50	WE-262B	7.00	715B	3.75	955	.35	8002R	15.00
2J38	10.00	5D22	7.00	RK-44	1.00	WE-264C	3.00	715C	12.00	956	.35	8005	4.75
2J39	10.00	5FP7	1.35	QK-47	30.00	WE-267B	7.50	WE717A	1.00	957	.35	8008	6.00
2J40	14.00	5FP14	5.00	RK-47	1.75	WE-268A	7.50	717A	.35	958A	.35	8011	.75
2J50	35.00	5GP1	5.00	CE-48	1.75	FG-271	25.00	WE-719A	9.50	959	1.45	8012	1.00
2J51	100.00	5J29	7.50	RK-49	2.85	WE-272A	5.00	721A	.75	972A	3.50	8012A	2.50
2J52	50.00	5J30	5.00	HY-51B	.75	WE-274A	3.00	721B	7.25	991	.30	8013	2.75
2J53	25.00	5J32	15.00	FP-54	44.00	WE-274B	1.00	722A	3.00	1000T	100.00	8013A	3.50
2J54	50.00	5JP1	12.50	HK-54	2.00	274B	.50	723A/B	9.00	CK-1005	.25	8016	2.50
2J55	50.00	5JP2	7.00	T-55	3.50	WE-275A	5.00	WE-724A	.85	CK-1006	2.50	8020	1.50
2J56	75.00	5JP4	7.00	RK-57	4.50	WE-276A	7.50	WE-724B	.85	CK-1007	.65	8021	.75
2J61	15.00	5JP5A	7.00	RK-58	.90	276A	2.50	WE-725A	3.00	CK-1009	3.50	8022	.75
2J62	4.75	5JP11	10.00	QK-59	25.00	WE-282A	7.50	WE-726A	5.00	CK-1026	3.00	8025	1.50
2J62A	50.00	5LP1	6.50	QK-60	25.00	WE-283A	4.00	WE-726B	25.00	R-1100	5.00	8025A	2.00
2J851	.35	5LP1A	20.00	RK-60	1.35	WE-285A	5.00	WE-726C	20.00	R-1130B	10.00	8026	3.50
2K25	12.50	5NP1	2.50	HY-61	1.25	WE-286A	6.00	WE-730A	7.50	1500T	115.00	PD-8365	50.00
2K28	35.00	5R4GY	.90	QK-61	25.00	287A	3.00	WE-732A	2.00	1603	3.00	9001	.85
2K30	100.00	5R4WGY	2.25	RK-61	2.75	WE-295A	5.00	WL-735	2.00	1608	3.75	9002	.65
2K33A	50.00	5X3	3.00	QK-62	25.00	WE-296A	25.00	WL-741	1.40	1611	1.50	9003	.90
2K41	75.00	5X3P1	75.00	RK-62	1.75	HF-300	17.50	750TL	40.00	1612	1.25	9004	.35
2K45	40.00	5Z2P7	50.00	RK-63	18.50	WE-300B	4.50	WL-759	12.50	1613	1.00	9005	1.40
2K47	125.00	5Z4P11	100.00	HY-65	1.85	CE-302	3.00	WL-786	15.00	1614	1.50	9006	.25

The prices quoted above are FOB shipping point

western engineers

ELK GROVE, CALIFORNIA

GEORGE WHITING, OWNER

All tubes are new individually cartoned, fully guaranteed

NEW YORK'S RADIO TUBE EXCHANGE

NEW TUBES

Standard brands. First grade only. No pull outs. No rejects. No rebrands. At lowest prices.

Type	Price	Type	Price	Type	Price	Type	Price	Type	Price	Type	Price	Type	Price
OA2	$1.00	2T36	35.00	5R29	15.50	12AP4	50.00	26TA	15.00	726C	45.00	808A	.60
OA3	1.10	3J36	90.00	5QP1	5.00	12DP7A	65.00	268AB	4.00	730A	22.50	959	2.25
OB2	.60	3Q38	8.95	5Z3I	75.00	LM15	200.00	271B	1.50	750TL	45.00	K1146	.25
OB3	.50	5J51	5.00	6B26	6.00	15E	2.75	285A	1.00	801A	.90	1249	.50
OC3	.50	3Q40	25.00	6C37	10.00	15R	.75	388A	1.40	802	1.95	1500T	135.00
OD3	.85	3J42	135.00	6C38	35.00	NE16	.50	398A	7.50	803	6.95	HK1554	75.00
OI3	.85	3J49	55.00	6F27	16.00	20A	.75	704A	3.95	805	4.95	1603	1.60
1B22	1.50	3Q50	35.00	6J21	60.00	KY21A	6.25	MX408U	.60	807	1.25	1613	1.60
1B23	6.50	3J50	150.00	6J26	60.00	RK21	2.50	417A	15.00	808	1.95	1618	1.25
1B24	9.00	3J51	150.00	6J30	60.00	RK31	8.00	434A	15.00	809	2.95	1619	1.75
1B26	1.75	3J61	20.00	6J38	60.00	RK34G	1.50	446A	1.95	810	10.50	1622	.45
1B27	15.00	3J61A	25.00	6J39	60.00	25T	2.95	446B	1.95	811A	3.75	1623	1.50
1B38	35.00	3J62	25.00	6J40	60.00	35TG	5.95	450TH	15.00	812A	3.75	1624	1.75
1B40	23.00	2K22	20.00	6J51	150.00	45TG	5.95	450TH	12.50	813	13.75	1625	.35
1B41	7.50	2K25	15.00	6J52	150.00	RK39	2.75	464A	7.50	814	3.75	1626	.25
1B42	35.00	2K26	45.00	6J53	150.00	50A	1.25	471A	1.25	815	2.95	1629	1.60
1B60	35.00	2K36	60.00	6J54	100.00	HK54	4.50	527	10.00	816	1.45	2000T	150.00
1N21A	.55	2K38	35.00	6J55	150.00	RK72	1.00	WL530	22.00	829	11.00	2050	1.80
1N23	.50	2K39	35.00	6J56	150.00	RK73	4.50	WL531	22.00	829A	17.00	2051	1.80
1N21B	1.50	2K39A	75.00	6J57	150.00	FG95	19.95	WL631	15.00	829B	32.50		
1N21C	12.50	2K49	160.00	6J58	150.00	100TH	7.95	HK654	15.00	830B	2.00	VARIOUS $500 AND 6000 SERIES OF NEW PRODUCTION	
1N22	.90	2K45	135.00	6J59	150.00	FG105	20.00	700AD	10.00	832A	9.95		
1N23	.50	2K42	180.00	6J60	150.00	122A	1.75	701A	4.50	833A	45.00		
1N23A	.90	2K43	199.00	6J61	150.00	203A	7.50	703A	3.95	836	2.50		
1N23B	1.50	2K44	350.00	6J62	150.00			704A	3.95	837	2.75		
1N23C	7.50	2K46	80.00	6J63	150.00	211C	12.00	705A	2.75	837	2.75		
1N25	4.00	2K48	95.00	6J52	225.00	242C	10.90	706AY/		838	5.95	5820	475.00
1N26	6.75	2K50	295.00	6J53	225.00	249B	4.50	FY	25.00	845	25.00	5826	450.00
1N27	1.50	2K54	35.00	6K5	1.95	249C	4.25	707A	6.75	857B	125.00	6012	2.00
1N34A	.75	2K55	25.00	6KP2A	12.00	250TH	19.95	707B	6.75	860	3.50	6012A	2.50
1N35	.90	2K56	125.00	6L6	1.50	250TL	19.95	714AY	12.00	861	12.50	6013	2.50
1N38	2.25	3AP1A	10.00	6QP1	3.00	252T	3.00	715A	4.50	866A	1.50	6013A	3.50
1P25	75.00	3BP1	7.20	6QP4	5.00	276D	1.00	715B	5.00	869B	67.50	6019	1.75
2C39A	11.50	3BP4	5.00	6S7A	10.00	304TH	10.00	715C	10.00	872A	2.50	6020	1.75
2C40	12.00	3B26	5.50	6CP12	15.00	304TL	10.00	717A	1.50	872A	3.50	6025	3.97
2C43	14.50	3B28	5.00	6D21	10.00	307A	2.50	719A	15.00	874	2.25	PD8566	90.00
2C44	8.00	3B28B	8.00	6F8	2.50	310A	4.50	721A/		878	3.50	9001	3.52
2C46	7.50	3L30	5.50	6JP2	10.50	316B	6.75	GY	50.00	879	.50	9002	.90
2D29	.99	3Q32	75.00	6JP4	27.50	311A	6.50	721A	1.50	884	1.50	9003	3.25
2J27	12.00	3Q31	7.75	6JP5	27.50	312A	3.50	721B	1.50	885	1.50	9004	2.25
2J28	5.00	3C31	2.95	6JP11A	25.00	323A	15.00	723A/B	10.00	902PI	6.75	9005	9.75
2J30	16.00	3DP1	3.50	6SP7	90.00	827A	3.75	724A	1.95	931A	5.00	9006	.25
2J31	16.00	3DP1A	10.00	6S6	11.00	826A	6.75	724B	2.25	954	.25		
2J32	24.00	4DP1A		6S7	7.50	350A	4.50	725A	10.00	955	.50	THOUSANDS OF OTHER TUBES	
2J33	29.00	5Z	10.00	7BP7	5.00	350B	5.95	726A	10.00	956	.75		
2J34	12.00	5ZP1	5.00	7DP4	5.00	HK354C	15.00	726B	45.00	957	.25		

Special! TS45 X BAND GENERATOR—$99.00

NEW **TS-147 B AND C/UP TEST SET SIGNAL GENERATOR**

Hard-to-get X-Band Now Available

Test Set TS 147 UP is a portable Microwave Signal Generator designed for testing and adjusting beacon equipment and radar systems which operate within the frequency range of 8500 MC to 9600 MC.

NEW UNUSED SURPLUS TS 259 K BAND
23400-24500 MEGACYCLES SIGNAL GENERATOR

NEW **MICROWAVE TEST EQUIPMENT TS148/UP SPECTRUM ANALYZER**



Field type X Band Spectrum Analyzer. Band 8430-9580 Megacycles.

Will Check Frequency and Operation of various X Band equipment such as Radar Magnetrons, Klystrons, TR Boxes. It will also measure pulse width, c-w spectrum width and Q or resonant cavities. Will also check frequency of signal generators in the X band. Can also be used as frequency modulated Signal Generator etc. Available now complete with all accessories, in carrying case.

SPECIAL! 5,000 V. POWER SUPPLY $99.90
For IP25 Infrared Image Converter from 3 V. Battery Source. NEW, Complete with RCA 1654 Tube.

OTHER TEST EQUIPMENT USED CHECKED OUT, SURPLUS

TSKI/SE	T35/AP	TS108	TS226	SURPLUS EQUIP.
TS3A/AP	TS36/AP	TS110/AP	TS239A-TS239C	APA10
RF4/AP	1-96A	TS125/AP	TS251	APA38
TS12/AP	TS-45	TS126/AP	TS258	APS 3 APS 4
TS13/AP	TS47/APR	TS147	TS270	APR4
TS14/AP	TS69/AP	TS174/AP	TF890/1	APR5A
TS33/AP	TS100	TS175/AP	834	APT2-APT5
TS34/AP	TS102A/AP	TS182		

You Can Reach Us on TWXNY1-3235

Large quantities of quartz crystals mounted and unmounted
Crystal Holders: FT243, FT171B others.
Quartz Crystal Comparators.
North American Philips Fluoroscopes Type 90.
Large quantity of Polystyrene beaded coaxial cable.

Minimum Order 25 Dollars

Phone: ORegon 4-7070

LIBERTY ELECTRONICS, INC.

119 PRINCE ST.
NEW YORK 12, N. Y.
Cables: TELSERUP

WRITE FOR OUR LATEST CATALOG

We have one of the largest and most complete electronic stocks in the country . . . thousands of tubes, capacitors, plugs, accessories, transmitters, receivers, test equipment, etc.

TS-184A/AP Signal Generator freq. range 400-430 mc.	New $69.50
TS-16/ARN for calibrating radio altimeters ars apn	69.50
TS-56/AP Slotted Line complete with indicator, in carrying case	Exc. 42.50
Weston Model 686 True Mutual Conductive Vacuum Tube Analyzer	New PUR*
Dumont Cathode-Ray Oscillograph Power Supply Unit Model 248, 550w, 115 v. 50-400 cy.	Exc. PUR*
BC-1206 Beacon Receiver	New 12.50
Fisher Research Lab. Transmitter-Receiver Type TS25-2	Exc. 69.50
TS-120/UP Test Set	Exc. PUR*
BC639A Receiver with Rectifier RA42A, frequency range 100-150 mc.	Exc. 125.00
RM29A Remote Control for telephones, phone patch, etc.	New 9.95
AN/APN4B Loran with ID6B Indicator, R9B Receiver, crystal, mount, plugs, and manual	New 129.95
PE-206 Inverter	New 14.95
FT-524 General Electric 3200 wattsecond Photoflash Tube	New 20.00
80 mfd. 4000 v. 640 wattsecond Photoflash Capacitor	New 50.00
Radio Surplus Conversion Manual Volume I	New 2.50
Volume II	New 2.50
Esterline-Angus model AW Recording Voltmeter 0.10 vac 400 ohms	Exc. 150.00

PHOTOCON SALES

417 N. Foothill Blvd. SY camore 2-4131
Pasadena 8, Calif. RY an 1-6751
CABLE: Photocon, Pasadena

POLYSTYRENE CAPACITORS

1% TOLERANCE
200 VDCW 500VDCT
Hermetically Sealed

0.5 MFD ..... $7.50 ea.
1.0 MFD ..... $12.10 ea.

Immediate Delivery

SYNCHROS

ALL TYPES IN STOCK
Immediate Delivery

LECTRONIC RESEARCH LABS.
715-19 Arch Street
Phila. 6, Pa. Phone Ma-7-6771

RELIABLE? RUGGEDIZED?

6H6WGT	.90
6SJ7WGT	2.25
5993	9.00
6095	1.50
6099	3.50

Reliable under any conditions

PAGE ELECTRONICS

TS-245/TRT-1

(5) five tuning fork frequencies—336 cps, 433 cps, 558 cps, 721 cps, 930 cps. Fifteen of these are available.

FS-8650, Electronics
330 W. 42 St., New York 36, N. Y.

We Buy / We Sell **All Brand RESISTORS**

Phone: Yonkers 9-6000

Legri S Company
391 Riverside Ave.
Yonkers 5, N. Y.

WANTED
TDQ — TDT
TRANSMITTERS
RCK RECEIVERS

Radalab Inc.

87 — 17 124th ST.
RICHMOND HILL 18
NEW YORK, N. Y.
Phone Virginia 9-8181-2-3 TWX-NY-4-4361

SCR-682-A
AIR SEARCH AND WEATHER RADAR

This is a 10 cm 3000mc ground based high power air surveillence, search and weather radar, using a 7" PPI. These sets will give excellent SERVICE IN A TORNADO OR STORM WARNING NETWORK OR AT AN AIRPORT for air surveillence up to 135 miles. Ease of operation and service will allow relatively inexperienced personnel to use this equipment with ease. The set consists of three major units as follows: 1—The paraboloid antenna system which includes the pedistal, reflector, dipole and RF section mounted on rear of reflector. 2—Modulator which includes the control panel for modulator, power supply and modulator unit. 3—P.P.I. indicator. This unit is a desk type plan position indicator utilizing a 7" screen and operating controls. All units have pull out decks that enable the set to be serviced without the entire set being taken out of use and are fully safety interlocked.

The technical specifications are as follows:

1—Oper. Freq.—3000 mc 10mc
2—Power output—225 kw
3—Pulse width—1 micro second
4—ranges—500-240,000 yds in four ranges. 10,000 yds, 40,000 yds, 160,000 yds, 240,000 yds.
5—360° scan.
6—azimuth accuracy 1° ±
7—7" PPI indicator
8⅞" coax transmission line.
9—8° antenna beam width.
10—110 v 60 cyc power input.



Figure 1. Radar equipment SCR-682-A

We can supply these sets for use in a building, or mounted in a shelter for transportation in a 2½ ton truck. These radars are supplied completely overhauled tested and guaranted. Test equipment is available to maintain and test this radar. Complete line of spare parts in stock. Write for price.

This SCR-682-A is Avail. for Inspection in Operation by Qualified Buyers on Appointment. Write or Call.

AN/ART-23 — AN/SRR-1 Radar relay equipment

The ART-23 is an air to ground and ground to ground and air to air VHF radar relay link set. The set operates on a freq. range of 78-102 mc. This equipment will accept video, synch pulses from an airborne or ground radar and relay them to the SRR-1 receiving equipment to be displayed on a remote radar indicator such as the VE, VE, VG, etc. The set will transmit a band width of 300cyc to 2 mc. The power output of the transmitter is 100 watts and has a range of app. 150 miles. This is the type of equipment used in the radar picket plane to relay information to a ground station. The ART-23 operates from 110v 400cyc. The SRR-1 input is 110v 60 cyc. Write for prices.



VG-1, 2, 3—24" P.P.I. repeater indicator

The type VG remote plan position indicator is an elaborate projection type radar repeater using a skiatron tube to project a radar image to the top of the console, which is a transparent 24" screen used as a plotting table, enabling the operator to make a tracing on a sheet of paper stored in the unit on a roll. This set will operate very well with the SCR-682 at an airport or weather observing station. Five scanning ranges are provided 4, 10, 20, 80, and 200 miles. Electronic range marks are also provided. This set will operate with any radar set with a pulse repetition rate of from 60-1000cyc per second. The VG operates from a power input of 110v 60cyc. A very bright image allows use in a well lit room. Complete line of spares for this equipment are in stock. Other repeaters in stock: VC, VD, VE, VF, VK. Write for prices.

AN/APN-3 — AN/CPN-2 — SHORAN

The AN/APN-3 and AN/CPN-2 are airborne and ground precision distance measuring and navigation installations respectively. This equipment operates on 250mc and provides an extremely accurate distance measuring system in relation to two ground beacons. The range is app. 250 miles with an accuracy of plus or minus 25 feet. This is probably the most accurate distance measuring equipment built to date. The AN/APN-3 used in conjunction with the K-1 computer (also available) will permit taking an aerial photograph or drop a bomb up to 250 miles distant from the CPN-2 beacons completely automatically. The AN/APN-3 can be fed into the auto pilot of the airplane to fly it if desired, to the drop point. This equipment is very widely used by geological survey companies for oil prospecting and mapping. Power input is 110v 400cyc and 28v DC. Write.

AN/GRC-3 thru 8
Late model field radios.

The GRC series are the new field and mobile military communications sets. These sets cover 20-58.4 mc depending on the transceiver used. These sets replace the SCR-508, 608 etc as the standard high freq. communications sets. The transmitter output is 15 watts. The transceiver are tuneable or fixed tuned. Input powers are 12 or 24v DC. Components are miniaturized and hermetically sealed. Complete installations are avail. Write.

AN/PRC-8, 9, 10

The PRC series of radio sets are the new F.M. high freq. back pack walkie-talkies superceding the SCR-300. These sets are completely miniaturized and weigh app. 18 lbs. complete, with battery. The PRC-8 covers 20-27.9 mc, PRC-9 covers 27 to 38.9 mc, PRC-10 covers 38-54.9 mc. The set has 16 tubes. The receiver is A.F.C. controlled and has a sensitivity of .5 microvolts. The transmitter power output is app. 1 watt F.M. A crystal calibrator is provided to check and calibrate the set. The receiver is equipped with a squelch control. This set can be used with the AN-GRA-6 to provide remote operation and automatic relay. We can supply spare parts for these sets. Write for prices.

AN/ASQ-1—Airborne Magnetometer

The AN/ASQ-1 is an airborne chart recording magnetometer. The set consists of an amplifier, oscillator, detector head, chart profile recorder, power supply, etc. The equipment has a sensitivity of 2 gamma or better. The AN/ASQ-1 will record on an Esterline-ANgus recorder disturbances in the earths magnetic field caused by an ore deposit or a sunken boat or submarine. A bearing indicator is also provided that gives a left right bearing on a magnetic disturbance. Power input is 28v. DC. Weight about 130 lbs.

OTHER EQUIPMENT

AN/URC-4 U.H.F. airsea rescue set.
AN/ARC-12 and higher.
AN/APC-15 and higher.
AN/APS-15 and higher.
AN/APR-4 and higher.
AN/TC-1 facsimile.
TS-587-U.
AN/TRC-7
AN/ART-18, 23, 24 relay equip.
AN/APN-19
AN/APN-12
AN/CPN-6, 8 beacons.
AN/UPN, 1, 2, 3, 4, beacons.
Test sets, field radios, radar, special equipment. Write.

9 CONDUCTOR CABLE

Army spec. CO-215 Weatherproof 9 Cond. No. 20 AWG stranded tinned copper, plastic ins., colored coded, double vinyl jackets with tinned copper braid between Dia. 9/16" made by G.E. Available 1000, 1500, 2000 ft. reels. Price 10¢ per foot. Sample 100 ft. Coil $10.00

NEW SCR-522A EQUIPMENT

Complete BC-624C receivers and BC-625AM Transmitters including mounting racks, plugs, connectors, dynamotor. Brand new equipment with instruction manuals. Write for full details.

NEW REPAIR PARTS FOR BC-348

(Models H, K, L, R only)

4 gang tuning capacitor ..... $ 3.95
Aluminum front panel ..... $ 3.75
1st, 2nd, 3rd, and 4th I.F. transformer assy. ..... Each $ 2.00
Crystal filter assy inc. 915 Kc. Crystal ..... $ 6.50
C.W. Oscillator assembly ..... $ 7.00
R.F. Unit Assembly in can $12.50
Dual Volume Control ..... $ 2.75
Spring tuning knob ..... $ .50
Ant., RF., Det. and Osc. coils for bands 1 to 8. Per Band ..... $ 2.00

RADAR ANTENNA ASSEMBLIES

SO-1 (10CM) assembly with reflector, waveguide nozzle and drive motor $279.50
SO-3 (3CM) Surface Search type with reflector and drive motor, but less plumbing $89.50
SO-13 (10CM) Complete assembly with 24" dish, dipole, drive motor and gearing $49.50
A&D (CS-66ACN-1) Complete with dish, 24 volt drive mechanism, waveguide plumbing, etc. New $39.50

HIGH POT TRANSFORMER

Westinghouse. Pri: 115, 60 cy. Sec: 15,000V C.T., @ .060A. C.T. ungrounded. Excellent for high potting tests. Size OA 12¾ x 8¼W x 9¼D. Weight 67 lbs. Fully enclosed steel case. Price $29.50

6 KVA. STEPDOWN TRANSFORMER

G. E. Step-Down. 6KVA. Pri: 230/460. Sec: 115/ 125, 60 Cy. Size: 20" x 11" x 9½". Weight 225 lbs. Navy grey finish, integral junction box and mounting brackets $49.50

AMPLIDYNES

5AM21JJ7. Input 27 VDC @ 15 A. Output 60 VDC @ 2.5A. 4600 RPM. New $34.50
5AM31NJ9A. Input 27 VDC @ 44 A. Output 60 VDC @ 8.8 A., 7500 RPM. New $23.50
5AM31NJ18A. Input 27 VDC @ 44 A. Output 60 VDC @ 8.8 A., 8300 RPM. New $12.50

INVERTERS

Leland Elec. C. PE206A. Input: 28DC at 38 Amp. Output, 80V, 800 Cy., 1 Ph., 485W. New $16.50
PE218H. Input: 28DC. Output: 115, 400 cy., 1 Ph., 1.5 KVA. New $32.50
G. E. 5AS13JJ1A. Input: 28DC. Output: 115, 400 cy., 1 Ph., 1.5 KVA. Regulated New $89.50

DYNAMOTORS

Navy type CAJO-211444. Input: 105 to 130 VDC. Output: either 28 VDC at 20 amps. or 13 VDC at 40 amps. Radio filtered and complete with line switch. New $89.50

SMALL DC MOTORS

G.E. 5BA50LJ2A. Armature 60 VDC at 8.3 Amps. Field 27.5 VDC at 2.3A RPM 4000. H.P. 0.5. New $27.50
Oster E-7-S, 27.5DC. 1/30 HP. 3600 RPM. Shunt Wound. New $9.50

HI-VOLT OIL CAPACITORS SPECIAL!

Mfd.	KV	Price
.001	50	22.95
.01	5	2.50
.02	20	6.75
.025	50	17.95
.025/.025	50	15.50
.1	3	1.75
.1	4.5	3.50
.135	7.5	6.95
.2	50	29.50
.25	15	9.95
.25	20	15.95
.25	50	44.50
.5	25	39.50
1.	7.5	6.95
1.	15	29.50
1.	20	42.50
2.	5.5	9.50

PYRANOL FILLED CAPACITOR Cat. No. 26F681 ONLY $6.95



.02 mfd. 20,000 volts. 10½x2½ dia. in. A real value at only $6.75

TEST EQUIPMENT

FLUX-METER. Measures flux of magnetron magnets from 500 to 4000 gauss. New $14.95
FREQ.-METER. TS-127/U. Range 375-725 Mcs. New with spare tubes and manual $34.50
PANADAPTER. AN/APA-10. For 115v., 60 cy. New with 80 page tech manual $97.50
40-500 Mc TEST OSC. TS-47/APR. New $149.50
RECEIVER. 158-210 Mc. BC-1068A. 60 cy. $29.50
RECEIVER MX-24/APR-1 ..... $97.50
PULSE TIMER. CUZ-50AGD. For 115/60/1. $65.00
OSCILLATOR 300-1600 Mc. AN/APT-5. New with cables, etc. Power supply $198.50
OSCILLATOR 450-710 Mc. AN-APT-3. New $29.75
MODULATOR BC-1203. For 115v., 60 cy. $125.00
MODULATOR BC-423B. Radiates 205Mc. pulsed sig. at 4,098 cps. New 60 cy. $19.50
PULSE ANALYZER. Airborne counter-measures model ID-59/APA-111. New $149.50
FREQ.-METERS. LINK 230-D2. For testing mobile equip. One each 152.270-157.530, 152.390-157.650, 152.510-157.770, 152.630-157.890, 35.420-43.420 Mc. Price per set $49.50
SIG GEN. I-222A, 115-230 Mc., 8-15 Mc. $89.50
20-250 Mc. PRFR. METER TS-174 ..... P.O.R.
SIG. GEN. 80-12/ARN. AM-PM 105-128 Mc. for aircraft loc. and glide slope tests ..... P.O.R.

Phone: DEerfield 7-0044

ELECTRONICRAFT INC.
27 MILBURN ST. BRONXVILLE 8, N. Y.

Bargains in Brand New Surplus

Write for special quantity prices on starred items*

OIL FILLED CAPACITORS

VOLTS	MFD	Price	VOLTS	MFD	Price
25KV	1.0	★49.95	2KV	.25	.95
25KV	0.5	★39.95	1000	28.0	5.50
25KV	0.1	14.95	1000	2.0	.69
7.5KV	0.5	4.25	600	10.	1.29
6KV	0.25	1.00	600	8	1.19
3KV	0.5	1.50	600	4	★ .59
3KV	0.1	★1.19	600	2	★ .39
2.5KV	2.0	★2.95	600	1	★ .19
2KV	5.0	2.95	660AC	5	2.95
			330AC	5	1.29

SPECIAL SWITCHES

SW 141 ( ) DPST normally open with or without lock-in position on push button, part of CD-318 cord set suitable for 115 V. AC

SPECIAL ★.19¢



SW 224 SPDT Antenna change switch Square D Cat. No. 9320-962 SC #3ZK-9503 - 20 Bakelite Base 2x8x¼

★.49¢

Sensitive MU-Switch 15A. 125 V. AC 15/32-32 threaded bushing. SPDT—69¢

MULTIPLE SECTION OIL CAPACITORS

10 Mfd 400 volts ★59c

Dual 5 mfd 3 term. bottom mount. Meets specs for 600 V operation at 40°C. 3¼x3¼x2

9½ Mfd 600 volts ★59c

8 Section 2-2-2-1-1-.5-.5-.5 Rated by Western Electric at —50 to +85C will pass 1000 V. test at 40°C 4¾x 4¾x1½

Molded, Upright and Ceramic-Cased Mica Capacitors

.01	4L5	600WV	GM45B103J	.32
.02	4L5T	600WV	GM50B203G	★.46
.001	A2L	2500WV	Thickness 7/8"	.49
.02	6S	2000WV		1.85
.0068	F2	3000WV		★1.35
.00015	Type 50	10,000WV	3Amp @ 1MC	★9.95
.0002	Type 50	10,000WV	1.6Amp @ 1MC	9.95

PULSE NETWORK SPECIAL ★$2.95

Sprague 15-1-400-50 15 Kv 1.0 usec 400 P.P.S. 50 Ohm Z

Variable Transmitting Capacitor: 19 to 116mmfd 27 plates. .085" air gap. O/a dim. 4¼Lx3½x2¼. SC# 3D 9019V-1 P/o Tuning Units TU-7A a TU-79 ..... ★98c

OCTAL SOCKETS ★$5.00 C

Johnson 122-128 steatite sockets; Amphenol 49-558, steatite ring mounting; Amphenol ceramic and mica filled 1⅛ and 1½ mounting centers.

RELAYS

Allied BJ6D36 DPDT, 24VDC coil contacts rated 5 Amp @ 24VDC, or 115V AC. ..... ★.59¢
Allied BO 13D35 5P5T Double break normally open 24V DC. Coil Silver contacts each rated 15 Amp @ 24V DC or 115V AC. ..... ★.98¢
Autelco Jr Type 16 115V AC coil DPDT Snap Action contacts rated 15 Amp 115V, 5 Amp 230V 3.95
Cook #773 Standard Telephone Relay 900 ohm DC coil double arm 14 contacts 11A-1B-1C-1D 4"Lx1½Wx 2½H ..... ★1.09
AMPERITE 6NO-110 ..... ★99¢

COAXIAL CABLE

RG 9 B/U ..... ★15.00 C. FT
PL 259 Plug ..... ★29¢
M 359 Angle Adapter ..... ★23¢

Power Rheostat famous make Model J 3000 Ohm 50 Watts ..... ★.79¢
Potentiometer JLU 2000 Ohm 2w with lock nut ..... ★.44¢

These are only a few of our specials; write us your requirements

ALL PRICES F.O.B. OUR WAREHOUSE

***TERMS:** Net 10 days to firms rated well in D.B. Others deposit or cash with order balance C.O.D. Please include postage.*

RUXUR ELECTRONICS CORP
623 HUDSON ST., NEW YORK 14
WAtkins 4-7260

BRAND NEW GUARANTEED

TYPE "J" POTENTIOMETERS

Type "J" .95 Type "JL" $1.10
Type "JJ" $2.95 Type "JJJ" $4.95

Ohms	Ohms	Ohms	Ohms	Ohms	Ohms
10	2000	50K	50-50	15K-30K	250K-250K
100	2500	100K	500-500	25K-40K	333K-333K
150	3000	150K	2K-2K1	40K-60K	500K-500K
200	4000	200K	2K-25K	100K-100K	1meg-500K
250	5000	250K	7K-1meg	100K-200K	1meg-1meg
350	10K	500K	15K-15K	150K-150K	2meg-2meg
400	15K	1meg	ohms	ohms	
500	25K	2meg	60-1K-5K	700K-700K-700K	
1000	25K	5meg	20K-200K-15K	800K-800K-800K	
1500	50K	5meg	45K-27K-250K	1meg-1meg-1meg	

Specify Screwdriver Slot or Knob Type Shaft



15. MFD 600 VOLTS D.C.

Famous Make Oil Filled Condenser 3" wide & 2-½" thick x 4-½" high, 3-½" mounting centers.

ea. 89¢ lots of 1000
$1.19 ea. lots of 100
$1.49 ea. smaller lots

MEDIUM POWER TRANS. MICAS

MFD	VDCW	Type	Each
.00005	3000	F1	3.15
.00005	5000	F2	4.33
.0001	2500	F1	3.15
.0001	3000	F1	3.15
.0001	9000	F3	8.81
.00015	5000	F2	4.33
.0002	5000	F2	4.33
.00022	3000	F1	3.15
.00025	5000	F2	4.33
.00026	8000	F3	8.81
.0003	3000	F1	3.15
.00035	5000	F2	4.33
.0004	3000	F1	3.15
.0004	6000	F2	4.33
.0005	8000	F3	8.81
.0006	2500	F1	3.15
.00062	3000	F1	3.15
.0007	5000	F2	4.33
.00072	6000	F2	4.33
.00075	2500	F2	4.33
.0008	1000	F2	4.33
.0008	5000	F2	4.33
.00085	2000	F2	4.33
.0009	5000	F2	4.33
.001	3000	F1	3.15
.001	3000	F2	4.33
.0011	5000	F2	4.33
.00125	2000	F1	3.15
.0015	1000	F2	4.33
.0015	3000	F2	4.33
.002	3000	F2	4.33
.002	5000	F2	4.33
.0025	2000	F1	3.15
.003	3000	F2	4.33
.004	3000	F2	4.33
.005	3000	F2	4.33
.006	2000	F1	3.15
.0075	1500	F1	3.15
.008	3000	F2	4.33
.01	8000	F3	13.60
.02	2000	F2	4.33
.024	1500	F2	4.33
.02	2000	F2	4.33
.025	1500	F2	4.33
.033	1500	F2	4.33
.062	1000	F2	4.33

A. MOGULL CO.
17 Warren St., N. Y. 7, N. Y.
Phone: WORTH 4-0865

FOR SALE

Large Quantities

- TEMPERATURE INDICATORS
- CONTROLLERS
- RECORDERS

New, Used and Rebuilt Leeds & Northrup Micromax and Speedomax, M. H.-Brown ElectroniKs, and others. Sold on Trial Basis.

INSTRUMENT SERVICE ENGINEERING LABORATORIES
1205 Lamar St. Dayton 4, Ohio AD-2241

TIME DELAY RELAY

Haydon 115v 60 cy. adj. in 5 sec. steps to 40 sec. spdt mu sw. $5.95. With 2 arms & 2 sw. $9.95
PULSE xfmr Utah 1069-AA, 3-50T Windings $3.95

Hundreds of other items, see ad in Buyers Guide Issue, write for listings.

EMPIRE ELECTRONICS COMPANY
409Q Ave. L Brooklyn 30, N. Y. Cloverdale 2-4000

SPECIAL–PURPOSE?

OA5	4.50
R1111	4.00
R4340	25.00
5556/PJ8	7.00
5740/FP54	35.00

Especially our purpose

PAGE ELECTRONICS

CONDENSERS

16 mfd.—600 V $1.39
Dual 8 mfd oil filled cond. hermetically sealed and packed. Tube type PT-SC-11 measuring 3¾"x2⅝"x2⅝". Stud mntg. centers 2". Plugs into standard four prong socket. *Quantity discount.*

1 mfd.—7500 V . . . $14.50
Dykanol—Ind. Cartoned
1 mfd.—15 KV $26.95
Pyranol—Gua. Disc.

Mfd	Volts	Price	Mfd	Volts	Price	Mfd	Volts	Price
.001	50KV	24.50	.5	3000	2.39	4	4000	15.95
.0023	16KV	6.95	.5	5000	3.00	4	5000	24.95
.01	5000	.79	.5	7500	6.25	4	7500	39.95
.01	10KV	4.95	.5-.1	2000	.39	4	10KV	65.95
.012	25KV	12.95	2x.5	600	.60	5	220AC	1.19
.02	8000	4.75	2x.5	9000	12.95	5	330AC	1.39
.02	10KV	5.25	2	15KV	69.50	5	600	1.19
.02	20KV	10.95	3	4KV	8.75	5	1000	1.89
.025	50KV	22.95	5	25KV	45.95	5	1500	1.98
2x			6S	12.5KV	13.95	5	5000	27.50
.025	50KV	34.50		500	.55	2x5	400	.89
.05	7500	4.50	1	1000	.69	2x5	600	1.19
.03	16KV	8.50	1	1500	.99	3x5	400	1.29
.035	10KV	5.95	1	2000	1.35	6	600	1.69
.05	7500	2.95	1	2500	2.20	6	330AC	1.69
.08	12.5KV	8.95	1	3000	2.50	6	1000	2.38
.1	1250	.29	1	5000	6.25	7	1500	2.95
.1	1500	.39	1	6000	6.95		110AC	.79
.1	2000	.45	1	6000	7.50	7	400	.98
.1	2000	.89	1	7500	8.95			
.1	2500	.98	1	7500	14.50	7	600	1.35
.1	3000	1.69	1	10KV	23.50	7	800	1.75
.1	3000	1.19	1	15KV	26.95	7	5000	29.95
.1	4000	1.29	1	20KV	45.95	8	110AC	.75
.1	7500	.85	1	25KV	49.50	8	500	.99
			1	25KV	65.00	8	600	1.49
.1	7500	4.25	1	25KV	75.00	8	660AC	4.25
.1	10KV	6.35	1.75	330AC	.69	8	800	1.89
.1	12KV	6.95	2	600	.55	8	1000	2.78
.1	50KV	42.50	2	600	.65	8	1400	3.05
2x.1	2000	.89	2	1000	.79	8	1500	3.65
2x.1	7000	3.50	2	1000TLA	1.29	8	2500	6.50
2x.1	6000	2.29	2	1500	1.35	2x8	600	1.89
.2	10KV	8.50	2	2000	2.80	10	400	.89
.2	13KV	10.50	2	2500	3.45	10	600	1.19
.2	15KV	13.90	2	3000	4.25	10	600	2.25
.2	50KV	39.50	2	4000	7.50	10	1000	3.75
3x.2	4000	2.85	2	5000	12.50	10	1500	4.25
.25	1500	.88	2	7500	21.95	10	2000	5.95
.25	2000	.98				10	6000	59.50
.25	3000	1.45	2	10KV	35.95	12	660AC	3.75
.25	4000	1.98	2	12.5KV	59.50	15	330AC	3.50
			2	20KV	89.75	15	600	2.29
.25	6000	.85	2x2	600	.85	15	440AC	3.85
.25	15KV	14.95	3	1000	.98	15	1000	3.95
.25	20KV	18.95	3	2000	2.50	15	1500	5.40
.25	25KV	40.00				15	5000	59.50
.25	32KV	49.50	3	4000	0.00	20	330AC	3.35
.25	50KV	62.50	3x3	400	.63	20	600	1.69
.3	2000	.89	4	500	.55	24	500	1.89
2x.25	2000	1.10	4	600	.79	28	1000	5.95
.4	10KV	10.90				30	330AC	5.25
2x.4	7500	5.25	4	600TLA	.98	30	600	3.95
.5	600	.39	4	1000	1.89	30	2500	12.95
.5	1500	.59	4	1500	2.65	50	330AC	6.50
			4	2000	2.95	70	220AC	6.50
.5	2000	1.19	4	2500	4.95	80	4000	45.50
.5	2500	1.49	4	3000	6.99			

PILLAR MICA CONDS

Mfd	Volts	Price	Mfd	Volts	Price
.000028	35KV	42.50	.0008	20KV	36.95
.000051	6000	7.95	.0008	30KV	52.50
.0001	6000	9.95	.001	6000	11.95
.0001	10KV	14.95	.001	10KV	19.95
.0001	20KV	32.95	.001	20KV	39.50
.0001	30KV	52.50	.001	25KV	55.95
.00015	6000	9.95	.00124	15KV	28.95
.00015	10KV	9.95	.002	6000	11.95
.00015	10KV	13.95	.002	15KV	38.95
.0002	6000	9.95	.002	20KV	54.50
.0002	10KV	14.95	.0025	25KV	57.50
.0002	20KV	32.95	.003	6000	15.00
.00024	6000	9.95	.003	8000	19.95
.00025	6000	9.95	.004	8000	19.95
.00025	10KV	15.95	.005	6000	12.85
.00025	20KV	32.95	.007	12KV	59.50
.0003	10KV	15.95	.008	15KV	62.50
.00032	10KV	47.00	.01	5000	10.95
.00035	20KV	33.95	.01	5000	20.95
.0004	20KV	33.95	.02	3000	8.95
.0005	6000	10.95	.03	2000	14.95
.0005	10KV	15.95	.04	1000	6.95
.0005	20KV	32.95	.09	1500	6.50
.0005	35KV	52.50	.1	4000	72.50
.0006	10KV	16.95	.115	2000	5.15

OIL CONDENSERS

.04 mfd	17KV	14.95	DUAL .05	12KV	9.95
1.5	15KV	49.50	.005	15KV	9.75
.25	35KV	65.00	.05	20KV	12.95
.005	25KV	22.95	.002	35KV	13.65
.15	65KV	73.50	.05	25KV	16.50
.01	25KV	19.50	.015	16KV	14.50
.5	35KV	57.50	.005	50KV	19.95
.03	30KV	25.50	DUAL .5	25KV	59.50

MICA CONDENSERS

6, 10, 15, 27, 30, 34, 39, 50, 51, 60, 70, 75, 85, 100, 140, 150, 200, 230, 240, 250, 300, 350, 390, 400, 500, 510, 600, 650, 750, 1000, 1200, 1400, 1600, 2000, 2400, 2500, 3000, 3300, 3700, 3900, 4000, 4700, 5000, 5100, 6000, 6200, 6500, 7900, 8000, & 9100 mmfd

6 to 750 mmfd 4c — 5000 to 8000 mmfd 6c
1000 to 4700 mmfd 5c — 9100 to 10000 mmfd 10c

Also Available Bathtub, Channel, Tubular & Mica and Silver Mica Condensers

MONMOUTH RADIO LABS.

Box 159 *Capital* 2-2776 Oakhurst, N.J.

CONSISTENTLY HIGH QUALITY

ELECTRON TUBES

GUARANTEED • UNUSED • BOXED • CRITICAL TYPES LAB TESTED FOR YOUR PROTECTION

OA4G	1.00	1J30	45.00	8D21	85.00	417A		891	125.00	5751	1.50
OB3/VR90	.85	3BP1	2.95	RK28A	7.70	Klystron	3.50	902 902P1	6.00	5763	1.10
OC3/VR105	.85	3BP11	7.00	V45		417A w/wv.		918	2.25	5783	4.50
OD3/VR150	.85	3DP1	3.00	Klystron	525.00	guide	2.75	931A	3.00	5787	5.75
1B24	4.95	3X2500A3		53	1.10	428A	8.75	932	1.25	5794	7.75
1B24A	15.00	(Surp)	88.00	QK-60	25.00	464A	2.55	958A	.40	5814	.80
1B26	1.50	4B24	5.00	RK60	1.00	CK501AX	1.00	CK-1007	.90	5814A	2.00
1B32	2.00	4B28 6 Amp		QK61	25.00	GL559	.50	1000T	137.50	5819 RCA	37.50
1B35	1.50	Rectigon	1.00	RK61	2.75	GL562	50.00	1500TSurp	120.00	5820 Ecom	500.00
1B45	37.00	4E27	9.50	RK-65	9.50	575-A	12.00	1603	1.00	5829	1.15
1B63A	22.50	4J21	77.50	FG67	12.00	WL651/5552	50.00	1619	.50	5840	4.50
1B85	8.95	4J30	39.50	RKR-72	.35	WL-653B	110.00	5517	2.15	5844	1.00
1B86	7.75	4J36	75.00	RKR-73	.50	GL673	13.00	GL5551		5879	1.25
1N21	.04	4J37	75.00	90-NB		703A	1.25	FG271	47.50	CK-5886	3.25
1N21B	1.50	4J63	7.00	Amperex	7.00	705A	.85	5551/655	95.00	5890	35.00
1N23E	1.50	4-65A/Surp	13.50	FG95/5560	18.00	707A	4.00	5633	8.00	5894	
1N34	.44	4-125A Surp	19.00	FG98A	20.00	707B	6.00	5634/SD828E	7.00	AX9903	16.00
1N34A	.65	4PR60A		100R Surplus	5.00	708A	2.00	5636	2.95	5896	4.50
1N48	.40	(Surp)	50.00	100TH Surp.	6.75	709A	1.75	5637	5.50	5902	6.00
1N54	.55	4X150A		100TL Surp.	8.50	715B	3.95	5638	8.00	5906	15.00
1N56	.85	Surp	22.50	FG105	15.00	717A	.35	5639	9.50	5915	1.00
1N64	.70	4X150G	32.50	VT127A	2.50	721A	.75	5641	6.50	5932	6.50
1N65	.75	4X250B	42.50	VXR130	1.75	721A/B	9.50	5642	1.00	5965	1.45
1N67	.45	4X500A		FG172	45.90	726A	4.50	5643	6.00	5993	10.00
1N69	.60	(Surp	80.00	HF201A	27.50	726B	25.00	5644	8.50	6021	4.50
1N70	1.20	4X500FSurp	65.00	QK181	35.00	726C	35.60	5647(Sylv.)	4.00	6073	1.65
1N81	.90	4-250A		203A	2.50	750TL(Surp	75.00	5651	2.25	6080WA	3.00
1P23	1.90	Surp	50.00	207	45.00	806	.90	5654	1.55	6095	.95
1P30	2.00	4-1000A		211/VT4C	.50	303	2.00	5656	6.50	6096	1.50
WL1P41	1.25	Surp	85.00	227A	2.00	807	1.20	5670	1.10	6097	1.50
2C39A	11.00	5BP1	3.75	FT-231	12.50	807-W	4.50	5672	1.25	6098	1.90
2C43	9.00	5BP4	3.95	245A	15.00	808	1.50	5675	.65	6099	1.40
2C45	10.75	5CP2	29.95	246A	10.00	809	2.25	5676	19.50	6100	4.75
2D21W	2.00	5D21	7.95	249A	1.50	810	9.95	5678	.90	6113	1.85
2E30	1.60	5FP7	1.20	HK253	5.00	811	3.00	5686	.65	6161RCA-	
2E35	1.95	6D21	7.75	266B	45.00	812A	3.50	5687	3.00	Jan	70.00
2J36	35.00	5JP5	10.00	272A	9.00	814	1.35	5691	5.50	6183	275.00
2J32	15.00	5LP1	7.50	274-A	.80	815	1.95	5692	5.25	6188	4.00
2J37	10.00	5LP5	10.00	275A	1.50	816	1.15	5693	4.75	6189	2.25
2J54	35.00	5MP1	10.00	276G	8.50	829B	9.95	5696	.58	6261	11.50
3B23/RK22	4.00	5TP4	20.00	287A	3.00	833A	34.00	5702	2.00	6264	11.50
3B24	1.00	6BM6	22.50	GL299	3.50	838	1.00	5704	1.50	6308	9.50
3B24/W	5.00	CL-6(West)	19.90	304TH Surp.	8.75	845	5.00	5718	4.24	8002-R	18.35
3B25	5.00	6C21	17.00	304TL Surp.	10.75	851	9.50	5718-A	5.00	8005	4.10
3B27	3.50	6F4	1.50	310-A	1.00	860	3.50	5719	4.00	8029 Surplus	1.25
3B29	6.00	6J4	3.00	311C	2.50	866A	1.25	5726/6ALSW	.60	8068	
3C31/C1B	2.25	6K4	2.25	347A	3.25	872A	1.25	5732	1.00	RCA872A	6.00
3C45	7.05	6SN7W	1.50	350B	2.75	872A(G.E.	2.75	5744	.75	8011A	3.95
3D21A	3.00	7C30	65.00	191A	3.50	874(RCA)	.60	5749	2.00	8301	1.25
						876(RCA)	.85			9006	.20

WE STOCK MANY OTHERS . . . . WRITE!

• BRAND NEW • **WESTERN ELECTRIC** • ORIGINAL BOXED •

2C51/396A	53.00	271-A	16.00	337-A	6.00	359-A	2.00	401-B	5591	3.15	418-A	12.00
2K25	22.50	274-B	1.00	339-A	14.00	377-A	3.00	404-A	1947	12.90	421-A	10.00
2K45	69.00	311-B	4.50	348-A	4.95	376-A	4.50	416-A		30.00	422-A	10.00
2K54	69.00	311-CA	2.95	356-A	3.00	387-A	4.00	416-B		15.00	427-A	210.00
231-A	45.00	311-CC	15.00	358-A	15.00	394-A	2.00	417-A		10.00	5795	250.00

We carry a complete stock of new, guaranteed, individually boxed Western Electric transmitting and special purpose tubes at very low prices. Write for latest complete listing of types and prices.

CUSTOM BUILT HIGH VOLTAGE POWER SUPPLIES

Built to your own specifications. From milliwatts to Kilowatts. Precision, well constructed power supplies employing only the very finest components. Fixed or variable voltages. Regulated or non-regulated. Heavy duty or intermittent use. Quotations cheerfully given. Write, giving your requirements in full.

P. A.'s! ENGINEERS

FREE TUBE ENCYCLOPEDIAS!

With every order for $150 or more of electron tubes, a brand new copy of the current edition of the INTERNATIONAL RADIO TUBE ENCYCLOPEDIA will be given absolutely free. Gives complete specs and other information on more than 18,000 tubes of all classes, foreign included. Ask for it on your Purchase order. Quantity limited.

TUBE CARTONS • STACKERS

Super gloss red & black, or plain glossy white. Both types with new safety partition that meet U. S. government specifications! Specify white or colored when ordering.

SIZE	FOR TUBE TYPE	PRICES Quantity (per case)	Per Case	Per 100
Miniature red & black 1" x 1" x 3"	6AU6, 6AL5, etc.	3000	$27.00	$1.00
Miniature glossy white " " "		3000	27.00	1.00
GT red & black 1¾ x 1¾" x 5⅛"	6SN7GT, 6W6GT, etc.	2000	22.50	1.25
GT glossy white " " "		2000	22.50	1.25
Large GT red & black 1 ½"x1 ½"x4 ½"	IB3, 6BQ6GT, etc.	1500	20.25	1.50
Large GT white " " "		1500	20.25	1.50
G red & black 2"x2"x6"	5U4G, 6BG6G, etc.	1000	18.00	2.00
G white " " "		1000	18.00	2.00
Small Jumbo, white 5"x3"x7 ½"	809, 866A, etc.	550	41.25	7.50
Large Jumbo, white 4"x4"x10"	813, 872A, etc.	300	27.00	10.00
Ministackers, white (holds 10 minitubes)		1000	13.50	1.50
GT stackers, white (holds 10 GT tubes)		1000	18.00	2.00
Lead sheaths for crystal diodes		144	12.90	10.00

NEW RECTIFIER TRANSFORMERS

Continuous Ratings
Pri: 115V, 60 cycles input
SEC: 9, 12, 18, 24, and 36 volts.

1 Amp.	$5.75
2 Amps.	6.75
4 Amps.	8.75
12 Amps.	16.65
24 Amps.	35.65
50 Amps.	59.00
100 Amps.	108.00

NEW RECTIFIER CHOKES

Continuous Ratings

1 Amp	1.5 ohm	$4.95
2 Amps	.64 Hy	.9 ohm 5.95
4 Amps	.07 Hy	.6 ohm 7.95
12 Amps	.01 Hy	.1 ohm 14.95
24 Amps	.004 Hy	.025 ohm 29.95
50 Amps	.005 Hy	.01 ohm 54.00

FILTER CAPACITORS

Capacity	W. Voltage	Each
500 MFD	150 V.	$1.95
500 MFD	50 V.	.85
1000 MFD	15 V.	.35
2000 MFD	50 V.	2.25

DIRECTRON SELENIUM RECTIFIERS

FULL-WAVE BRIDGE TYPE

Max. AMPS.	18VAC 14VDC	36VAC 28VDC	54VAC 42VDC	72VAC 56VDC	110VAC 100VDC
1	$1.35	$2.35	$3.75	$4.50	$7.45
2	2.00	2.75	5.35	5.50	9.15
2½-3	2.95	4.15	6.85	7.85	12.75
4	3.50	6.45	11.35	14.35	21.75
6	4.80	7.75	12.85	17.50	29.75
10	5.90	11.45	19.50	24.80	41.35
12	7.25	14.35	22.10	29.75	44.25
20	13.95	25.85	37.25	48.75	78.50
24	14.25	28.75	44.50	57.65	81.00
30	17.95	34.35	56.50	73.50	109.00
36	22.45	42.35	65.00	86.95	134.00
50	29.50	54.35	105.45	115.75	174.00
100	59.50	119.00			

We build other Selenium Rectifiers, Transformers, and Chokes to your specifications. Buy from the Direct Source for Quick Delivery.

Terms: F O B—N Y C—25% Deposit with order—or send full remittance to save C O D charges—D & B Rated Firms (F2½ or Better) Net 10 days. CABLE: BARRYLECT, N. Y. TELEGRAPH: BARRY ELECTRONICS, FAX, N. Y. C.

BARRY ELECTRONICS CORP.

Dept. 1-E
512 Broadway, N. Y. 12, N. Y.
***Phone:* Walker 5-7000**

MOTOR GENERATORS AND CONVERTERS

50, 60, 400 and 800 cycle and DC Power Supplies

28dc to 110/1/800 @ 1kva (Overall length: 12 inches)	$49.50
110dc to 110/1/800 @ 350va	150.00
110ac to 110/1/800 @ 350va	235.00
220-440/3/60 to 110/1/400 @ 2kva	435.00
32dc to 110/1/60 @ 350va	100.00
110dc to 110/1/60 @ 350va	59.50
110dc to 28dc @ 250va	49.50
110/1/60 to 28dc @ 250va	97.50
220/1, 3/60 to 28dc @ 250va	97.50
110dc to 110/1/60 @ 1.25kva	135.00
220dc to 110/1/60 @ 1.25kva	145.00
110dc to 110/1/60 @ 350va	85.00
110dc to 110/1/60 @ 500va	95.00
110dc to 110/1/60 @ 5kva	285.00

Partial Listings—Please Advise Your Needs

SYNCHROS & SELSYNS

1F	$55.00	6G	$34.50
1SF	55.00	7G	49.50
1G	55.00	2J1F1	10.00
1DG	42.50	2J1G1	10.00
5F	39.50	2J1H1	10.00
5G	39.50	6DG	34.50
5CT	45.00	AY-43 autosyn	
5SDG	27.50		

Torque Unit, Pioneer # 12602-1-A $34.50

Includes CK-5 Motor and AY-43 autosyn

MICRO WAVE ACCESSORIES

Echo Box, motor driven, 3 cm. **new** ... write
Echo Box, motor driven, 10 cm. **new** ... write
Flex. Wave Guide—12' long, UG-51, -52 flanges, **new,** at ... $12.50
Flex. Wave Guide—E-plane 90° gooseneck bend, rect. plain flanges, guide is equiv. to RG-51/U Airtron #309,40, **new,** at ... 9.50
Flex. Twist—E to H, RG-51/U size, UG-51/O & rect. plain flange, Airtron #30810, **new,** at ... 9.50
Rigid W. G., Silver pl. brass, RG-51/U with UG-51, 52 flanges, 6' long ... 21.50
Rigid W. G., RG-51/U, 13" long, 2 UG-51 flanges, **new,** at ... 10.00
CG-85/APQ-7, Alum. W. G., RG-51 with two UG-52 flanges, 60° & 22° H plane bends, 22" long, **new,** at ... 22.50
Elbows, Sil. pl. brass, RG-51 with UG-51, -52 flanges, mitered, 90° H-plane ... 14.50
Elbows, Sil. pl. brass, RG-51, two UG-52 flanges, mitered, 90° E-plane ... 13.50
Elbow, RG-51, UG-51, -52 flanges, 90° H-plane and 22° E plane bends ... 11.50
Bi-directional Coupler—UG-51, -52, Type N take offs, Broadband ... 27.50
Rotating Feed Arm Assy's. P/O AN/MPG-1 Sil pl. brass RG-52, **new** ... write
Magnets, Alnico V, for 3 & 10 cm Magnetrons various gap widths, 15 lbs ... 16.00
Transformer, Output for 725A etc. with fil. wndg. and magnatron well ... 21.50
Utah Pulse xfmr. Philco #352-7190 ... 7.50
Rotating Antenna parts—for AS-18/APS-15, AS-17/APS-3 etc. Drive motors, torque units, wave guide, feed horns, gears, etc. ... write

. . . and crystal mounts, Klystron mounts, duplexers, I.f. strips, converters and many special bands and devices too numerous to list. Send sketch if possible.

We maintain our own fully equipped testing laboratory to test and guarantee anything we sell

Wholesale, Industrial and Institutional Sales Only

COMPASS
ELECTRONICS SUPPLY
A Division of Compass Communications Corp.
75 VARICK ST. NEW YORK 13, N. Y.
CANAL 6-7455
Cable Address: COMPRADIO, N. Y.

SELLING

Receivers
Transmitters
Radar
Special Purpose Tubes
Relays
Meters
Switches
Connectors
Rectifiers
Transformers
Motors & Generators
Wiring Cable
Instruments and
All Electronic Components

WILL BUY ALL

New or Used

Leach Relay #5050-R, #5058, #5055, #5053-SM, #5053
Price Bros. Relay #10
Relay #5586, #5587
Antenna Switching Relay Box # CBY 23049, # BG-AN-198, # BC -408
Tubes #53A, VT-127A, 3ST, WL-530

Highest prices paid for most all types of aircraft sparkplugs any condition

Wholesale Only

RADIO & ELECTRONIC SURPLUS
13933-9 BRUSH STREET
Detroit 3, Mich. TO 9-3403

Wholesale Only

A BARGAIN FOR YOU in a ....

SOLA Constant Voltage TRANSFORMER

End Fluctuating Line Voltage

OVER 60% OFF . . .



the factory price of a 1-Input 2,000 VA unit! And here's another bonus! This Air Forces 2,000 VA overstock, Sola Cat. No. 30768, has 4 inputs! 90-125 V., 190-250 V., 60 cy. or 50 cy. Isolated secondary is constant 115.0 V. ± 1% from no-load to full-load of 17.4 amp. So, if you choose, use it as a 220:115 V. step-down. And slash $147.50 off the factory 1-input price!

Brand new in original wood box. 4 cu. ft. Ship. wt. 254 lbs. F.O.B. Pasco, Wash. Only ... **$97.50**

(EXPORTERS: Note choice of 50 cycles.)

THE M. R. COMPANY
P. O. Box 1220-B Beverly Hills, Calif.

Exceptional offer

40.000 BALL BEARINGS
brand new

SKF Rigid Type EL4—4 mm. int.—13 mm. ext. —5 mm. thick one range of balls—net price: **Belg. francs 10.- or $. 0,20.**

Type 126—6 mm. int.—19 mm. ext.—6 mm. thick two ranges of balls—rotule rolling net price: **Belg. francs 7.50 or $. 0,15**

F.O.B. Antwerp, export packing included.

SOCIETE INDUSTRIELLE ALFA Soc. Anon.
80, rue de la Senne, Brussels (Belgium)

"PACKAGED" RESISTORS

Buy your odd-size resistors by the "package." All sizes, 5 & 10 on a card. Half, one & two-watts—5% —10%.

Write to
GOULD GREEN
252 Greenwich St. New York 7, N. Y.

ART-13 APR-4 BC-610-E

BC-348, BC-312, BC-342, TCS-12, BC-221, ARC-1, Dumont #241 Scope DY-17, Teletype, Boehme Keyers

ALLTRONICS, Box 19, Boston 1, Mass.
Richmond 2-0048

BELVISION'S COMPONENT BARGAINS

TUBES

6J6 — 6AQ5 — 5A5 ... 25¢
6FS ... 15¢ 316A ... 12¢
3BP1 — WITH SOCKET ... 75¢

INSULATED CARBON RESISTORS

½ Watt — $10.00 per M • 1 Watt..$15.00 per M
2 Watt..$25.00 per M • Minimum 250 of a number

Ceramic Condenser ... $20.00 per M. All Sizes

And Many Other Items
We Also Purchase Your Surplus Inventory

INSULATED CARBON RESISTOR KITS

100 Pieces/ In Plastic Bag—All Tolerances 5% are ½ watt, 10 are 1 watt, 5 are 2 watt ... **$1.45**

TERMINAL STRIPS—ALL SIZES—$7.00 per M
KIT OF 50 STRIPS—10 SIZES ... 45¢

Condensers—20/20 mfd, 250 V. F.P. (Plug-in) 15¢

BELVISION, INC.
254 Greenwich St., N. Y. 7, N. Y. BA 7-6063

SEARCHLIGHT SECTION

For:

★ Tests Sets
★ Airborne Electronics
★ Radar
★ Navigation Aids
★ Parts—Meters—Tubes

Ask for:

NEW CATALOG NO. 114
Lists latest inventory of aircraft, industrial and military electronics equipment.

"VARIAC"
(Mfg. by American Transformer Co.)
100 amp. 110 V. or 220 VAC. 60 cycle input. Output variable from 0 to 130 V. or 0 to 240 V.
Brand new. Special..... **$99.50**

ARROW SALES, INC.
P. O. Box 3007-E, North Hollywood, Cal.
Phones: STanley 7-0406 POplar 5-1810
Telegraph Address: WUX, No. Hollywood
Cable Address: ARROWSALES, North Hollywood

RECTIFIERS?

KC4	35.00
5R4GY	1.50
WL681/686	20.00
816	1.00
8008	4.95

Rectify Any Problem Thru

PAGE ELECTRONICS

IF

there is anything

you want . . .

that other readers of this paper can supply

or—

something

you don't want

that other readers can use, advertise it in the

SEARCHLIGHT SECTION

THE LARGEST STOCK OF RELAYS IN THE WORLD!

RELAYS

WESTON Type 705 SENSITROL



#R561

Stationary contact is a small powerful permanent magnet and movable contact is iron "rider" mounted on pointer which travels over relay scale. Operating torque moves pointer into magnetic field of stationary contact which draws movable contact and holds it firmly. Contacts remain closed until reset. Will operate directly from a photocell or a group of thermocouples. Net weight 14 oz.

Double contact with Solenoid Reset; Sensitivity 7.5 Microamps; Reset coil 6-24 VDC or 24 VAC; Makes contact on increasing or decreasing values; Contacts; "Twintacts", Capacity 100 ma at 110 volts; Nickel plated, Brass cover; Weston Model 705 Type 6 #R560 .....**18.75; 10 for 170.00**
Same as #R560 but with glass face; Weston Model 705 Type 6 #R561....**19.75 10 for 180.00**

Single contact (Normally Open), Solenoid Reset; Sensitivity; 10 Microamperes; Reset coil; 6-24 V DC or 24 V AC; Contact; "Twintact", capacity 100 ma at 110 volts; Glass Face; Weston Model 705 Type 4 #R523 .....**17.75 10 for 160.00**
Same as #R523 with Brass Cover Weston Model 705 Type 4 #R523N.....**16.75 10 for 150.00**

SS5



Step & Reset

STEPPING SWITCHES

Mfd. by Western Electric Minor Switch 10 steps and off Contacts: #'s R960, 975, 976 Gold plated brass; Bridging Wiper; Net Wt. 1 lb. Lots of 10

	Each	Lots of 10
#R960; Single Level; 6 to 12 VDC.	9.50	8.00
#R975; Single Level; 24 to 36 VDC.	10.50	9.00
#R976; Single Level; 48 to 60 VDC.	11.50	10.00
#R977; Two Level; 6 to 12 VDC.	11.50	10.00
#R978; Two Level; 24 to 36 VDC.	12.50	11.00
#R979; Two Level; 48 to 60 VDC.	13.50	12.00

SS6 Mfd. by Western Electric Co.; **22 step; 5 levels;** Bridging Wipers; Contacts; Gold plated brass. Interrupter Switch: 1 Break-Make; Net Weight: 2 lb. 2 oz. **"Homing" Type; 180° Wipers; Step in One Direction**

	Each	Lots of 10
#R926; 6 to 12 VDC.....	13.75	11.50
#R980; 24 to 36 VDC.....	14.75	12.50
#R981; 48 to 60 VDC.....	15.75	13.50

SS7 Mfd. by Western Electric Co.; 44 step; 2 Levels; Bridging Wipers; Contacts: Gold plated brass; Interrupter Switch; 1 Break-Make; Net Weight 1 lb. 14 oz. **"Homing" Type; 360° Wipers; Step in One Direction**

	Each	Lots of 10
#R927; 6 to 12 VDC.....	13.75	11.50
#R982; 24 to 36 VDC.....	14.75	12.50
#R983; 48 to 60 VDC.....	15.75	13.50

IMMEDIATE DELIVERY
PRODUCTION QUANTITIES

AUTOMATIC ELECTRIC TYPE 13 "Homing" type; Step in one direction; 25 position; 180° wipers, one bridging and remainder non-bridging; Interrupter switch: 1 break.

Our #	Nom	DCV Max	Levels	Auto Elec #	Price Ea
886	6	12	3	RG26	16.75
900	24	36	3	RA92	16.75
887	48	56	3	RA95	16.75
888	6	12	6	RB31	18.75
889	24	36	6	RB36	18.75
890	48	56	6	RB38	18.75

CLARE TYPE 20 "Homing" type; Step in one direction; 20 position; 180° wipers, one bridging and remainder non-bridging; Interrupter Switch: 1 break. #R891; 24-36VDC; 3 levels; Clare #SD19..**12.95 each**

WESTERN ELECTRIC MERCURY CONTACT

Pressure Sealed; Octal Plug Base
D171584; (Equivalent to 275B); SPDT; 1 coil of 4500 ohms plus 24V Heater. Operating current: 8.0 ma, release current: 5.2 ma. Overall length: 3¼", overall diameter: 1-3/16" #R1021 .....**$6.95 ea.**
10 for 65.00 100 for 625.00
D168479; (Equivalent to 275C); SPDT; 2 coils: 3300 and 700 ohms. Operating current: Windings in series 6.6 ma, release: 5.2; #1022 .....**8.95 ea.**
10 for 82.50 100 for 750.00

SIGMA SENSITIVE

SIGMA 4F8000S; 1 ma; SPDT (1C); 8000 ohm; #R425 .....**3.95 ea.**
3 for 10.00 10 for 30.00
SIGMA 5F16000S; 0.5 ma; SPDT (1C); 16000 ohm; #R627.....**5.95 ea.**
10 for 50.00 100 for 450.00

HERMETICALLY SEALED

ALLIED SMHX-1; 24-VDC; 6PDT(6C); 10 Amp contacts; 230 ohm; Solder lug header; #271 **6.50 ea.**

ALLIED SKHXCC; 24 VDC; DPDT(2C) 425 ohm; Solder lug header; #R85..**$4.95 ea.**

ALLIED SKHXCCCC; 24VDC; 4PDT(4C); 425 ohm; Solder lug header; #R86 **5.50 ea.**

A-C RELAYS

GUARDIAN SNAP-ACTION; SPST; 30 Amp contacts; 115V, 50-60 cyc; #R1023 **$1.95 ea.**
10 for 18.00 220V A-C #R1024 **$2.50 ea.**
10 for 22.50

ALLIED PO12A115; 115V, 50-60 cyc; 4PDT; 10 Amp contacts; #R1025....**4.50 ea.**
10 for 40.00 100 for 350.00
GUARDIAN 150; 115V, 50-60 cyc; SPDT, 3 Amp contacts; #R1029 **1.50**
10 for 12.50 100 for 110.00

24 VOLT TRANSFORMER; 1.5 Amp; Pri; 115V; 50-60 cyc; Double shielded; Net wt: 1½ lb; #T120 .....**1.50 ea.**
10 for 13.00 100 for 100.00

SEND FOR LATEST CIRCULAR. TERMS:—All Prices F.O.B. Our Plant. Rated Firms Net 10 Days; All Others Remittance with Order. Orders Under $10.00 Remittance with Order. Plus Approximate Shipping Charges (Overage Will Be Returned). **Cable address: UNIGENCOR, N. Y.**

324 CANAL ST., N.Y.C., 13, N.Y. WAlker 5-9642

Universal general corp.

"TAB"
Trade Aids Buy

HI-FI HDQTS

COMPLETE LINE OF HI-FI
Speakers, Tuners, Amplifiers,
Record Changers & Components,
GET OUR PRICE B-4-U-BUY
NEW G.E. PHONO CARTRIDGES
Original Boxed, $, $, $, Back Gtd

RPX050A .001 & .003 ..... $6.98
RPX052A Dual (D) .001 & .003 Tetrad 10.98
RPX051A Gold Treasure 19.98
RPX053A Dual (DI) .001 & .003 Tetrad 16.98
RPX040A Single (S) .003 ..... 5.25
RPX041A Single (S) .001 ..... 5.25

Repic'ment Needles "TETRAD" Diamond†
RPX010A Dual (S) .001 & .003 GE $1.98
RPX012A Dual (D) .001 & .003 Tetrad 10.98
RPX013A Dual (DI) .001 & .003 Tetrad† 16.98
Repic'ments for New A Cartridge Only
RPX010 or RPX012D Single (D) Tetrad† 9.98
RP 1013 or RPX015 Single (DI) 9.98
Repic'ment Styli for RPX040 & 041 Only
RP 2001 or RPX005 Single (S) GE 1.35
RP 2003 or RPX004 Single (SD) 9.98
Complete Stock of Repic'ment Needles
Send Cartridge Name and Number

New Collaro RC-54 Changer
with Hi-Fi Crystal Pickup $39.75

"TAB" HI-FI SPEAKERS
Labelle network 2 wires needed for 8" & 12" Response. Famous Hi-Fi make. Coaxial Pair & Tweeter.
8" Coaxial PM & Tweeter $12.75
12" Coaxial PM (A 3M) TW. & X-over 19.75
10-15 XC Model PICO 37.75

HI-FI RECORDING TAPE
Finest, $, $, $, Back Gtd
PRECISION COATED & SLIT
Old Reliee free. Quality Controlled. Plastic Reel. Qtd. Constant Output. Freq. 7½ IPS, 40-16KC Guide Wnd. In 7½" reel, 1200 ft. per reel.
"TAB" @ $1.68 ea; 3/$4.85; 12/$18; 24/$36

WRITE FOR OUR NEW
BONUS HI-FI GRAM

CIRCUIT BREAKERS

Heinmann Magn. Brks. Amps: 3, 4, 5, 6, 10, 15, 20, 30 ..... $1.98 ea; 3/$5.75
Same as above 3/$9.75
Gp. B & CH Toggle Sw. Brks. Amps: 5, 10, 15, 20, 25 ..... @$.98
Thermo Thermal Circuit Brks. Amps: 10, 15, 20, 30, 40 ..... @$.98; 3/$2.75

TRANSFORMERS

ALL 115V 60 CYC INPUT
3000V/30MA, 2.5V/6A, 5V/1.75A & 6.3V/4.5 Amps Resimat $2.98
440V/30MA, 2.5V/3A, 5V/2A, 1800V DBLR TWO 5KS PIV RECTIFIER $5.98
270VCT/200MA, 5V/3A & 6.3V/2A TRANSFORMER ..... $4.98; 2 for $9.00
Also 2 for 524 770V/2.5 MA, 5.5V/3A, MVLR MINIATURE FILTER CHOKE ..... $3.49; 2 for $6.00
340VCT/150MA, 6V/3A & 6.3V/2.5A ..... 115V 50 & CHD RCA ..... $4.50; 2 for $8.00

NEW LO PRICES!

PRECISION RESISTORS
1% Accuracy Gtd
No Mfg Choice . . .
We Ship Types in Stk

0.110	849	1034	7320	42000	270000
0.49	370	1050	7500	47000	274000
0.75	390	3000	7717	50000	294000
0.95	390	3080	7900	51000	300000
1.0	392	3300	8000	54000	316000
1.02	392	3187	8300	56000	325000
1.5	400	3193	8500	60000	325000
1.6	400	3300	8700	62000	330000
1.8	420.9	3360	9100	64000	350000
1.9	430	3900	9900	61420	360000
2.0	450	4000	10000	68000	360000
2.5	460	4300	10500	68000	360000
2.8	470	4300	11000	68000	390000
3.0	480	4700	11300	68000	400000
3.2	490	4800	12000	69000	400000
3.3	500	4900	12300	82000	430000
3.5	500	5000	12500	82000	430000
3.6	500	5100	13000	82000	440000
3.8	500	5200	13300	85000	450000
3.9	510	5300	14400	88000	450000
4.0	510	5600	15000	90000	470000
4.2	510	5700	16000	91000	470000
4.3	510	5800	16000	91000	470000
4.4	510	5900	16000	93000	500000
4.5	510	6000	16000	93000	500000
4.6	510	6000	16000	93000	510000
4.7	510	6000	16000	93000	510000
4.8	510	6000	16000	93000	510000
4.9	510	6000	16000	93000	510000
5.0	510	6000	16000	93000	510000
5.1	510	6000	16000	93000	510000
5.2	510	6000	16000	93000	510000
5.3	510	6000	16000	93000	510000
5.4	510	6000	16000	93000	510000
5.5	510	6000	16000	93000	510000
5.6	510	6000	16000	93000	510000
5.7	510	6000	16000	93000	510000
5.8	510	6000	16000	93000	510000
5.9	510	6000	16000	93000	510000
6.0	510	6000	16000	93000	510000
6.1	510	6000	16000	93000	510000
6.2	510	6000	16000	93000	510000
6.3	510	6000	16000	93000	510000
6.4	510	6000	16000	93000	510000
6.5	510	6000	16000	93000	510000
6.6	510	6000	16000	93000	510000
6.7	510	6000	16000	93000	510000
6.8	510	6000	16000	93000	510000
6.9	510	6000	16000	93000	510000
7.0	510	6000	16000	93000	510000
7.1	510	6000	16000	93000	510000
7.2	510	6000	16000	93000	510000
7.3	510	6000	16000	93000	510000
7.4	510	6000	16000	93000	510000
7.5	510	6000	16000	93000	510000
7.6	510	6000	16000	93000	510000
7.7	510	6000	16000	93000	510000
7.8	510	6000	16000	93000	510000
7.9	510	6000	16000	93000	510000
8.0	510	6000	16000	93000	510000
8.1	510	6000	16000	93000	510000
8.2	510	6000	16000	93000	510000
8.3	510	6000	16000	93000	510000
8.4	510	6000	16000	93000	510000
8.5	510	6000	16000	93000	510000
8.6	510	6000	16000	93000	510000
8.7	510	6000	16000	93000	510000
8.8	510	6000	16000	93000	510000
8.9	510	6000	16000	93000	510000
9.0	510	6000	16000	93000	510000
9.1	510	6000	16000	93000	510000
9.2	510	6000	16000	93000	510000
9.3	510	6000	16000	93000	510000
9.4	510	6000	16000	93000	510000
9.5	510	6000	16000	93000	510000
9.6	510	6000	16000	93000	510000
9.7	510	6000	16000	93000	510000
9.8	510	6000	16000	93000	510000
9.9	510	6000	16000	93000	510000
10.0	510	6000	16000	93000	510000

MEGOHMS

1	1.5	1.8	2.5	3.5	12
1.1	1.67	1	2.7	0.05	12.89
1.2	1.6	2	3	9.5	13
1.3	1.65	2.5	3.3	11	13.85
1.35	1.75	2	3	11.55	15

"TAB" Special
10 of One Value ..... ea 10¢
100 of One Value $8.00
10 Assorted Values $1.50
Write for Complete Listing

NEW "TABTRON" SELENIUM RECTIFIERS
ENGINEERED for INDUSTRY

"Technical Apparatus Builders" mfgrs. Power Rectifiers to your specs. From one amp up to and above 1000 amps, convection or fan cooled, single or 3 phase. "NEMA" & JAN. Specs. Write for catalog.

FULL WAVE BRIDGE • DOES & ONE YEAR GTD

Max Amp	15VAC 14VDC	25VAC 28VDC	55VAC 42VDC	72VAC 56VDC	330VAC 300VDC	266VAC 227VDC	Ctr Tap AC/DC	3 Phase 120VAC 1500VDC	Bridge 240VAC 3000VDC
1	$1.60	$2.70	$4.30	$5.15	$9.45	$25.25	$2.45	$17.10	$31.25
2	2.45	4.40	6.75	8.15	15.50	41.50	3.75	28.15	51.50
3	3.00	5.40	8.30	10.00	19.00	51.00	4.70	34.50	63.00
4	3.45	6.15	9.50	11.50	21.75	58.25	5.40	39.50	72.50
5	3.85	6.75	10.50	12.75	24.00	64.50	5.95	43.75	80.00
6	4.25	7.45	11.50	14.00	26.50	71.00	6.55	48.25	88.00
8	5.00	8.75	13.50	16.50	31.00	83.00	7.70	56.50	103.00
10	5.70	10.00	15.50	18.85	35.50	95.00	8.80	64.50	118.00
12	6.30	11.00	17.00	20.75	39.00	104.00	9.70	71.00	130.00
15	7.30	12.75	19.75	24.00	45.00	120.00	11.25	82.50	150.00
20	9.00	15.75	24.50	29.75	56.00	149.00	13.90	102.00	186.00
25	10.60	18.60	28.80	35.00	66.00	175.00	16.40	120.00	219.00
30	12.00	21.00	32.50	39.50	74.50	198.00	18.50	135.50	247.00
40	14.50	25.50	39.50	48.00	90.00	240.00	22.50	165.00	300.00
50	16.75	29.50	45.50	55.50	104.00	277.00	26.00	190.00	347.00

SELENIUM IS WORTH $ $ $
RETURN YOUR OLD DUD RECTIFIER—DEDUCT 5% FROM PRICE
DISCOUNT TO INDUSTRIALS, SCHOOLS & COLLEGES

Heavy Duty Battery "Fast" Charger Rectifier

12-0-12V(CT) 100 Amp Fan Cooled or 24 Amp Air Cooled. Rep'mt 6V Booster Charger.
Model CR16 ..... $12.00
16-0-16V(CT) Fan Cooled for 12V/60A and 6V/100A Booster Charge.
Model CR36 ..... $16.00

New Variable 0 to 6 & 12 Volt/12 Amp

DC POWER SUPPLY

Stock Number	Battery Eliminator Charger Model RB Pioter Aircraft Marine or any DC Rig.	Continuous Rating	With Meters
T28V1A	0-28 V VDC 28 5 Amp		
T28V1ACC	5 Amp (1% Ripple)		$55
T28V1A2CC	5 Amp 0.01% Ripple		145
T28V12A	0-28 VDC at 12 Amp		125
T28V12ACC	12 Amp (1% Ripple)		160
T28V12A2CC	12 Amp 0.01% Ripple		230
T28V24A	0-28 VDC at 24 Amp		185
T28V24ACC †	24 Amp (1% Ripple)		225
T27V24A2CC †	24 Amp 0.01% Ripple		315
T28V50A †	0-28 VDC at 50 Amp		310
T28V50ACC †	50 Amp (1% Ripple)		410
T28V100A †	0-28 VDC at 100 Amp		545
T28V100ACC †	100 Amp (1% Ripple)		695

Variable 75 to 135 VDC Completely Built, Ready to go. Includes F. W. Selenium Bridge Rectifier 4" Rectangular Volt & Ammeter Overload output Dsgnd for cont. service. Specify for 115 or 230 VAC 1 phase, 60 or Input $100
T120V1AC 75 to 135 VDC at 6 Amp $100
T120V1ACC 6 Amp (1% Ripple) 240
T120V10AC 75 to 135 VDC at 10 Amp 260
T120V10ACC 10 Amp (1% Ripple) 295

POWER SUPPLIES TO YOUR SPECS
WRITE US YOUR REQUIREMENTS

New! Quality VOLTAGE REGULATOR

$ $ Popularly Priced $ $
ONLY $16.98

Line Voltage Stabilizer
Stabilizes line voltage within one or more 5% regardless of VOLTAGE & FREQ. Rmfd. Ideal for INDUSTRIAL LAB or TV & RADIO use. Insures full ouse. strength, & sync of TV picture regardless of line voltage. Automatically operated regulator runs on A.C. with set or equipment. TROUBLE FREE, QUIET, needs no adjustment. Universal Use—from 100 to 800 Watts. Input 190-130 V Output 115 volts or minus 5% 50/60 cycles. Sold for "TAB" at Less Than Rock GUARANTEE. ORDER SIX ADDITIONAL 10% DISCOUNT.

FILTER CAPACITORS

EE1516M	6000MFD 15V	3/$1.50; 10/$5
EE4015M	3000MFD 40V	$3.98; 2 for $7

230 to 115V Autoformers

For 230V/50cy Input. To 110-130V or Step up. 1 Wnk Cord, Plug & Receptacle.
TPA50/50W † $2.95
TPA100/100W † 3.65
TPA150/150W † 4.00
TPA200/200W † 5.25
TPA250/250W † 6.25
TPA400/400W † 8.75
TPA750/750W † $13
Model TPA1000 1000 Watts KW † $8.98
TPA1500/1500W † $22.50; TPA2000/2KW $34
* Less Cord, Plug & Receptacle.

DC Power Supply

6 or 12V DC Power Supply
Full Wave Rectification
6000 MFD Condenser Filter
Ready to operate Input 115V 85cy Output 6.2 or 12.6V.
Model 2DCF (2 amp $12.98
Model 3DCF (3 amp 20.95
5DCF ACC/6 amp/1% Ripple 38.95

High Current Power Supplies

ONE YEAR GTD
Variable 6-28VDC Completely Built, Ready to Go. Full Wave Selenium Rectifier Transformer, Variac, Volt & Amp Meters, Switch, Terminals & Fuse. Hvy Duty Steel Cabinet Std 115V/60cy Input or 220V † (3 phase) to order.

Stock Number	Continuous Rating	With Meters
T28V5A	0-28 V VDC 5 Amp	
T28V5ACC	5 Amp (1% Ripple)	$85
T28V5A2CC	5 Amp 0.01% Ripple	145
T28V12A	0-28 VDC at 12 Amp	125
T28V12ACC	12 Amp (1% Ripple)	160
T28V12A2CC	12 Amp 0.01% Ripple	230
T28V24A	0-28 VDC at 24 Amp	185
T28V24ACC †	24 Amp (1% Ripple)	225
T27V24A2CC †	24 Amp 0.01% Ripple	315
T28V50A †	0-28 VDC at 50 Amp	310
T28V50ACC †	50 Amp (1% Ripple)	410
T28V100A †	0-28 VDC at 100 Amp	545
T28V100ACC †	100 Amp (1% Ripple)	695

Variable 75 to 135 VDC Completely Built, Ready to go. Includes F. W. Selenium Bridge Rectifier 4" Rectangular Volt & Ammeter Overload output Dsgnd for cont. service. Specify for 115 or 230 VAC 1 phase, 60 or Input $100
T120V1AC 75 to 135 VDC at 6 Amp $100
T120V1ACC 6 Amp (1% Ripple) 240
T120V10AC 75 to 135 VDC at 10 Amp 260
T120V10ACC 10 Amp (1% Ripple) 295

POWER SUPPLIES TO YOUR SPECS
WRITE US YOUR REQUIREMENTS

New Variable Voltage X-fmrs

SUPERIOR-GR-STACO-UTC

6-125V-1.25A *	$7.25
6-135V/3A *	10.65
Cased/6-135V/7.5A *	19.60
Uncased/6-135V/7.5A *	16.30
Cased/6-270V/3A *	19.60
Uncased/6-270V/3A *	16.30
Cased/6-135V/15A *	30.10
Cased/6-270V/15A *	30.10
Uncased/6-270V/15A *	30.10
Uncased 6/27/2.5A *	$1.60
Cased 0-270V/5A *	31.60
Cased 0-270V/12A †	44.50
Cased 0-270V/15A †	54.50
Cased 0-270V/30A †	104.70
GR500B/0-270V/31A/LN	$155.00

LN, Like New (*) New (†) 3 Phase New

"TABTRAN" Rectifier Chokes

CR6001/1 Amp/0.1 HY/1.4 Ohm $4.50; 2 for $8
CR6002/3 Amp/0.1 HY/47 Ohm $5.75; 2 for $10
CR6003/7 Amp/07 HY/0.5 Ohm $7.50; 2 for $13
CR6004/12 Amp/.01 HY/.1 Ohm $14.50; 2for$28
CR6005/24 Amp/.004 HY/.025 Ohm ..... $29.50; 2/$50

"TABTRAN" Rectifier Xfmrs

See'd Volts (DUAL†) 18-15-9-0-9-15-18V.

TR5001	1 Amp†	$5.45; 2/$10.50
TR5002	2 Amp†	$8.45; 2/$12.25
TR5003	3 Amp†	$8.45; 2/$15.75
TR5001	12 Amp†	$15.50; 2/$27
TR5002	24 Amp†	$25.50; 2/$70
TR5004	30 Amp*	$68.50; 2/$115
TR5005	50 Amp*	$107.50; 2/$210

16 Volt 2 Amp ..... $3.98; 2 for $3.50
1 Windings in Series at Ratings shown; Parallel 2/Amps; Voltage cut max.
* Dual Pri 115 & 220V 60cy; Tapped 36VCT

"TAB" NEW YORK DISTRIBUTOR

Write for Discounts and Rectifier Catalog PR156

TUBES

1st Quality
TESTED — GUARANTEED

0A2	$ .74	3A8A	1.30	6LF7/27	1.77
0A3	.75	3B24A	1.95	6T8	1.54
0B2	.44	4J4A	3.94	6T16	189.95
0B3/VR90	.84	4J60	3.94	6U8	2.39
0C3/ VR105	.82	5BP1/TH 5Z4GT 5Z4A 5Z4W	72.45 2.95	6V6GT	1.72
0D3/ VR150	.78	5U4G 5U4GA 5V4G 5V4GA	2.95	6X4	.42
1AD4	3.35			6X8	1.54
1AG4	3.25	5Y3GA	1.55	6Y6G	1.54
1B3	.46	5Y3GT 5Y3GTA 5Y3GTB	2.95	6Z4	.42
1B24	4.98	5Z4X	2.95	7A4	1.54
1B35	1.88	6BCX	.97	7A5	2.99
1B61A	42.50	HY615	.46	7A6	1.28
1C5	1.54	6C4	.42		
1Q3	100.00	7BA	.98	7B5	49.95
1X2A	.52	7BA	.98	7B6	49.95
1X2B	.56			7B7	49.95
2AP1A	36.50			7B8	49.95
2D21	.75	7B8A	1.68	7B25	11.99
2E22	1.89	7B8B	11.98	7B26	5.98
2E24	2.48	7C7A	5.98	7B27	5.98
		7J7A	.98	7B41	7.98
2E26	3.78	7J8AB	2.98	7B42	12.00
2E30	3.98	7J8B	1.54	7B43	4.49
2E42	1.43	7J8B	.96	7B52A	7.97
2J38	56.50	7J8A	6.49		
2J41	2.48	7K8	1.54	7B57	59.50
2K25	23.88	807W	4.98	7B63	49.94
2K28	29.50			7B65	49.95
2K29	29.50			7B67B	2.98
2K32	5.98	8L6	2.48	7C6	12.49
2K33	139.00	8L6	2.48	7C8	1.50
2K35	219.48	8JSB	6.49	7C9	1.50
		8L6	2.48	7C10	1.54
2K41	175.00	864	.34	7C19	.74
2K42	149.50	927	1.26	7C22	.87
2K43	149.50	927	1.26	7C24	89.50
2K47	465.00	1633	.98	7C31	5.00
4J52	649.95	1642	.62	7C32	4.87
4J100A	56.00	1654	.62	7C33	49.95
		1684A	99.00	7C34	49.95
5C22	29.50	1685A	4.98	7C35	49.95
5D21	9.48	2050W	2.48	7C37	169.95
5U4G	.46	2051	.48	7C43	199.95
6AN5	2.68	2C34	4.98		
6AN8	1.54	5516	1.51	8005	4.97
6AS7G	2.98	5517	2.22	8012	1.09
6BE6	.48			8013	1.09
6BN7	.56	5588	189.26	8014A	50.15
6V6GT	.56	5588	119.95	8016A	2.98
6X4	.42	5642	1.54	8020	2.98
		5640	11.57	8021	.98
12AU7	.84	5641	4.59	8002	.98
12AX7	.84	5642	1.54	8003	.98
12GG7	3.01	5643	2.72		
19BG6	1.38	5656	9.98	C-Ray Tubes	
24G	1.54	5670	2.24	1BP1	5.45
6M24	4.98	5670	2.24	1CP1S1	5.98
25Z5	.46			1DP1	4.81
35Z4	.46	5672	1.58	1EP1	4.81
50L6	.46	5676	1.58	1FP1	4.71
		5686	2.98	1FP7	1.91
72A	.74	5687	2.98	1GP1A	1.91
6V6G	5.49	5692	5.49	1GP1	5.91
QK585	699.99	5693	5.49	1HP1	1.98
QK586	699.99	5694	5.49		
2D21A	7.38	CK4697	3.78	5CP1A	14.49
215 A	10.35	CK5702	2.58	5CP1	3.58
2C51	2.52	5704	2.98	5JP1	3.58
2D2B	10.95			5JP2	14.95
250TH	35.00	5713	173.50	5JP7	7.94
304TH	15.00	5715	5.98	5KP1	7.94
		5719	5.98	5MP7	100.00
304TL	15.00	5721	189.55	7BP7	6.98
316A	.48	5725	2.98		

We Wholesale to Dealers, Stock Markets, Xporters & Tube Brokers!
GET OUR PRICE B4 U BUY! ! !

SPECIAL BUYS

New miniature Diehl PM motor Type FD6-21, RPM 10,000/27 & VDC Excellent mtr for fan cooling ..... $2.50 @ 5/$10—Diehl miniature motor & fan ..... $3.50; 5/$12

"GIANNI" Pressure Transmitter, Similar to 481A40 mfg. for Sperry part #7873240 consists Twin Altimeter Bellows actuating Precision Potentiometers. Temp Comp cost over $100; "TAB" Special $20 ea; 2 for $30
Same accept Sperry part #7000532 only one bellows actuated resistor—Special $12 ea; 2 for $20
Bourns Miniature Precision "Trimpot" 5000 Ohms—Special ..... $2.50; 5 for $10
Fenwal Thermoswitch #371211 Precision adjustable Weld or Air Control —100 to +400° F/10A/115 VAC ..... @ $12.77
Fairchild Type 735 Five Gang Precision Potentiometer, 3 units 10,000 Ohms, one 25,000 Ohms one with 2 taps accy ±5% 5 watts BERCO mtg. Reg $100—"TAB" Special $8 @; 4/$28

WRITE FOR BARGAIN FLYER
$ $ Real Money Savers $ $

Miniature Hi Q Inductors—0.6 Hy. Hi accy Mu metal core. Only $1.25; 5 for $5
Delay Line—Miles 1 mu sec ..... @ $2.98; 4/$9
Delay Line—RSC #2200/0.4 mu sec ..... $2; 6/$10
Proprietary Drive—5/1 & 1 to 1 Ratio, Sealed, Clare SRS010/DPDT/1B-28 VDC/3A CTS Octal Base ..... @ $2.98; 3 for $7.50
Edison Time Delay Relay, Octal base 28 or 120 Volts @ $1.25; 10/$10
Micro Positioner, Harper—Coilmaker AYL23522-8 polarized DC relay Dbe coil, differential current sens, 50 ma max. for remote control positioning ..... $2.50; 2/$4
"1-A" Special @ $2; ..... 3 for $5; 10 for $10
Filter FL-5 Kenge or Veico, Future 1050 style audio excellent for W. worker ..... 89c; 2/$1
Sylvania Crystal Diode 1N23B ..... $1.25; 10/$10
YAL Diode IW25, @ 25c, ... 3 for $1
Sine-Cosine Linear Sawtooth DC Precision Line Potentiometer, 100 Ohms, (RS15138 Reg. $100 ..... 89c; 5 for $5
"TAB" Special Buy @ ..... 89c; 5 for $5
Full Wave Selenium Rectifier—35 ma. 115VDC rated ..... Special @ 39c; 10/$3.49

THAT'S A BUY "TAB" THAT'S A BUY
Dept 1E6 111 Liberty St. New York 6, N. Y. U.S.A. PH. RECTOR 2-6245 CABLE TABPARTS

Money Back Guarantee (Cost of Mdse. Only) $5 Min. Order FOB N. Y. C. Add shpg. charges or for COD 25% Dep. Prices Subject to Change Without Notice.

POCKET AC-DC Multitester

"TAB" 27C $7.75 ea

Hi-accuracy precision VOM 1000 Ohms per V. Reads AC & DC Volts 0, 5, 25, 250, 1000V. DCMA 0, 1, 10, 100MA. Ohms 0 to 100K. Size 1¾D, 4¾L 2 W. Test Leads (Plus 40c ship in U. S. A.)

Dealers Distributor Writer for Discounts

HI-MEG HI-VOLT RESISTORS

2 MEG 5W/10KV	89c 12 for $9.00
2 MEG 10W/10KV	$1.00 12 for $10.00
2 MEG 10W/20KV	$1.50 12 for $15.00
20 MEG MVO 15W/50KV	$2.00 12 for $20.00
50 MEG MVO 25W/50KV	$2.50 12 for $25.00
50 MEG MVE 25W/50KV	$2.50 12 for $25.00

Lots Fifty 20% Disc.; Lots 100 Disc. 40%

NEW MINIATURE METER
0-1 Milliamp

Precision Jeweled D'Arsonval Mvt. Better than 2% accy. Readable long 1¾" scale 20 div. Nonglare. Well damped. Bakelite cased. Front Sq. or Rear Round Face mtg. Mounts 1¾ holes, 2 screws 1¾" ctrs. Not a surplus

Milliamp Shunts each 25
"TAB" SPECIAL ..... $3.95; 2 for $7.00

INFRARED SNOOPERSCOPE
SEE IN DARK TUBE

Selected, GTD Image-Converter Tube Hi-Sensitivity simplified design 2" dia. Wilcoxite screen—Resolution up to 250 lin./in. Tube & Data "TAB" Special $3.98; 2/$7.50

Snooperscope Pwr Supply ..... 4500VDC/18MA. Using Dual Doubler Ckt. Transformer, Rectifiers Sockets, Resistors, Capacitors and Diagram 115V/60cy Oper. $12.95

PRECISION POTENTIOMETERS

Helipot 1000 Ohms/0.5%/3 Turn
Helipot 2000 Ohms/0.5%/10 Turn
Helipot 20K Ohm/0.5%/10 Turn
Helipot 10K Ohm/0.5%/3 Turn
Special Buy @ ..... $6.45 ea; 6 for $24
$100 or more 20% Discount

PHOTOFLASH & STROBE LAMPS

"TAB" No.	Nopiece	W-Sec Max	Each
TWF	FA 10A/F11B	100	$8.98
THI	Argle 5804X	100	10.98
2257	GE FT 210	200	9.98
2 THV	GE FT 4250	300	9.98
V4X4	X400	300	10.98
TDX	DXC/FA100	150	9.00
TDX	DXC/250-250	150	10.00
2525GTQ FT	503	2000	49.98
TDX	DXC/FA10	1500	51.47

TRIGGER COIL TO VOLT FLASH $1.47
Write for Complete Listing
OIL COND-525 MFD/450VDC/53 Watt can 4x NEW low leakage tantalum mfgr ..... 50; 2/$15
FIVE-90 Volt (N60) Batteries $12.50

INDEX TO ADVERTISERS

Ace Electronic Associates 351
Ace Engineering & Machine Co., Inc. 287
Acme Electric Corp 348
Admiral Corporation 239
Advance Electric & Relay Co 355
Aeronautical Communications Equipment, Inc. 50
Ainslie Corp. 335
Airborne Instruments Laboratory, Inc. . 253
Aircraft-Marine Products, Inc. 231, 251
Air Marine Motors, Inc 333
Airpax Products Co 33
Allegheny Ludlum Steel Corp 58
Allen-Bradley Co. 46
Allied Radio Co. 330
Alpha Metals, Inc. 51
American Electronic Mfg., Inc. 389
American Lava Corporation 65
American Phenolic Corp 182
American Television & Radio Co 332
Amperex Electronic Corp 245
Ampex Corporation 233
Anaconda Wire & Cable Corp 325
Arnold Engineering Co 13
Associated Commodity Corp 360
Astron Corporation 205
Atlas Precision Products Co 220
Avien, Inc. 321
Avion, Division A C F Industries, Inc. 337
Axel Brothers, Inc., Electronics Div. 36

Ballantine Laboratories, Inc 299
Barry Controls, Incorporated 21
Bausch & Lomb Optical Co 264
Beaver Gear Works, Inc 246
Bell Telephone Laboratories 78
Bendix Aviation Corporation
Red Bank Div. 302
Scintilla Div. 285
Bentley Harris Mfg. Co 32
Berkeley Div. Beckman Instruments, Inc. 92, 93
Bird & Co., Inc., R. H 316
Bird Electronic Corp 343
Biwax Corporation 354
Black Light Corp. of America 350
Bliley Electric Company 268
Boesch Mfg. Co., Inc 356
Bomac Laboratories, Inc 57
Bourns Laboratories 282
Brew & Co., Inc., Richard D 357
British Electronic Sales Co., Inc 412
Brush Electronics Company 96A, 96B
Burgess Battery Company 344
Burlington Instrument Co 345
Burnell & Co., Inc 263
Bussmann Mfg. Co 76

Caledonia Electronics & Transformer Corp. 341
Cambridge Thermionic Corp 42
Camloc Fastener Corp 206
Centralab, a Division of Globe-Union, Inc. 81
Cerf & Co., Art 360
Chicago Standard Transformer Corp 250
Chicago Telephone Supply Corp 165
Cinch Mfg. Corp 173
Clarostat Mfg. Co., Inc 221
Cleveland Container Co 377
Clifton Precision Products Co., Inc 223
Cohn Corp., Sigmund 320
Collectron Corp. 353
Color Television, Inc 192
Colortone Electronics, Inc 355
Comar Electric Company 240
Communication Accessories Company ... 95
Communication Measurements Laboratory, Inc. 261
Communication Products Co., Inc 347
Computer-Measurement Corp. 415
Condenser Products, Div. of the New Haven Clock & Watch Co 328
Consolidated Vacuum Corp 276
Continental Wire Corp 194
Cornell-Dubilier Electric Corp 103
Corning Glass Works 258
Cornish Wire Company 412
Coto Coil Co., Inc 340
Crane Packing Company 273
Crest Transformer Corp 353
Cross Co., H 355
Cubic Corp. 286

Dano Electric Co 351
Daven Company .....3rd Cover
DeJur-Amsco Corporation 298
DeMornay Bonardi 184
Dialight Corporation 301
Docicam, A Division of Minneapolis-Honeywell 104
Driver-Harris Company 87
Du Mont Laboratories, Inc., Allen B. ... 183
duPont de Nemours & Co. (Inc) E. I. Film Dept. 97
Polychemicals Dept. 63

SWITCHING
SAMPLING
SEQUENCING

HIGH SPEED

Multi-Pole Commutators

Precision, rotary, electro-mechanical switching unit with precious metal contacts for long life, low noise, trouble-free operation. Contact cleaning device extends life, permits low level switching in some applications. Multi-pole units with any number of contacts can be furnished. Switching can be "make before break" or "break before make."

MODEL 85561
Torque: 2 oz-in. or less. Weight: 4 oz. Will withstand 50G acceleration and operate within specifications at 10G vibration from 55 to 500 cps. Noise Level: Will not exceed 1.0% of full signal amplitude.
MODEL 85562
Motor driven model. DC governor-controlled constant speed ½ to 1800 rpm., or speed varies linearly w/ applied voltage. Other drives available.

Giannini

Product of Electromechanical Division
EAST ORANGE, NEW JERSEY

for information write
G. M. GIANNINI & CO. INC.
PASADENA 1, CALIFORNIA

Want more information? Use post card on last page.

no alternative exists*

PAINTON

MIDGET WIRE-WOUND VITREOUS RESISTORS

*"The summing network of our precision computer project required extremely stable resistors, mutually matched with identical dynamic retrace characteristics under wide ambient conditions. On request, selected prominent manufacturers of military quality resistors submitted samples for our test. We also tried British-made Paintons out of local stock and found them to be the only ones which had all the desired characteristics in combination. They were in a class by themselves. Now they are specified with approval in many of our U. S. Government projects" . . . .

Prominent U. S. Electronics Contractor (name supplied upon request)



NOW! NEW! 100% hermetically sealed, fully insulated to 1000 Volts RMS. 100% inspected. Values to 150,000 ohms, temperature coefficient not exceeding .004%/°C even at the highest resistance values of the P300A Series. Paintons are insulated to 1000 megohms DC resistance even at maximum working temperature. Meet operational characteristics of MIL-R-26B. Painton resistors are readily available in the U.S.A. All orders are handled by cable and air transportation when additional production from the English plant is required.

SEND FOR FREE SAMPLES AND COMPLETE DATA

BRITISH ELECTRONIC SALES CO., INC.
23-03 45th RD., LONG ISLAND CITY 1, N. Y.
Telephone EXeter 2-6660

BE *Sure* with CORNISH

Electronic WIRES and CABLES

MICROPHONE CABLES

Designed for low capacitance, high insulation resistance, low attenuation—in plastic or rubber insulation to stand severe service

T-V LEAD-IN CABLES



Furnished only in pure virgin polyethylene to insure best electrical properties and long life under severe operating conditions

T-V LEAD-IN CABLES

Made hollow, of pure virgin polyethylene, for maximum efficiency in receiving Ultra High Frequency signals

INTERCOMMUNICATION CABLES

These quality cables are made in various constructions, utilizing plastic insulation for both conductors and jacket

SHIELDED INTERCOMMUNICATION

When installation conditions dictate, shielded cables are recommended. Made with internal or external shield—2 and 3 conductors

MADE BY ENGINEERS FOR ENGINEERS

CORNISH WIRE COMPANY, INC.
50 Church Street — New York 7, N. Y.

Eagle Signal Corp. 265
Eastern Air Devices, Inc. 248
Eastern Industries, Inc. 306
Elsier Engineering Co., Inc. 414
Eitel-McCullough, Inc. 75
Eico Corporation 358
Electrical Industries Div. of Amperex Electronic Corp. 109
Electro Impulse Laboratory 353
Electro Motive Mfg. Co., Inc. 116
Electro-Pulse, Inc. 313
Electro-Snap Switch & Mfg. Co. 249
Electro Tec Corporation 257
Electronic Associates, Inc. 315
Electronic Instrument Co., Inc. (EICO) . . 352
Emerson & Cuming Inc. 280
Engineering Co., The 234
Epsco, Inc. 238
Erie Electronics Division Erie Resistor Corp. 228
Essex Wire Corp., R-B-M Division 186

Fairchild Camera & Instrument Corp. . . . 115
Falcon Electronics Corp. 327
Fansteel Metallurgical Corp. 270, 271
Farnsworth Electronics Company 101
Federal Telephone & Radio Co. 243
Filtron Company, Inc. 31
Fisher & Crome 356
Five Star Co. 347
Ford Instrument Co. 321
Freed Transformer Co., Inc. 261
Frenchtown Porcelain Co. 69

G-V Controls Inc. 208
Gamewell Co. 278
General Ceramics Corp. 30
General Dry Batteries Inc. 202
General Electric Co.
Apparatus Dept. 241
Electronics Dept. 112
Tube Dept. 23
General Radio Co. 17
General Research & Supply Co. 234
Genisco, Inc. 346
Giannini & Co., Inc., G. M. 411
Good-all Electric Mfg. Co. 91
Green Instrument Co. 246
Gries Reproducer Corp. 348

Hammarlund Mfg. Co., Inc. 25
Haydon Company, A. W. 198
Haydon Manufacturing Co., Inc. 272

Handy & Harman 232
Haydu Brothers of New Jersey 191
Heath Company 341
Heiland, A Div. of Minneapolis-Honeywell 297
Helipot Corp., Div. of Beckman Instruments, Inc. 179
Hermetic Seal Products Co 247
Hewlett-Packard Company 72, 73
Hudson Tool & Die Company, Inc 187
Hughes Aircraft Co 61
Hughes Research & Development Laboratories 60, 306
Hycon Eastern, Inc 236, 237
Hycor Company, Inc 331

Indiana Steel Products Company 229
Industrial Development Committee of 100, Lakeland Florida 342
Industrial Hardware Mfg. Co., Inc 340
Industrial Test Equipment Co 354
Infra Electronic Corp 308
Institute of Radio Engineers 90
International Business Machines 262
International Nickel Co., Inc 66
International Rectifier Corp 109
Ippolito & Co., Inc., James 334

Jennings Radio Mfg. Corp 288
Jet Propulsion Laboratory 292, 343
Johnson Company, E. F 294
Jones Div., Howard B., Cinch Mfg. Co 261
Joy Manufacturing Co 217

Kahle Engineering Co 15
Kaiser Metal Products Inc 34
Karp Metal Products Co 111
Kartron 360
Kay Electric Co 29
Kearfott Co., Inc 113
Kellogg Co., M. W 74
Kennedy & Co., D. S 224
Kepco Laboratories 177
Kester Solder Co 215
Kinney Mfg. Division, New York Air Brake Company 87
Kleiner Metal Specialties, Inc 293
Kollsman Instrument Corp 77
Kurman Electric Co., Inc 353
Kwikheat Manufacturing Co 356

L M Electronics, Inc 349
Laboratory for Electronics, Inc 259
Lambda Electronic Corp 38, 39
Lampkin Laboratories, Inc 357
Land-Air Inc. 336
Lapp Insulator Co., Inc 106

we work with Fluorocarbons ...and "know-how"



Electronics Test Cage



Physical Testing Laboratory



Injection Molding



Fluorocarbon Machining

The United States Gasket Company is the recognized leader in the fabrication and application of the "Wonder Plastics", duPont TEFLON, Kellogg KEL-F and BAKELITE Fluorothene—leadership earned through many years of pioneering.

Today, this company offers engineering and manufacturing talent and facilities unmatched in the industry to assist its customers in the profitable application of Fluorocarbon Products for almost countless purposes.

To render this service, three highly specialized laboratories are maintained—electronic, chemical and physical—staffed by engineers who continue to produce most of the advanced ideas and practices in the application of these plastics to commercial, A.E.C. and military requirements.

Manufacture is Quality Controlled, utilizing the most modern facilities for rapid, low cost production. Many machines and equipment have been designed or converted by our own engineering department to the peculiar requirements of Fluorocarbon Plastic Fabrication.

• Write for the twenty-page brochure "Inside U. S. G." that suggests how this organization can fit into your development and production program.

U S G BELMONT

UNITED STATES GASKET CO.

CAMDEN 1, NEW JERSEY

LABORATORY INSTRUMENTS

PHASE DISPLAY EQUIPMENT

The PDE-1 displays the transfer function of any network, amplifier, or complete system as a simultaneous polar plot of phase and amplitude. Phase and amplitude distortion can be measured over the range of 100 kc to 10 mc. The self-contained sweep is adjustable to 10 mc, at a recurrence rate of 30 c.p.s. A built-in marker generator provides markers at 100-kc and 500-kc intervals, for Z-axis modulation of the display oscilloscope. The PDE-1 is ideal for the study of phase response about the subcarrier frequency in color television receiver design.



NETWORK SYNTHESIZER AND UNIVERSAL FILTER



The NS-1 permits rapid synthesis of any filter characteristic over the entire video range, eliminating cut-and-try design procedures. The unit will synthesize 10 terms of a Fourier series or 10 steps of any transient response function. Voltages are selected from a 50-section delay line (.034 μ sec per section) and combined by means of 10 cathode followers, each having an attenuator and polarity (algebraic sign) selector switch. Controls can be reset to repeat a desired network. Built-in regulated power supply.

Write for complete literature on these items.

Wickes ENGINEERING AND CONSTRUCTION COMPANY

ESTABLISHED 1920

12TH STREET AND FERRY AVENUE — CAMDEN 4, NEW JERSEY



You Name It EISLER Makes It...

Eisler tipless stem patents have been extensively used by incandescent lamp and radio tube manufacturers. Eisler patents are free and have been a source of protection to the radio tube and lamp industry. Why not consider your next machine an Eisler? Serving the Industry over 35 years.

Send for Catalog



CHAS. EISLER JR., PRES.

EISLER ENGINEERING CO., INC.

751 So. 13th St. NEWARK 3, N. J.

Leach Corp., Leach Relay Div. 203
Lear Inc. 184B, 185
Lewis Spring & Mfg. Co. 242
Librascope, Inc. 71
Lockheed Missile Systems Div. 218, 219
Los Alamos Scientific Laboratory 332

MacDonald Inc., Samuel K. 360
Magnatran, Inc. 320
Magnecraft Electric Co. 335
Magnetic Amplifiers, Inc. 334
Magnetics, Inc. 197
Maico Tool & Mfg. Co. 415
Mallory and Co., Inc., P. R. 56, 120, 175
Marconi Instruments, Ltd. 98
Markem Machine Co. 347
Martin Company, Glenn L. 296
Maxson Instruments, A Division of the Maxson Corp. 358
McCoy Electronics Co. 281
McGraw-Hill Book Co. 338
Measurements Corporation 188
Metals & Controls Corp., General Plate Div. 118
Microtran Division of Crest Laboratories, Inc. 283
Midland Mfg. Co., Inc. 55
Millen Mfg. Co., Inc., James 103
Millivac Instrument Corp. 295
Minneapolis-Honeywell Regulator Co., Industrial Div. 80
Missouri Division of Resources & Development 338
Molded Fiberglass, Inc. 339
Moseley Co., F. L. 305
Muirhead & Co., Ltd. 5
Mullard Overseas Ltd. 102

N J E Corporation 119
National Moldite Co. 213
Natvar Corporation 88
Neely Enterprises 79
Newhope Corp. 360
Ney Company, J. M. 345
Norden-Ketay Corp. 317
New Hermes Engraving Machine Corp. 337
North Electric Co. 312
Nothelfer Winding Laboratories, Inc. 307

Offner Electronics, Inc. 89
Ohmite Manufacturing Co. 32A, 32B
Oster Manufacturing Co., John 70

Panoramic Radio Products, Inc. 350
Perkin Engineering Corp. 27

Permag Corporation 357
Peter Partition Corp..... 336
Phalo Plastics Corp..... 279
Phaostron Instrument & Electric Co.... 303
Phelps Dodge Copper Products Corp., Inca Mfg. Div. 84, 85
Philco Corporation 43
Phillips Control Corp..... 284
Phillips Process Co., Inc..... 222
Pix Manufacturing Co., Inc..... 326
Polarad Electronics Corporation.. 52, 53
Polymer Corp. of Penna..... 314
Polytechnic Research & Development Co., Inc. 54
Potter & Brumfield Mfg. Co..... 318
Potter Instrument Co., Inc..... 289
Precision Apparatus Co., Inc..... 416
Precision Paper Tube Co..... 230
Pye Ltd. 114

Quaker City Gear Works, Inc..... 204

R-B-M Division, Essex Wire Corp..... 186
Radiation Inc. 354
Radio Cores, Inc. 244
Radio Corporation of America..110, 4th Cover
Radio Engineering Products..... 330
Radio Frequency Laboratories, Inc..... 235
Radio Materials Corp..... 225
Radio Receptor Co., Inc..... 40
Railway Express Agency, Air Express Div. 211
Raytheon Mfg. Company.....18, 19, 35
Reeves Instrument Corp..... 100
Remington Rand Univac Div. of Sperry Rand Corp. 47, 48, 49
Resinite Corp., Div. of Precision Paper Tube Co. 304
Resistance Products Co..... 106
Revere Corporation of America..... 310
Rex Rheostat Co..... 300
Rome Cable Corp..... 99
Rowe Engravers 360

Saft Corporation of America..... 227
Scintilla Div. of Bendix Aviation Corp.... 285
Sierra Electronic Corporation 260
Sigma Instruments, Inc..... 212
Signal Engineering & Mfg. Co..... 342
Sola Electric Co..... 44
Solartron Electronic Group Ltd..... 67
Sorensen & Co., Inc..... 4
Southern Electronics Corp..... 323
Sprague Electric Co.....11, 181, 309

the **ONLY** *instrument in the field that offers* **ALL** *these features at*

NO EXTRA COST!

- **FREQUENCY** Measurement
- **1 and 10 SECOND** Time Base
- **PERIOD** Measurement
- **1 and 10 CYCLE** Gate Time
- **PRECISION ACCURACY** Over 1-100,000 cps range
- **EASILY PORTABLE** Only 28 Pounds
- **SMALL SIZE** 14¾"W x 7⅞"H x 13"D

the new

DS-6100-T

FREQUENCY-PERIOD electronic counter

A compact frequency-period counter designed for direct measurement of any mechanical, electrical or optical phenomena which can be converted to a varying voltage. Read-out in direct digital form. Ideal for use by skilled or unskilled personnel. Price **$700.00.**

Write for complete catalog data TODAY!

- **TOTALIZING COUNTERS**
- **PRESET COUNTERS**
- **DECADE TOTALIZERS**

Detectron

Representatives in all major areas.

COMPUTER-MEASUREMENT CORP.

5457 Cleon Avenue, Dept. 78-A
North Hollywood, California

Malco **IS YOUR BEST SOURCE** *for*

SOLDERING LUGS
SOLDERLESS LUGS
TERMINALS



- Specialized high production techniques afford lowest possible unit cost.
- Precision tooling, rigid quality control assure tolerances to critical specifications.
- Ample stocks of over 1000 different parts permit prompt delivery.
- Malco specializes in a complete line of small stampings for Radio-TV, electrical/electronic and automotive industries.

Let Malco show you how you can save on production time and costs. Contact us today.

Request handy reference catalog containing specifications on standard and custom-made lugs, terminals, corona rings, pins, contacts and similar stampings.

Malco **TOOL and MANUFACTURING CO.**

4023 W. LAKE ST., • CHICAGO 24, ILLINOIS

PRECISION

Model E-300

SINE-SQUARE WAVE SIGNAL GENERATOR

(AUDIO-VIDEO RANGE)



The Series E-300 provides sine and square wave signals of high accuracy and stability for direct-performance testing of:

- *High Fidelity Audio Amplifiers*
- *TV Video Amplifiers*
- *Carrier Current Systems, etc.*

GENERAL SPECIFICATIONS

★ **Variable-Frequency Sine Wave Ranges:** 20 Cps. to 200 KC. in Four Bands.

★ **Variable Frequency Square Wave Ranges:** 20 Cps. thru 20,000 Cps. in Three Bands.

★ **Four Fixed, High-Frequency Square Waves:** for analysis of wide-band amplifiers up to 20 MC band width: **50 KC.—100 KC.—250 KC.—500 KC. steps.**

★ **Output Characteristics:**
Variable Frequency Ranges: 0-2000 ohms, 0-10 volts RMS, ± 1 db.
Accuracy: ± 2% from 50 cycles to 200 KC. ± 1 cycle from 20 cycles to 50 cycles.
Distortion: Less than 1% from 20 cycles through 200 KC.
20 KC Square Wave Rise Time: .5 microseconds.
Fixed High Frequency Square Waves: 0-250 ohms, 0-5 volts P-P
Rise Time: .05 microsecond
Overshoot: Negligible

★ **Tube Complement:** 1-5879, 1-6CL6, 1-6J6, 2-6AU6, 1-6BL7, 1-6AH6, 1-6X4.

★ **Separate Output Circuits:** for the variable and fixed frequency ranges.

★ **Terminated, Low-Loss, High Frequency Coaxial Output Cable**

★ **External 'Sync' Terminal Post:** for synchronizng scope to H.F. square wave.

★ **Etched-Anodized Tuning Dial and Panel**

MODEL E-300 DELUXE (Illustrated): In blue-grey, hooded steel cabinet and 2-color brushed aluminum panel with contrasting knobs. 11½x13x6⅝". Complete with tubes, coaxial output cable and instruction manual. **Net Price: $180.00**

MODEL E-300 STANDARD: Standard black ripple finished cabinet with black aluminum panel. 10½x12x6". Complete with all accessories, as above. **Net Price: $175.00**

PRECISION Apparatus Company, Inc.
70-31 84th Street, Glendale 27, L. I., N. Y.
Export: 458 Broadway, New York 13, U. S. A.
Canada: Atlas Radio Corp., Ltd., 50 Wingold Ave., Toronto 10

Want more information? Use post card on last page.

Simpson Electric Co. 82, 83
Spencer Kennedy Laboratories, Inc. 316
Stackpole Carbon Co. 195
Staedtler Inc., J. S. 200
Star Porcelain Co. 350
Sterling Engineering Co. 318
Sterling Transformer Corp. 346
Stevens Arnold Inc. 321
Stoddart Aircraft Radio Co., Inc. 275, 311
Stupakoff Ceramic & Mfg. Co. Div. of the Carborundum Company 290, 291
Sturtevant Co., P. A. 261
Superior Tube Co. 94
Sylvania Electric Products, Inc. 9, 255

Taylor Fibre Co. 80
Tech Laboratories, Inc 68
Technicraft Laboratories, Inc. 226
Technology Instrument Corp. 329
Tektronix, Inc. 62
Tel-Instrument Electronics Corp. 347
Transicoil Corporation 64
Transradio, Ltd. 344
Transitron Electronic Corp. 107
Trans-Sonics, Inc. 252
Triplett Electrical Inst. Co. 209
Tung-Sol Electric, Inc. 45

Union Switch & Signal Div. of Westinghouse Air Brake Company 266, 267
United Electronics 59
United States Gasket Co. 413
United Transformer Co ..... 2nd Cover
Universal Winding Co. 117

Varian Associates 326
Varflex Corp. 269
Veeder-Root, Inc. 201
Virginia Electric and Power Co. 210

Waldes Kohinoor, Inc. 41
Waterman Products Co., Inc. 196
Waters Manufacturing, Inc. 319
Weckesser Co. 357
Welch Scientific Co., W. M. 328
Welwyn International Inc. 349
Wenco Manufacturing Co. 351
Western Gear Corporation 189
Westinghouse Electric Corp. 96
Weston Electrical Instrument Corp. 106
Westronics, Inc. 327
Whitney Blake Company 274
Wickes Engineering and Construction Co. 414
Woods Aircraft Supply 352

Zophar Mills, Inc. 353

MANUFACTURER'S REPRESENTATIVES 360

PROFESSIONAL SERVICES 359

CLASSIFIED ADVERTISING
F. J. Eberle, Asst Mgr.

SEARCHLIGHT ADVERTISING 395-410
ADVERTISERS INDEX 394
EMPLOYMENT OPPORTUNITIES..361-394
ADVERTISERS INDEX 393

This index is published as a convenience to the readers. Every care is taken to make it accurate, but ELECTRONICS assumes no responsibility for errors or omissions.

electronics

READER SERVICE SECTION

A method that provides readers with a . . .

"DIRECT-TO-THE-MANUFACTURER"

method of obtaining information on:

1. Products advertised in this issue
2. New Products and Literature covered in the editorial section of this issue

This direct method prevents loss of time in remailing your request from publication to manufacturer.

THESE POST CARDS ARE FOR YOUR USE

and

HERE IS WHAT YOU DO:

1. Fill in with ink or typewriter your name, company, address and title.

2. Then fill in the name of the specific product and the page number on which it appears.

3. Place a check mark in the box or boxes applicable to your needs.

4. Tear out the postcard on the perforated lines and address it to the manufacturer(s) whose products you are interested in. Place a stamp in the box indicated and drop into the mail.

THE MANUFACTURER WILL PROMPTLY SEE THAT YOU RECEIVE THE NECESSARY PRODUCT DATA OR THAT HIS REPRESENTATIVE CALLS UPON YOU, WHICHEVER YOU DESIRE.

If there is insufficient space on the postcard for describing your problem specifically, we suggest you write to the manufacturer, spelling out your requirements in detail. Be sure your filled in postcard accompanies your letter.

THIS SERVICE IS A CONVENIENCE FOR THE READERS OF ELECTRONICS.

Name .....

Company .....

Address .....

Title .....

Please send me further information on

(Product or Service) .....

As described in ad on page ..... of January 1956 Issue

or, Check

New Product | | ..... on Page .....

Literature | | (Name of Product or Literature)

☐ I want this information for my files

☐ I wish to see your representative

☐ Please contact me by telephone. Phone Number .....

electronics

Name .....

Company .....

Address .....

Title .....

Please send me further information on

(Product or Service) .....

As described in ad on page ..... of January 1956 Issue

or, Check

New Product | | ..... on Page .....

Literature | | (Name of Product or Literature)

☐ I want this information for my files

☐ I wish to see your representative

☐ Please contact me by telephone. Phone Number .....

electronics

Name .....

Company .....

Address .....

Title .....

Please send me further information on

(Product or Service) .....

As described in ad on page ..... of January 1956 Issue

or, Check

New Product | | ..... on Page .....

Literature | | (Name of Product or Literature)

☐ I want this information for my files

☐ I wish to see your representative

☐ Please contact me by telephone. Phone Number .....

electronics

Name .....

Company .....

Address .....

Title .....

Please send me further information on

(Product or Service) .....

As described in ad on page ..... of January 1956 Issue

or, Check

New Product | | ..... on Page .....

Literature | | (Name of Product or Literature)

☐ I want this information for my files

☐ I wish to see your representative

☐ Please contact me by telephone. Phone Number .....

electronics

ELECTRONICS
January 1956

Place Stamp Here

TO: _____

_____

_____

ELECTRONICS
January 1956

Place Stamp Here

TO: _____

_____

_____

ELECTRONICS
January 1956

Place Stamp Here

TO: _____

_____

_____

ELECTRONICS
January 1956

Place Stamp Here

TO: _____

_____

_____

To the Readers

of

electronics

A New Reader Service designed to provide prompt response

You, as a reader, may never have thought specifically of the viewpoint of the advertisers whose informative and up-to-date product news reaches you through the advertising pages of ELECTRONICS.

They are VITALLY interested in you and your needs. You and thousands like you constitute the market and without you they cannot continue to present their product story; indeed, they cannot remain in business.

These manufacturers whose products and services are shown in this issue welcome your inquiries and your desire for more information.

If your requirements are complicated and you require more space, we suggest that you write directly to the manufacturer, stating your problem in detail and asking for specific information or assistance. Be sure to include the postcard with your detailed request in order that your inquiry be given prompt and expeditious attention. Make certain that you specify which PRODUCT you are interested in if more than one appears in the advertisement.

electronics

READER SERVICE SECTION

A method that provides readers with a . . .

"DIRECT-TO-THE-MANUFACTURER"

method of obtaining information on:

1. Products advertised in this issue
2. New Products and Literature covered in the editorial section of this issue

This direct method prevents loss of time in remailing your request from publication to manufacturer.

THESE POST CARDS ARE FOR YOUR USE

and

HERE IS WHAT YOU DO:

1. Fill in with ink or typewriter your name, company, address and title.

2. Then fill in the name of the specific product and the page number on which it appears.

3. Place a check mark in the box or boxes applicable to your needs.

4. Tear out the postcard on the perforated lines and address it to the manufacturer(s) whose products you are interested in. Place a stamp in the box indicated and drop into the mail.

THE MANUFACTURER WILL PROMPTLY SEE THAT YOU RECEIVE THE NECESSARY PRODUCT DATA OR THAT HIS REPRESENTATIVE CALLS UPON YOU, WHICHEVER YOU DESIRE.

If there is insufficient space on the postcard for describing your problem specifically, we suggest you write to the manufacturer, spelling out your requirements in detail. Be sure your filled in postcard accompanies your letter.

THIS SERVICE IS A CONVENIENCE FOR THE READERS OF ELECTRONICS.

Name .....

Company .....

Address .....

Title .....

Please send me further information on

(Product or Service).....

As described in ad on page ..... of January 1958 Issue

or, Check

New Product	..... on Page .....
Literature	(Name of Product or Literature)

☐ I want this information for my files

☐ I wish to see your representative

☐ Please contact me by telephone. Phone Number.....

electronics

Name .....

Company .....

Address .....

Title .....

Please send me further information on

(Product or Service).....

As described in ad on page ..... of January 1958 Issue

or, Check

New Product	..... on Page .....
Literature	(Name of Product or Literature)

☐ I want this information for my files

☐ I wish to see your representative

☐ Please contact me by telephone. Phone Number.....

electronics

Name .....

Company .....

Address .....

Title .....

Please send me further information on

(Product or Service).....

As described in ad on page ..... of January 1958 Issue

or, Check

New Product	..... on Page .....
Literature	(Name of Product or Literature)

☐ I want this information for my files

☐ I wish to see your representative

☐ Please contact me by telephone. Phone Number.....

electronics

Name .....

Company .....

Address .....

Title .....

Please send me further information on

(Product or Service).....

As described in ad on page ..... of January 1958 Issue

or, Check

New Product	..... on Page .....
Literature	(Name of Product or Literature)

☐ I want this information for my files

☐ I wish to see your representative

☐ Please contact me by telephone. Phone Number.....

electronics

ELECTRONICS
January 1956

Place Stamp Here

TO: _____

_____

_____

ELECTRONICS
January 1956

Place Stamp Here

TO: _____

_____

_____

ELECTRONICS
January 1956

Place Stamp Here

TO: _____

_____

_____

ELECTRONICS
January 1956

Place Stamp Here

TO: _____

_____

_____

For PRODUCTS and SERVICES

not specifically advertised

or described in the issue

of

Electronics

Consult your

1955-1956 ELECTRONICS BUYERS' GUIDE

or

Write to:

Reader Service Department

Electronics

330 West 42nd Street

New York 36, N. Y.



... and everything in between—

With Over 3500 Standard Switches In The Daven Line From Which To Choose—and which in turn can be modified to provide countless additional switch combinations—it's easy to see why *Daven* is equipped to meet your most exacting switch requirements on short notice.

Knee-Action Rotor Lowers Contact Resistance . . . Gives Longer, Trouble-Free Switch Life! Every *Daven* switch features the exclusive, patented *Knee-Action* rotor arm with two separate wiper blades, each individually spring-loaded—to insure extremely low and uniform contact resistance throughout the life of the switch. *Daven's* special design renders these blades tamper-proof . . . they withstand rugged treatment in the field. Because of their self-wiping action, little or no servicing is required.

Compact Design for Smaller-Size Components—With *Daven's* space-saving design, up to 8 poles per deck can be supplied . . . a significant factor for maximum performance where depth and mounting space are at a premium. *Daven* switch sizes start at 1-3/8" diameter x 1-11/16" in depth. Solid silver alloy rotors, slip rings, and contacts are used exclusively. These switches meet all applicable military specifications.

Write today for FREE catalog.

THE DAVEN CO. 526 West Mt. Pleasant Avenue Livingston, New Jersey

WORLD'S LARGEST MANUFACTURERS OF ATTENUATORS

Exciting News for TV-Set Manufacturers...

NEW RCA FM-DETECTOR TUBE-AND-CIRCUIT FOR TV SOUND SYSTEMS...

...provides high sensitivity and high output voltage at low cost!

The new RCA-6DT6 sharp-cutoff pentode and new FM-detector circuit make possible an improved TV-intercarrier sound system featuring excellent signal sensitivity, AM rejection, and quieting action—with a minimum of circuit components. Functioning as a limiter, detector, and audio amplifier in this new circuit, the RCA-6DT6—a low-cost tube of conventional design—offers new cost economies to TV-set manufacturers.

For data on the RCA-6DT6, its series-heater string equivalent, RCA-3DT6, and the new RCA FM-Detector Circuit, call your RCA Field Representative. Or write RCA, Commercial Engineering, Section A19Q, Harrison, N. J.

EAST.....HUmboldt 5-3900
744 Broad Street
Newark 1, N. J.

MIDWEST...WHitehall 4-2900
Suite 1181, Merchandise Mart Plaza
Chicago 54, Ill.

WEST..... RAymond 3-8361
6355 East Washington Blvd.
Los Angeles 22, Calif.

RADIO CORPORATION of AMERICA
TUBE DIVISION HARRISON, N. J.